

### Installation of Trunk Water Mains Along Grand Street Project

Phase I: Grand St. between Broadway and Bowery

Phase II: Grand St. between Bowery and Essex St.

Project # MED 609(606)

The New York City Department of Design and Construction (NYCDDC) is managing a capital construction project MED609(606) along Grand Street between Broadway and Essex Street, including each intersection. DDC will install new trunk water mains, new traffic signs, street lighting, reconstruct distribution water mains, new roadway surface, curbs and sidewalks in certain locations, as well as, rehabilitate sewer, and upgrade private utilities. The entire project is anticipated to be completed by Spring 2017. Phase I of this project is scheduled to be completed by Fall 2014. Phase I final restoration has begun in April, 2014. **Phase II is scheduled to begin in September, 2014.**

#### Work Completed to Date (Within Phase I Limits)

1. Curbs, Sidewalks & Roadway Have Been Replaced on Grand Street between Lafayette & Bowery
2. **All** Distribution Gas Mains Have Been Replaced (Over 2,000 feet)
3. **All** Distribution Water Mains Have Been Replaced (Over 2,000 feet)
4. **All** 36" Trunk Water Main including Necessary Appurtenances Have Been Constructed (Over 2,000 feet)
5. Sewers in Need Have Been Rehabilitated or Replaced (Approx. 500 feet)
6. Substandard Catch Basins (22) Have Been Replaced with Upgraded Structures for Improved Drainage
7. **All** Trunk Water Mains Have Been Activated on Broadway, Bowery and Grand Street

#### Proposed Work Schedule September/October 2014

##### Phase I Daytime Work Operations from Broadway Up to Bowery:

1. Curbs & Sidewalk Replacement to Be Completed
2. Roadways to Be Excavated & Concrete Road Base Placed Throughout
3. Asphalt Paving of All Disturbed Areas

##### Phase I Nighttime Work Operations on Bowery:

1. Curbs & Sidewalk Replacement to Be Completed
2. Roadways to Be Excavated & Concrete Road Base Placed Throughout
3. Asphalt Paving of All Disturbed Areas

##### Phase II Nighttime Work Operations:

1. East of Bowery to Forsyth St.
  - Gas Main Replacement
  - Distribution Water Main Replacement
2. Chrystie to Eldridge Streets
  - Sewer Cleaning & Video Inspection of Sewers



New Roadway with Street Markings on Grand Street between Centre Street & Centre Market Place

#### Special Needs

Individuals with special needs who may be uniquely impacted by this project should contact the project's Community Construction Liaison, as soon as possible, to make them aware of your situation. DDC will work with you to attempt to minimize the inconvenience as much as possible.

#### Water Service Interruption

During the course of the project there will be service interruptions. To accommodate water main replacement, the existing water service must be shut off by closing the valves at either end of the section. Advance notice will be given for all planned interruptions. Water service will be restored at the end of the day.

#### Community Construction Liaison (CCL)

The DDC has assigned **Nikita Sin** of JED/HAKS Engineers (joint venture), as the Community Construction Liaison (CCL) for this project. Please contact **Nikita** for any project related inquiries/concerns you may have:

Phone: 646-412-3502

Email: grandstccl@gmail.com

Field Office: 110 Lafayette Street, 1<sup>st</sup> Floor, NY, NY 10013

#### Newsletter Distribution

Construction Newsletters for this project are distributed regularly within the project area and to Community Board#2 and #3 – Manhattan.