

Installation of Distribution Water Mains in West 10th Street

West 10th Street (West Street-5th Avenue)

Project # MED-617

The New York City Department of Design and Construction (NYCDDC) is managing a capital construction project MED 617 along West 10th Street from West Street to 5th Avenue, including each intersection. DDC will install new distribution water mains, new traffic signs and street lighting, new roadway surface, curbs and sidewalks in certain locations, as well as, installing catch basins, and upgrade private utilities.

Proposed Work Schedule

March/April 2014

Daytime work operations include:

1. Excavation and Replacement of the Distribution 20" Water Mains:
 - West 10th Street from Bleecker Street & West 4th Street
 - West 10th Street from West 4th Street & 7th Avenue South
2. Installation of distribution Water Mains (and Appurtenances)
 - In and around West 10th Street & 7th Avenue South
3. Installation of Catch Basins in (various locations)

Weekend work operations include:

1. Replacement of the 12" and 20" Distribution Water Mains in and around the intersection of West 10th Street & 7th Avenue (North & South sides of the street)

Work Completed to Date

1. Con-Ed Gas Mains Replacement on West 10th Street and Bleecker Street
2. Distribution Water Mains Replacement in West 10th St. from Washington St. to the intersection of Bleecker St.
3. Catch basins were replaced in (various locations)

WHAT ARE THE COMMUNITY IMPACTS?

DDC is committed to maintaining a work site that is safe and clean. However, dust, noise and heavy equipment are common elements of construction and we ask for your patience during the project. As per DDC stipulations, the Contractor should monitor the noise frequently and comply with the City specifications.

Special Needs

Individuals with special needs who may be uniquely impacted by this project should contact the project's Community Construction Liaison, as soon as possible, to make them aware of your situation. DDC will work with you to attempt to minimize the inconvenience as much as possible.

Water Service Interruption

During the course of the project there will be service interruptions. To allow water replacement, the existing water service must be shut off by closing the valves at either end of the section. Advance notice will be given for all planned interruptions. Water service will be restored at the end of the day.

Community Construction Liaison (CCL)

The DDC has assigned **Diane Guskin**, EnTech Engineering, as the Community Construction Liaison (CCL) for this project. Please contact **Diane** for any project related inquiries/concerns you may have:
 Phone: 212-354-4126 Fax: 212-575-0745
 Email: med617ccl@gmail.com
 Field Office: 262 West 38th Street, Room 903, New York, NY 10018

Newsletter Distribution

Construction Newsletters for this project are distributed regularly within the project area and to Community Board#2 - Manhattan.



↑
Excavation of 20' Distribution Water Main on Bleecker Street looking South of West 10th Street