

Memorial Sloan - Kettering Cancer Center
Ambulatory Care Center and CUNY - Hunter College -
Science and Health Professions Building

Final Environmental Impact Statement

CEQR No.:

13DME003M

ULURP Nos.:

130214 ZMM

N130215 ZRM

130216 ZSM

130217 ZSM

130218 ZSM

130219 PPM

Lead Agency:

Office of the Deputy Mayor for Economic Development

Lead Agency Contact:

Robert R. Kulikowski, Ph.D.

Project Applicants:

*Memorial Hospital for Cancer and Allied Diseases
The City University of New York*

Prepared by:

AKRF, Inc.

August 2013

**Memorial Sloan-Kettering Cancer Center Ambulatory Care Center and
CUNY-Hunter College—Science and Health Professions Building
FINAL ENVIRONMENTAL IMPACT STATEMENT (FEIS)**

Project Location: Community District 8
Borough of Manhattan

CEQR No. 13DME003M

Type of Action: Type I

ULURP Nos. 130214 ZMM, N130215 ZRM,
130216 ZSM, 130217 ZSM,
130218 ZSM, 130219 PPM

Lead Agency: Office of the Deputy Mayor for Economic Development

Lead Agency Contact: Robert R. Kulikowski, Ph.D.

Project Applicants: Memorial Hospital for Cancer and Allied Diseases
The City University of New York

Preparers: AKRF, Inc.
440 Park Avenue South
New York, NY 10016

Acceptance Date: August 8, 2013

The FEIS is available for review on the website of the Mayor's Office of Environmental Coordination.

<http://www.nyc.gov/oec>

Table of Contents

Foreword	F-1
Executive Summary	S-1
1: Project Description	1-1
A. Introduction.....	1-1
B. Background.....	1-2
C. Project Purpose and Need.....	1-2
MSK.....	1-2
Hunter.....	1-3
D. Project Site.....	1-4
E. Project Design.....	1-4
Introduction.....	1-4
Site Plan and Circulation.....	1-4
MSK ACC.....	1-5
CUNY-Hunter Building.....	1-5
Overall Design Approach.....	1-5
F. Proposed Actions.....	1-6
City Actions.....	1-6
Other Agency Approvals.....	1-9
G. Project Population.....	1-9
MSK ACC.....	1-9
CUNY-Hunter Building.....	1-9
H. Analytical Framework.....	1-10
Environmental Review Process.....	1-10
Legislative Applicability.....	1-10
Process Overview.....	1-10
Coordination With Waterfront Revitalization Process.....	1-12
I. Framework for Environmental Analysis.....	1-13
Scope of Environmental Analysis.....	1-13
Analysis Year.....	1-13
Definition of Study Areas.....	1-13
Defining Baseline Conditions.....	1-13
Defining the Action for Environmental Analysis.....	1-14
Mitigation.....	1-14
Alternatives.....	1-15
2: Land Use, Zoning, and Public Policy	2-1
A. Introduction.....	2-1
Principal Conclusions.....	2-2

B. Methodology.....	2-3
C. Existing Conditions	2-3
Land Use.....	2-3
Zoning.....	2-5
Public Policy.....	2-6
D. The Future Without the Proposed Project	2-8
Land Use.....	2-8
Zoning and Public Policy.....	2-9
E. Probable Impacts of the Proposed Project	2-9
Land Use.....	2-9
Zoning.....	2-10
Public Policy.....	2-13
Conclusions	2-25
3: Open Space	3-1
A. Introduction	3-1
Principal Conclusions	3-1
B. Methodology.....	3-2
Study Area	3-2
Study Area Population.....	3-3
Inventory of Open Space Resources.....	3-3
Adequacy of Open Space Resources	3-4
C. Existing Conditions	3-4
Study Area Non-Residential Population.....	3-4
Study Area Open Spaces	3-5
Adequacy of Open Space Resources	3-5
D. The Future Without the Proposed Project	3-7
Study Area Population.....	3-7
Study Area Open Spaces	3-7
Adequacy of Open Space Resources	3-7
E. Probable Impacts of the Proposed Project	3-8
Study Area Population.....	3-8
Open Space Resources.....	3-8
Adequacy of Open Space Resources	3-9
4: Shadows	4-1
A. Introduction	4-1
Principal Conclusions	4-1
B. Definitions and Methodology.....	4-1
Definitions	4-2
Methodology.....	4-2
C. Preliminary Screening Assessment	4-3
Tier 1 Screening Assessment.....	4-3
Tier 2 Screening Assessment.....	4-4
Tier 3 Screening Assessment.....	4-5
D. Detailed Shadow Analysis.....	4-6
March 21/September 21 (Figures 4-7 to 4-9)	4-8
May 6/August 6 (Figures 4-10 to 4-13).....	4-8

June 21 (Figures 4-14 to 4-19)	4-8
December 21 (4-20 to 4-25)	4-9
E. Conclusions	4-9
One East River Place Plaza	4-9
John Jay Park.....	4-10
East River Esplanade.....	4-10
Roosevelt Island’s Western Promenade, Octagon Park, and Manhattan Park	4-11
Church of the Epiphany Windows	4-11
East River	4-11
5: Historic and Cultural Resources	5-1
A. Introduction	5-1
Principal Conclusions.....	5-2
B. Existing Conditions	5-2
Project Site	5-2
Study Area.....	5-2
C. The Future Without the Proposed Project	5-3
Project Site	5-3
Study Area.....	5-3
D. Probable Impacts of the Proposed Project.....	5-4
Project Site	5-4
Study Area.....	5-4
6: Urban Design and Visual Resources	6-1
A. Introduction	6-1
Principal Conclusions.....	6-1
B. Preliminary Assessment	6-2
C. Existing Conditions	6-2
Project Site	6-2
Study Area.....	6-3
D. The Future Without the Proposed Project	6-5
Project Site	6-5
Study Area.....	6-5
E. Probable Impacts of the Proposed Project.....	6-6
Project Site	6-6
Study Area.....	6-7
7: Hazardous Materials	7-1
A. Introduction	7-1
Principal Conclusions.....	7-1
B. Existing Conditions	7-2
Topography and Subsurface Conditions	7-2
Phase I ESA Findings.....	7-2
Management of Laboratories and Chemical, Biological, and Radiological Materials.....	7-5
C. The Future Without the Proposed Project	7-10
D. Probable Impacts of the Proposed Project.....	7-10

8: Water and Sewer Infrastructure	8-1
A. Introduction	8-1
Principal Conclusions	8-1
B. Methodology.....	8-2
C. Existing Conditions	8-2
Water Supply	8-2
Sewer System	8-3
D. The Future Without the Proposed Project	8-4
E. Probable Impacts of the Proposed Project	8-4
Water Supply Demand.....	8-4
Sewer System and WWTP Treatment Capacity Demand.....	8-5
9: Transportation	9-1
A. Introduction	9-1
Principal Conclusions	9-1
B. Preliminary Analysis Methodology and Screening Assessment	9-4
Level 1 Screening Assessment	9-5
Level 2 Screening Assessment	9-10
C. Detailed Traffic Analysis.....	9-14
Methodology and Impact Criteria.....	9-14
2012 Existing Conditions	9-16
Future Without the Proposed Project (2019 No Build Condition)	9-19
Probable Impacts of the Proposed Project (2019 Build Condition).....	9-22
D. Detailed Transit Analysis	9-26
Subway Line-Haul Analysis	9-27
Subway Station Analysis	9-28
Bus Line-Haul Analysis.....	9-34
E. Detailed Pedestrian Analysis	9-36
Methodology and Impact Criteria.....	9-37
2012 Existing Conditions	9-39
Future Without the Proposed Project (2019 No Build Condition)	9-40
Probable Impacts of the Proposed Project (2019 Build Condition).....	9-41
F. Vehicular and Pedestrian Safety Evaluation.....	9-42
Methodology.....	9-42
Accident Data	9-43
G. Parking Conditions Assessment	9-45
Methodology.....	9-45
2012 Existing Conditions	9-46
Future Without the Proposed Project (2019 No Build Condition)	9-47
Probable Impacts of the Proposed Project (2019 Build Condition).....	9-48
H. Detailed Analysis Results Tables	9-50
10: Air Quality	10-1
A. Introduction	10-1
Principal Conclusions	10-2
B. Pollutants for Analysis.....	10-2
Carbon Monoxide	10-2
Nitrogen Oxides, VOCs, and Ozone.....	10-3

Lead.....	10-3
Respirable Particulate Matter—PM ₁₀ and PM _{2.5}	10-3
Sulfur Dioxide.....	10-4
Noncriteria Pollutants.....	10-4
C. Air Quality Regulations, Standards, and Benchmarks.....	10-5
National and State Air Quality Standards.....	10-5
NAAQS Attainment Status and State Implementation Plans.....	10-7
Determining the Significance of Air Quality Impacts.....	10-8
D. Methodology for Predicting Pollutant Concentrations.....	10-9
Mobile Sources.....	10-9
Stationary Sources.....	10-14
E. Existing Conditions.....	10-23
Modeled CO Concentrations for Existing Traffic Conditions.....	10-24
F. The Future Without the Proposed Project.....	10-24
Mobile Sources.....	10-24
Stationary Sources.....	10-25
G. Probable Impacts of the Proposed Project.....	10-25
Mobile Sources.....	10-25
Stationary Sources.....	10-27
11: Greenhouse Gas Emissions and Climate Change.....	11-1
A. Introduction.....	11-1
Principal Conclusions.....	11-1
B. GHG Emissions.....	11-2
Pollutants of Concern.....	11-2
Policy, Regulations, Standards, and Benchmarks for Reducing GHG Emissions.....	11-3
Methodology.....	11-5
Projected GHG Emissions from the Proposed Project.....	11-7
Elements of the Proposed Project That Would Reduce GHG Emissions.....	11-9
Conclusion.....	11-12
C. Adaptation to Climate Change.....	11-12
Development of Policy to Improve Climate Change Resilience.....	11-13
Resilience of the Proposed Project to Climate Change.....	11-16
12: Noise.....	12-1
A. Introduction.....	12-1
Principal Conclusions.....	12-1
B. Acoustical Fundamentals.....	12-1
“A”-Weighted Sound Level (dBA).....	12-2
Sound Level Descriptors.....	12-2
C. Noise Standards and Criteria.....	12-3
New York CEQR Noise Criteria.....	12-3
D. Impact Definition.....	12-4
E. Existing Noise Levels.....	12-4
Equipment Used During Noise Monitoring.....	12-4
F. Noise Prediction Methodology.....	12-5
General Methodology.....	12-5
Analysis Procedure.....	12-7

G. The Future Without the Proposed Project	12-7
H. Probable Impacts of the Proposed Project	12-8
I. Noise Attenuation Measures.....	12-9
J. Noise Levels At the Proposed Open Space Areas	12-10
K. Mechanical Equipment	12-11
13: Public Health	13-1
A. Introduction	13-1
Principal Conclusions	13-1
B. Public Health Assessment—Hazardous Materials	13-1
C. Public Health Assessment—Noise	13-2
14: Neighborhood Character.....	14-1
A. Introduction	14-1
Principal Conclusions	14-1
B. Methodology.....	14-2
Neighborhood Character Components.....	14-2
Study Area	14-3
Impact Assessment	14-3
C. Preliminary Assessment	14-3
Defining Features.....	14-3
Potential to Affect the Defining Features of the Neighborhood	14-4
15: Construction	15-1
A. Introduction	15-1
Principal Conclusions	15-2
B. Governmental Coordination and Oversight.....	15-8
C. Construction Phasing and Schedule	15-9
D. Construction Description.....	15-10
Overview	15-10
General Construction Practices.....	15-10
General Construction Tasks.....	15-11
E. Number of Construction Workers and Material Deliveries.....	15-14
F. The Future Without the Proposed Project	15-15
G. Environmental Effects of Project Construction Activities	15-15
Transportation.....	15-15
Air Quality	15-24
Noise and Vibration.....	15-27
Other Technical Areas	15-40
16: Alternatives.....	16-1
A. Introduction	16-1
Principal Conclusions	16-1
B. No Action Alternative	16-2
Description of the No Action Alternative.....	16-2
Land Use, Zoning, and Public Policy	16-2
Open Space	16-3
Shadows.....	16-3

Historic and Cultural Resources.....	16-3
Urban Design and Visual Resources.....	16-4
Hazardous Materials.....	16-4
Water and Sewer Infrastructure.....	16-4
Transportation.....	16-5
Air Quality.....	16-7
Greenhouse Gas Emissions.....	16-7
Noise.....	16-8
Public Health.....	16-8
Neighborhood Character.....	16-8
Construction.....	16-8
C. No Unmitigated Impact Alternative.....	16-11
Open Space.....	16-11
Transportation.....	16-11
17: Mitigation.....	17-1
A. Introduction.....	17-1
Principal Conclusions.....	17-1
B. Transportation.....	17-2
Traffic.....	17-2
Effects of Traffic Mitigations on Pedestrian Operations.....	17-9
C. Construction.....	17-9
Transportation.....	17-9
18: Unavoidable Adverse Impacts.....	18-1
A. Introduction.....	18-1
B. Open Space.....	18-1
C. Transportation.....	18-2
Traffic.....	18-2
D. Construction.....	18-2
Transportation.....	18-2
19: Growth-Inducing Aspects of the Proposed Actions.....	19-1
20: Irreversible and Irretrievable Commitment of Resources.....	20-1
21: Response to Comments.....	21-1
A. Introduction.....	21-1
B. List of Organizations and Individuals Who Commented on the Draft Generic Environmental Impact Statement.....	21-1
Elected Officials.....	21-1
Community Boards.....	21-1
Interested Individuals and Organizations.....	21-1
C. Comments and Responses.....	21-2
Project Description.....	21-2
Land Use, Zoning, and Public Policy.....	21-7
Open Space.....	21-9
Hazardous Materials.....	21-12

MSK/CUNY-Hunter Project at 74th Street

Transportation.....21-14
Neighborhood Character.....21-17
Alternatives.....21-19
Mitigation21-20
Comments Not Directly Related to the DEIS—Process.....21-21

Appendices

- Appendix A** Proposed Text Amendment
- Appendix B** Smart Growth Impact Statement and WRP Coastal Assessment Forms
- Appendix C** Historic and Cultural Resources Agency Correspondence
- Appendix D** Noise
- Appendix E** Construction
- Appendix F** Comments on DEIS

List of Tables

2-1	Zoning Districts in the Study Area	2-5
3-1	Existing Open Space Resources Within the Non-Residential Study Area	3-5
3-2	Existing Conditions: Adequacy of Open Space Resources	3-6
3-3	The Future Without the Proposed Project: Adequacy of Open Space Resources.....	3-6
3-4	The Future With the Proposed Project: Adequacy of Open Space Resources.....	3-7
3-5	The Future With the Proposed Project: Open Space Ratios Summary	3-7
4-1	Sunlight-Sensitive Resources.....	4-4
8-1	Existing Surface Coverage.....	8-4
8-2	The Future With the Proposed Project: Water Consumption	8-5
8-3	Proposed Surface Coverage	8-6
8-4	DEP Flow Volume Matrix: Existing and Build Volume Comparison.....	8-6
9-1	Summary of Significant Adverse Traffic Impacts	9-3
9-2	MSK ACC Population	9-6
9-3	CUNY-Hunter Building Population	9-6
9-4	Travel Demand Assumptions.....	9-7
9-5	Trip Generation Summary	9-9
9-6	Pedestrian Study Locations.....	9-15
9-7	LOS Criteria for Signalized Intersections.....	9-16
9-8	Existing Traffic Level of Service Summary	9-18
9-9	Planned Projects Within or Near the Study Area By 2019	9-20
9-10	Traffic Level of Service Summary Comparison: 2012 Existing vs. 2019 No Build Conditions.....	9-21
9-11	Traffic Level of Service Summary Comparison: 2019 No Build vs. 2019 Build Conditions.....	9-24
9-12	2019 No Build Condition: AM Peak Hour Subway Line Haul	9-28
9-13	2019 Build Condition: AM Peak Hour Subway Line Haul	9-28
9-14	LOS Criteria for Non-Elevator Subway Station Elements	9-29
9-15	2019 No Build Condition: Subway Escalator Analysis	9-31

MSK/CUNY-Hunter Project at 74th Street

9-16 2019 No Build Condition: AM Peak Hour Subway Elevator Analysis9-31

9-17 2019 No Build Condition: Subway Control Area Analysis9-32

9-18 2019 Build Condition: Subway Escalator Analysis9-33

9-19 2019 Build Condition: AM Peak Hour Subway Elevator Analysis9-33

9-20 2019 Build Condition: Subway Control Area Analysis9-34

9-21 NYCT Local Bus Routes Serving the Study Area9-35

9-22 2012 Existing Conditions: Bus Line-Haul Analysis9-35

9-23 2019 No Build Condition: Bus Line-Haul Analysis9-36

9-24 2019 Build Condition: Bus Line-Haul Analysis9-36

9-25 Level of Service Criteria for Pedestrian Elements9-38

9-26 Significant Impact Guidance for Sidewalks.....9-38

9-27 Significant Impact Guidance for Corners and Crosswalks.....9-39

9-28 2012 Existing Conditions Pedestrian Sidewalk Level of Service Summary.....9-40

9-29 2012 Existing Conditions Pedestrian Corner Level of Service Summary.....9-40

9-30 2012 Existing Conditions Pedestrian Crosswalk Level of Service Summary.....9-40

9-31 2019 No Build Condition Pedestrian Sidewalk Level of Service Summary.....9-41

9-32 2019 No Build Condition Pedestrian Corner Level of Service Summary.....9-41

9-33 2019 No Build Condition Pedestrian Crosswalk Level of Service Summary.....9-41

9-34 2019 Build Condition Pedestrian Sidewalk Level of Service Summary.....9-42

9-35 2019 Build Condition Pedestrian Corner Level of Service Summary9-42

9-36 2019 Build Condition Pedestrian Crosswalk Level of Service Summary.....9-42

9-37 Accident Summary9-43

9-38 Vehicle and Pedestrian Accident Details9-44

9-39 On-Street Parking Regulations.....9-46

9-40 2012 Existing Off-Street Parking - ¼-Mile Weekday Utilization.....9-47

9-41 2012 Existing and 2019 No Build Parking Supply and Utilization.....9-48

9-42 Proposed Project Incremental Parking Demand.....9-49

9-43 2019 No Build and Build Parking Supply and Utilization.....9-49

9-44 2012 Existing Conditions Level of Service Analysis Signalized Intersections.....9-50

9-45 2012 Existing and 2019 No Build Conditions Level of Service Analysis Signalized Intersections9-52

9-46 2019 No Build and Build Conditions Level of Service Analysis Signalized Intersections...9-54

9-47 2012 Existing Conditions Sidewalk Analysis9-56

9-48	2012 Existing Conditions Corner Analysis.....	9-57
9-49	2012 Existing Conditions Crosswalk Analysis.....	9-58
9-50	2019 No Build Condition Sidewalk Analysis.....	9-59
9-51	2019 No Build Condition Corner Analysis.....	9-60
9-52	2019 No Build Condition Crosswalk Analysis.....	9-61
9-53	2019 Build Condition Sidewalk Analysis.....	9-62
9-54	2019 Build Condition Corner Analysis.....	9-63
9-55	2019 Build Condition Crosswalk Analysis.....	9-64
10-1	National Ambient Air Quality Standards (NAAQS)	10-6
10-2	Maximum Background Pollutant Concentrations for Mobile Source Sites.....	10-13
10-3	Emission Rates and Stack Parameters	10-16
10-4	Maximum Background Pollutant Concentrations for Stationary Source Analysis....	10-17
10-5	Expected Hazardous Materials in the Proposed Laboratories.....	10-19
10-6	Chemicals Selected for Worst-Case Spill Analysis	10-20
10-7	Emission Rates and Stack Parameters	10-22
10-8	Representative Monitored Ambient Air Quality Data	10-23
10-9	Modeled Existing 8-Hour Average CO Concentrations (2012).....	10-24
10-10	Maximum Predicted Future (2019) 8-Hour Average Carbon Monoxide No Build Concentrations	10-24
10-11	No Build Condition Maximum Predicted 24-Hour Average PM ₁₀ Concentrations (µg/m ³)	10-24
10-12	Maximum Predicted 2019 CO Concentrations	10-25
10-13	Maximum Predicted 24-Hour Average PM ₁₀ Concentrations (µg/m ³)	10-26
10-14	2019 Maximum Predicted 24-Hour Average PM _{2.5} Concentration	10-26
10-15	2019 Maximum Predicted Annual Average PM _{2.5} Concentration	10-26
10-16	Future (2019) Maximum Modeled Pollutant Concentration (in µg/m ³)	10-27
10-17	Future (2019) Maximum Predicted PM _{2.5} Concentrations (in µg/m ³)	10-28
10-18	Fume Hood Recirculation Analysis Maximum Predicted Concentrations (ppm).....	10-29
10-19	Maximum Predicted Concentrations (ppm).....	10-29
10-20	Maximum Modeled Pollutant Concentrations from NYPH and Con Edison Steam Plants on the Proposed Project (in µg/m ³)	10-30
11-1	Global Warming Potential (GWP) for Major GHGs	11-3
11-2	Annual Vehicle Miles Traveled (Miles Per Year)	11-7
11-3	Building Operational Emissions—RWCDs	11-8

MSK/CUNY-Hunter Project at 74th Street

11-4	Mobile Source Emissions (Metric Tons CO ₂ e).....	11-8
11-5	Summary of Annual GHG Emissions 2015 RWCDs (Metric Tons CO ₂ e)	11-9
12-1	Common Noise Levels	12-2
12-2	Noise Exposure Guidelines for Use in City Environmental Impact Review1	12-3
12-3	Required Attenuation Values to Achieve Acceptable Interior Noise Levels.....	12-4
12-4	Existing Noise Levels (in dBA)	12-5
12-5	2019 Future Noise Levels Without the Proposed Project (in dBA)	12-8
12-6	2019 Future Noise Levels With the Proposed Project (in dBA)	12-8
12-7	MSK/CUNY-Hunter CEQR Attenuation Requirements.....	12-9
15-1	Construction Oversight in New York City.....	15-8
15-2	Conceptual Construction Schedule	15-9
15-3	Average Number of Daily Workers and Trucks By Quarter.....	15-14
15-4	Build Construction Trip Generation.....	15-17
15-5	2016 Build Peak Construction Vehicle Trip Projections	15-19
15-6	No Build, Build, and Mitigated Conditions Construction AM Peak Hour Traffic Level of Service.....	15-21
15-7	No Build, Build, and Mitigated Conditions Construction PM Peak Hour Traffic Level of Service.....	15-21
15-8	Typical Construction Equipment Noise Emission Levels (dBA).....	15-32
15-9	Noise Receptor Locations	15-34
15-10	Locations Where Noise Increases Exceed CEQR Criteria for Two or More Consecutive Years	15-35
17-1	Summary of Significant Adverse Traffic Impacts	17-1
17-2	Recommended Mitigation Measures.....	17-3
17-3	2019 No Build, Build, and Mitigation Conditions Level of Service Analysis Weekday AM Peak Hour	17-4
17-4	2019 No Build, Build, and Mitigation Conditions Level of Service Analysis Weekday Midday Peak Hour	17-5
17-5	2019 No Build, Build, and Mitigation Conditions Level of Service Analysis Weekday PM Peak Hour	17-6

List of Figures

	<i>following page</i>
S-1 Project Location	S-2
S-2 Project Site and Surrounding Blocks	S-4
S-3 Project Site Photographs	S-4
S-4 Ground Floor Plan	S-4
S-5 Perspective View	S-4
S-6 Existing Zoning.....	S-6
S-7 Proposed Zoning.....	S-6
S-8 Signage - North Elevation.....	S-8
S-9 Signage - East and West Elevations.....	S-8
S-10 Signage - Wayfinding Signage	S-8
1-1 Project Location.....	1-2
1-2 Project Site and Surrounding Blocks	1-4
1-3 Project Site Photographs	1-4
1-4 Ground Floor Plan	1-6
1-5 Perspective View	1-6
1-6 Existing Zoning.....	1-6
1-7 Proposed Zoning.....	1-6
1-8 Signage - North Elevation.....	1-8
1-9 Signage - East and West Elevations.....	1-8
1-10 Signage - Wayfinding Signage	1-8
2-1 Existing Land Use.....	2-4
2-2 Existing Zoning.....	2-6
2-3 Coastal Zone Boundary	2-8
3-1 Open Space Study Area • Census Tracts	3-4
3-2 Open Space Study Area • Resources	3-6
3-3 Andrew Haswell Green Park	3-10
4-1 Tier 1 and Tier 2 Assessment.....	4-4

MSK/CUNY-Hunter Project at 74th Street

4-2	Tier 3 Assessment - March 21/September 21	4-6
4-3	Tier 3 Assessment - May 6/August 6	4-6
4-4	Tier 3 Assessment - June 21	4-6
4-5	Tier 3 Assessment - December 21.....	4-6
4-6	3D Computer Model for Detailed Analysis View Southwest	4-6
4-7	March 21/September 21 - 2:20 PM.....	4-8
4-8	March 21/September 21 - 3:20 PM.....	4-8
4-9	March 21/September 21 - 4:20 PM.....	4-8
4-10	May 6/August 6 - 2:10 PM.....	4-8
4-11	May 6/August 6 - 3:10 PM.....	4-8
4-12	May 6/August 6 - 4:10 PM.....	4-8
4-13	May 6/August 6 - 5:10 PM.....	4-8
4-14	June 21 - 6:00 AM.....	4-8
4-15	June 21 - 2:00 PM	4-8
4-16	June 21 - 3:00 PM	4-8
4-17	June 21 - 4:00 PM	4-8
4-18	June 21 - 5:00 PM	4-8
4-19	June 21 - 6:00 PM	4-8
4-20	December 21 - 12:20 PM	4-8
4-21	December 21 - 12:50 PM	4-8
4-22	December 21 - 1:20 PM	4-8
4-23	December 21 - 1:50 PM	4-8
4-24	December 21 - 2:20 PM	4-8
4-25	December 21 - 2:50 PM	4-8
4-26	John Jay Park and East River Esplanade at East 74th Street.....	4-10
5-1	Architectural Resources	5-2
5-2	Project Site	5-2
5-3	Known Architectural Resources.....	5-2
5-4	Potential Architectural Resources	5-4
6-1	Urban Design and Visual Resources Study Area Map and Key to Photographs	6-2
6-2	Aerial View of Study Area.....	6-2
6-3	Urban Design and Visual Resources Photographs	6-4
6-4	Urban Design and Visual Resources Photographs	6-4

6-5	Urban Design and Visual Resources Photographs.....	6-4
6-6	Urban Design and Visual Resources Photographs.....	6-4
6-7	Urban Design and Visual Resources Photographs.....	6-4
6-8	Urban Design and Visual Resources Photographs.....	6-4
6-9	Urban Design and Visual Resources Photograph.....	6-6
6-10	View from Roosevelt Island.....	6-6
6-11	View of the Main Entrance on East 74th Street.....	6-6
6-12	Context Elevation from the East River.....	6-8
6-13	View East from East 74th Street and York Avenue.....	6-8
6-14	View Northeast from Midblock of East 73rd Street between York Avenue and FDR Drive.....	6-8
6-15	View Southwest from East River Esplanade adjacent to FDR Drive.....	6-8
9-1	Proposed Project Generated Vehicle Trips Weekday AM Peak Hour.....	9-12
9-2	Proposed Project Generated Vehicle Trips Weekday Midday Peak Hour.....	9-12
9-3	Proposed Project Generated Vehicle Trips Weekday PM Peak Hour.....	9-12
9-4	Traffic Analysis Locations.....	9-12
9-5	Transit.....	9-14
9-6	Project Generated Pedestrian Volumes Weekday AM Peak Hour.....	9-14
9-7	Project Generated Pedestrian Volumes Weekday Midday Peak Hour.....	9-14
9-8	Project Generated Pedestrian Volumes Weekday PM Peak Hour.....	9-14
9-9	Pedestrian Analysis Locations.....	9-14
9-10	2012 Existing Traffic Volumes Weekday AM Peak Hour.....	9-18
9-11	2012 Existing Traffic Volumes Weekday Midday Peak Hour.....	9-18
9-12	2012 Existing Traffic Volumes Weekday PM Peak Hour.....	9-18
9-13	Future Development Projects in the No Build Condition.....	9-20
9-14	2019 No Build Traffic Volumes Weekday AM Peak Hour.....	9-20
9-15	2019 No Build Traffic Volumes Weekday Midday Peak Hour.....	9-20
9-16	2019 No Build Traffic Volumes Weekday PM Peak Hour.....	9-20
9-17	2019 Build Traffic Volumes Weekday AM Peak Hour.....	9-24
9-18	2019 Build Traffic Volumes Weekday Midday Peak Hour.....	9-24
9-19	2019 Build Traffic Volumes Weekday PM Peak Hour.....	9-24
9-20	Existing Pedestrian Volumes Weekday AM Peak Hour.....	9-40
9-21	Existing Pedestrian Volumes Weekday Midday Peak Hour.....	9-40

MSK/CUNY-Hunter Project at 74th Street

9-22 Existing Pedestrian Volumes Weekday PM Peak Hour..... 9-40

9-23 2019 No Build Pedestrian Volumes Weekday AM Peak Hour..... 9-40

9-24 2019 No Build Pedestrian Volumes Weekday Midday Peak Hour..... 9-40

9-25 2019 No Build Pedestrian Volumes Weekday PM Peak Hour 9-40

9-26 2019 Build Pedestrian Volumes Weekday AM Peak Hour..... 9-42

9-27 2019 Build Pedestrian Volumes Weekday Midday Peak Hour..... 9-42

9-28 2019 Build Pedestrian Volumes Weekday PM Peak Hour 9-42

9-29 On-Street Parking Regulations..... 9-46

9-30 Off-Street Parking Facilities..... 9-46

12-1 Noise Receptor Locations 12-4

15-1 Conceptual Construction Schedule 15-10

15-2 Peak Construction Generated Traffic Volumes Weekday (6AM to 7AM)..... 15-20

15-3 Peak Construction Generated Traffic Volumes Weekday (3PM to 4PM) 15-20

15-4 2017 No Build Traffic Volumes Weekday (6AM to 7AM)..... 15-20

15-5 2017 No Build Traffic Volumes Weekday (3PM to 4PM) 15-20

15-6 2017 Construction Traffic Volumes Weekday (6AM to 7AM) 15-20

15-7 2017 Construction Traffic Volumes Weekday (3PM to 4PM) 15-20

15-8 Existing Noise Receptors 15-34

*