

1 RCNY §3616-03

CHAPTER 3600

Appendices

§3616-03 National Fire Protection Association (“NFPA”) 14 amendment Relating to Hydrostatic Tests.

Pursuant to Section 28-103.19 of the New York City Administrative Code, NFPA 14, as modified by Section BC Q105 of the New York City Building Code, is hereby amended by adding a new section 11.4.1 to read as follows:

11.4.1* Delete and replace with the following:

General. All new systems, including yard piping and fire department connections, shall be tested hydrostatically at not less than 20.7 bar (300 psi) of pressure for one (1) hour. For systems where the maximum system pressure exceeds 17.2 bar (250 psi), such systems shall be tested for one (1) hour at a minimum pressure of 3.5 bar (50 psi) above the maximum expected system pressure.