NYC BUILDINGS

NYC Department of Buildings
280 Broadway, New York, NY 10007
Patricia Lancaster, FAIA, Commissioner
(212) 566-5000, TTY: (212) 566-4769

Report of Materials and Equipment Acceptance Division

Pursuant to Administrative Code Section 27-131, the following equipment or material has been found acceptable for use subject to the terms and conditions contained herein.

MEA 429-05-E

Manufacturer:	Hobart Bakery Systems/Baxter Mfg., 19220 SR 162 East, Orting, WA 98360
Trade Name(s):	Hobart/Baxter
Product:	Commercial electric proofer/retarder
Pertinent Code Section(s):	27-787, 27-792
Prescribed Test(s):	RS 14-6 (UL 197)
Laboratory:	Underwriters Laboratories, Inc.
Test Report(s):	UL File E188526 dated August 27, 2002.

Description: These units are electrically-operated proofing cabinets intended to be permanently connected to the electrical supply source and to be connected to a water source. The units are comprised of heaters with sheathed elements, contactors, regulating and limiting controls, and a stainless steel and aluminum enclosure. The sheathed elements are not subdivided above 48 amps due to a suitable enclosure. The maximum wait density of the ovens tested is 74 watts/cu. ft.

Models Approved

HP, HR, HPR and **BXP**
BXR, BXPR

Terms and Conditions: The above electric commercial oven units are accepted under the following conditions:

1. Units shall be installed in accordance with manufacturer's instructions and New York City Electrical Code requirements.

2. Approval of all electrical equipment apparatus, materials and devices shall be obtained from the Department's Electrical Advisory Board before installation.

3. Units shall be used in compliance with the Energy Conservation Construction Code of New York State.

4. All shipments and deliveries of such equipment shall be provided with a metal tag, suitably placed, certifying that the equipment shipped or delivered is equivalent to that tested and acceptable for use, as provided in Section 27-131 of the New York City Building Code.

Final Acceptance _1/30/07_

Examined By _[signature]_