



THE CITY OF NEW YORK

Department of Transportation








STANDARD DETAILS OF CONSTRUCTION




JULY 2010


LIST OF DRAWINGS

1. H-1003A PEDESTRIAN CROSSWALKS - MALL TYPE A
2. H-1003B PEDESTRIAN CROSSWALKS - MALL TYPE B
3. H-1004 TYPICAL TEMPORARY PEDESTRIAN PASSAGEWAY IN ROADWAY AREA DURING CONSTRUCTION
4. H-1005 BUS STOP IN NEW ROADWAY
5. H-1005A BUS STOP IN EXISTING ROADWAY
6. H-1009 CHAIN LINK FENCE DETAILS TENSION WIRES TOP AND / OR BOTTOM
7. H-1010 STEEL FACED CONCRETE CURB STEEL FACING TYPE D
8. H-1011 SIDEWALK PEDESTRIAN RAMPS
9. H-1012 TIMBER CURB
10. H-1013 ILLUMINATED TIMBER BARRICADE
11. H-1014 TEMPORARY PEDESTRIAN STEEL BARRICADE
12. H-1015 STEEL FACED DROP CURB DRIVEWAYS
13. H-1017 BAR PICKET FENCE (4'-0" HIGH)
14. H-1021 CHAIN LINK FENCE - DETAILS (SH. 1 TO 4)
15. H-1022 BEAM BARRIER FOR DEAD END STREETS
16. H-1029 CRITERIA FOR DESIGN & CONSTRUCTION OF CANOPIES
17. H-1030 STANDARD RECESS IN VAULT CONSTRUCTION TO PROVIDE FOR STREET WIDENING, RECEIVING BASINS, INLETS, AND 12'-0" CORNER RADIUS
18. H-1031 TYPICAL PAVEMENT KEY
19. H-1032 TYPICAL NEW PAYMENT IN UNPAVED WING AREA
20. H-1033 TYPICAL RESURFACING ON ASPHALT PAVEMENT &/OR WEARING COURSE (LESS THAN FULL WIDTH)
21. H-1034 TYPICAL CONSTRUCTION JOINTS FOR CONCRETE BASE FOR PAVEMENT
22. H-1035 REINFORCED CONCRETE CURB & DROP CURB
23. H-1036 CONCRETE POURED-IN-PLACE MALL CURB
24. H-1037 UNDER SIDEWALK DRAIN
25. H-1038 TYPE III BREAKAWAY BARRICADE
26. H-1040 TRANSVERSE CONSTRUCTION JOINTS FOR CONCRETE BASE
27. H-1041 CONCRETE COLLAR AROUND STEAM MANHOLE AND STEAM VALVE
28. H-1042A STANDARD TRENCH OR HOLE RESTORATION FOR STREETS PROTECTED BY NYC ADMINISTRATIVE CODE § 19-144 
29. H-1042B CONCRETE PAVEMENT RESTORATION
30. H-1042C ROADWAY RESTORATION FOR NEWLY CONSTRUCTED ROADWAYS 
31. H-1042D STANDARD TRENCH OR HOLE RESTORATION FOR STREETS UNDER GUARANTEE BY NYC ADMINISTRATIVE CODE § 19-147 
32. H-1043 STEEL FACED CURB STEEL FACING TYPE D FOR STRUCTURES
33. H-1044 CONCRETE CURB
34. H-1045 CONCRETE SIDEWALK
35. H-1046 STREET TREE PLANTING DETAIL TYPE I
36. H-1046A PROTECTIVE TREE BARRIER
37. H-1047 TYPICAL CURB DETAIL AT EXISTING TREES
38. H-1049 PLASTIC BARREL
39. H-1050 REINFORCED CONCRETE PAVEMENT CONSTRUCTION DETAILS (SH. 1 TO 4)
40. H-1051 TEMPORARY WOODEN STEPS
41. H-1053 DETAILS FOR CONSTRUCTING AREAS OF ADJUSTMENT AND TRANSITION SECTIONS
42. H-1054 LIMITS OF MEASUREMENT FOR PAYMENT OF TEMPORARY ASPHALT PAVEMENT
43. H-1055 PAVEMENT KEY TYPE A, B-1, B-2, C
44. H-1056 TYPICAL GRANITE CURB
45. H-1056A NY HISTORICAL GRANITE CURB
46. H-1057 TEMPORARY STORAGE AREA
47. MS-1000 NEW YORK CITY COMPARISON OF DATUM PLANES
48. MS-1001 SIDEWALK PAYMENT LIMITS
49. MS-1003 TYPICAL ROADWAY CROSS-SECTION/RESURFACING
50. MS-1004 CATCH BASIN ADJUSTMENT - TYPE 2
51. MS-1005 ADJUSTMENT AT CATCH BASINS




| | | | |
|-------------------------------------------------------------------------------------|-------------------------------------|---------|----------|
| | | | |
|  | ADDED DRAWING H-1042D | 3/15/16 | D. NG |
|  | REPLACED DRAWINGS H-1042A & H-1042C | 3/15/16 | D. NG |
| REVISION NO. | DESCRIPTION | DATE | APPROVED |




CHECKED BY: MZ
HWS-H1003A




SECTION C-C
NOT TO SCALE

| | | | |
|----------------------------------------------------------------------------------------------------------------------------------------------------------|--|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------|
|  | | <p>New York City Department of Transportation</p> | |
| <p>PEDESTRIAN CROSSWALKS-MALL TYPE-A</p> | | | |
| <p>Approved:</p>  Chief Engineer Department of Transportation | | <p>Approved:</p>  Associate Commissioner Infrastructure/Design Department of Design + Construction | |
| <p>Date Issued: 7/1/10</p> | | <p>Scale: None</p> | <p>Drawing # H-1003A</p> |




TOP VIEW - STEEL FACED CONC. CURB




TOP VIEW - CONCRETE CURB


DETAIL -A




ELEVATION
NOT TO SCALE




PLAN
NOT TO SCALE



SECTION 1-1
NOT TO SCALE



SECTION 2-2
NOT TO SCALE







SECTION 3-3
STEEL FACED CONCRETE HEADER
N.T.S.

CHECKED BY: MA

| REVISION NO. | DESCRIPTION | DATE | APPROVED |
|--------------|-------------|------|----------|
| | | | |
| | | | |
| | | | |

| | | | |
|-------------------------------------------------------------|--|-----------------------------------------------------------------------------------------------------|-------------------|
| NEW YORK CITY | | New York City Department of Transportation | |
| PEDESTRIAN CROSSWALKS-MALL TYPE-B | | | |
| Approved: Chief Engineer Department of Transportation | | Approved: Associate Commissioner Infrastructure/Design Department of Design + Construction | |
| Date Issued: <u>7/1/10</u> | | Scale: None | Drawing # H-1003B |



NOTES









1. ALL TIMBER SHALL BE DOUGLAS FIR GRADE NO 1.
2. ALL WORK SHALL CONFORM WITH NATIONAL DESIGN SPECIFICATIONS FOR STRESS GRADE LUMBER AND ITS FASTENINGS.
3. LIGHTING FIXTURES CAN BE BATTERY TYPE FLASHER WARNING LIGHT OR AS DIRECTED BY THE ENGINEER.
4. RAILS & POSTS ARE TO RECEIVE TWO (2) COATS OIL PAINT, ORANGE & WHITE COLORS, IN ACCORDANCE WITH THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES.
5. CONTRACTOR TO PROVIDE SHOP DRAWING CERTIFIED BY LICENSED PROFESSIONAL ENGINEER, CURRENTLY REGISTERED IN THE STATE OF NEW YORK, FOR APPROVAL.

CHECKED BY: MZ

HWS-H1004

| REVISION NO. | DESCRIPTION | DATE | APPROVED |
|--------------|-------------|------|----------|
| | | | |
| | | | |
| | | | |

| | | | |
|------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------------------------------|------------------|
| NEW YORK CITY | | New York City Department of Transportation | |
| TYPICAL TEMPORARY PEDESTRIAN PASSAGEWAY IN ROADWAY AREA DURING CONSTRUCTION | | | |
| Approved: Chief Engineer Department of Transportation | | Approved: Associate Commissioner Infrastructure/Design Department of Design + Construction | |
| Date Issued: <u>7/1/10</u> | | Scale: None | Drawing # H-1004 |







- NOTES:**
- BUS PADS ARE NOT REQUIRED, WHEN REINFORCED CONCRETE PAVEMENT IS PLACED IN THE ROADWAY.
 - EDGE OF THE BUS PAD AT INTERSECTIONS SHALL BE PARALLEL TO CROSSWALK MARKING LINES OR INTERSECTING BUILDING LINE OR AS DETERMINED BY ENGINEER.
 - DRAINAGE STRUCTURES AND MANHOLES SHALL BE TOTALLY WITHIN OR TOTALLY OUTSIDE THE BUS PAD.
 - LAPS IN WELDED WIRE FABRIC SHALL BE A MINIMUM OF 12 INCHES.
 - DIMENSIONS SHOWN ARE FOR DEPARTMENT OF ENVIRONMENTAL PROTECTION 27"Ø STANDARD SEWER MANHOLE. ADJUST TO ACCOMMODATE OTHER SIZE HARDWARE, AS APPROVED BY THE ENGINEER.
 - THE EXACT LOCATION OF THE HYDRANT SHALL BE DETERMINED IN THE FIELD BY THE ENGINEER.

CHECKED BY: MZ



| REVISION NO. | DESCRIPTION | DATE | APPROVED |
|--------------|-------------|------|----------|
| | | | |
| | | | |
| | | | |

| | |
|-----------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------|
| NEW YORK CITY New York City Department of Transportation | |
| BUS STOP IN NEW ROADWAY | |
| Approved: Chief Engineer Department of Transportation | Approved: Associate Commissioner Infrastructure/Design Department of Design + Construction |
| Date Issued: <u>7/1/10</u> | Scale: None Drawing # H-1005 |



- NOTES:**



1. EDGE OF THE BUS PAD AT INTERSECTIONS SHALL BE PARALLEL TO CROSSWALK MARKING LINES OR INTERSECTING BUILDING LINE OR AS DETERMINED BY ENGINEER.
2. DRAINAGE STRUCTURES AND MANHOLES SHALL BE TOTALLY WITHIN OR TOTALLY OUTSIDE THE BUS PAD.
3. LAPS IN WELDED WIRE FABRIC SHALL BE A MINIMUM OF 12 INCHES.
4. DIMENSIONS SHOWN ARE FOR DEPARTMENT OF ENVIRONMENTAL PROTECTION 27"Ø STANDARD SEWER MANHOLE. ADJUST TO ACCOMMODATE OTHER SIZE HARDWARE, AS APPROVED BY THE ENGINEER.




CHECKED BY:


HYV-S-H1005A

| | | | |
|--------------|-------------|------|----------|
| | | | |
| | | | |
| | | | |
| REVISION NO. | DESCRIPTION | DATE | APPROVED |


| | | | |
|------------------------------------------------------------------------------------------------------------------------------------------------------|--|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|
|  | | New York City Department of Transportation | |
| BUS STOP IN EXISTING ROADWAY | | | |
| Approved:  Chief Engineer Department of Transportation | | Approved:  Associate Commissioner Infrastructure/Design Department of Design + Construction | |
| Date Issued: <u>7/1/10</u> | | Scale: None Drawing # H-1005A | |




TYPICAL FENCE LOCATION




SECTION A-A
DETAIL OF POST EXTENSION AND TENSION
WIRE ATTACHMENT TO POST




DETAIL C
LINE POST EXTENSION




SECTION B-B
DETAIL OF TOP TWO WAY CLAMP
OF TENSION WIRE TO POST AND
TURNBUCKLES




SECTION C-C
DETAIL OF RIGID SPLICE INSTALLATION
OF NEW POST TO EXISTING POST BASE



DETAIL OF RIGHT OF WAY FENCING



Temporary Compression brace
(2" dia line post with proper clamps)
Use during fabric tensioning, remove
after fabric is properly tied to posts
To be used at all end, corner &
pull posts (typical)



FOOTING DETAIL


NOTES

1. The tension wire shall be secured at the top with a two-way clamp at each seventh post for 6'-0" high or at each fifth post for 8'-0" high fencing so that the max. untied span of tension wire does not exceed 36'-0" for 6'-0" high or 32'-0" for 8'-0" high fence. Whereas, if the total length of damaged fabric to be replaced is less than 16'-0", no tension wire shall be installed, but the damaged top rail shall be replaced with new top rail. New tension wires shall be installed only when damages to top or bottom rails have been incurred and replacement is necessary.
 2. Corner posts shall be used at sharp breaks in vertical grade and changes in horizontal alignment of 15° and over. Intermediate Pull Posts shall be installed along tangent fence runs and shall be spaced at intervals not exceeding 180'.
 3. All fabrication and installation details of this fencing are shown on the contract plans. Any proposed changes by the Contractor shall be submitted in writing, explaining the reason for such requested change and supplemented by clear shop drawings defining the Contractors proposal.
 4. Layout of chain link fence post locations shall be performed by the Contractor in accordance with the intent of the Contract Plans. All such layout shall be checked and approved by the Engineer prior to erection of fence.
 5. The fence shall be carefully aligned to a uniform grade by the Contractor. Before the posts are permanently affixed, the Engineer shall inspect the line and grade, order any necessary adjustments and approve the final alignment in that section of fencing.
 6. Materials: All new "Right-of-Way" fence to be no higher than six (6'-0") feet. All posts shall be standard weight galvanized steel pipe conforming to the requirements of A.S.T.M. designation A 120-6ST, except that the pipe shall be unthreaded and untested for water pressure. All new posts to be set-in-place with a concrete footing.
- Line Post Top: Industrial grade galvanized malleable flat casting for 2" Nominal Dia. Line Post.
- Gate, End, Corner & Pull Post Posts: Malleable flat arc terminal top galvanized casting inside fit for standard 2-1/2" Nominal Dia. Post.
- Tension Bars: 72" long 1/4" x 1/2" flat galvanized steel tension bars.
- Tension Bands: Heavy weight 1/8" x 1" galvanized steel tension bands for a 2-1/2" Nom. Dia., minimum wt. 42lbs. The carriage bolt to be supplied for each of those bands shall be gal. Steel 3/16" x 1-1/2" carriage bolt and nut.
- The Contractor shall supply to the Engineer, catalog cuts of all fittings and connections to be used in the contract for the Engineers approval. The above list of fittings and connections shall be deemed only a listing of typical parts to be used in construction of fence, all other fittings and connections required for a proper fence installation shall be used by the Contractor. These undesignated fittings and connections shall be good grade galvanized steel of a quality comparable or superior to these fittings and connections designated.
- Fence Fabric: shall be hot-dipped galvanized steel fabric with the zinc coating not less the 2g per sq. ft. or aluminum-coated steel fabric meeting the requirements of A.A.S.H.O. Specification W181 except that base metal shall have a nominal strength of 80,000 p.s.i. after weaving.
- The size of the mesh opening and nominal Dia. Of fabric wire shall be 2 inches and 0.148 inches respectively and shall be knuckled top and bottom.
7. When fences terminate at structures, the clear spaces between the fences and structure shall not exceed 4".
 8. Gore Treatment: 150'-0" of clear area from the point of gore will hereafter be maintained.
 9. For fence heights other than those shown refer to H-1021 for size of fence posts and size of members and fabrics. Omit top and bottom rails.


CHECKED BY: MA

HS-H1009


| | | | |
|---------------------------------------------------------------|-------------|-----------------------------------------------------------------------------------------------------|----------|
| | | New York City Department of Transportation | |
| CHAIN LINK FENCE DETAILS TENSION WIRES TOP AND / OR BOTTOM | | | |
| Approved: Chief Engineer Department of Transportation | | Approved: Associate Commissioner Infrastructure/Design Department of Design + Construction | |
| Date Issued: <u>7/1/10</u> | | Scale: None Drawing # H-1009 | |
| REVISION NO. | DESCRIPTION | DATE | APPROVED |




PLAN - CASE I, CASE III
N.T.S.



PLAN - CASE II
N.T.S.




DOME SECTION




DOME SPACING

DETECTABLE WARNING SURFACE DETAILS



ELEVATION B-B
N.T.S.



SECTION A-A
N.T.S.

NOTES

1. REFER TO H-1010 (LATEST REVISION) FOR STEEL FACED CURB-TYPE D.
2. ALL MATERIALS AND CONSTRUCTION METHODS USED SHALL CONFORM TO SECTIONS #4.08 / 4.09 / 4.13 / 4.13DE OF THE STANDARD SPECIFICATIONS, LATEST EDITION, AS AMENDED.
3. WHEN INSTALLING PEDESTRIAN RAMPS IN OTHER THAN PRE ENGINEERED CAPITAL RECONSTRUCTION PROJECTS, ALLOWANCE SHALL BE MADE FOR EXISTING CONDITIONS PROVIDED THAT THE SLOPE OF THE RAMP SHALL NOT EXCEED 1:12 AND THE ZERO INCH REVEAL IS OBTAINED. TO INSURE THAT SOUND ENGINEERING JUDGMENT IS USED IN MEETING EXISTING CONDITIONS, ANY AND ALL VARIATIONS FROM THE DETAILS OF CONSTRUCTION HEREIN SHOWN MUST HAVE THE APPROVAL OF BOTH THE ASSISTANT COMMISSIONER OF DESIGN AND THE ASSISTANT COMMISSIONER OF CONSTRUCTION.
4. CASE II PLAN SHALL BE USED ONLY WHERE EXPLICITLY DIRECTED BY THE ENGINEER AND APPROVED BY THE COMMISSIONER PRIOR TO DESIGN / INSTALLATION.
5. SURFACE OF ALL PEDESTRIAN RAMPS SHALL BE STABLE, FIRM AND SLIP RESISTANT. CONCRETE RAMP SURFACE SHALL HAVE A COARSE BROOM FINISH RUNNING PERPENDICULAR TO THE SLOPE, EXCLUSIVE OF THE DETECTABLE WARNING FIELDS.
6. LANDINGS BETWEEN THE PROPERTY LINES AND THE BACK EDGE OF RAMPS SHALL HAVE A MINIMUM CLEAR DIMENSION OF 5 FT. BY 5 FT. SQUARE; HOWEVER, WHERE CASE I RAMPS ARE USED THE MINIMUM CLEAR DIMENSION SHALL BE 4 FT. BY 4 FT. SQUARE. THE MAXIMUM CROSS SLOPE AT LANDINGS IS 1/4" PER FOOT IN ANY DIRECTION. LANDINGS MAY OVERLAP WITH ADJACENT LANDINGS OR A SINGLE LANDING MAY SERVE MULTIPLE CURB RAMPS.
7. ALL EXPOSED STEEL SURFACES SHALL BE GROUND SMOOTH.
8. ON FULL WIDTH SIDEWALKS, EXPANSION JOINTS TO BE PLACED AT BUILDING FACES, STRUCTURES AS WELL AS AT BACK FACE OF CURB.
9. ALL DIMENSIONS AND NOTES SHALL BE APPLICABLE TO GRANITE CURB INSTALLATIONS AND / OR CONCRETE CURB INSTALLATIONS.
10. THE FOLLOWING GUIDELINES SHALL BE APPLIED IN DETERMINING THE APPLICATIONS OF THE SPECIFIC CASES WHERE THE INTERIOR $\theta = 180^\circ - \theta_a$

| CASE I FOR CORNERS WITH | CASE II FOR CORNERS WITH | CASE III FOR CORNERS WITH |
|------------------------------------------------------|------------------------------------|---------------------------------------|
| R=12' INTERIOR $\theta \geq 90^\circ$ | R<12' INTERIOR θ ANY ANGLE | R>15' INTERIOR θ ANY ANGLE |
| R=13' INTERIOR θ BET. 83° & 93° | R=12' INTERIOR $\theta < 90^\circ$ | R=15' INTERIOR $\theta \geq 81^\circ$ |
| R=14' INTERIOR θ BET. 77° & 90° | R=13' INTERIOR $\theta < 83^\circ$ | R=14' INTERIOR $\theta \geq 90^\circ$ |
| R=15' INTERIOR θ BET. 72° & 81° | R=14' INTERIOR $\theta < 77^\circ$ | R=13' INTERIOR $\theta \geq 93^\circ$ |
| | R=15' INTERIOR $\theta < 72^\circ$ | |

11. THE DETAILS PROVIDED ARE NOT DRAWN TO SCALE, THE QUANTITY OF DOMES DEPICTED ON THE DETECTABLE WARNING FIELD (THE DOMES AND THE ENTIRE 2 FT. WIDE SURFACE) IS FOR ILLUSTRATION ONLY.
12. THE SIZE OF THE DETECTABLE WARNING FIELD SHALL BE 2 FT. IN THE DIRECTION OF TRAVEL AND SHALL EXTEND THE FULL WIDTH OF THE CURB RAMP AS SHOWN, EXCLUSIVE OF SIDE FLARES.
13. DETECTABLE WARNINGS SHALL BE LOCATED SO THAT THE EDGE OF THE WARNING FIELD NEAREST TO THE ROADWAY OR STREET SURFACE IS 0" TO 3" FROM THE BACK OF CURB, AS SHOWN.
14. DOME ALIGNMENT, DOMES SHALL BE ALIGNED ON A SQUARE GRID IN THE PREDOMINANT DIRECTION OF TRAVEL.
15. COLOR REQUIREMENT, THE DETECTABLE WARNING FIELD SHALL BE THE COLOR SPECIFIED IN THE CONTRACT DOCUMENTS OR SHALL VISUALLY CONTRAST WITH THE ADJOINING CURB RAMP, OR OTHER ADJACENT WALKWAY SURFACES WHERE THERE IS NO CURB RAMP. EITHER LIGHT-ON-DARK OR DARK-ON-LIGHT AS DEFINED IN THE AMERICANS WITH DISABILITIES ACCESSIBILITY GUIDELINES (ADAAG).
16. PAYMENT LINES FOR DETECTABLE WARNING UNITS ARE THE 2 FT. DIMENSION SHOWN IN THE DETAILS EXTENDING THE FULL WIDTH OF THE CURB RAMP.
17. WHEN STREET FURNITURE (LAMP POSTS, TRAFFIC SIGNAL POSTS, UTILITY POSTS, HYDRANTS, ETC.) INTERFERES WITH THE CONSTRUCTION OF A SIDE FLARE ADJACENT TO A NON-WALKING (GRASS) AREA, SAID SIDE FLARE SHALL BE REPLACED WITH A CONCRETE CURB, AS DIRECTED BY THE ENGINEER, PROVIDED THE INTERFERENCE CAN BE AVOIDED AND LEFT IN PLACE.
18. IN CASE OF INFEASIBILITY AND IN ORDER TO CLEAR INTERFERENCE WITH THE STREET FURNITURE (LAMPPOSTS, TRAFFIC SIGNAL POSTS, UTILITY POST, HYDRANTS, ETC.), UPON DOCUMENTATION AND APPROVAL BY THE ASSISTANT COMMISSIONER OF THE CONSTRUCTION DIVISION, THE WIDTH OF THE RAMP COULD BE REDUCED TO NO LESS THAN 3'-0" FEET.
19. PEDESTRIAN RAMPS SHALL BE INSTALLED PARALLEL TO THE CROSSWALKS WHERE FEASIBLE. HOWEVER, WHERE DUE TO OBSTRUCTIONS AND INTERFERENCE WITH THE STREET FURNITURE (LAMPPOST, TRAFFIC SIGNAL POSTS, HYDRANTS, ETC.) IT WOULD NOT BE FEASIBLE TO INSTALL THE RAMPS PARALLEL TO THE CROSSWALKS, UPON DOCUMENTATION AND AS ORDERED AND APPROVED BY THE ENGINEER THE RAMPS COULD BE REORIENTED TO CLEAR THE OBSTRUCTIONS.



New York City
Department of Transportation

SIDEWALK PEDESTRIAN RAMPS

Approved:

[Signature]
Chief Engineer
Department of Transportation

Approved:

[Signature]
Associate Commissioner
Infrastructure/Design
Department of Design + Construction

Date Issued:

7/1/10

Scale:

None


Drawing # H-1011

CHECKED BY:


M2

HVS-H1011


| REVISION NO. | DESCRIPTION | DATE | APPROVED |
|--------------|-------------|------|----------|
| | | | |
| | | | |
| | | | |




ELEVATION
N.T.S.



SECTION B-B
SCALE: 1" = 1'-0"



DETAIL "A"
N.T.S.



SECTION C-C
N.T.S.

GENERAL NOTES:


1. ALL TIMBER AND LUMBER TO BE DENSE STRUCTURAL GRADE DOUGLAS FIR OR LONGLEAF YELLOW PINE.
2. WHITE AND ORANGE EXTERIOR ENAMEL.
3. WHITE TO BE REFLECTORIZED.

CHECKED BY: MZ


BWS-H1012

| REVISION NO. | DESCRIPTION | DATE | APPROVED |
|--------------|-------------|------|----------|
| | | | |
| | | | |
| | | | |


| | | | |
|-------------------------------------------------------------|--|-----------------------------------------------------------------------------------------------------|------------------|
| NEW YORK CITY | | New York City Department of Transportation | |
| TIMBER CURB | | | |
| Approved: Chief Engineer Department of Transportation | | Approved: Associate Commissioner Infrastructure/Design Department of Design + Construction | |
| Date Issued: <u>7/1/10</u> | | Scale: None | Drawing # H-1012 |



ELEVATION
NOT TO SCALE



PLAN
NOT TO SCALE



SIDE VIEW
NOT TO SCALE


NOTES:

1. ALL TIMBER SHALL BE DOUGLAS FIR GRADE NO. 1 OR EQUAL.
2. ALL WORK SHALL CONFORM WITH NATIONAL DESIGN SPECIFICATIONS FOR STRESS GRADE LUMBER AND ITS FASTENINGS.
3. ALL PAINTING SHALL BE ON TRAFFIC FACE, 2-COATS APPROVED ORANGE AND STAIN RESISTANT REFLECTORIZED WHITE.
4. ALL ELECTRICAL WORK FOR BARRICADE LIGHTING SHALL CONFORM TO THE DETAILS SHOWN IN D.W.S.G. & E. STANDARD DRAWING NO. H-3009 AND IN D.W.S.G. & E. "GENERAL SPECIFICATION FOR THE INSTALLATION OF LIGHTING SYSTEMS".
5. THIS STANDARD APPLIES FOR BOTH BATTERY OPERATED FLASHING UNITS OR ELECTRICAL UNITS AS SHOWN.
PROJECT SPECIFICATIONS WILL DICTATE THE TYPE OF POWER SUPPLY.


CHECKED BY: MZ
HWS-H1013

| REVISION NO. | DESCRIPTION | DATE | APPROVED |
|--------------|-------------|------|----------|
| | | | |
| | | | |
| | | | |

| | | | |
|-------------------------------------------------------------|--|-----------------------------------------------------------------------------------------------------|------------------|
| | | New York City Department of Transportation | |
| ILLUMINATED TIMBER BARRICADE | | | |
| Approved: Chief Engineer Department of Transportation | | Approved: Associate Commissioner Infrastructure/Design Department of Design + Construction | |
| Date Issued: <u>7/1/10</u> | | Scale: None | Drawing # H-1013 |



ELEVATION
N.T.S.




SECTION A-A
N.T.S.

CHECKED BY: MZ


WWS-H1014

| REVISION NO. | DESCRIPTION | DATE | APPROVED |
|--------------|-------------|------|----------|
| | | | |
| | | | |
| | | | |


| | | | |
|-----------------------------------------------------------------|--|---------------------------------------------------------------------------------------------------------|------------------|
| | | New York City Department of Transportation | |
| TEMPORARY PEDESTRIAN STEEL BARRICADE | | | |
| Approved: Chief Engineer Department of Transportation | | Approved: Associate Commissioner Infrastructure/Design Department of Design + Construction | |
| Date Issued: <u>7/1/10</u> | | Scale: None | Drawing # H-1014 |




PLAN
N.T.S.



ELEVATION
N.T.S.



SECTION M-M
N.T.S.



DETAIL-STEEL FACED CURB
N.T.S.

NOTES:



- 1/2" Ø x 5" HEADED ANCHOR STUDS (GRANULAR OR SOLID FLUX FILLED) MAY BE SUBSTITUTED.
- STRUCTURAL STEEL AS PER ASTM DESIGNATION A-36.
- STEEL FACING TO BE CLEANED AND PAINTED AS PER SUBSECTION 2.13.4 OF THE NYCDOT STANDARD HIGHWAY SPECIFICATION. THE COLOR OF TOP COAT SHALL BE GRAY AS APPROVED BY THE ENGINEER.
- CONCRETE TO BE CLASS B-32, TYPE II A.
- 3'-6" TO 5'-0" AS ORDERED BY THE ENGINEER EXCEPT FOR THE FIRE DEPARTMENT DRIVEWAYS WHICH WILL SLOPE STRAIGHT BACK TO THE PROPERTY LINE. FIRE DEPARTMENT DRIVEWAYS SHALL BE TYPE III SIDEWALK-SEE H1045.

CHECKED BY: 112


HWS-H1015

| REVISION NO. | DESCRIPTION | DATE | APPROVED |
|--------------|-------------|------|----------|
| | | | |
| | | | |
| | | | |


| | | | |
|-----------------------------------------------------------------|--|---------------------------------------------------------------------------------------------------------|------------------|
| NEW YORK CITY DOT | | New York City Department of Transportation | |
| STEEL FACED DROP CURB DRIVEWAYS | | | |
| Approved: Chief Engineer Department of Transportation | | Approved: Associate Commissioner Infrastructure/Design Department of Design + Construction | |
| Date Issued: <u>7/1/10</u> | | Scale: None | Drawing # H-1015 |




SECTION A-A
TYPICAL WELD




DETAIL 1
PANEL TO POST DETAIL AT EXP. JOINT



CASE - I
INDIVIDUAL FOOTING IN EARTH



CASE - II
INDIVIDUAL FOOTING IN SIDEWALK AREAS
ADDITIONAL EMBEDMENT DETAILS
DETAIL 2



CASE - III
FOOTING AT CURB OR WALL (TYP.)









NOTES

1. SLEEVES REQUIRED IN NEW CONCRETE MASONRY STRUCTURES
2. SLEEVES NOT REQUIRED FOR INDIVIDUAL NEW FOOTING.
3. IN EXISTING CONCRETE OR MASONRY STRUCTURES, CONTRACTOR TO DRILL 3" DIA. HOLES FOR 1-3/4" x 1-3/4" POSTS.
4. ALL STEEL SHALL CONFORM TO SPECIFICATION C1015 OF THE A.I.S.I.
5. ALL JOINTS TO BE WELDED UNLESS NOTED OTHERWISE.
6. ALL STEEL TO BE PAINTED WITH ONE (1) SHOP COAT OF PRIMER. ALL STEEL FACING WHICH WILL BE EXPOSED TO VIEW AFTER INSTALLATION SHALL BE GIVEN ONE (1) SHOP COAT OF INTERMEDIATE AND ONE (1) SHOP COAT (OR ROLLED FIELD COAT) OF FINISH TOP COAT IN COMPLIANCE WITH THE REQUIREMENTS OF SUBSECTION 2.13.4 OF THE NYC DOT STANDARD HIGHWAY SPECIFICATIONS. THE COLOR OF TOP COAT SHALL BE AS APPROVED BY THE ENGINEER.
7. ALL FASTENING HARDWARE TO BE COMPATIBLE.
8. CONCRETE IN INDIVIDUAL FOOTINGS - CLASS B-25, TYPE IIA.
9. CEMENT GROUT - 1:1 MIX.

| | | | |
|-----------------------------------------------------------------|--|---------------------------------------------------------------------------------------------------------|------------------|
| NEW YORK CITY | | New York City Department of Transportation | |
| BAR PICKET FENCE (4'-0" HIGH) | | | |
| Approved: Chief Engineer Department of Transportation | | Approved: Associate Commissioner Infrastructure/Design Department of Design + Construction | |
| Date Issued: 7/1/10 | | Scale: None | Drawing # H-1017 |

CHECKED BY: M3

| REVISION NO. | DESCRIPTION | DATE | APPROVED |
|--------------|-------------|------|----------|
| | | | |
| | | | |



BOLT AND FABRIC NOTES

PEEN END OF ALL BOLTS.

BOLTS WHICH ARE INSTALLED 8" OR LESS ABOVE GRADE SHALL NOT PROTRUDE MORE THAN 1/4" BEYOND THE NUT AFTER TIGHTENING. ALL ROUGH EDGES SHALL BE FILED SMOOTH TO THE SATISFACTION OF THE ENGINEER.

ON FENCES OVER 12 FEET HIGH WHERE THE TWO WIDTHS OF FABRIC ARE REQUIRED, THE BOTTOM PIECE SHALL BE KNUCKLED TOP AND BOTTOM AND THE TOP PIECE KNUCKLED AT BOTTOM AND BARBED AT TOP.

THE TWO PIECES SHALL BE SPliced IN SUCH A WAY AS TO GIVE A FINISHED NEAT APPEARANCE.

FABRIC TO BE KNUCKLED AT TOP AND BOTTOM RAILS ON FENCES UP TO AND INCLUDING 8'-0" HIGH AND BARBED AT TOP RAIL ON FENCES OVER 8'-0" HIGH.

WIRE FABRIC NOTES

THE MESH SHALL BE PLACED ON THE OUTSIDE OF THE POSTS OF ALL EXTERIOR CHAIN LINK FENCES INCLUDING HOODED BACKSTOPS AND HANDBALL COURT FENCES WHERE THESE ARE AN INTEGRAL PART OF THE EXTERIOR FENCE.

SCHEDULE OF SIZES OF MEMBERS - AS PER ASTM A 53, ALL SIZES NPS

| HEIGHT OF FENCE | DIAMETER OF LINE POSTS | POST DIA. MAXIMUM | CORNER & END POST | TOP RAIL | MD RAIL | BOTTOM RAIL | DEPTH OF POST INTO CURB AND FTG AT: | | HORIZONTAL BRACES AT CORNER & END POST | DIAGONAL BRACES |
|-----------------|------------------------|-------------------|-------------------|----------|----------|-------------|-------------------------------------|----------------------|----------------------------------------|-----------------|
| | | | | | | | LINE POST | END/CORNER/GATE POST | | |
| 3'-6" | 2" | 6'-0" | 2 1/2" | 5/8" | 0 | 5/8" | 1'-0" | 1'-0" | 0 | 0 |
| 4'-0" | 2" | 6'-0" | 2 1/2" | 5/8" | 0 | 5/8" | 1'-8" | 1'-8" | 0 | 1/2" DIA. |
| 6'-0" | 2 1/2" | 6'-0" | 3" | 5/8" | 0 | 5/8" | 1'-8" | 1'-8" | 1 AT 1/2" | 1/2" DIA. |
| 10'-0" | 3" | 10'-0" | 4" | 5/8" | 1 - 5/8" | 5/8" | 3'-2" | 3'-2" | 2 AT 1/2" | 1/2" DIA. |
| 12'-0" | 3" | 10'-0" | 4" | 5/8" | 1 - 5/8" | 5/8" | 3'-2" | 4'-2" | 2 AT 1/2" | 1/2" DIA. |
| 14'-0" | 3 1/2" | 10'-0" | 4" | 5/8" | 2 - 5/8" | 5/8" | 3'-2" | 4'-2" | 2 AT 1/2" | 1/2" DIA. |
| 16'-0" | 3 1/2" | 10'-0" | 4" | 5/8" | 2 - 5/8" | 5/8" | 3'-2" | 4'-2" | 2 AT 1/2" | 1/2" DIA. |
| 18'-0" | 3 1/2" | 10'-0" | 4" | 5/8" | 2 - 5/8" | 5/8" | 3'-2" | 4'-2" | 2 AT 1/2" | 1/2" DIA. |
| 20'-0" | 4 1/2" | 10'-0" | 4 1/2" | 5/8" | 3 - 5/8" | 5/8" | 4'-2" | 4'-6" | 3 AT 1/2" | 1/2" DIA. |

FABRIC WIDTHS

| HEIGHT OF FENCE | WIDTH OF BOTTOM FABRIC | WIDTH OF TOP FABRIC |
|-----------------|------------------------|---------------------|
| 3'-6" - 4'-0" | 3'-0" - 4'-0" | 0 |
| 6'-0" | 6'-0" | 0 |
| 8'-0" | 8'-0" | 0 |
| 10'-0" | 10'-0" | 0 |
| 12'-0" | 8'-0" | 4'-0" |
| 14'-0" | 10'-0" | 4'-0" |
| 16'-0" | 10'-0" | 6'-0" |
| 18'-0" | 10'-0" | 8'-0" |
| 20'-0" | 10'-0" | 10'-0" |

PIPE SCHEDULE

| NOMINAL OUTSIDE DIAMETER | ACTUAL OUTSIDE DIAMETER |
|--------------------------|-------------------------|
| 6" | 1.660 |
| 2" | 2.375 |
| 2 1/2" | 2.875 |
| 3" | 3.500 |
| 3 1/2" | 4.000 |
| 4" | 4.500 |
| 4 1/2" | 5.000 |

PIPE & RAIL NOTES

PIPE POSTS AND RAILS SHALL BE TYPE I OR TYPE II.

TYPE I - ROUND MEMBERS SHALL BE HOT DIPPED GALVANIZED CONFORMING TO ASTM A - 53 STANDARD WEIGHT SCHEDULE 40

TYPE II - ROUND MEMBERS SHALL BE MANUFACTURED FROM STEEL CONFORMING TO ASTM A - 568 COLD ROLLED WELDED AND HAVE GIVEN CORROSION PROTECTION AS PER SPEC FOR SS - 40

NEW YORK CITY
Department of Transportation

CHAIN LINK FENCE - DETAILS

Approved: Chief Engineer
Department of Transportation

Approved: Associate Commissioner
Infrastructure/Design
Department of Design + Construction

Date Issued: 7/1/00


Scale: None

Drawing # H-1021-1


| REVISION NO. | DESCRIPTION | DATE | APPROVED |
|--------------|-------------|------|----------|
| | | | |

CHECKED BY: P. J. E.
HWS-H1021-1


1 EXTEND FENCE HEIGHT - SECTION




2 DIFFERENT CURB ELEVATIONS




3 SUPPLY NEW PORTAL





4 PROTECTIVE END PIECE



5 REPLACE FENCE POST 10'-0\"/>



6 REPLACE FENCE POST UP TO 8'-0\"/>



SCHEDULE FOR POST INSERTS

| EXISTING POST DIAMETER | NOMINAL O.D. PIPE SIZE | 2" | 2 1/2" | 3" | 3 1/2" | 4" |
|--------------------------|--------------------------|--------|--------|--------|--------|--------|
| | ACTUAL O.D. PIPE SIZE | 1.9" | 2.375" | 2.875" | 3 1/2" | 4" |
| | ACTUAL I.D. PIPE SIZE | 1.610" | 2.087" | 2.489" | 3.068" | 3.548" |
| SLEEVE DIAMETER REQUIRED | NOMINAL O.D. PIPE SLEEVE | 2" | 2 1/2" | 3" | 3 1/2" | |
| | ACTUAL O.D. PIPE SLEEVE | 1.9" | 2.375" | 2.875" | 3 1/2" | |



New York City
Department of Transportation

CHAIN LINK FENCE - SPECIAL CONDITIONS

Approved:

[Signature]
Chief Engineer
Department of Transportation

Approved:

[Signature]
Associate Commissioner
Infrastructure/Design
Department of Design + Construction

Date Issued:

7/1/10

Scale:

None


Drawing # H-1021-2

CHECKED BY: *MJE*


HWS-H1021-2

REVISION NO. DESCRIPTION DATE APPROVED


1 4'-0" & 3'-6" FENCE




5 6'-0" FENCE




6 8'-0" FENCE




7 10'-0" FENCE




12 12'-0" FENCE




13 16'-0" FENCE




2 4'-0" SINGLE FENCE GATE




8 12'-0" SINGLE FENCE GATE




14 PRESSED STEEL HINGE



3 GATE POST SPLIT FITTING AND CAP



9 MALLEABLE IRON HINGE



SCHEDULE OF MEMBER SIZES


PIPE POSTS & RAILS SHALL BE TYPE I OR TYPE II

| HEIGHT OF FENCE | DIAMETER OF LINE POSTS | POST SPACING MAXIMUM | GATE POST | HORIZ BRACE AT GATE POST | SIZE OF GATE MEMBERS | HORIZ BRACE ON GATES | SINGLE GATE HEIGHT | SINGLE GATE WIDTH | DIAG. TRUSS ON GATE | DIAG. TRUSS- FENCE PANELS | PORTAL | HEAD RAIL | DEPTH OF POST FOOTING |
|-----------------------|------------------------------|----------------------------|--------------|--------------------------------------|----------------------------|-------------------------------|--------------------------|-------------------------|------------------------------|------------------------------------|--------|--------------|--------------------------------|
| 3'-6" | 2" | 6'-0" | 3" | 0 | 2" | 0 | 3'-6" | 4'-0" | 1/2" DIA. | 0 | NO | 0 | 1'-6" |
| 4'-0" | 2" | 6'-0" | 3" | 0 | 2" | 0 | 4'-0" | 4'-0" | 1/2" DIA. | 0 | NO | 0 | 1'-6" |
| 6'-0" | 2" | 6'-0" | 3" | 0 | 2" | 0 | 6'-0" | 4'-0" | 1/2" DIA. | 1/2" DIA. | NO | 0 | 2'-0" |
| 8'-0" | 2 1/2" | 6'-0" | 3" | (1) - 1 1/2" | 2" | 1 1/2" | 7'-7" | 4'-0" | 1/2" DIA. | 1/2" DIA. | NO | 0 | 2'-0" |
| 10'-0" | 3" | 10'-0" | 4" | (2) - 1 1/2" | 2" | 1 1/2" | 7'-7" | 4'-0" | 1/2" DIA. | 1/2" DIA. | YES | 3" | 3'-2" |
| 12'-0" | 3" | 10'-0" | 4" | (2) - 1 1/2" | 2" | 1 1/2" | 7'-7" | 4'-0" | 1/2" DIA. | 1/2" DIA. | YES | 3" | 4'-2" |
| 14'-0", 16'-0" | 3 1/2" | 10'-0" | 4" | (2) - 1 1/2" | 2" | 1 1/2" | 7'-7" | 4'-0" | 1/2" DIA. | 1/2" DIA. | YES | 3" | 4'-2" |


TYPE I: ROUND MEMBERS SHALL BE HOT DIPPED GALVANIZED CONFORMING WITH ASTM-A-53
STANDARD WEIGHT SCHEDULE 40

TYPE II: ROUND MEMBERS SHALL BE MANUFACTURED FROM STEEL CONFORMING TO ASTM-A569
COLD ROLLED HEAVY, HAVE A TENSILE STRENGTH OF 50,000 P.S.I. AND BE GIVEN
CORROSION PROTECTION AS PER SPECIFICATIONS FOR SS-40 PIPE.


4 GATE STOP TYPE 'B' - TOP



10 GATE LOCK GATE STOP TYPE "B" - BOTTOM



11 GATE PIN



NOMINAL THICKNESS CHARTS

SS-40

| NOMINAL O.D. SIZE | ACTUAL I.D. SIZE | ACTUAL O.D. SIZE | STEEL WT/LF |
|----------------------|---------------------|---------------------|----------------|
| 1 1/2" | 1.549 | 1.660 | 1.84 |
| 2" | 1.780 | 1.900 | 2.28 |
| 2 1/2" | 2.245 | 2.375 | 3.12 |
| 3" | 2.715 | 2.875 | 4.64 |
| 3 1/2" | 3.340 | 3.500 | 5.71 |
| 4" | 3.840 | 4.000 | 6.56 |

SCHEDULE 40 - ASTM A53

| NOMINAL PIPE SIZE | ACTUAL I.D. SIZE | ACTUAL O.D. SIZE | STEEL WT/LF |
|----------------------|---------------------|---------------------|----------------|
| 1 1/2" | 1.380 | 1.660 | 2.27 |
| 1 1/2" | 1.610 | 1.900 | 2.72 |
| 2" | 2.067 | 2.375 | 3.65 |
| 2 1/2" | 2.469 | 2.875 | 5.79 |
| 3" | 3.066 | 3.500 | 7.58 |
| 3 1/2" | 3.548 | 4.000 | 9.11 |

NEW YORK CITY
Department of Transportation

CHAIN LINK FENCE - SINGLE GATE

Approved:

Chief Engineer
Department of Transportation

Approved:

Associate Commissioner
Infrastructure/Design
Department of Design + Construction

Date Issued: 7/1/10

Scale: None


Drawing # H-1021-3

CHECKED BY:


HWS-H1021-3

| REVISION NO. | DESCRIPTION | DATE | APPROVED |
|--------------|-------------|------|----------|
| | | | |
| | | | |


1 3'-6" & 4'-0" FENCE




5 6'-0" FENCE




9 8'-0" FENCE




10 10'-0" FENCE




14 12'-0" FENCE




15 16'-0" FENCE




2 4'-0" DOUBLE GATE FENCE




6 8'-0" DOUBLE GATE FENCE




11 12'-0" DOUBLE GATE FENCE




3 GATE STOP AND LOCK - DOUBLE GATE, TOP




7 LOCK BOLT LIFT AND GATE HANDLE




12 GATE STOP - DOUBLE GATE, BOTTOM




4 HEAD RAIL AND TENSIONING ELEMENTS



8 CONCRETE PAVEMENT - DOUBLE GATE



13 GATE LOCK



NOMINAL THICKNESS CHARTS

| SS-40 | NOMINAL O.D. SIZE | ACTUAL O.D. SIZE | ACTUAL I.D. SIZE | STEEL WT/LF |
|--------|-------------------|------------------|------------------|-------------|
| 1 1/2" | 1.549 | 1.660 | 1.84 | |
| 2" | 1.780 | 1.900 | 2.28 | |
| 2 1/2" | 2.245 | 2.375 | 3.12 | |
| 3" | 2.715 | 2.875 | 4.64 | |
| 3 1/2" | 3.340 | 3.500 | 5.71 | |
| 4" | 3.840 | 4.000 | 6.56 | |

| SCHEDULE 40 | NOMINAL O.D. SIZE | ACTUAL O.D. SIZE | ACTUAL I.D. SIZE | STEEL WT/LF |
|-------------|-------------------|------------------|------------------|-------------|
| 1 1/2" | 1.380 | 1.660 | 2.27 | |
| 2" | 1.610 | 1.900 | 2.71 | |
| 2 1/2" | 2.067 | 2.375 | 3.65 | |
| 3" | 2.469 | 2.875 | 5.79 | |
| 3 1/2" | 3.060 | 3.500 | 7.58 | |
| 4" | 3.543 | 4.000 | 9.10 | |

SCHEDULES OF MEMBER SIZES & PIPES

| HEIGHT OF FENCE | DIAMETER OF LINE POSTS | POST SPACING MAXIMUM | GATE POST | HORIZ BRACE AT GATE POST | SIZE OF GATE MEMBERS | HORIZ BRACE ON GATES | DOUBLE GATE HEIGHT | DOUBLE GATE WIDTH | DIAG. TRUSS ON GATE | DIAG. TRUSS-FENCE PANELS | PORTAL | HEAD RAIL | DEPTH OF POST FOOTING |
|--------------------|------------------------|----------------------|-----------|--------------------------|----------------------|----------------------|--------------------|-------------------|---------------------|--------------------------|--------|-----------|-----------------------|
| 3'-6" | 2" | 8'-0" | 3" | 0 | 2" | 0 | 3'-6" | 10'-0" | 0 | 0 | NO | 0 | 7'-6" |
| 4'-0" | 2" | 8'-0" | 3" | 0 | 2" | 0 | 4'-0" | 10'-0" | 0 | 0 | NO | 0 | 7'-6" |
| 6'-0" | 2" | 8'-0" | 3" | 0 | 2" | 0 | 6'-0" | 10'-0" | 1/2" DIAM. | 1/2" DIAM. | NO | 0 | 2'-0" |
| 8'-0" | 2 1/2" | 8'-0" | 3" | (1) - 1 1/2" | 2" | 1 1/2" | 7'-7" | 10'-0" | 1/2" DIAM. | 1/2" DIAM. | NO | 0 | 2'-0" |
| 10'-0" | 3" | 10'-0" | 4" | (2) - 1 1/2" | 2" | 1 1/2" | 9'-7" | 10'-0" | 1/2" DIAM. | 1/2" DIAM. | NO | 0 | 3'-2" |
| 12'-0" | 3" | 10'-0" | 4" | (2) - 1 1/2" | 2" | 1 1/2" | 9'-7" | 10'-0" | 1/2" DIAM. | 1/2" DIAM. | YES | 3" | 4'-2" |
| 14'-0" THRU 20'-0" | 3 1/2" | 10'-0" | 4" | (2) - 1 1/2" | 2" | 1 1/2" | 9'-7" | 10'-0" | 1/2" DIAM. | 1/2" DIAM. | YES | 3" | 4'-2" |

CHECKED BY: ME

HWS-H1021-4

| REVISION NO. | DESCRIPTION | DATE | APPROVED |
|--------------|-------------|------|----------|
| | | | |
| | | | |

NEW YORK CITY
Department of Transportation

CHAIN LINK FENCE - DOUBLE GATE






Approved: 
Chief Engineer
Department of Transportation

Approved: 
Associate Commissioner
Infrastructure/Design
Department of Design + Construction

Date Issued: 2/1/10

Scale: None


Drawing # H-1021-4





KEY PLAN
NOT TO SCALE

| BARRIER SCHEDULE | | | | | | | |
|------------------|---------------|-------------|--------|--------|--------|--------|--------|
| TYPE | ROADWAY WIDTH | POST SPACES | | | | | |
| | | D | C | B | A | B | C |
| 1 | 20'-0" | - | - | - | 8'-0" | - | - |
| 2 | 25'-0" | - | - | - | 10'-6" | - | - |
| 3 | 30'-0" | - | - | - | 12'-6" | - | - |
| 4 | 34'-0" | - | - | - | 12'-6" | - | - |
| 5 | 38'-0" | - | - | 9'-4" | 9'-4" | 9'-4" | - |
| 6 | 40'-0" | - | - | 12'-6" | 6'-3" | 12'-6" | - |
| 7 | 44'-0" | - | - | 12'-6" | 9'-0" | 12'-6" | - |
| 8 | 46'-0" | - | - | 12'-6" | 11'-0" | 12'-6" | - |
| 9 | 50'-0" | - | - | 12'-6" | 7'-6" | 12'-6" | - |
| 10 | 52'-0" | - | - | 12'-6" | 8'-6" | 12'-6" | - |
| 11 | 54'-0" | - | - | 12'-6" | 9'-6" | 12'-6" | - |
| 12 | 60'-0" | - | - | 12'-6" | 12'-6" | 12'-6" | - |
| 13 | 62'-0" | - | - | 12'-6" | 12'-6" | 12'-6" | - |
| 14 | 68'-0" | - | 12'-6" | 12'-6" | 8'-0" | 12'-6" | 12'-6" |
| 15 | 70'-0" | - | 12'-6" | 12'-6" | 10'-0" | 12'-6" | 12'-6" |
| 16 | 76'-0" | - | 12'-6" | 12'-6" | 8'-0" | 12'-6" | 12'-6" |
| 17 | 80'-0" | - | 12'-6" | 12'-6" | 10'-0" | 12'-6" | 12'-6" |
| 18 | 90'-0" | 12'-6" | 12'-6" | 10'-0" | 10'-0" | 10'-6" | 12'-6" |

- NOTES**
- ALL MATERIALS SHALL COMPLY WITH AASHTO DES. M180.
 - DEAD-END SIGN (2) 12"x24" RECTANGLES 0.08 ALUMINUM AS NOTED AND DETAILED, #2271 YELLOW "SCOTCHLITE" SCREENED #705 BLACK OR PROVED EQUIVALENT.
 - THE VERTICAL WHITE STRIPES ON THE BEAM BARRIER SHALL BE REFLECTORIZED WITH #7216 "CODIT" REFLECTIVE LIQUID AS MADE BY MINN. MINING AND MANUFACTURING COMPANY OR APPROVED EQUIVALENT.
 - POSTS SHALL CONFORM TO ASTM A36 WITH 0.2% COPPER AND SHALL BE GALVANIZED PER ASTM 123.
 - NUTS AND BOLTS SHALL CONFORM TO ASTM A307 AND SHALL BE GALVANIZED PER ASTM 123.
 - BEAMS AND TERMINAL SECTIONS SHALL BE MADE FROM 12 GAGE OR HEAVIER SHEET ROLLED FROM NEW BILLET, OPEN HEARTH OR ELECT. FURNACE STEEL. THE ULTIMATE TENSILE STRENGTH OF A SPECIMEN OF THE FULL SIZE OF THE BEAM, INCLUDING A SPLICE AT THE CENTER OF THE SPECIMEN SHALL BE AT LEAST 80,000 P.S.I. THE MIN. ELONGATION OF A SPECIMEN SHALL BE 12% IN A 2" GAGE LENGTH.
 - GALVANIZING PRIMER AND PAINT FOR BLACK STRIPES SHALL BE AS APPROVED BY THE ENGINEER.



CROSS SECTION THROUGH GUARD RAIL SPLICE
N.T.S.



HARDWARE
N.T.S.

CHECKED BY: MZ

HWS-H1022

| REVISION NO. | DESCRIPTION | DATE | APPROVED |
|--------------|-------------|------|----------|
| | | | |
| | | | |
| | | | |

NEW YORK CITY
Department of Transportation

BEAM BARRIER FOR DEAD END STREETS


Approved: [Signature]
Chief Engineer
Department of Transportation

Approved: [Signature]
Associate Commissioner
Infrastructure/Design
Department of Design + Construction


Date Issued: 7/1/10

Scale: None

Drawing # H-1022



PLAN VIEW



SIDE VIEW

NOTE-A

PRIOR APPROVAL MUST BE OBTAINED FROM THE FIRE DEPARTMENT FOR DISTANCE LESS THAN 15'-0".

NOTE-B

PRIOR APPROVAL MUST BE OBTAINED FROM THE BUREAU OF TRAFFIC OPERATIONS WHERE EXISTING PARKING METERS ARE LOCATED WITHIN THE PROPOSED CANOPY AREA.

A PERMIT MUST BE OBTAINED FROM THE NYC DEPARTMENT OF TRANSPORTATION BEFORE ANY CANOPY IS ERECTED.

DESIGN SPECIFICATIONS

SIZE LIMITATIONS

WIDTH

THE WIDTH OF THE CANOPY IS LIMITED TO THE WIDTH OF THE ENTRANCE TO THE BUILDING OR PLACE OF BUSINESS, BUT IN NO CASE MAY THE WIDTH BE LESS THAN FOUR FEET.

HEIGHT

THE BOTTOM OF THE COVERING OF THE CANOPY SHALL BE NOT LESS THAN EIGHT FEET ABOVE THE SIDEWALK.

LENGTH

THE CANOPY MAY EXTEND FROM THE BUILDING TO NO MORE THAN A MIN. OF ONE FOOT OR A MAX. OF 2 FEET FROM CURB LINE.

COVERING MATERIAL

MAY BE OF FLAMEPROOF CANVAS OR CLOTH, APPROVED SLOW BURNING PLASTIC, SHEET METAL OR OTHER EQUIVALENT MATERIAL.

COLOR

MUST HARMONIZE WITH THE ARCHITECTURE OF THE BUILDING THAT IT IS INTENDED FOR AND ALSO BE IN KEEPING WITH THE SURROUNDING AREA.

PAINTING

WHERE FRAMEWORK IS IRON, STEEL OR GALVANIZED, IT SHALL BE PAINTED AT A MAXIMUM OF FIVE YEAR PERIODS THEREAFTER.

LETTERING

LETTERING ON COVERING MAY BE OF A PAINTED, IMPRINTED OR STENCILED TYPE AS APPROVED AND SHALL BE LIMITED TO A SINGLE HORIZONTAL LINE OF LETTERING ON EACH SIDE FACE OF THE CANOPY COVERING. THE SUM OF THE AREAS OF THE PERMITTED CANOPY LETTERING AND THE SIGNS ON THE BUILDING WITH WHICH THE CANOPY IS CONNECTED SHALL NOT EXCEED THE SIGN LIMITS ESTABLISHED IN THE ZONING RESOLUTION OF THE CITY OF NEW YORK.

SIDE CURTAINS

NO SIDE CURTAINS ARE PERMITTED.

SUPPORT AND FRAMEWORK MATERIAL

SUPPORTING FRAMEWORK SHALL BE CONSTRUCTED OF NON-COMBUSTIBLE METAL MEMBERS VERTICAL UPRIGHTS SHALL BE OF SUFFICIENT SIZE AND STRENGTH AND SHALL BE NO LESS THAN A STANDARD STEEL PIPE 1 1/4 INCH DIAMETER. WHERE SPECIAL CONSTRUCTION IS USED INSTEAD OF PIPE, THE DESIGN SHALL BE EQUIVALENT TO THE ABOVE NOTED MINIMUM STANDARD FOR PIPE.

CONSTRUCTION

THE VERTICAL UPRIGHTS SHALL BE IMBEDDED IN A CONCRETE FOOTING OF ADEQUATE SIZE DESIGNED TO TAKE CARE OF WIND UPLIFT. INTERMEDIATE SUPPORTS OR DIAGONAL BRACING FOR VERTICAL SUPPORTS ARE NOT PERMITTED. EXCEPT FOR ADDITIONAL UPRIGHT SUPPORTS AT THE FACE OF THE BUILDING.

REPAINTING

WHERE INITIALLY PAINTED, IT SHALL BE REPAINTED AT A MAXIMUM OF FIVE YEAR INTERVALS.

LIGHTING


AREA UNDER CANOPY COVERING SHALL BE LIGHTED TO THE SATISFACTION OF THE NYC DEPARTMENT OF TRANSPORTATION (NYCDOT), WHERE DEEMED NECESSARY BY THE NYCDOT. IF CANOPY IS WITHIN TWENTY FEET OF A LAMP POST, LIGHTING SHALL BE PROVIDED UNDER THE CANOPY TO A MINIMUM OF 30 FOOT CANDLES. LIGHTING INSTALLATION MUST BE MADE BY A LICENSED ELECTRICIAN AND APPROVED BY THE NYCDOT DIVISION OF TRAFFIC OPERATIONS, STREET LIGHTING SECTION.

CHECKED BY: MC

HWS-H1029

| REVISION NO. | DESCRIPTION | DATE | APPROVED |
|--------------|-------------|------|----------|
| | | | |
| | | | |
| | | | |


| | | | |
|-------------------------------------------------------------|--|-----------------------------------------------------------------------------------------------------|------------------|
| | | New York City Department of Transportation | |
| CRITERIA FOR DESIGN & CONSTRUCTION OF CANOPIES | | | |
| Approved: Chief Engineer Department of Transportation | | Approved: Associate Commissioner Infrastructure/Design Department of Design + Construction | |
| Date Issued: <u>2/1/10</u> | | Scale: None | Drawing # H-1029 |



PLAN


STANDARD RECESS REQUIRED IN VAULT CONSTRUCTION WHERE CORNER CURB IS TO BE TURNED AT A 12'-0" RADIUS.

EXISTING RECEIVING BASIN TO BE REMODELED IN ACCORDANCE WITH STANDARD DRAWINGS ON FILE IN THE DEPT. OF ENVIRONMENTAL PROTECTION




PLAN


STANDARD RECESS REQUIRED IN VAULT CONSTRUCTION WHERE STREET IS TO BE WIDENED & CORNER TURNED TO A 12'-0" RADIUS. EXISTING BASINS REMODELED & INLETS BUILT.




SECTION A-A




SECTION B-B




SECTION C-C



SECTION D-D




SECTION E-E



PLAN

(WHERE ROADWAY IS NOT WIDENED)



PLAN

(WHERE ROADWAY IS WIDENED)

NOTES:


1. DESIGN VAULT ROOF TO CONFORM TO REQUIREMENTS OF THE DEPARTMENT OF BUILDINGS.
2. CURB & SIDEWALK SHALL BE SET TO LINE AND GRADE AS DETERMINED BY THE NYC DEPARTMENT OF TRANSPORTATION (NYCDOT).
3. RECESS FOR CURB, TO BE NOT LESS THAN 1'-6" BELOW GRADE, TO BE FURNISHED BY THE CITY.
4. CURB SHALL CONFORM TO THE STANDARD SPECIFICATION ON FILE IN THE NYC DEPARTMENT OF TRANSPORTATION.
5. SIDEWALK AREA BETWEEN EXISTING AND PROPOSED CURB LINES TO BE MAINTAINED FOR PEDESTRIAN TRAFFIC PENDING WIDENING OF THE ROADWAY.
6. PERMIT FROM THE NYC DEPARTMENT OF TRANSPORTATION AND DEPARTMENT OF BUILDINGS MUST BE OBTAINED BEFORE ANY WORK IS PERFORMED WITHIN THE AREA.

CHECKED BY: MA

HWS-H1030

| REVISION NO. | DESCRIPTION | DATE | APPROVED |
|--------------|-------------|------|----------|
| | | | |
| | | | |
| | | | |

| | |
|---------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------|
| NEW YORK CITY New York City Department of Transportation | |
| STANDARD RECESS IN VAULT CONSTRUCTION TO PROVIDE FOR STREET WIDENING, RECEIVING BASINS, INLETS, AND 12'-0" CORNER RADIUS | |
| Approved: Chief Engineer Department of Transportation | Approved: Associate Commissioner Infrastructure/Design Department of Design + Construction |
| Date Issued: <u>7/1/10</u> | Scale: None Drawing # H-1030 |




TYPICAL PAVEMENT KEY
N.T.S.

CHECKED BY: MP

HWS-H1031

| REVISION NO. | DESCRIPTION | DATE | APPROVED |
|--------------|-------------|------|----------|
| | | | |
| | | | |
| | | | |

| | | | |
|-------------------------------------------------------------|--|-----------------------------------------------------------------------------------------------------|-----------------|
| NEW YORK CITY | | New York City Department of Transportation | |
| TYPICAL PAVEMENT KEY | | | |
| Approved: Chief Engineer Department of Transportation | | Approved: Associate Commissioner Infrastructure/Design Department of Design + Construction | |
| Date Issued: <u>7/1/10</u> | | Scale: None | Drawing # H1031 |




CHECKED BY: ME

HWS-H1032

| REVISION NO. | DESCRIPTION | DATE | APPROVED |
|--------------|-------------|------|----------|
| | | | |
| | | | |
| | | | |

| | | | |
|-------------------------------------------------------------|--|-----------------------------------------------------------------------------------------------------|------------------|
| | | New York City Department of Transportation | |
| TYPICAL NEW PAVEMENT IN UNPAVED WING AREA | | | |
| Approved: Chief Engineer Department of Transportation | | Approved: Associate Commissioner Infrastructure/Design Department of Design + Construction | |
| Date Issued: <u>7/1/10</u> | | Scale: None | Drawing # H-1032 |





SECTION
N.T.S.

NOTE:
ADJUST ALL MANHOLES, GRATES,
CATCH BASINS, VAULTS, BOXES, ETC.
WITHIN AREA OF RESURFACING.

CHECKED BY: ME

HWS-H1033

| | | | |
|-----------------------------------------------------------------------------------------------|-------------|-----------------------------------------------------------------------------------------------------|------------------|
| | | New York City Department of Transportation | |
| TYPICAL RESURFACING ON ASPHALT PAVEMENT &/OR WEARING COURSE (LESS THAN FULL WIDTH) | | | |
| Approved: Chief Engineer Department of Transportation | | Approved: Associate Commissioner Infrastructure/Design Department of Design + Construction | |
| Date Issued: <u>7/1/10</u> | | Scale: None | Drawing # H-1033 |
| REVISION NO. | DESCRIPTION | DATE | APPROVED |



NOTES:


1. TYPE I CONSTRUCTION JOINT TO BE USED FOR LONGITUDINAL ROADWAY JOINTS.
2. TYPE II CONSTRUCTION JOINT SHALL BE INSTALLED ON ALL TRANSVERSE ROADWAY JOINTS.
3. ALL ASPHALT JOINTS SHALL BE SAW-CUT, FULL DEPTH. TACK COAT TO BE APPLIED TO ALL SURFACES. JOINT SHALL BE PARALLEL TO CURBLINE OR AS OTHERWISE DIRECTED.

CHECKED BY: *MA*


HWS-H1034

| REVISION NO. | DESCRIPTION | DATE | APPROVED |
|--------------|-------------|------|----------|
| | | | |
| | | | |
| | | | |


| | | | |
|------------------------------------------------------------------------------------------------------------------------------------------------------|--|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------|
| NEW YORK CITY DOT | | New York City Department of Transportation | |
| TYPICAL CONSTRUCTION JOINTS FOR CONCRETE BASE FOR PAVEMENT | | | |
| Approved:  Chief Engineer Department of Transportation | | Approved:  Associate Commissioner Infrastructure/Design Department of Design + Construction | |
| Date issued: <i>7/1/10</i> | | Scale: None | Drawing # H-1034 |



CURB ELEVATION VIEW
NOT TO SCALE



SECTION A-A
NOT TO SCALE



SECTION B-B
NOT TO SCALE

NOTES:

1. CONCRETE SHALL BE CLASS A-40, 4000 P.S.I. AS PER SECTION 3.05 OF STANDARD HIGHWAY SPECIFICATIONS.
2. STEEL REINFORCEMENT SHALL BE AS PER ASTM A615, GRADE 60.
3. THE SLOPE OF THE TOP OF CURB SHALL CONFORM TO SLOPE OF SIDEWALK IN ALL CASES.
4. EXPANSION JOINTS IN CURB SHALL NOT EXCEED 20'-0" O.C.
5. THE EXPANSION JOINTS OF THE CURB SHOULD LINE UP WITH THE EXPANSION JOINTS IN THE CONCRETE SIDEWALK.


* REVEAL AT PEDESTRIAN RAMPS SHALL BE 0" AS SHOWN. REVEAL AT DRIVEWAY TO BE 1-1/2".

CHECKED BY: WBS


HWS-H1035

| REVISION NO. | DESCRIPTION | DATE | APPROVED |
|--------------|-------------|------|----------|
| | | | |
| | | | |
| | | | |

| | | | |
|-------------------------------------------------------------|--|-----------------------------------------------------------------------------------------------------|------------------|
| NEW YORK CITY | | New York City Department of Transportation | |
| REINFORCED CONCRETE CURB & DROP CURB | | | |
| Approved: Chief Engineer Department of Transportation | | Approved: Associate Commissioner Infrastructure/Design Department of Design + Construction | |
| Date Issued: <u>7/1/10</u> | | Scale: None | Drawing # H-1035 |



ELEVATION
N.T.S.



SECTION A-A
N.T.S.

NOTES:


1. ALL EXPOSED SURFACES TO BE STEEL - TROWEL FINISHED.
2. THE MATERIAL UNDERLYING THE CURB SHALL BE SATISFACTORY AND THOROUGHLY COMPACTED TO THE SATISFACTION OF THE ENGINEER.
3. PREFORMED JOINT FILLER TO BE USED AT ALL EXPANSION JOINTS. THICKNESS OF EXPANSION JOINT TO MATCH THAT OF ADJACENT SIDEWALK.
4. COLOR TO BE AS DIRECTED.

CHECKED BY: MB


NYS-H1036

| REVISION NO. | DESCRIPTION | DATE | APPROVED |
|--------------|-------------|------|----------|
| | | | |
| | | | |
| | | | |


| | | | |
|-----------------------------------------------------------------|--|---------------------------------------------------------------------------------------------------------|------------------|
| NEW YORK CITY | | New York City Department of Transportation | |
| CONCRETE POURED-IN-PLACE MALL CURB | | | |
| Approved: Chief Engineer Department of Transportation | | Approved: Associate Commissioner Infrastructure/Design Department of Design + Construction | |
| Date Issued: <u>2/1/10</u> | | Scale: None | Drawing # H-1036 |



CROSS SECTION



SINGLE DRAIN (AS SHOWN)



MULTIPLE DRAIN

SECTION A-A
N.T.S.


NOTE:
AUTHORIZATION REQUIRED BY N.Y.C. DEPT. OF
BUILDINGS & DEPT. OF ENVIRONMENTAL PROTECTION FOR
NEW INSTALLATIONS.

CHECKED BY: M35


NYSDOT H-1037

| REVISION NO. | DESCRIPTION | DATE | APPROVED |
|--------------|-------------|------|----------|
| | | | |
| | | | |
| | | | |

| | | | |
|-------------------------------------------------------------|--|-----------------------------------------------------------------------------------------------------|------------------|
| NEW YORK CITY | | New York City Department of Transportation | |
| UNDER SIDEWALK DRAIN | | | |
| Approved: Chief Engineer Department of Transportation | | Approved: Associate Commissioner Infrastructure/Design Department of Design + Construction | |
| Date issued: <u>7/1/10</u> | | Scale: None | Drawing # H-1037 |



PLAN




SIDE

TYPICAL TYPE III BREAKAWAY BARRICADE UNIT
ALTERNATE "A"
NOT TO SCALE

NOTES:

1. ALL PIPE SHALL BE POLYVINYL CHLORIDE (PVC) PRESSURE RATED PIPE SDR 21 OR SDR 26 ASTM D2241.
2. JOINT FITTINGS SHALL BE PVC ASTM D2665.
3. ALL PIPE SHALL BE WHITE. WHITE FITTINGS ARE PREFERRED, BLACK MAY BE USED.
4. SOLVENT CEMENT ASTM D2564 TYPE I.
5. ALUMINUM FACE PANELS N.Y.S.D.O.T. 730-01.
6. REFLECTIVE SHEETING N.Y.S.D.O.T. 730.05-01 OR 730.05-02.
7. PAN HEAD METAL SCREWS N.Y.S.D.O.T. 715.04.
8. ALL JOINTS TO BE GLUED.

ORANGE AND WHITE REFLECTIVE SHEETING SEE FIG. MC 4 OF N.Y.S. MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES




FRONT


TYPICAL TYPE III BREAKAWAY BARRICADE UNIT
ALTERNATE "B"
NOT TO SCALE

NOTES:

1. ALL PIPE SHALL BE POLYVINYL CHLORIDE (PVC) PRESSURE RATED PIPE SDR 21 OR SDR 26 ASTM D2241.
2. JOINT FITTINGS MAY BE PVC ASTM D2665 OR ACRYLONITRILE BUTADIENE STYRENE (ABS)ASTM D2661 (DRAINAGE AND VENT).
3. ALL PIPE SHALL BE WHITE. WHITE FITTINGS ARE PREFERRED, BLACK MAY BE USED.
4. ALL JOINTS SHALL BE FREE TO SEPARATE UPON VEHICLE IMPACT.
5. SHADED CONDUIT TO BE TIED TOGETHER WITH ROPE THREADED INTO PIPE INTERIOR. USE 3/16" NO. 6 SOLID BRAIDED NYLON OR EQUIVALENT.
6. A FIXED FRANGIBLE PAVEMENT CONNECTION IS PREFERRED. SAND BAGS MAY BE SUBSTITUTED.
7. TIE WIRE 8 GAGE ALUMINUM OR GALVANIZED STEEL.
8. ALUMINUM FACE PANELS N.Y.S.D.O.T. 730-01.
9. REFLECTIVE SHEETING N.Y.S.D.O.T. 730.05-01 OR 730.05-02.



PLAN



SIDE


10. NO. 14 PAN HEAD METAL SCREWS 1" LONG N.Y.S.D.O.T. 715.04.
11. FOR LIGHTED BARRICADES THE MOUNTING OF BATTERY PACKS FOR LIGHTING ON CONSTRUCTION BARRICADES SHALL BE AT THE BASE OF THE BARRICADES.

CHECKED BY: MR


NYS-H-1038

| REVISION NO. | DESCRIPTION | DATE | APPROVED |
|--------------|-------------|------|----------|
| | | | |
| | | | |
| | | | |

| | | | |
|-------------------------------------------------------------|--|-----------------------------------------------------------------------------------------------------|------------------|
| NEW YORK CITY | | New York City Department of Transportation | |
| TYPE III BREAKAWAY BARRICADE | | | |
| Approved: Chief Engineer Department of Transportation | | Approved: Associate Commissioner Infrastructure/Design Department of Design + Construction | |
| Date Issued: <u>7/1/10</u> | | Scale: None | Drawing # H-1038 |



PLAN
(TYPICAL PAVEMENT JOINT LAYOUT)
N.T.S.



SECTION X-X
TYPICAL TRANSVERSE JOINT
N.T.S.


NOTES:

1. TYPE I CONSTRUCTION JOINTS TO BE INSTALLED ON ALL LONGITUDINAL ROADWAY JOINTS.
2. TRANSVERSE JOINTS TO BE SAW CUT WITHIN 24 HOURS OF POURING OF CONCRETE. TRANSVERSE JOINTS SHALL BE 5 FT. SKEWED AND SHALL BE PROVIDED AT 20 FT. CENTERS. SEE TYPICAL LAYOUT AND SECTION X-X FOR DETAILS. (1/8" WIDE)
3. AN 18 INCH WIDTH OF R.C. MEMBRANE IS TO BE APPLIED OVER TRANSVERSE AND LONGITUDINAL JOINTS TO PREVENT REFLECTIVE CRACKING. R.C. MEMBRANE TO BE APPROVED BY THE ENGINEER.
4. R.C. MEMBRANE TO BE INSTALLED AS PER MANUFACTURER'S SPECIFICATIONS.
5. ROADWAY JOINTS (LONGITUDINAL OR TRANSVERSE) TO BE PAID FOR UNDER NEW CONC. BASE ITEM.
6. CONTRACTOR WILL BE PERMITTED TO INSTALL ALTERNATE COLD JOINT FOR TRANSVERSE SECTIONS, SUBJECT TO THE APPROVAL OF THE FIELD ENGINEER.
7. R.C. MEMBRANE WILL BE PAID FOR UNDER ITEM 6.91, REFLECTIVE CRACKING MEMBRANE (18" WIDE).


CHECKED BY: MRS

| REVISION NO. | DESCRIPTION | DATE | APPROVED |
|--------------|-------------|------|----------|
| | | | |
| | | | |
| | | | |

| | | | |
|-----------------------------------------------------------------|--|---------------------------------------------------------------------------------------------------------|------------------|
| NEW YORK CITY | | New York City Department of Transportation | |
| TRANSVERSE CONSTRUCTION JOINTS FOR CONCRETE BASE | | | |
| Approved: Chief Engineer Department of Transportation | | Approved: Associate Commissioner Infrastructure/Design Department of Design + Construction | |
| Date Issued: <u>7/1/00</u> | | Scale: None | Drawing # H-1040 |



PLAN
N.T.S.



PARTIAL SECTION
N.T.S.

NOTES



1. DEPTH "D" TO BE TO THE TOP OF THE EXISTING CONC. BASE. THE CONC. BASE SHALL BE CHIPPED CLEAN AND AN EPOXY BONDING COMPOUND SHALL BE APPLIED THERETO.
2. SHOULD THE DEPTH "D" TO THE TOP OF THE EXISTING CONC. BASE BE LESS THAN 6" THE BASE SHALL BE CUT DOWN TO A MIN. OF 6" AND AN EPOXY BONDING COMPOUND WILL BE APPLIED TO THE EXPOSED CONC. SURFACE.
3. CONC. PAVEMENT SHALL BE CLASS "A" CONC. (4000 psi AT 28 DAYS).
4. PRICE BID SHALL INCLUDE ALL EXCAVATION, PREPARATION, EPOXY, CONC., FINISHING, ETC., REQ'D FOR THE PROPER INSTALLATION.
5. THE PERIMETER OF THE EXCAVATED AREA SHALL BE CUT SQUARE IN ORDER TO PROVIDE FOR AN EVENLY FINISHED AREA.
6. IF THE SEPARATION BETWEEN TWO OR MORE CASTINGS IS SMALLER THAN 3" THE RESTORATION SHALL BE AS ONE UNIT WHILE THE PAY ITEM SHALL BE THE NUMBER OF MANHOLES (VALVE BOXES) INCORPORATED INTO THE WORK.
7. FOR CONC. COLLAR AROUND STEAM VALVE BOXES CONSTRUCTION WILL BE SIMILAR EXCEPT EDGE DISTANCE "E" SHALL BE 1'-0".

CHECKED BY: MJE

NYSDOT-H-1041

| REVISION NO. | DESCRIPTION | DATE | APPROVED |
|--------------|-------------|------|----------|
| | | | |
| | | | |
| | | | |

| | | | |
|-------------------------------------------------------------|--|-----------------------------------------------------------------------------------------------------|------------------|
| NEW YORK CITY | | New York City Department of Transportation | |
| CONCRETE COLLAR AROUND STEAM MANHOLE AND STEAM VALVE | | | |
| Approved: Chief Engineer Department of Transportation | | Approved: Associate Commissioner Infrastructure/Design Department of Design + Construction | |
| Date Issued: <u>7/1/10</u> | | Scale: None | Drawing # H-1041 |



NOTES:

1. ALL UNDERMINED, DISTURBED OR UNSTABLE SUB BASE MATERIAL SHALL BE REMOVED PRIOR TO BACKFILLING. IT SHALL BE FULLY RESTORED AND COMPACTED WHILE THE TRENCH IS BEING FULLY BACKFILLED AND COMPACTED.
2. ALL TRENCHES SHALL BE BACKFILLED AS PER SECTION 4.11 OF NYCDOT STANDARD HIGHWAY SPECIFICATIONS.
3. ALL TRENCH RESTORATIONS SHALL BE SQUARE OR RECTANGULAR SHAPED. SAW CUTTING BACK EXISTING ASPHALT PAVEMENT AND CONCRETE BASE, SQUARING AND ALIGNING OF CUT LIMITS TO BE PERFORMED ONLY AFTER COMPLETION OF THE COMPACTION OF THE BACKFILL TO THE BOTTOM OF THE BASE.
4. BACKFILL MATERIAL SHALL BE DEPOSITED IN HORIZONTAL LAYERS NOT EXCEEDING 12" IN THICKNESS PRIOR TO COMPACTION. A MINIMUM OF 95% OF STANDARD PROCTOR MAXIMUM DENSITY WILL BE REQUIRED. WHEN PLACING BACKFILL AROUND PIPES, LAYERS SHALL BE DEPOSITED TO PROGRESSIVELY BURY THE PIPE TO EQUAL DEPTHS ON BOTH SIDES. COMPACTION SHALL BE ACHIEVED BY THE USE OF IMPACT RAMMERS, PLATE OR SMALL DRUM VIBRATORS OR PNEUMATIC BUTTON HEAD COMPACTION EQUIPMENT. HAND TAMPING IS NOT PERMITTED EXCEPT IN THE IMMEDIATE AREA OF THE UNDERGROUND FACILITY.
5. ALL RESTORATION SHALL CONFORM TO THE STANDARDS AND SPECIFICATIONS OF NYC DEPARTMENT OF TRANSPORTATION AND IN PROCESS INSPECTION AND TESTING SHALL BE CERTIFIED BY A LICENSED PROFESSIONAL ENGINEER.
6. WHEN THE EXISTING PAVEMENT IS ASPHALT ON CONCRETE BASE THEN THE RESTORATION SHALL BE AS SHOWN ON RESTORATION DETAIL. CONCRETE SHALL BE REMOVED TO A WIDTH OF $W + 1$ FOOT BY FULL DEPTH SAW CUTTING FOR CRITICAL ROADWAYS AND FOR PROTECTED STREETS, AND FOR NON-PROTECTED STREETS CONCRETE SHALL BE REMOVED TO A WIDTH OF $W + 1$ FOOT BY EITHER FULL DEPTH SAW CUTTING OR OTHER METHODS. ASPHALT SHALL BE REMOVED TO A WIDTH OF NOT LESS THAN $W + 3$ FEET BY SAW CUTTING AND GRINDING OR PEELING SO AS NOT TO DAMAGE CONCRETE BASE. THE SAW CUTTING SHALL ALIGN WITH THE LANE MARKING OR DIRECTION OF TRAFFIC IF THERE ARE NO LANE MARKINGS, AND PERPENDICULAR THERETO.
7. APPLY BITUMINOUS CURING COMPOUND OVER NEWLY PLACED CONCRETE BASE (SECTION 2.14 NYCDOT HIGHWAY SPECIFICATION).
8. WHEN THE EXISTING PAVEMENT IS ASPHALT MACADAM WITHOUT CONCRETE BASE. THE CONTRACTOR SHALL SAWCUT A WIDTH OF NOT LESS THAN $W + 1$ OF THE EXISTING PAVEMENT AND RESTORE THIS TO CONFORM TO THE EXISTING PAVEMENT AND SUB-BASE MATERIAL BUT MUST PLACE NOT LESS THAN 6" OF ASPHALT MACADAM ON 6" OF CRUSHED STONE AGGREGATE SIZED TO 1" TO 3". THE RESTORATION SHALL CONFORM TO THE TYPICAL TYPE RESTORATION ABOVE. WHERE NO MARKINGS EXIST THE ALIGNMENT SHALL BE SO THAT SAWCUT DOES NOT FALL UNDER A WHEEL TRACK.
9. WHEN X DISTANCE BETWEEN HOLES IS GREATER THAN 10 FT. FROM EDGE TO ABUTTING EDGE. THE CONCRETE BASE SHALL BE OPENED SEPARATE FOR EACH HOLE. A SERIES OF SMALL HOLES SPACED 10 FT. OR LESS FROM EDGE TO ABUTTING EDGE SHALL BE OPENED TO A CONTINUOUS TRENCH. SEE TYPE V RESTORATION.
10. ALL REPAIRS SHALL CONFORM TO TYPICAL TYPE RESTORATION I THRU V ABOVE.
11. FOR TRENCH OR HOLE RESTORATION AT BUS STOPS OF FULL DEPTH CONCRETE OR ANY FULL DEPTH CONCRETE PAVEMENT, SEE STANDARD DRAWING H-1050 FOR CONSTRUCTION DETAILS AND STANDARD DRAWING 1042B FOR RESTORATION DETAILS.
12. FOR RESTORATION OF CONCRETE COLLARS AROUND STEAM MANHOLES SEE STANDARD DRAWING H-1041. FOR BUS STOPS REFER TO STANDARD DRAWING H-1005 AND H-1005A.
13. NOTWITHSTANDING THE REQUIREMENTS SET FORTH PER THIS DRAWING, IT SHALL REMAIN THE CONTRACTOR'S RESPONSIBILITY TO COMPLY WITH ADDITIONAL REQUIREMENTS THAT MAY BE STIPULATED IN THE DOT PERMIT.

CHECKED BY: *M. Z.*


HWS-H1042A

| REVISION NO. | DESCRIPTION | DATE | APPROVED |
|--------------|-----------------------------------------------------------------------------------------------------|--------|----------|
| 1 | REVISED NON-PROTECTED STREETS TO PROTECTED. REVISED NOTES 1, 3, 7 | 3/1/16 | D. NG |
| 2 | REVISED AND CLASSIFIED ROADWAY RESTORATION DETAIL. ADDED NEW NOTES 7 & 13. REVISED NOTES 2, 6 & 11. | 3/1/16 | D. NG |


| | |
|--------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------|
| NEW YORK CITY Department of Transportation | |
| STANDARD TRENCH OR HOLE RESTORATION FOR STREETS PROTECTED BY NYC ADMINISTRATIVE CODE § 19-144 | |
| Approved: <i>[Signature]</i> Chief Engineer Department of Transportation | Approved: <i>[Signature]</i> Associate Commissioner Infrastructure/Design Department of Design + Construction |
| Date Issued: 3/15/16 | Scale: None Drawing # H-1042A |

NOTES


1. ALL TRENCHES SHALL BE BACKFILLED WITH GOOD TO EXCELLENT FILL AS PER THE NYC DEPARTMENT OF TRANSPORTATION SPECIFICATIONS.
2. BACKFILL MATERIAL SHALL BE DEPOSITED IN HORIZONTAL LAYERS NOT EXCEEDING 12" IN THICKNESS PRIOR TO COMPACTION. A MINIMUM OF 95% OF STANDARD MAXIMUM DENSITY WILL BE REQUIRED WHEN PLACING BACKFILL. LAYERS SHALL BE DEPOSITED TO PROGRESSIVELY BURY THE UTILITY TO EQUAL DEPTHS ON BOTH SIDES. COMPACTION SHALL BE ACHIEVED BY THE USE OF IMPACT HAMMERS, PLATE OR SMALL DRUM VIBRATORS OR PNEUMATIC BUTTON HEAD COMPACTION EQUIPMENT. HAND TAMPING IS NOT PERMITTED EXCEPT IN THE IMMEDIATE AREA OF THE UNDERGROUND FACILITY.
3. ALL MATERIALS USED IN THE RESTORATION SHALL CONFORM TO THE STANDARDS AND SPECIFICATIONS OF THE NYC DEPARTMENT OF TRANSPORTATION AND/OR SHALL BE APPROVED BY THE OCMC.
4. THE OUTLINE OF THE PATCH SHALL BE FULL DEPTH SAW CUTTING AT A MINIMUM DISTANCE OF 1'-6" FROM ALL EDGES OF THE EXCAVATION. (SEE SKETCH FOR DETAIL) THE BREAKUP WITH PNEUMATIC HAMMERS IS TO BEGIN AT THE CENTER OF THE PATCH AREA NOT AT THE SAW CUTS. IF THE CONTRACTOR SPALLS THE CONCRETE DURING THE REMOVAL, HE MUST MAKE A NEW SAW CUT OUTSIDE THE SAWED AREA AND REMOVE THE CONCRETE WITHOUT ADDITIONAL COMPENSATION.
5. TO MINIMIZE OR ELIMINATE PATCH HOCKING, PUMPING, AND BREAKUP, THE WIDTH OF THE PATCH SHALL NOT BE LESS THAN ONE FULL LANE WIDTH. HOWEVER, IF THE EXCAVATION EXTENDS INTO AN ADJACENT LANE THE CONCRETE IN THIS ADJACENT LANE IS TO BE REMOVED TO THE NEXT LONGITUDINAL JOINT (TO THE CURB LINE IF CUT IS IN CURB LANE). EXISTING JOINTS THEREBY REMOVED ARE TO BE RESTORED IN SUCH A MANNER SO THAT THE STRUCTURAL INTEGRITY OF THE ORIGINAL JOINT IS RETAINED. TIE BARS, IF PRESENT, SHALL IN ALL CASES BE RETAINED OR REPLACED.
6. THE EDGE OF THE PATCH SHALL NOT BE CLOSER THAN 10' TO THE NEAREST TRANSVERSE JOINT. IF SAID EDGE FALLS WITHIN THIS TEN (10) FOOT DISTANCE ALL CONCRETE UP TO THE JOINT SHALL BE REMOVED AND REPLACED TO SAID BOUNDARY. LIKEWISE, THE EDGE OF THE PATCH SHALL NOT BE CLOSER THAN 1'-0" BEYOND THE FAR SIDE OF THE HARDWARE. JOINTS MAY BE ROUGH FACED OR SMOOTH FACED BUT IN ALL CASES THE STRUCTURAL INTEGRITY OF THE EXISTING JOINT IS TO BE RETAINED. LOAD TRANSFER DEVICES, IF PRESENT, SHALL BE RETAINED OR REPLACED.
7. IMMEDIATELY PRIOR TO THE PLACING OF THE NEW CONCRETE ALL EXPOSED EDGES OF THE OLD CONCRETE SHALL HAVE A CEMENT-WATER-SAND GROUT OR EPOXY BONDING COMPOUND BRUSHED ON.
8. A WIRE MESH OF THE SAME SIZE AS THAT IN THE ORIGINAL PAVEMENT SHALL BE PLACED IN THE PATCH AREA. NO PHYSICAL TIE TO THE EXISTING MESH WILL BE REQUIRED. THIS MESH WILL BE PLACED APPROX. 2-1/2" BELOW THE ROADWAY SURFACE.
9. A CONVENTIONAL CONCRETE MIXTURE CONTAINING AN INCREASED CEMENT FACTOR (9 BAG MIX TYPE III CEMENT), REDUCED WATER CONTENT, SUPERPLASTICIZER AND AN ACCELERATOR IS TO BE USED SO THAT THE PATCH CAN BE OPENED TO TRAFFIC WITHIN A TWENTY-FOUR HOUR PERIOD, OR BEFORE, IF AND WHEN THE CONCRETE HAS OBTAINED A STRENGTH OF 2500 PSI OR BETTER. UNTIL THIS TIME THE PATCH SHALL BE PROTECTED FROM TRAFFIC BY PLATING AND/OR BARRICADING.
10. EXTRA ATTENTION IS TO BE GIVEN TO ENSURE THAT THE PATCH IS WELL VIBRATED AROUND THE EDGES AND THAT IT IS NOT OVER FINISHED. THE PATCH SHOULD BE STRUCK OFF TWO OR THREE TIMES TO ENSURE THAT ITS SURFACE IS EVEN WITH THE ADJACENT CONCRETE. THE FINISHED TEXTURE SHALL MATCH THAT OF THE ADJACENT PAVEMENT.
11. A CLEAR CURING AND SEALING COMPOUND SHALL BE APPLIED TO THE FINISHED SURFACE.



CONCRETE PAVEMENT
RESTORATION DETAIL
N.T.S.



DETAIL "A"
N.T.S.




PLAN VIEW
TYPICAL PATCH REPAIRS

- LEGEND
- EXCAVATION AREA
 - STREET HARDWARE
 - ▨ PATCH AREA


CHECKED BY: *MR*

| REVISION NO. | DESCRIPTION | DATE | APPROVED |
|--------------|-------------|------|----------|
| | | | |
| | | | |


| | |
|-----------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------|
| NEW YORK CITY Department of Transportation | |
| CONCRETE PAVEMENT RESTORATION | |
| Approved: <i>[Signature]</i> Chief Engineer Department of Transportation | Approved: <i>[Signature]</i> Associate Commissioner Infrastructure/Design Department of Design + Construction |
| Date issued: 7/1/10 | Scale: None Drawing # H-1042B |



PLAN



SECTION A-A



SECTION B-B

NOTES:



1. ALL UNDERMINED, DISTURBED OR UNSTABLE SUB BASE MATERIAL SHALL BE REMOVED PRIOR TO BACKFILLING. IT SHALL BE FULLY RESTORED AND COMPACTED WHILE THE TRENCH IS BEING FULLY BACKFILLED AND COMPACTED.
2. ALL TRENCHES SHALL BE BACKFILLED WITH MATERIAL MEETING NYC DEPARTMENT OF TRANSPORTATION STANDARD HIGHWAY SPECIFICATIONS, SECTION 4.11.
3. WHEN PLACING FILL OR BACKFILL AROUND PIPES OR OTHER UNDERGROUND FACILITIES, SIX (6") INCH LAYERS SHALL BE DEPOSITED TO PROGRESSIVELY BURY THE FACILITY TO EQUAL DEPTH ON BOTH SIDES AND FOR THE FULL DEPTH AND WIDTH OF THE TRENCH EXCAVATED FOR THE FACILITY. THE ABOVE METHOD OF FILL OR BACKFILL SUPERSEDES THE FILL OR BACKFILL METHODS AS SPECIFIED ELSEWHERE IN THE NYC DEPARTMENT OF TRANSPORTATION (DOT) STANDARD SPECIFICATIONS FOR THE PRIVATELY OWNED OR CITY OWNED UTILITIES. IN DEEP TRENCHES, IN LIEU OF DEPOSITING AND COMPACTING THE BACKFILL FROM TWO (2) FEET ABOVE THE UNDERGROUND FACILITY TO A PLANE FIVE (5) FEET BELOW FINAL SURFACE IN ACCORDANCE WITH THE ABOVE SPECIFIED PROCEDURE, THE CONTRACTOR MAY SUBMIT TO THE COMMISSIONER OF DEPT. OF TRANSPORTATION, FOR APPROVAL, AN ALTERNATE BACKFILL METHOD (i.e., PUDDLING, JETTING, DEEPER COMPACTION LAYERS, ETC.). THIS SUBMITTAL MUST FULLY DESCRIBE THE ALTERNATE METHOD, INCLUDING PROPOSED EQUIPMENT, BACKFILL MATERIAL, DEPTH OF COMPACTION LAYER AND TRENCH LOCATIONS WHERE IT WILL BE EMPLOYED. HOWEVER, APPROVAL OF ANY ALTERNATE BACKFILL METHOD SHALL NOT RELIEVE THE CONTRACTOR FROM OBTAINING A MINIMUM 95% STANDARD PROCTOR MAXIMUM DENSITY. SHOULD THE COMMISSIONER DETERMINE THAT THE SPECIFIED DENSITY IS NOT BEING OBTAINED, THE AREA MUST BE RE-EXCAVATED AND BACKFILLED UNTIL THE REQUIRED COMPACTION DENSITY IS ACHIEVED.
4. ALL RESTORATION SHALL CONFORM TO THE STANDARDS AND SPECIFICATIONS OF THE NYC D.O.T. AND IN PROCESS INSPECTION AND TESTING SHALL BE CERTIFIED BY A LICENSED PROFESSIONAL ENGINEER.
5. THE CONCRETE BASE OF THE EXISTING COMPOSITE PAVEMENT SHALL BE REMOVED WITH A BEVELED SAW CUT, AS SHOWN ON THE DETAIL, TO DIMENSIONS A MINIMUM OF SIX INCHES GREATER THAN THE EXCAVATION AT THE BASE OF THE BEVEL. ASPHALT SHALL BE REMOVED TO DIMENSIONS TWELVE INCHES GREATER THAN THE OPENING OF THE CONCRETE BASE AT THE TOP OF THE BEVEL BY SAW CUT AND GRINDING OR PEELING SO AS NOT TO DAMAGE THE CONCRETE BASE. ALL TRENCH RESTORATIONS SHALL BE SQUARE OR RECTANGULAR SHAPED.
6. THE BEVELED SAW CUT SURFACE SHALL BE ROUGHENED WITH A SMALL IMPACT HAMMER, 20 LBS. OR LESS, WITH A CHISEL POINT AT LEAST ONE INCH WIDE.
7. STEEL REINFORCING BARS, AS SPECIFIED ON THE DETAIL, SHALL BE GROUTED INTO DRILLED HOLES WITH CONCRETE GROUTING MATERIAL CONFORMING TO NEW YORK STATE DEPARTMENT OF TRANSPORTATION SPECIFICATION 701-05.
8. THE ROUGHENED BEVELED SURFACE SHALL BE AIR BLASTED TO REMOVE DUST AND LOOSE PARTICLES PRIOR TO COATING WITH A TWO COMPONENT BONDING COMPOUND CONFORMING TO NEW YORK STATE DEPARTMENT OF TRANSPORTATION SPECIFICATION 721-03, EPOXY POLYSULFIDE GROUT.
9. A CONVENTIONAL CONCRETE MIXTURE CONTAINING AN INCREASED CEMENT FACTOR (9 BAG MIX, TYPE III CEMENT), REDUCED WATER CONTENT, SUPERPLASTICIZER AND AN ACCELERATOR SHALL BE USED SO THAT THE RESTORATION CAN BE OPENED TO TRAFFIC WITHIN A TWENTY-FOUR HOUR PERIOD WHEN THE CONCRETE HAS ATTAINED A STRENGTH OF 2,500 PSI OR BETTER. UNTIL THIS TIME, THE RESTORATION SHALL BE PROTECTED FROM TRAFFIC BY PLATING AND/OR BARRICADING.
10. MATCH EXISTING TRANSVERSE JOINTS AND SAW CUTS IN EXISTING CONCRETE BASE.
11. INSTALL REFLECTIVE CRACKING MEMBRANE OVER EACH BEVELED SAW CUT. REPLACE OR PLACE REFLECTIVE CRACKING MEMBRANE OVER ALL TRANSVERSE JOINTS OR CRACKS THAT CARRY THROUGH. IF THE WIDTH OF THE RESTORATION IS TWO FEET OR LESS, PLACE THE REFLECTIVE CRACKING MEMBRANE OVER THE FULL WIDTH OF THE REPAIR.
12. APPLY BITUMINOUS CURING COMPOUND OVER NEWLY PLACED CONCRETE BASE (SECTION 2.14 NYCDOT HIGHWAY SPECIFICATION) AND A TACK COAT TO ALL EXPOSED CONCRETE SURFACES BEFORE INSTALLING NEW ASPHALTIC CONCRETE WEARING COURSE.

CHECKED BY: M. Z.

HWS-H1042C

| REVISION NO. | DESCRIPTION | DATE | APPROVED |
|--------------|------------------------|--------|----------|
| 1 | REVISED NOTES 1, 5, 12 | 3/1/16 | D. NG |

| | | | |
|-------------------------------------------------------------|--|-----------------------------------------------------------------------------------------------------|-------------------|
| | | New York City Department of Transportation | |
| ROADWAY RESTORATION FOR NEWLY CONSTRUCTED ROADWAYS | | | |
| Approved: Chief Engineer Department of Transportation | | Approved: Associate Commissioner Infrastructure/Design Department of Design + Construction | |
| Date Issued: <u>3/15/16</u> | | Scale: None | Drawing # H-1042C |



NOTES:

- ALL UNDERMINED, DISTURBED OR UNSTABLE SUB BASE MATERIAL SHALL BE REMOVED PRIOR TO BACKFILLING. IT SHALL BE FULLY RESTORED AND COMPACTED WHILE THE TRENCH IS BEING FULLY BACKFILLED AND COMPACTED.
- ALL TRENCHES SHALL BE BACKFILLED AS PER SECTION 4.11 OF NYCDOT STANDARD HIGHWAY SPECIFICATIONS.
- ALL TRENCH RESTORATIONS SHALL BE SQUARE OR RECTANGULAR SHAPED. SAW CUTTING BACK EXISTING ASPHALT PAVEMENT AND CONCRETE BASE, SQUARING AND ALIGNING OF CUT LIMITS TO BE PERFORMED ONLY AFTER COMPLETION OF THE COMPACTION OF THE BACKFILL TO THE BOTTOM OF THE BASE.
- BACKFILL MATERIAL SHALL BE DEPOSITED IN HORIZONTAL LAYERS NOT EXCEEDING 12" IN THICKNESS PRIOR TO COMPACTION. A MINIMUM OF 95% OF STANDARD PROCTOR MAXIMUM DENSITY WILL BE REQUIRED. WHEN PLACING BACKFILL AROUND PIPES, LAYERS SHALL BE DEPOSITED TO PROGRESSIVELY BURY THE PIPE TO EQUAL DEPTHS ON BOTH SIDES. COMPACTION SHALL BE ACHIEVED BY THE USE OF IMPACT RAMMERS, PLATE OR SMALL DRUM VIBRATORS OR PNEUMATIC BUTTON HEAD COMPACTION EQUIPMENT. HAND TAMPING IS NOT PERMITTED EXCEPT IN THE IMMEDIATE AREA OF THE UNDERGROUND FACILITY.
- ALL RESTORATION SHALL CONFORM TO THE STANDARDS AND SPECIFICATIONS OF NYC DEPARTMENT OF TRANSPORTATION AND IN PROCESS INSPECTION AND TESTING SHALL BE CERTIFIED BY A LICENSED PROFESSIONAL ENGINEER.
- WHEN THE EXISTING PAVEMENT IS ASPHALT ON CONCRETE BASE THEN THE RESTORATION SHALL BE AS SHOWN ON RESTORATION DETAIL. FOR NON-PROTECTED STREETS CONCRETE SHALL BE REMOVED TO A WIDTH OF $W + 1$ FOOT BY EITHER FULL DEPTH SAW CUTTING OR OTHER METHODS. ASPHALT SHALL BE REMOVED TO A WIDTH OF NOT LESS THAN $W + 3$ FEET BY SAW CUTTING AND GRINDING OR PEELING SO AS NOT TO DAMAGE CONCRETE BASE. THE SAW CUTTING SHALL ALIGN WITH THE LANE MARKING OR DIRECTION OF TRAFFIC IF THERE ARE NO LANE MARKINGS, AND PERPENDICULAR THERETO.
- APPLY BITUMINOUS CURING COMPOUND OVER NEWLY PLACED CONCRETE BASE (SECTION 2.14 NYCDOT HIGHWAY SPECIFICATION).
- WHEN THE EXISTING PAVEMENT IS ASPHALT MACADAM WITHOUT CONCRETE BASE. THE CONTRACTOR SHALL SAWCUT A WIDTH OF NOT LESS THAN $W + 1'$ OF THE EXISTING PAVEMENT AND RESTORE THIS TO CONFORM TO THE EXISTING PAVEMENT AND SUB-BASE MATERIAL BUT MUST PLACE NOT LESS THAN 6" OF ASPHALT MACADAM ON 6" OF CRUSHED STONE AGGREGATE SIZED TO 1" TO 3". THE RESTORATION SHALL CONFORM TO THE TYPICAL TYPE RESTORATION ABOVE. WHERE NO MARKINGS EXIST THE ALIGNMENT SHALL BE SO THAT SAWCUT DOES NOT FALL UNDER A WHEEL TRACK.
- WHEN X DISTANCE BETWEEN HOLES IS GREATER THAN 10 FT. FROM EDGE TO ABUTTING EDGE. THE CONCRETE BASE SHALL BE OPENED SEPARATE FOR EACH HOLE. A SERIES OF SMALL HOLES SPACED 10 FT. OR LESS FROM EDGE TO ABUTTING EDGE SHALL BE OPENED TO A CONTINUOUS TRENCH. SEE TYPE V RESTORATION.
- ALL REPAIRS SHALL CONFORM TO TYPICAL TYPE RESTORATION I THRU V ABOVE.
- FOR TRENCH OR HOLE RESTORATION AT BUS STOPS OF FULL DEPTH CONCRETE OR ANY FULL DEPTH CONCRETE PAVEMENT, SEE STANDARD DRAWING H-1050 FOR CONSTRUCTION DETAILS AND STANDARD DRAWING 1042B FOR RESTORATION DETAILS.
- FOR RESTORATION OF CONCRETE COLLARS AROUND STEAM MANHOLES SEE STANDARD DRAWING H-1041. FOR BUS STOPS REFER TO STANDARD DRAWING H-1005 AND H-1005A.
- NOTWITHSTANDING THE REQUIREMENTS SET FORTH PER THIS DRAWING, IT SHALL REMAIN THE CONTRACTOR'S RESPONSIBILITY TO COMPLY WITH ADDITIONAL REQUIREMENTS THAT MAY BE STIPULATED IN THE DOT PERMIT.

CHECKED BY: *M.7*

HWS-H1042D




| REVISION NO. | DESCRIPTION | DATE | APPROVED |
|--------------|-------------|------|----------|
| | | | |
| | | | |
| | | | |
| | | | |

| | | | |
|--------------------------------------------------------------------------------------------------------------------------------|--|------------------------------------------------------------------------------------------------------------------------|-------------------|
| NEW YORK CITY DOT | | New York City Department of Transportation | |
| STANDARD TRENCH OR HOLE RESTORATION FOR STREETS UNDER GUARANTEE BY NYC ADMINISTRATIVE CODE § 19-147 | | | |
| Approved: <i>[Signature]</i> Chief Engineer Department of Transportation | | Approved: <i>[Signature]</i> Associate Commissioner Infrastructure/Design Department of Design + Construction | |
| Date Issued: <i>3/15/16</i> | | Scale: None | Drawing # H-1042D |




1. EXPANSION JOINTS IN THE STEEL CURB FACING AND CONCRETE BACKING SHALL BE AT A MAXIMUM SPACING OF 24 FEET.
2. THE EXPANSION JOINTS OF THE CURB AND STEEL CURB FACING SHALL LINE UP WITH THE EXPANSION JOINTS OF THE CONCRETE SIDEWALKS.
3. NO PIECE OF STEEL CURB FACING HAVING LESS THAN TWO (2) WELDED DOWELS MAY BE INSTALLED UNLESS IT IS WELDED TO THE ADJACENT STEEL CURB FACING.
4. 1/2" Ø x 5" HEADED ANCHOR STUDS (GRANULAR OR SOLID FLUX FILLED) MAY BE SUBSTITUTED.
5. STRUCTURAL STEEL AS PER BOARD OF STD. SPECS. 20-S-35 TYPE A-1 (A.S.T.M. DESIGNATION A36).
6. SURFACE TO BE PAINTED SHALL BE THOROUGHLY CLEANED AND THEN PAINTED AS PER REQUIREMENTS OF SECTION 2.13 IN THE NYC DOT STANDARD HIGHWAY SPECIFICATIONS. THE COLOR OF TOP COAT SHALL BE GRAY AS APPROVED BY THE ENGINEER.
7. WHERE TWO (2) PIECES OF STEEL CURB FACING ARE JOINED BUT NOT WELDED, TWO (2) ONE-HALF (1/2) INCH RODS, TWENTY FOUR (24) INCHES LONG SHALL BE INSERTED INTO THE CONCRETE BACKING, ONE-HALF (1/2) THE LENGTH AT EACH SIDE OF THE JOINT.
8. CORNER CURB-VERTICAL FACE WILL BE ACCEPTABLE FOR CORNER CURBS PROVIDING THE ENDS ARE WARPED TO FORM A TRANSITION WITH ADJACENT BATTERED FACE CURBS.

ELEVATION-STEEL FACING FOR BRIDGE DECK CURBS
N.T.S.

| | | | |
|--------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------|-------------------------|--|
|  | <p>New York City Department of Transportation</p> | | |
| <p>STEEL FACED CURB STEEL FACING TYPE D FOR STRUCTURES</p> | | | |
| <p>Approved:</p>  | <p>Approved:</p>  | | |
| <p>Chief Engineer Department of Transportation</p> | <p>Associate Commissioner Infrastructure/Design Department of Transportation + Construction</p> | | |
| <p>Date Issued: <u>7/1/10</u></p> | <p>Scale: None</p> | <p>Drawing # H-1043</p> | |

| | | | |
|--------------|-------------|------|----------|
| | | | |
| | | | |
| | | | |
| REVISION NO. | DESCRIPTION | DATE | APPROVAL |

CHECKED BY: ME






NOTES:


1. ALL MATERIALS AND CONSTRUCTION METHODS USED ARE TO CONFORM TO SECTION #4.08 OF THE NYC DEPARTMENT OF TRANSPORTATION STANDARD HIGHWAY SPECIFICATIONS.

CHECKED BY: MZ


NYSDOT H-1044

| REVISION NO. | DESCRIPTION | DATE | APPROVED |
|--------------|-------------|------|----------|
| | | | |
| | | | |
| | | | |


| | | | |
|---------------------------------------------------------------------------------------------------------------------------------------------------|--|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------|
|  | | New York City Department of Transportation | |
| CONCRETE CURB | | | |
| Approved:  Chief Engineer Department of Transportation | | Approved:  Associate Commissioner Infrastructure/Design Department of Design + Construction | |
| Date issued: <u>7/1/10</u> | | Scale: None | Drawing # H-1044 |



**TYPE I - SIDEWALK, OUTSIDE DRIVEWAY
AND CORNER QUADRANTS**
N.T.S.



**TYPE II - SIDEWALK, IN DRIVEWAY
AND IN CORNER QUADRANTS**
N.T.S.



**TYPE III - SIDEWALK
WITH WELDED WIRE FABRIC**
N.T.S.

NOTES:

1. ALL MATERIALS AND CONSTRUCTION METHODS USED ARE TO CONFORM TO SECTION #4.13 OF THE NYC DEPARTMENT OF TRANSPORTATION (DOT) STANDARD HIGHWAY SPECIFICATIONS.
2. WELDED WIRE FABRIC, WHERE SPECIFIED, SHALL BE ASTM DESIGNATION A-185, GAUGE # 8/8 AT 6"x6" SPACING, AND CONFORM TO SECTION # 2.25 OF THE NYCDOT STANDARD HIGHWAY SPECIFICATIONS.

CHECKED BY: MZ


HWS-H1045

| REVISION NO. | DESCRIPTION | DATE | APPROVED |
|--------------|-------------|------|----------|
| | | | |
| | | | |
| | | | |


| | | | |
|-----------------------------------------------------------------|--|---------------------------------------------------------------------------------------------------------|------------------|
| | | New York City Department of Transportation | |
| CONCRETE SIDEWALK | | | |
| Approved: Chief Engineer Department of Transportation | | Approved: Associate Commissioner Infrastructure/Design Department of Design + Construction | |
| Date Issued: <u>7/1/10</u> | | Scale: None | Drawing # H-1045 |

NOTES:

1. ALL MATERIALS AND CONSTRUCTION METHODS USED ARE TO CONFORM TO SECTION # 4.16 OF THE STANDARD HIGHWAY SPECIFICATIONS, LATEST EDITION.
2. PRIOR TO THE START OF WORK, THE CONTRACTOR SHALL OBTAIN THE NECESSARY PERMIT FROM THE DEPT. OF PARKS AND RECREATION FOR THE REMOVAL AND PLANTING OF TREES.
3. TREE PITS SHOULD BE LOCATED TWO (2) FEET MINIMUM FROM GAS, OIL OR WATER BOXES.
4. TREE STAKES ARE TO BE REMOVED BY THE TREE SUBCONTRACTOR NOT LESS THAN ONE YEAR AFTER PLANTING OF SAID TREES AND PRIOR TO THE FINAL ACCEPTANCE OF THE WORK.
5. USE OF SIDEWALK PAVEMENT MATERIALS OTHER THAN GRANITE BLOCK MUST BE SPECIFICALLY APPROVED, IN WRITING, BY ENGINEER.
6. GRANITE BLOCK IN TREE PIT SHALL BE PAID FOR UNDER ITEM NO. 6.06 AB OR 6.06 BB, AS APPLICABLE.
7. WHERE CONCRETE PAVERS ARE SPECIFIED FOR USE IN TREE PITS THEY SHALL BE PAID FOR UNDER ITEM NO. 6.47 TP.




SECTION A-A



PLAN

TREE PLANTING, STAKING AND TREE PIT PAVEMENT DETAILS FOR SIDEWALK AREAS




TREE PITS SHALL BE 4' X 5' OR 5' X 5' OR 5' X 10' AS SPECIFIED



REQUIRED STREET TREE SPACING

| | | | |
|-----------------------------------------------------------------|-------------|---------------------------------------------------------------------------------------------------------|----------|
| NEW YORK CITY | | New York City Department of Transportation | |
| STREET TREE PLANTING DETAIL TYPE 1 | | | |
| Approved: Chief Engineer Department of Transportation | | Approved: Associate Commissioner Infrastructure/Design Department of Design + Construction | |
| Date Issued: 7/1/10 | | Scale: None Drawing # H-1046 | |
| REVISION NO. | DESCRIPTION | DATE | APPROVED |

CHECKED BY: MZ
HWS-H1046



SECTION A-A
DETAILS - PROTECTIVE TREE BARRIER


* WIDTH MAY BE REDUCED TO 5' ON NARROW
SIDEWALKS AS REQUIRED TO MAINTAIN
SIDEWALK CLEARANCE OF 3' (THREE FEET)
AT THE TREE BARRIERS ONLY.

CHECKED BY: MP

HWS-H1046A

| REVISION NO. | DESCRIPTION | DATE | APPROVED |
|--------------|-------------|------|----------|
| | | | |
| | | | |
| | | | |

| | | | |
|------------------------------------------------------------------------------------------------------------------------------------------------------|--|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------|
|  | | New York City Department of Transportation | |
| PROTECTIVE TREE BARRIER | | | |
| Approved:  Chief Engineer Department of Transportation | | Approved:  Associate Commissioner Infrastructure/Design Department of Design + Construction | |
| Date Issued: <u>7/1/10</u> | | Scale: None | Drawing # H-1046A |



NOTES:


1. BARREL MUST BE PLASTIC AND SPECIFICALLY DESIGNED AS A TRAFFIC CONTROL DEVICE. THE BARREL MUST BE FLATTENED ON AT LEAST ONE SIDE OR OTHERWISE DESIGNED SO THAT IT WILL NOT ROLL IF OVERTURNED.
2. THE BATTERY POWERED LIGHT IS FOR NIGHT USE ONLY. USE TYPE A LOW INTENSITY FLASHING LIGHT FOR POINT HAZARDS. USE TYPE C LOW INTENSITY STEADY BURN LIGHTS FOR CHANNELIZATION. THE LIGHT SHALL BE PHOTO CELL CONTROLLED FOR NIGHT USE.
3. ALL MATERIALS & METHODS USED ARE TO CONFORM TO SECTION #6.87 OF THE STANDARD SPECIFICATIONS, LATEST EDITION, AS AMENDED.

CHECKED BY: MB


MVS-H1049

| REVISION NO. | DESCRIPTION | DATE | APPROVED |
|--------------|-------------|------|----------|
| | | | |
| | | | |
| | | | |

| | | | |
|-------------------------------------------------------------|--|-----------------------------------------------------------------------------------------------------|------------------|
| NEW YORK CITY | | New York City Department of Transportation | |
| PLASTIC BARREL | | | |
| Approved: Chief Engineer Department of Transportation | | Approved: Associate Commissioner Infrastructure/Design Department of Design + Construction | |
| Date Issued: <u>7/1/10</u> | | Scale: None | Drawing # H-1049 |



METAL REINFORCEMENT FOR CONCRETE PAVEMENT
NOT TO SCALE




HINGE DETAIL
NOT TO SCALE


GENERAL NOTES:

1. WELDED WIRE FABRIC SHALL MEET REQUIREMENTS OF ASTM A-185.
2. WELDED WIRE FABRIC SHALL BE 4x4-W4xW4.
3. CONCRETE SHALL BE HIGH-EARLY STRENGTH AS SPECIFIED.
4. SHEETS MAY BE HINGED AS SHOWN IN THE DETAIL. HINGED SHEETS SHALL BE HINGED AT LEAST TWO LONGITUDINAL MEMBERS OFF CENTER, AND EACH ADJOINING SHEET SHALL BE REVERSED IN PLACING, IN ORDER THAT THE HINGES SHALL NOT OVERLAY EACH OTHER AT THE LAPS.
5. THE METAL REINFORCEMENT SHALL BE PLACED AT 1/2 DEPTH OF PAVEMENT.
6. THE DETAIL OF REINFORCEMENT IS SHOWN FOR HALF OF THE WIDTH OF THE ROADWAY AND IS SIMILAR IN THE OTHER HALF.
7. REINFORCEMENT FOR OTHER WIDTHS OF ROADWAY SHALL BE IN ACCORDANCE WITH THE DETAILS SHOWN, WITH APPROPRIATE DIMENSIONS.
8. CONCRETE PAVEMENT SURFACE TO BE TRANSVERSELY TEXTURED WITH A SET OF SPRING STEEL TINES (3/16\"


CONTINUED ON SHEET 2 OF 4



SECTION A-A
NOT TO SCALE



SECTION B-B
NOT TO SCALE



LAP DETAIL
NOT TO SCALE


CHECKED BY: MZ

| REVISION NO. | DESCRIPTION | DATE | APPROVED |
|--------------|-------------|------|----------|
| | | | |
| | | | |
| | | | |

| | |
|-------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------|
| | |
| <p>New York City Department of Transportation</p> | |
| <p>REINFORCED CONCRETE PAVEMENT CONSTRUCTION DETAILS</p> | |
| <p>Approved:</p> <p>Chief Engineer Department of Transportation</p> | <p>Approved:</p> <p>Associate Commissioner Infrastructure/Design Department of Design + Construction</p> |
| <p>Date Issued: <u>7/1/10</u></p> | <p>Scale: None</p> |
| <p>Drawing # H-1050-1</p> | |


GENERAL NOTES CONTINUED

9. ALL JOINT DOWELS MUST BE LEVEL, TRUE AND ADEQUATELY SUPPORTED SO THERE IS NO MOVEMENT DURING THE PLACEMENT OF CONCRETE.
10. DOWELS MUST BE PARALLEL TO THE CURB LINES AND THE SURFACE OF THE SLAB. TOLERANCE OF THIS PLACEMENT SHALL BE $\pm 1/4$ INCH.
11. THE CONCRETE SHALL BE DEPOSITED ON A MOIST GRADE IN SUCH MANNER AS TO REQUIRE AS LITTLE REHANDLING AS POSSIBLE. PLACING SHALL BE CONTINUOUS BETWEEN TRANSVERSE JOINTS WITHOUT THE USE OF INTERMEDIATE BULKHEADS. NECESSARY HAND SPREADING SHALL BE DONE WITH SHOVELS, NOT RAKES. WORKMEN SHALL NOT BE ALLOWED TO WALK ON THE FRESHLY MIXED CONCRETE WITH BOOTS OR SHOES COATED WITH EARTH OR FOREIGN SUBSTANCES.
12. CONCRETE SHALL BE THOROUGHLY CONSOLIDATED AGAINST AND ALONG THE FACES OF ALL FORMS AND ALONG THE FULL LENGTH AND ON BOTH SIDES OF ALL JOINTS ASSEMBLIES. VIBRATORS SHALL NOT BE PERMITTED TO COME IN CONTACT WITH A JOINT ASSEMBLY, THE GRADE, OR A SIDE FORM. THE VIBRATOR SHALL NEVER BE OPERATED LONGER THAN 10 SECONDS IN ANY ONE LOCATION.
13. CONCRETE SHALL BE DEPOSITED AS NEAR TO EXPANSION AND CONTRACTION JOINTS AS POSSIBLE WITHOUT DISTURBING THEM BUT SHALL NOT BE DUMPED ONTO A JOINT ASSEMBLY.
14. THE CONTRACTOR SHALL WITHIN EIGHT WEEKS OF THE NOTICE TO PROCEED PREPARE AND SUBMIT TO THE CHIEF ENGINEER OF HIGHWAY DESIGN DETAILED SHOP DRAWINGS FOR THE ENTIRE PAVEMENT, SHOWING: ALL PROPOSED TRANSVERSE AND LONGITUDINAL CONSTRUCTION, EXPANSION AND CONTRACTION JOINTS; PROPOSED CURB JOINTS; THE PROPOSED METHOD OF JOINT FORMING; THE PROPOSED METHOD OF DOWEL SUPPORT; AND THE PROPOSED SEALANT METHOD FOR THE PRIOR APPROVAL OF THE ENGINEER.
15. SAWING OF THE JOINTS SHALL BEGIN AS SOON AS THE CONCRETE HAS HARDENED SUFFICIENTLY TO PERMIT SAWING WITHOUT EXCESSIVE RAVELING. ALL JOINTS SHALL BE SAWED BEFORE UNCONTROLLED SHRINKAGE CRACKING OCCURS. IF NECESSARY, THE SAWING OPERATIONS SHALL BE CARRIED ON BOTH DAY AND NIGHT, REGARDLESS OF WEATHER CONDITIONS. A STANDBY SAW SHALL BE AVAILABLE IN THE EVENT OF BREAKDOWN.
16. THE SAWING OF ANY JOINT SHALL BE OMITTED IF A CRACK OCCURS AT OR NEAR THE JOINT LOCATION BEFORE THE TIME OF SAWING. SAWING SHALL BE DISCONTINUED IF A CRACK DEVELOPS AHEAD OF THE SAW. IN GENERAL, ALL JOINTS SHALL BE SAWED IN SEQUENCE. ALL CONTRACTION JOINTS IN LANES ADJACENT TO PREVIOUSLY CONSTRUCTED LANES SHALL BE SAWED BEFORE UNCONTROLLED CRACKING OCCURS. IF EXTREME CONDITIONS MAKE IT IMPRACTICABLE TO PREVENT ERRATIC CRACKING BY EARLY SAWING, THE CONTRACTION JOINT GROOVE SHALL BE FORMED BEFORE INITIAL SET OF THE CONCRETE BY APPROVED METHODS.



DETAIL OF EXPANSION JOINT
NOT TO SCALE


NOTE:
METAL REINFORCEMENT IS NOT SHOWN
ON JOINT DETAILS.



SAWED LANE JOINT
NOT TO SCALE

NOTE:


TRANSVERSE CONSTRUCTION JOINTS ARE NECESSARY FOR PLANNED INTERRUPTIONS, AND WHERE EMERGENCY INTERRUPTIONS SUSPEND OPERATIONS FOR 30 MINUTES OR MORE.



TYPICAL SECTION FOR
TRANSVERSE CONTRACTION JOINTS
NOT TO SCALE


NOTES: (APPLY TO ALL JOINTS)

1. THE JOINTS CAN BE COMPLETELY FILLED WITH SEALANT MATERIAL OR PREMOLDED JOINT FILLER CAN BE INSERTED IN THE JOINT FIRST TO REDUCE THE AMOUNT OF SEALANT REQUIRED.
2. SEALER TO BE POURED TO WITHIN 1/8" OF TOP OF PAVEMENT.
3. PRIOR TO SEALING, JOINT SURFACES MUST BE CLEANED AND FREE OF CURING COMPOUND, RESIDUE, LAITANCE AND ANY OTHER FOREIGN MATERIAL.
4. THE SURFACE SHOULD BE DRY WHEN THE SEALANT IS POURED.



**TYPICAL SECTION FOR TRANSVERSE AND
LONGITUDINAL CONSTRUCTION JOINTS**
NOT TO SCALE

| | | | |
|------------------------------------------------------------------------------------------------------------------------------------------------------|--|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------|
|  | | New York City Department of Transportation | |
| REINFORCED CONCRETE PAVEMENT CONSTRUCTION DETAILS | | | |
| Approved:  Chief Engineer Department of Transportation | | Approved:  Associate Commissioner Infrastructure/Design Department of Design + Construction | |
| Date Issued: <u>7/1/10</u> | | Scale: None | Drawing # H-1050-2 |



TRANSVERSE JOINT NOTES


- CONTRACTION JOINTS SHALL BE PROVIDED IN THE NEW PAVEMENT BY SAWING THE HARDENED SLAB OR BY PLACING AN INSERT OR GROOVE IN THE SLAB SURFACE WHILE THE CONCRETE IS PLASTIC.
- TRANSVERSE CONTRACTION JOINTS SHALL BE SKEWED JOINTS WITH A MAXIMUM SPACING OF 20 FEET AND A MINIMUM SPACING OF 15 FEET.
- TRANSVERSE JOINTS SHALL BE ALIGNED TO COINCIDE WITH THE JOINTS IN THE ADJACENT CURBS WHERE PRACTICAL.
- TRANSVERSE JOINTS ARE TO BE SAWED TO A DEPTH OF 1/4". ALL JOINTS ARE TO BE SAWED IN SUCCESSION AND SHOULD BE SAWED WHILE THE PAVEMENT IS UNDER COMPRESSION TO PREVENT THE SLAB FROM CRACKING AHEAD OF THE SAW.
- WHEN A WIDER JOINT-SEALANT RESERVOIR IS REQUIRED THE RESERVOIR MAY BE SAWED SIMULTANEOUSLY WITH THE INITIAL SAW CUT BY PLACING BLADES OF DIFFERENT SIZES ON THE MANDREL.
- PRIOR TO SEALING, THE JOINT SURFACES MUST BE CLEAN AND FREE OF CURING COMPOUND RESIDUE, LAITANCE, AND ANY OTHER FOREIGN MATERIAL.
- FIELD MOLDED SEALANTS MEETING AASHTO M173 AND/OR ASTM D1190 OR ASTM D1850 OR AN APPROVED EQUAL ARE TO BE PLACED AS PER MANUFACTURER'S RECOMMENDATIONS.
- THE SURFACES MUST BE DRY WHEN THE SEALANT IS PLACED AND THE JOINTS ARE TO BE FILLED TO 1/8" BELOW FLUSH WITH THE PAVEMENT SURFACE $\pm 1/16$ INCH.
- IF THE CONTRACTOR ELECTS TO USE PREFORMED SEALANTS THEY ARE TO MEET THE SPECIFICATIONS FOR AASHTO M220 AND/OR ASTM D2628. THE SHAPE FACTOR FOR THE JOINT SEALANT RESERVOIRS AS SHOWN ON THE PLANS ARE TO BE REVISED AS PER RECOMMENDATIONS OF THE MANUFACTURER OR SUPPLIER.
- IF AN EMERGENCY CONSTRUCTION JOINT OCCURS AT OR NEAR THE LOCATION OF A PLANNED CONTRACTION JOINT, A BUTT-TYPE JOINT WITH DOWEL BARS IS TO BE USED. IF SAID JOINT OCCURS IN THE MIDDLE THIRD OF THE NORMAL JOINT INTERVAL, A KEYED JOINT WITH TIE BARS IS TO BE USED.
- TRANSVERSE CONSTRUCTION JOINTS FALLING AT PLANNED LOCATIONS FOR CONTRACTION OR EXPANSION JOINTS ARE TO BE BUILT AND SEALED TO CONFORM WITH THE SPECIFICATIONS FOR THOSE JOINTS.

TYPICAL JOINT LAYOUT

(SEE GENERAL NOTE #14)

LONGITUDINAL JOINT NOTES

- LANE JOINTS ARE TO BE SAWED JOINTS (1/4" WIDE X 1/4D+1/2"). TIE BARS WILL NOT BE REQUIRED BUT A SEALANT RESERVOIR SIMILAR TO THOSE USED FOR THE TRANSVERSE CONTRACTION JOINTS MUST BE INSTALLED.
- THE CENTER LINE JOINT IS TO BE A KEYED CONSTRUCTION JOINT WITH TIE BARS SPACED AS SHOWN ON THE PLANS AND SET PERPENDICULAR TO THE CENTER LINE AND PARALLEL TO THE TOP OF THE SLAB.
- TIE BARS SHALL BE RIGIDLY SECURED BY CHAIRS OR OTHER APPROVED SUPPORTS TO PREVENT DISPLACEMENT.
- TIE BARS SHALL NOT BE COATED WITH ANY MATERIALS DELETERIOUS TO BOND.
- LONGITUDINAL JOINTS SHALL BE AT LEAST 1/4D+1/2" AND 1/4" WIDE.
- AFTER SAWING, THE JOINTS ARE TO BE FLUSHED OUT, DRIED AND SEALED TO ELIMINATE A SECOND CLEANING.
- THE SAWED GROOVE CAN BE COMPLETELY FILLED WITH SEALANT MATERIAL OR A ROPE, CORD OR OTHER APPROVED MATERIAL CAN BE INSERTED IN THE GROOVE FIRST TO REDUCE THE AMOUNT OF SEALANT REQUIRED.
- JOINTS ARE TO BE FILLED TO 1/8" BELOW FLUSH WITH THE PAVEMENT SURFACE $\pm 1/16$ INCH.
- NOTES 6, 7, 8, AND 9 UNDER TRANSVERSE JOINTS APPLY TO LONGITUDINAL JOINTS ALSO.



E=EXPANSION JOINT
C=CONSTRUCTION JOINT

KEY

NOTE:


FOR ADDITIONAL NOTES SEE SHEETS 1 AND 2.

CHECKED BY: MZ


NYSDOT-H1050-3

| REVISION NO. | DESCRIPTION | DATE | APPROVED |
|--------------|-------------|------|----------|
| | | | |
| | | | |
| | | | |

| | | | |
|--------------------------------------------------------------|--|-----------------------------------------------------------------------------------------------------|--------------------|
| NEW YORK CITY | | New York City Department of Transportation | |
| REINFORCED CONCRETE PAVEMENT CONSTRUCTION DETAILS | | | |
| Approved: Chief Engineer Department of Transportation | | Approved: Associate Commissioner Infrastructure/Design Department of Design + Construction | |
| Date Issued: <u>7/1/10</u> | | Scale: None | Drawing # H-1050-3 |




TYPICAL TRANSVERSE JOINT DETAIL
NOT TO SCALE




- NOTES - SAWCUT**
- ① APPLY ASPHALT TACK COAT TO ALL SURFACES.
 - ② PAYMENT WILL BE MADE FOR NUMBER OF LINEAR FEET OF SAW-CUTTING AS ORDERED BY ENGINEER.
 - ③ EXISTING ASPHALT TO BE REMOVED UNDER OTHER ITEMS AND THE ADJUSTMENT AREA RESTORED WITH NEW 3" A.C.W.C. ON NEW BINDER MIXTURE AS REQUIRED TO MATCH THE EXISTING ASPHALT PAVEMENT.

DETAIL OF SAW CUT AT END OF NEW PAVEMENT
NOT TO SCALE



DETAIL AT THE JUNCTION OF PAVEMENT AND CURB
NOT TO SCALE


- CASE I**
JOINT, IF CONTINUED, WILL PASS THRU THE MANHOLE BUT NOT THRU THE CENTER.
- CASE II**
JOINT, IF CONTINUED, WILL PASS WITHIN 1'-0" OF MANHOLE RIM.
- CASE III**
JOINT CLEARS THE MANHOLE RIM BY 1'-0" OR MORE.




DETAILS FOR SLAB JOINT/MANHOLE ARRANGEMENTS
NOT TO SCALE

PAVEMENT LIMITS

1. THE LIMITS OF CONCRETE PAVEMENT IN THE INTERSECTING STREETS SHALL BE APPROXIMATELY AT THE BUILDING LINE ALONG ROADWAY. PLACED SO AS NOT TO INTERSECT ANY STREET HARDWARE.
2. ADJUSTMENT AREAS SHALL BE AS DIRECTED BY THE ENGINEER. (5' TO 15') AND SHALL NOT INTERSECT ANY STREET HARDWARE.





| | | | |
|-------------------------------------------------------------|-------------|-----------------------------------------------------------------------------------------------------|--------------------|
| NEW YORK CITY | | New York City Department of Transportation | |
| REINFORCED CONCRETE PAVEMENT CONSTRUCTION DETAILS | | | |
| Approved: Chief Engineer Department of Transportation | | Approved: Associate Commissioner Infrastructure/Design Department of Design + Construction | |
| Date Issued: 7/1/10 | | Scale: None | Drawing # H-1050-4 |
| REVISION NO. | DESCRIPTION | DATE | APPROVED |
| | | | |
| | | | |
| | | | |



NOTES:

1. ALL MATERIAL AND CONSTRUCTION METHODS USED ARE TO CONFORM TO SECTION # 7.15 OF THE NYC DEPARTMENT OF TRANSPORTATION STANDARD HIGHWAY SPECIFICATIONS.
2. ALL FASTENERS SHALL BE GALVANIZED INDUSTRIAL STANDARD.
3. 2'-8" DIMENSION IS FROM FRONT OF STEP TO TOP OF POST.
4. TOP OF RAIL TO BE PLANE SMOOTH.





CHECKED BY: *MB*

MWS-H1051

| REVISION NO. | DESCRIPTION | DATE | APPROVED |
|--------------|-------------|------|----------|
| | | | |
| | | | |
| | | | |

| | | | |
|-----------------------------------------------------------------|--|---------------------------------------------------------------------------------------------------------|------------------|
| NEW YORK CITY | | New York City Department of Transportation | |
| TEMPORARY WOODEN STEPS | | | |
| Approved: Chief Engineer Department of Transportation | | Approved: Associate Commissioner Infrastructure/Design Department of Design + Construction | |
| Date Issued: 7/1/10 | | Scale: None | Drawing # H-1051 |



NOTES:


- *1. 20' MAXIMUM UNLESS OTHERWISE SPECIFIED.
2. CONCRETE BASE FOR AREA OF ADJUSTMENT AND NEW ROADWAY PAVEMENT BASE TO BE KEYED TOGETHER.
3. CROWN OF MAJOR ROADWAY TO BE MAINTAINED. TRANSITION CROWN OF SIDE STREET TO MEET MAIN STREET GUTTER LINE. (MAIN STREET WATER FLOW ACROSS SIDE STREET TO BE MAINTAINED).
4. CONCRETE PAVEMENT EDGE TO BE MIN. OF 1'-0" FROM EDGE OF STREET HARDWARE.
5. ASPHALT CONCRETE FOR AREA OF ADJUSTMENT AND NEW ROADWAY PAVEMENT TO BE PLACED MONOLITHICALLY UNLESS OTHERWISE ORDERED BY THE ENGINEER.
6. TACK COAT (SECTION 6.58) ALL EDGES.
7. ADDITIONAL THICKNESS GREATER THAN 3" A.C.W.C. WILL BE PAID FOR UNDER ASPH. CONC. MIXTURE (ITEM 4.02 CB) OR BINDER MIXTURE (ITEM 4.02 CA).

CHECKED BY: MR

HVS-H1053


| REVISION NO. | DESCRIPTION | DATE | APPROVED |
|--------------|-------------|------|----------|
| | | | |
| | | | |
| | | | |

| | | | |
|-----------------------------------------------------------------------------|--|---------------------------------------------------------------------------------------------------------|------------------|
| NEW YORK CITY DOT | | New York City Department of Transportation | |
| DETAILS FOR CONSTRUCTING AREAS OF ADJUSTMENT AND TRANSITION SECTIONS | | | |
| Approved: Chief Engineer Department of Transportation | | Approved: Associate Commissioner Infrastructure/Design Department of Design + Construction | |
| Date Issued: <u>7/1/10</u> | | Scale: None | Drawing # H-1053 |




IN ROADWAY AREA
ADJACENT TO ALL NEW
CURB INCLUDING CORNERS

* 3" THICK AND 2.6 FT. WIDE IN TEMPORARY
PEDESTRIAN RAMPS AT CORNERS AFTER NEW
CONCRETE BASE IS PLACED. (RAMP SIMILAR
TO DETAIL 5)




IN FULL WIDTH SIDEWALK AREA
ADJACENT TO ALL NEW
CURB EXCEPT AT CORNERS

BACKFILL WITH SOIL IN STRIP SIDEWALK
AREA (NO DIRECT PAYMENT)




IN ROADWAY AREA, OVER
12" D.I. PIPE CONNECTION




SECTION A-A

4" THICK IN ROADWAY AREA AROUND ALL NEW
CATCH BASINS AND AT ABANDONED BASIN
LOCATIONS.




SECTION A-A


IN ROADWAY AREA AROUND
EVERY NEW OR MODIFIED
MANHOLE




NEW TREE PIT CUTOUT
(FULL WIDTH SIDEWALK ONLY)
* OR FULL LENGTH OF EXTENDED TREE PIT.



2" THICK IN SIDEWALK AREA
ADJACENT TO THE CURB AT
ALL CORNERS




IN ROADWAY OVER NEW
TRAFFIC SIGNAL OR FIRE
COMMUNICATION LINE
TRENCHES



SECTION A-A

WHEN AREA ③
IS UNDER CONSTRUCTION



NOTES:

- PAYMENT FOR FURNISHING, DELIVERING, PLACING, AND REMOVAL OF TEMPORARY RESTORATION OF PAVEMENT SHALL BE MADE UNDER ITEM NO. 4.02 CB. TYPICAL LIMITS OF PAYMENT FOR TEMPORARY PAVEMENT RESTORATION, USING ITEM NO. 4.02 CB, ARE SHOWN ABOVE. NO ADDITIONAL PAYMENT FOR ITEM 4.02 CB, WILL BE MADE BEYOND THE LIMITS SHOWN ABOVE, UNLESS OTHERWISE DIRECTED BY THE ENGINEER TO MAKE THE WORK SITE SAFE OR AS SPECIFIED UNDER NOTE 2, BELOW.
- TEMPORARY PAVEMENT FOR TRENCH RESTORATIONS SHALL BE DONE IN ACCORDING TO THE REQUIREMENTS OF SECTION 4.08 IN BOTH THE NYCDEP STANDARD SEWER SPECIFICATIONS AND THE NYCDEP STANDARD WATER MAIN SPECIFICATIONS, DATED AUGUST 1, 2009, AND PAID FOR UNDER ITEM NO. 4.02 CB.
- UNLESS OTHERWISE SHOWN ON PLAN OR DIRECTED BY THE ENGINEER, ASPHALTIC CONCRETE MIXTURE PLACED FOR TEMPORARY RESTORATION OF PAVEMENT SHALL HAVE A THICKNESS OF 4" IN THE ROADWAY PAVED AREAS AND A THICKNESS OF 2" IN THE SIDEWALK PAVED AREAS.

CHECKED BY: M75

NYSDOT-H-1054



New York City
Department of Transportation

LIMITS OF MEASUREMENT FOR PAYMENT OF TEMPORARY ASPHALT PAVEMENT

Approved:

[Signature]

Chief Engineer
Department of Transportation

Approved:

[Signature]

Associate Commissioner
Infrastructure/Design
Department of Design + Construction


Date Issued:

7/1/10

Scale:
None

Drawing # H-1054

| REVISION NO. | DESCRIPTION | DATE | APPROVED |
|--------------|-------------|------|----------|
| | | | |
| | | | |
| | | | |




PAVEMENT KEY-TYPE A
ITEM 6.51A
N.T.S.

NOTES:


1. THICKNESS OF ASPHALTIC CONCRETE WEARING COURSE OVER SAW-CUT EDGE SHALL BE ZERO INCHES.
2. THICKNESS OF ASPHALTIC CONCRETE WEARING COURSE OVER CHISEL-CUT EDGE SHALL BE A MINIMUM OF ONE INCH.
3. MATERIAL USED TO FILL WITHIN LIMITS OF PAVEMENT KEY TYPE A SHALL BE PAID FOR UNDER ITEM 6.51A TYPE A KEY.
4. PAYMENT FOR FEATHERED ASPHALTIC CONCRETE WEARING COURSE ITEMS OVER PAVEMENT KEY. TYPE A SHALL BE FOR FULL THICKNESS OF ASPHALTIC CONCRETE WEARING COURSE AS ORDERED BY THE ENGINEER.
5. 2"x12" PLANK TO BE PLACED IN KEY WHEN STREET IS OPENED TO TRAFFIC. PLANK TO BE REMOVED PRIOR TO PAVING.

LEGEND:

--- PAVEMENT KEY




**PLAN
TYPICAL LOCATION**
N.T.S.



PAVEMENT KEY - TYPE B-1
ITEM 6.51 B-1
N.T.S.

NOTES:


1. WHERE THERE IS NO CONCRETE BASE, OR WHERE IT IS NECESSARY TO REMOVE CONCRETE BASE SUBSEQUENT TO INSTALLING TYPE "B" PAVEMENT KEY, PAYMENT FOR DEPTHS GREATER THAN 3" WILL BE MADE UNDER ITEM 6.02AA, UNCLASSIFIED EXCAVATION.
2. CONTRACTOR MAY AT HIS OPTION, EITHER STRIP OR GRIND THE AREA TO THE REQUIRED DEPTH. IF THE CONTRACTOR CHOOSES TO STRIP THERE WILL BE NO ADDITIONAL PAYMENT FOR OVER-CUTTING OR ADDITIONAL BINDER.
3. THIS ITEM WHEN ORDERED BY THE ENGINEER WILL BE USED TO ELIMINATE HIGH POINTS IN THE EXISTING PAVEMENT PRIOR TO RESURFACING.
4. (A.O.B.E.) AS ORDERED BY ENGINEER.



PAVEMENT KEY - TYPE B-2
ITEM 6.51 B-2
N.T.S.

NOTES:

1. WHERE THERE IS NO CONCRETE BASE, OR WHERE IT IS NECESSARY TO REMOVE CONCRETE BASE SUBSEQUENT TO INSTALLING TYPE "B" PAVEMENT KEY, PAYMENT FOR DEPTHS GREATER THAN 3" WILL BE MADE UNDER THE UNCLASSIFIED EXCAVATION ITEM.
2. THE CONTRACTOR IS TO GRIND THE AREAS TO THE REQUIRED DEPTH USING AN ACCEPTABLE GRINDING METHOD.
3. THIS ITEM WHEN ORDERED BY THE ENGINEER WILL BE USED TO ELIMINATE HIGH POINTS IN THE EXISTING PAVEMENT PRIOR TO RESURFACING.
4. (A.O.B.E.) AS ORDERED BY ENGINEER.



PAVEMENT KEY - TYPE C
ITEM 6.51C
N.T.S.

NOTES:

1. IF THE EXISTING CURB REVEAL E" IS GREATER THAN 2-1/2" THIS PAVEMENT KEY WILL NOT BE REQUIRED.
2. PAYMENT FOR THIS ITEM SHALL BE THE NUMBER OF TONS OF BOTH THE WEARING COURSE AND BINDER MIXTURE INCORPORATED INTO THE WORK. PAYMENT SHALL INCLUDE, SAW CUTTING, EXCAVATION (INCLUDING CONCRETE BASE REMOVAL IF REQUIRED), TACK COATING AND PLACING OF THE NEW BINDER MIXTURE AND 1 1/2" WEARING COURSE.
3. (A.O.B.E.) AS ORDERED BY THE ENGINEER.
4. THE CONTRACTOR MAY AT HIS OPTION, EITHER STRIP, EXCAVATE OR GRIND THE AREA TO THE REQUIRED DEPTH.

CHECKED BY: *M2E*

HWS-H1055



New York City
Department of Transportation

**PAVEMENT KEY
TYPE A, B-1, B-2, C**

Approved:

[Signature]
Chief Engineer
Department of Transportation

Approved:

[Signature]
Associate Commissioner
Infrastructure/Design
Department of Design + Construction

Date Issued:


7/1/10

Scale:



None

Drawing # H-1055

| REVISION NO. | DESCRIPTION | DATE | APPROVED |
|--------------|-------------|------|----------|
| | | | |
| | | | |
| | | | |





DIMENSIONS AND FINISH ON GRANITE CURB
N.T.S.

- | | | | |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------|
|  | | <p align="center">New York City Department of Transportation</p> | |
| <p align="center">TYPICAL GRANITE CURB</p> | | | |
| <p>Approved: </p> <p>Chief Engineer Department of Transportation</p> | | <p>Approved: </p> <p>Associate Commissioner Infrastructure/Design Department of Design + Construction</p> | |
| <p>Date Issued: <u>7/1/10</u></p> | | <p>Scale: None</p> | <p>Drawing No: H-1056</p> |

CHECKED BY: MF

HWS-H1058




TYPICAL DETAIL OF NY HISTORICAL
GRANITE CURB INSTALLATION
N.T.S.


CHECKED BY: MJO

1055A


| | | | |
|-----------------------------------------------------------------|-------------|---------------------------------------------------------------------------------------------------------|-------------------|
| NEW YORK CITY | | New York City Department of Transportation | |
| HISTORICAL CURB DETAIL | | | |
| Approved: Chief Engineer Department of Transportation | | Approved: Associate Commissioner Infrastructure/Design Department of Design + Construction | |
| Date Issued: <u>7/1/10</u> | | Scale: None | Drawing # H-1056A |
| REVISION NO. | DESCRIPTION | DATE | APPROVED |
| | | | |
| | | | |
| | | | |



PLAN
N.T.S.



ALTERNATE (A)
SECTION
N.T.S.



ALTERNATE (B)
SECTION
N.T.S.

TEMPORARY STORAGE AREA
PROJECT NAME
CONTRACTOR'S NAME
FIELD OFFICE ADDRESS
TELEPHONE NO.:

DETAIL ①
INFORMATION SIGN


***NOTES**

- NO DIRECT PAYMENTS FOR MAINTENANCE OF TRAFFIC CONTROL DEVICES.
- PROVIDE TAPER AT APPROACH END TO CHANNELIZE TRAFFIC PER NATIONAL MUTCD WITH NYS SUPPLEMENT.

CHECKED BY: MB
MWS-H1057

| REVISION NO. | DESCRIPTION | DATE | APPROVED |
|--------------|-------------|------|----------|
| | | | |
| | | | |
| | | | |

| | | | |
|-------------------------------------------------------------|--|-----------------------------------------------------------------------------------------------------|------------------|
| NEW YORK CITY | | New York City Department of Transportation | |
| TEMPORARY STORAGE AREA | | | |
| Approved: Chief Engineer Department of Transportation | | Approved: Associate Commissioner Infrastructure/Design Department of Design + Construction | |
| Date Issued: <u>2/1/10</u> | | Scale: None | Drawing # H-1057 |



NOT TO SCALE

NOTES:

1. MEAN LOW WATER VARIES FROM -1.5 TO -3.5
U.S. COASTAL AND GEODETIC SURVEY DATUM
DEPENDING ON DISTANCE FROM THE OCEAN.
2. MEAN HIGH WATER VARIES FROM +2.0 TO +4.0
U.S. COASTAL AND GEODETIC SURVEY DATUM
DEPENDING ON DISTANCE FROM THE OCEAN.
3. UNITS SHOWN ON THIS SHEET ARE IN "FEET".


CHECKED BY: MZ
HWS-MS1000

| | | | |
|--------------|-------------|------|----------|
| | | | |
| | | | |
| | | | |
| REVISION NO. | DESCRIPTION | DATE | APPROVED |

| | | | |
|------------------------------------------------|--|----------------------------------------------------------------------------------------|-------------------|
| | | New York City Department of Transportation | |
| NEW YORK CITY COMPARISON OF DATUM PLANES | | | |
| Approved: | | Approved: | |
| Chief Engineer Department of Transportation | | Associate Commissioner Infrastructure/Design Department of Design + Construction | |
| Date Issued: <u>7/1/10</u> | | Scale: None | Drawing # MS-1000 |

STANDARD DRAWINGS

| | |
|-----------------------------------|--------|
| STEEL FACED CURB, TYPE D | H-1010 |
| SIDEWALK PEDESTRIAN RAMP | H-1011 |
| STEEL FACED DROP CURB (DRIVEWAYS) | H-1015 |
| CONCRETE CURB | H-1044 |
| CONCRETE SIDEWALK | H-1045 |




SIDEWALK VIOLATION & PAYMENT
N.T.S.

CHECKED BY: MS
HWS-MS1001

| | | | |
|--------------|-------------|------|----------|
| | | | |
| REVISION NO. | DESCRIPTION | DATE | APPROVED |

| | | | |
|------------------------------------------------------------------------------------------------------------------------------------------------------|--|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------|
|  | | New York City Department of Transportation | |
| SIDEWALK PAVEMENT LIMITS | | | |
| Approved:  Chief Engineer Department of Transportation | | Approved:  Associate Commissioner Infrastructure/Design Department of Design + Construction | |
| Date Issued: <u>7/1/10</u> | | Scale: None | Drawing # MS-1001 |




CHECKED BY: MZ


MS-MS1003

| REVISION NO. | DESCRIPTION | DATE | APPROVED |
|--------------|-------------|------|----------|
| | | | |
| | | | |
| | | | |

| | | | |
|---------------------------------------------------------------|--|-----------------------------------------------------------------------------------------------------|-------------------|
| NEW YORK CITY DOT | | New York City Department of Transportation | |
| TYPICAL ROADWAY CROSS-SECTION/RESURFACING | | | |
| Approved: Chief Engineer Department of Transportation | | Approved: Associate Commissioner Infrastructure/Design Department of Design + Construction | |
| Date Issued: <u>7/1/10</u> | | Scale: None | Drawing # MS-1003 |



PLAN
N.T.S.



SECTION A-A
N.T.S.

NOTES


1. UPON BEING ORDERED BY THE ENGINEER TO PERFORM THIS REQUIRED ADJUSTMENT, THE CONTRACTOR IS TO FIELD INVESTIGATE EACH LOCATION AND DETERMINE THE HEIGHT REQUIRED TO BRING GRATING TO THE PROPOSED GRADE.
2. THIS METHOD OF ADJUSTMENT MAY BE USED ONLY WHERE AN UPWARD ADJUSTMENT OF 3" TO 5" IS REQUIRED AND WHERE ORDERED BY THE ENGINEER.
3. THE ADJUSTMENT COLLAR WHEN INSTALLED SHALL HAVE NO LATERAL OR VERTICAL MOVEMENT OF ANY KIND.
4. EACH GRATING WHEN SET ON NEW SEAT SHALL BEAR EVENLY SO THAT NO VERTICAL MOVING OR ROCKING OCCURS DURING TRAFFIC.
5. THE CONTRACTOR MAY USE AN APPROVED EQUAL ADJUSTMENT FRAME.
6. NO WORK SHALL PROCEED UNTIL SHOP DRAWINGS HAVE BEEN SUBMITTED AND APPROVED BY THE DEPARTMENT.

CHECKED BY: HR


MS-1004

| REVISION NO. | DESCRIPTION | DATE | APPROVED |
|--------------|-------------|------|----------|
| | | | |
| | | | |
| | | | |

| | | | |
|-------------------------------------------------------------|--|-----------------------------------------------------------------------------------------------------|-------------------|
| NEW YORK CITY | | New York City Department of Transportation | |
| CATCH BASIN ADJUSTMENT - TYPE 2 | | | |
| Approved: Chief Engineer Department of Transportation | | Approved: Associate Commissioner Infrastructure/Design Department of Design + Construction | |
| Date Issued: <u>7/1/10</u> | | Scale: None | Drawing # MS-1004 |



PLAN
N.T.S.



ELEVATION
N.T.S.
SECTION A-A

CHECKED BY: MA

NYSDOT MS-1005

| REVISION NO. | DESCRIPTION | DATE | APPROVED |
|--------------|-------------|------|----------|
| | | | |
| | | | |
| | | | |

| | | | |
|-------------------------------------------------------------|--|-----------------------------------------------------------------------------------------------------|-------------------|
| NEW YORK CITY | | New York City Department of Transportation | |
| ADJUSTMENT AT CATCH BASINS | | | |
| Approved: Chief Engineer Department of Transportation | | Approved: Associate Commissioner Infrastructure/Design Department of Design + Construction | |
| Date Issued: <u>7/1/10</u> | | Scale: None | Drawing # MS-1005 |