

*The Citywide LTCP shall include the East River and Open Waters

LTCP Submittal Dates

CSO Watershed	LTCP Due Date	
Alley Creek	Submitted to DEC June 2014	
Westchester Creek	Submitted to DEC June 2014	
Hutchinson River	Submitted to DEC September 2014	
Flushing Creek	Submitted to DEC December 2014	
Bronx River	Submitted to DEC June 2015	
Gowanus Canal	Submitted to DEC June 2015	
Flushing Bay	June 2016	
Coney Island Creek	June 2016	
Jamaica Tributaries & Bay	June 2017	
Newtown Creek	June 2017	
Harlem River	Due Date Pending	
Citywide*	Due Date Pending	



CSO Improvement Projects

1995–2013:

- 4 CSO Storage Tanks (118 MG)
- Pumping Station Expansion (Additional 60 MGD)
- Floatables Control (Bronx & Gowanus)
- NYC Green Infrastructure Program Initiated

2014-2030:


- Wet Weather Maximization (Tallman Island)
- Dredging (Paerdegat & Hendrix Creek)
- Flushing Tunnel and PS Upgrades (Gowanus)
- Aeration (Newtown Creek)
- Regulator Modifications (Westchester Creek, Newtown Creek, Jamaica Tributaries)
- Sewer Work (Pugsley Creek, Fresh Creek HLSS, Belt Pkwy Crossing, and Flushing Bay Low Lying Sewers)
- Plant Wet Weather Stabilization
- Dredging (Flushing Bay)
- GI Program to manage 1" of rain on 4% of impervious surfaces in CS area by 2020, and 10% by 2030

Total Costs:

Grey Infrastructure: \$2.7 Billion

Green Infrastructure: \$1.5 Billion

\$4.2 Billion






Rainfall Selection for Model Updates

Evaluated a comprehensive range of rainfall data:


- Historical data range:
 42 years from 1969 to 2010
- Four representative rainfall gauges: Central Park, LGA, JFK, and ERW
- Selected 2008 JFK rainfall as the most representative of average annual rainfall across all four gauges





Model Calibration & Updates

- Calibrated with Harbor Survey and LTCP sampling data
- Future wastewater flows based on 2040 population projections
- Recalibrated 2012 InfoWorks based on revised impervious areas
- Alternative Model runs based on 1-yr data (JFK 2008 "Typical Year Rainfall")
- Selected Plan Model runs based on 10-yr data (2001 to 2011) to address elevated rainfall amount due to climate change







CSO Mitigation Toolbox


	INCREASING COMPLEXITY						
INCREASING COST	Source Control	Additional Green Infrastructure		High Level Sewer Separation (HLSS)			
	System Optimization	Fixed Weir	Parallel Interceptor / Sewer	Bending Weirs Control Gates	Pump Station Expansion		
	CSO Relocation	Gravity Flow Tipping to Other Watersheds	Pumping Station Modification	Flow Tipping with Conduit / Tunnel and Pumping			
	Water Quality / Ecological Enhancement	Floatables Control	Dredging	Dissolved Oxygen Improvement	Flushing Tunnel		
	Treatment Satellite:	Outfall Disinfection	Retention Treatment Basin (RTB)		High Rate Clarification (HRC)		
	Centralized:	WWTP Expansion					
	Storage	In-System	Shaft	Tank	Tunnel		




Potential LTCP Alternatives


















Flushing Creek LTCP Preferred Alternative

Disinfection for Outfalls TI-010 and TI-011



TI-010

Recreational Season Disinfection at Influent Screens & Regulator Chamber DC5 (May 1st to October 31st)



TI-011

Recreational Season Disinfection Downstream of Regulator 9 (May 1st to October 31st)



History of Chlorination

Chlorination of sewage remains the most common practice of wastewater disinfection today

1890's	Became common practice in English municipal water treatment
1908	Application proven effective in Chicago and Jersey City water districts
1910	City of Philadelphia first to chlorinate wastewater in U.S.
1911	First application in NYC for disinfection of Croton water supply
1918	Over 1,000 U.S. cities use chlorination for drinking water supplies
1936	First application in NYC for seasonal disinfection of wastewater effluent
Today	Most widely-used disinfectant for water & wastewater treatment in the U.S.



CSO Disinfection

Disinfection with sodium hypochlorite (liquid chlorine) is practiced nationwide for CSO treatment

Key Benefits

- Liquid chlorine is best suited for the intermittent and variable character of CSO discharges.
- Other disinfection methods are not as effective, reliable or economical.
- Extensive experience nationwide for CSO treatment.
- NYCDEP has extensive experience in storing, handling, and applying liquid chlorine at water and wastewater facilities.



Common Methods of Disinfection

	%Utilization across USA* (WWTPs > 1 mgd)	Benefits	Challenges
Chlorine	e 75.3 %	 Effective against a wide range of pathogens Relatively inexpensive 	Residual chlorine can be toxic to some aquatic life
UV	20.6 %	Effective against a wide range of pathogens	 Relatively expensive Energy intensive Requires larger footprint than chlorination Not as effective as chlorine for CSO disinfection
Ozone	0.2 %	Highly effective against a wide range of pathogens	 Relatively expensive Energy intensive Requires larger footprint than chlorination Not used for CSO disinfection
None	3.9 %		

Pathogens – Disease causing organisms

*Source: Disinfection of Wastewater Effluent – Comparison of Alternative Technologies, WERF, 2008.



Residual Chlorine Management

The amount of chlorine being discharged into the waterways must be regulated. Two common management strategies are:

- 1) Instrumentation: to closely monitor & control chlorine dosage
- 2) Dechlorination: add additional chemical (sodium bisulfite) to quench residual chlorine

SPRING CREEK PILOT

To be completed in time to inform final design and control requirements for proposed disinfection facilities

- Test and measure chlorine residuals and potential toxicity to receiving waters
- Determine proper disinfection control protocols and potential dosage ranges
- Determine if dechlorination may be required based upon potential toxicity issues

