



Flushing Bay CSO/Flood Storage Tunnel Project

LONG-TERM CONTROL PLAN (LTCP)

*Consent Order Modification Update
Public Meeting*

December 16, 2025



Introductions

DEP Team:

Tara Deighan, Bureau of Public Affairs & Communication – Senior Advisor, Government Relations

Ovidiu Pena, Bureau of Engineering Design & Construction – Portfolio Manager

Keith Mahoney, Bureau of Sustainability – CSO Consent Order Program Manager

Agenda

- What is a Combined Sewer Overflow (CSO)?
- Long Term Control Plans (LTCPs) and Harbor Water Quality
- Approved Flushing Bay LTCP
- Flushing Bay LTCP Modifications
- Projected CSO Discharges and Water Quality Attainment
- Proposed Project Scope, Cost, and Schedule
- Q&A

What is a Combined Sewer Overflow (CSO)?

NYC Sewer History

1660s: First sewer in NYC constructed—an open trench that sent wastewater directly into the East River



1849: NYC constructs a more modern sewer system, prompted by cholera outbreaks, but still sends wastewater directly into surrounding waterbodies

1890s: First wastewater treatment plants are constructed to divert wastewater and a portion of stormwater to plants to be cleaned before being discharged into harbor

Today: NYC's sewer system is approximately 60% combined, which means it is used to convey both wastewater and stormwater to treatment plants


Combined Sewer Overflow

Treatment plants can handle double the capacity of a dry weather day. However, intense rainfall can push the combined sewer system over capacity and if this happens, a diluted mixture of rainwater and sewage may be released into local waterways. **This is called a combined sewer overflow (CSO) and is intended to prevent flooding and sewer backups into homes.**



Combined Sewer Overflow Long-Term Control Plans (LTCP)

- In 2012, a groundbreaking consent order between NYC DEP and NYS DEC initiated development of 11 comprehensive plans aimed at reducing CSOs and improving harbor water quality.
- LTCPs included \$2.7B in grey infrastructure projects (completed) and \$8.7B in new LTCP projects (~\$1.2B completed).
- DEP committed an additional \$3.5B to Green Infrastructure projects citywide (~\$1.4B completed).




Water Quality Improvements

DEP investments in both our treatment plants and CSO reduction efforts have resulted in **significantly improved water quality** for all waterbodies including the **Flushing Bay**.

1973-2011	~\$40B to upgrade and construct 2 new *WRRFs
1999-2022	~\$1.2B to upgrade 8 plants for biological nitrogen removal
1995-2024	~\$5.3B spent to date on CSO & GI projects
2025-2050	~\$7.4B in future CSO spending

**Wastewater Resource Recovery Facility*

Historical NYC Water Quality Improvement



DEP’s Harbor Survey Program added Enterococcus to its sampling program in CY2003.

2017 Approved Flushing Bay LTCP

After an extensive community engagement process, the LTCP for Flushing Bay was approved by NYS DEC in March 2017.


The approved plan requires DEP to:

1. Commit to baseline green and grey infrastructure projects for CSO reductions
 - ✓ Install green infrastructure in combined sewer areas (on-going)
 - ✓ Make improvements to Bowery Bay wastewater treatment plant (complete)
 - ✓ Complete regulator improvements to high-level interceptor (complete)
2. Construct a 25 million gallon CSO tunnel to capture CSO overflow from outfalls BB-006 and BB-008



Original 25 MG CSO Storage Tunnel Alignment


Green Infrastructure in the Flushing Bay Watershed



- **Right of Way**
 - 750+ assets constructed including rain gardens, infiltration basins, and porous pavement
 - Upcoming contract to use new green infrastructure standards to add more rain gardens, infiltrations and porous pavement
- **Large-Scale Medians**
 - Union Turnpike between Metropolitan Ave and 71st Rd – under construction
 - Justice Ave & 56th Ave – constructed
- **Public Partnerships**
 - 20+ projects constructed/in construction at parks and schools and one project upcoming
- **Stormwater Regulations**
 - Willets Point – under construction, includes rain gardens and infiltration basins

Corona Cloudburst Hub

- Total of 2.9 acres of precast porous concrete pavement in parking lanes across the neighborhood.
- Three subsurface detention sites, including:
 - Park of the Americas
 - NYSCI front lawn
 - NYSCI parking lot
- In total, the green infrastructure storage is designed to reduce flood extents during a 10-year, 1hr storm by 14.2 acres, or 30% reduction.



2022 Flushing Bay LTCP Modifications

In consultation with NYS DEC, the Flushing Bay LTCP was modified in 2022 and commitments included:

1. Submit a Conceptual Engineering Report (CER) for 25 MG CSO Storage Tunnel to DEC in December 2023 (complete)
2. Undertake "State of Good Repair" projects at wastewater treatment plants (on-going)

More recently, DEP committed to NYS DEC to submit a modification request by December 31, 2025, that includes a revised CER with a new proposed scope and schedule (in progress)


Milestone	2016 LTCP	2023 CER
Design Start	July 2021	January 2026
Construction NTP	July 2026	January 2035
Construction Completion	June 2035	February 2051
Construction Estimate	\$683M	\$2.4B

2025 Flushing Bay LTCP Modification Goals

After extensive engineering analysis and evaluation, DEP is seeking approval to further modify the LTCP to optimize the plan for Flushing Bay to:

- ✓ Meet or exceed consent order CSO reduction and water quality requirements
- ✓ Provide early CSO reduction benefit
- ✓ Provide multi-benefit and address flooding where practical
- ✓ Balance multiple large capital projects and state of good repair needs
- ✓ Coordinate with other capital projects to avoid overlap of tunneling activities and manage labor resources.
- ✓ Rate affordability

This proposed modification will also be subject to public review and comment.



LTCP project area

2025 Proposed Modification Details

1. **Deliver an earlier project** to provide 6.5 million gallons of in-line storage capacity
2. **Increase tunnel storage** capacity from 25 million gallons to 40 million gallons
3. **Modify tunnel alignment**

PROS:

- ✓ In-line storage will reduce CSO discharges by 252 million gallon per year from baseline conditions.
- ✓ In-line storage will provide reduction in floatable materials.
- ✓ Tunnel + in-line storage will reduce CSO discharges by 951 million gallons per year from baseline conditions, resulting in an additional 205 million gallons per year of CSO reductions beyond the approved LTCP.
- ✓ Mitigates flooding in high-risk areas of Lefrak City / Rego Park

CONS:

- X Longer time frame and higher cost than approved LTCP



Flushing Bay – Proposed Tunnel Alignment & Phasing

Phase 2 Improvements

Phase 1 Improvements



Phase	CSO Storage Volume	Cumulative Annual CSO Reduction ²	Flood Reduction ³
1: In-Line Storage	6.5 MG ¹	229 MG/year	125 MG
2: CSO / Flood Storage Tunnel	46.5 MG (+40)	928 MG/year	974 MG

1: CSO storage volume assumes a 10% factor of safety as detailed survey information has not been collected to confirm storage volume

2: Cumulative total from baseline with the 2008 Hydrologic Year

3: Flood volume reduction in Hurricane Ida from existing conditions



Projected CSO Reductions

Improvements from Baseline:

- ✓ Inline Storage reduces CSO AOV by 252 MGY and overflow events by 16 per year
- ✓ Inline Storage + Tunnel reduces CSO by 951 MGY and overflow events by 72 per year.

Improvements from Approved LTCP:

- ✓ Inline Storage + Tunnel reduces CSO by 205 MGY and overflow events by 8 per year.





Projected Water Quality Attainment

All Alternatives:




- ✓ Full attainment with Annual Fecal Monthly GM < 200 cfu/100 ml
- ✓ Full Attainment with Recreational Entero 30-d GM < 35 cfu/100 ml
- ✓ Full Attainment with Annual Entero 30-d GM < 72 cfu/100 ml

Improvements from Baseline:

- ✓ In-line storage projected to increase attainment 12% in the bay
- ✓ ILS + 40 MG Tunnel projected to increase attainment by almost 80% in the inner bay



Projected Water Quality Attainment



Proposed Project Scope

Phases:


1. In-Line Storage (ILS)

- Construct new diversion structures on outfalls BB-006 and BB-008 with floatable controls.
- Use outfall barrels to provide 6.5 million gallon in-line storage capacity.
- Eliminate a hydraulic restriction identified in lower barrel to improve drainage.


2. CSO/Flood Storage Tunnel

- 3 mile long, 22 foot diameter tunnel with 40 million gallon storage capacity
- Allows for Lefrak City/Rego Park area sewer flow to be diverted into the tunnel during a storm event to mitigate flooding
- Dewatering pump station will pump stored CSO/stormwater from the tunnel to Bowery Bay for treatment after the storm event.

Hurricane Ida Flooding Condition




Phase 1 Components




Main Features:

- Bending Weir
- Bar Rack (increased floatable control)
- Tide Gates




Phase 2 Components

- ~ 3 miles (14,100 LF), 22-foot diameter tunnel spanning from World's Fair Marina area to Woodhaven Blvd.
- Mining in soft ground.
- 3 Shafts:
 - 1 large Shaft (~120 ft diameter) for TBM launch and Tunnel Dewatering Pump Station (TDPS)
 - 1 drop Shaft in the marina (~65 ft diameter)
 - 1 drop Shaft at Woodhaven Blvd (~50 ft diameter)
- Diversion facilities.
- Tunnel Dewatering Pump Station houses all the equipment necessary to pump the stored CSO to Bowery Bay for treatment after the storm event.



Project Implementation Schedule

CSO/Flood Storage Tunnel Schedule (P80 estimate)



	Design & DSDC
	CEQR / ULURP / EIS / Site Acquisition
	Procurement
	Construction
★	Beneficial Use/Substantial Completion of CSO Facility
★	Anticipated NTP

Project Cost - In-Line Storage

Components	Cost
In-Line Storage Facility	\$267M
Total Construction Cost	\$267M
Engineering/Design	\$16M
Design Services During Construction	\$11M
Construction Management	\$32M
Subtotal – Other Project Costs	\$59M
Project Total	\$326M

Note: Costs escalated based on midpoint of construction.



Project Cost – CSO/Flood Storage Tunnel

Components	Cost
CP-1 Site Preparation	\$123M
CP-2 Tunnel and Shafts	\$1.659B
CP-3 Tunnel Dewatering Pump Station	\$606M
Subtotal Construction Cost	\$2.388B
Engineering/Design	\$143M
Design Services During Construction	\$95M
Construction Management	\$287M
Land Acquisition	\$185M
Subtotal Engineering/Acquisition Cost	\$710M
Subtotal Project Cost	\$3.098B
Total with In-Line Storage	\$3.424B

Note: Costs escalated based on midpoint of construction for each contract package.

Comparison of Flushing Bay Project Schedules

Milestone	2016 LTCP Tunnel	2023 CER Tunnel	2025 Inline Storage	2025 CSO/Flood Tunnel
Design Start	July 2021	January 2026	Q4 of 2027	Q1 of 2032
Construction NTP	July 2026	January 2035	Q4 of 2032	Q3 of 2039
Construction Completion	June 2035	February 2051	Q2 of 2037	Q4 of 2053
Construction Estimate	\$683M	\$2.4B	\$267M	\$3.098B

Next Steps

- NYC DEP to submit final modification request with an updated Conceptual Engineering Report on or before December 31, 2025.
- Pending NYS DEC review, NYS DEC will publish this modification request for 30-days in the Environmental News Bulletin for public review
- Preliminary Schedule:

Milestone	Proposed Date
In-Line Storage Design NTP	Q4, 2027
In-Line Storage Construction NTP	Q4, 2032
In-Line Storage Construction Completion	Q2, 2037
CSO/Flood Mitigation Tunnel Design NTP	Q1, 2032
CSO/Flood Mitigation Tunnel Construction NTP	Q3, 2039
CSO/Flood Mitigation Tunnel Construction Completion	Q4, 2053

Questions?