CITY OF NEW YORK DEPARTMENT OF CORRECTION



FOR FURNISHING ALL LABOR AND MATERIAL NECESSARY AND REQUIRED FOR:

Vernon C. Bain Center (VCBC) Chilled Water Risers and Pumps Replacement

PROCUREMENT IDENTIFICATION NUMBER PIN 072201821CPD

EPIN 07218B0009

Acting Commissioner Cynthia Brann

INVITATION FOR BIDS

THE CITY OF NEW YORK DEPARTMENT OF CORRECTION CONSTRUCTION CONTRACT

FOR FURNISHING ALL LABOR AND MATERIAL NECESSARY AND REQUIRED FOR:

Vernon C. Bain Center (VCBC) Chilled Water Risers and Pumps Replacement

PROCUREMENT IDENTIFICATION NUMBER (PIN): 072201821CPD EPIN: 07218B0009

NOTICE TO BIDDERS: (Instructions)

This bid document book is organized into Parts A - F, so that bidders can easily access information about the bid, the contract and related bid forms in an ordered sequence.

PART A: INFORMATION FOR BIDDERS

PART B: BID FORMS AND RELATED DOCUMENTS

PART C: DETAILED SPECIFICATIONS DESCRIBING SCOPE OF WORK

PART D: TERMS OF CONTRACT

PART E: BONDING AND INSURANCE

PART F: OTHER ATTACHMENTS

PLEASE ALSO NOTE THE FOLLOWING:

TABLE OF CONTENTS

The Bid Document Book is subdivided into the following Parts:

PART A:	INFORMATION FOR BIDDERS	PAGE #
Section 1:	Description of Procurement •••••••	• A-4
Section 2:	Time and Place for Receipt of Bids ••••••••••••••••••••••••••••••••••••	A-4
Section 3:	Procurement Policy Board Rules ••••••••••••••••••••••••••••••••••••	A-5
Section 4:	Definitions ••••••	A-5
Section 5:	Bid Documents ·····	A-5
Section 6:	Pre-Bid Conference ·····	A-6
Section 7:	Agency Contact ······	A-7
Section 8:	Examination of Proposed Contract ······	A-7
Section 9:	Form of Bid ······	A-7
Section 10:	Bidders Oath ·····	A-8
Section 11:	Site Visit ·····	A-8
Section 12:	Irrevocability of Bid ······	A-9
Section 13:	Acknowledgement of Amendments •••••••	A-9
Section 14:	Bid Samples & Descriptive Literature ••••••••••••••••••••••••••••••••••••	A-9
Section 15:	Proprietary Information/Trade Secrets ·····	A-9
Section 16:	Pre-Opening Modification or Withdrawal of Bids •••••••	A-9
Section 17:	Bid Evaluation and Award •••••••	A-10
Section 18:	Late Bids, Late Withdrawal and Late Modifications •••••••	A-10
Section 19:	Withdrawal of Bids	A-10
Section 20:	Mistakes in Bids ••••••	A-11
Section 21:	Tied Low Bids ·····	A-12
Section 22:	Rejection of Bids ••••••	A-12
Section 23:	Right to Appeal Determination of Non-Responsiveness or	
	Non-Responsibility and Right to Protest Solicitation and Award •••••••	• A-13
Section 24:	Affirmative Action and Equal Employment Opportunity ••••••••	A-13
Section 25:	Vendex Questionnaire •••••••	A-13
Section 26:	Complaints about Bid Process ······	A-14
Section 27:	Bid, Performance and Payment Security •••••••	A-14
Section 28:	Insurance ·····	A-15
Section 29:	Failure to Execute Contract and Furnish Security or Insurance •••••••	• A-16
Section 30:	Sales, excise and Federal Transportation Taxes ••••••••••••••••••••••••••••••••••••	A-16
Section 31:	Bidder Qualifications – Evidence of Ability and Financial	
	Qualifications ••••••	A-16
Section 32:	Department of Business Services, Division of Labor Services	
	(Employment Report) •••••••	A-17
Section 33:	Prompt Payment ••••••••••••••••••••••••••••••••••••	A-18
Section 34:	Bids shall be Typewritten or Written Legibly in Ink •••••••	
Section 35:	Approval of Contract ••••••••••••••••••••••••••••••••••••	A-19

TABLE OF CONTENTS (continued)

Section 36:	Performance Evaluations •••••••	A-19	
Section 37:	Bid Sheets ·····	A-19	
Section 38:	M/WBE Notice·····	A-19	
Section 39:	No Blasting	A-19	
Section 40:	Labor Law ······	A-20	
Section 41:	Iran Divestment Act Compliance Rider For New York City Contractors	s A-20	
Section 42:	Subcontractor Reporting	A-21	
	. 0		
PART B:	BID MATERIALS and FORMS	PAGE #	
I. BID	DER INFORMATION	B-1	
	DER REPRESENTATION AND WARRANTIES		
		B-3	
	SCHEDULE OF PRICES AND SIGNATURE OF BIDDER AND	B-7	
	AFFIRMATION	B-12	
	N DIVESTMENT ACT CERTIFICATION.	B-13	
	BOND FORMS	B-14	
PART C:	DETAILED SPECIFICATIONS/SCOPE OF WORK		
Section I:	Chilled Water Risers and Pumps Replacement.	C-1	
PART D:	STANDARD CONSTRUCTION CONTRACT 2017		
PART E:	BONDING AND INSURANCE	PAGE #	
Schedule "A	A" (Bonding and Insurance Requirements) •••••••	E-2	
Broker's Ce	ertification ••••••	E-11	
Payment Bo	ond	E-13	
Performanc	e Bond·····	E-17	
D. D. D. D.			
PART F:	<u>ATTACHMENTS</u>		
Attachment	A Participation By Minority-Owned And Women-Owned Business Enterpri	ises	
1 10000 2 11111 2 110	In City Procurement	.5.05	
	 Notice to Prospective Contractors 		
	Schedule B		
Attachment			
Attachment	1		
Attachment	The state of the s	f	
	and Other Inmates		
Attachment	E Security Clearance Request and Authorization Form -		
Attachment	Attachment F Security Requirements for All Work Performed on Riker's Island		
Attachment	· · · · · · · · · · · · · · · · · · ·		
Attachment H Notice to Bidders Apprenticeship Agreements			

PART A: INFORMATION FOR BIDDERS

DEPARTMENT OF CORRECTION

The pages in each Part of this document are numbered consecutively. Prospective Bidders must examine the documents carefully. Before bidding, prospective Bidders must notify the agency contact person listed in Section 7 below, in writing, if pages are missing and request that these missing pages be furnished to them.

1. <u>DESCRIPTION OF PROCUREMENT</u>

A. The description and location of the services to be performed are as follows:

This project is the Chilled Water Risers and Pumps Replacement of the Vernon C. Bain Center in the Bronx (Hunts Point).

Work consist of furnishing all labor, materials, equipment and appliances, supervision, project management, necessary and required to completely execute the items specified herein. This is a "work order" based General construction requirement contract. During the term of the contract, the Department shall order all required GC work for all Departmental locations as specified by the Department.

B. The term for this service is: <u>365 Consecutive Calendar Days.</u>

2. <u>TIME AND PLACE FOR RECEIPT OF BIDS</u>

A. The Department shall receive all sealed bids at the following location on or before the date and time set forth below:

New York City Department of Correction Central Office of Procurement 75-20 Astoria Blvd., Suite 160, Conf. Rm. B East Elmhurst, New York 11370

DATE:	
TIME:	(bid opening)

- **B.** It is the Bidder's responsibility to assure that its bid is received at the bid location on or before the date and time of the scheduled bid opening and that the bid and all other documents requiring signature are signed and notarized.
- C. The completed bid must be submitted in a sealed envelope on or before the time and at the place indicated above. The envelope must indicate:
 - (1) The name of the person, firm or corporation presenting the bid;
 - (2) The bid opening date;
 - (3) The PIN number; and
 - (4) The bid title.

D. Failure to comply with the instructions in this Section 2 may result in rejection of the bid.

3. PROCUREMENT POLICY BOARD RULES

This Bid document is subject to the Rules of the Procurement Policy Board of the City of New York ("PPB Rules") effective September 1, 1990, as amended from time to time. In the event of a conflict between said Rules and a provision of any of these bid documents, then the Rules shall take precedence. A copy of the rules may be obtained by contacting the agency contact person for this project, or online at http://www.nyc.gov/html/mocs/ppb/html/home/home.shtml

4. **DEFINITIONS**

The definitions set forth in the PPB Rules shall apply to this bid document.

5. BID DOCUMENTS

- **A.** <u>Documents to be Included</u>. Except for titles, sub-titles, headings, running headlines, tables of contents and indices (all of which are printed herein merely for convenience) the following, except for such portions thereof as may be specifically excluded, shall be deemed to be part of the Contract and the bid documents.
 - (1) The Advertisement for Bids;
 - (2) The Information for Bidders;
 - (3) The Bid;
 - (4) The Contract;
 - (5) The Procurement Policy Board Rules;
 - (6) The Specifications and Description of the Work;
 - (7) The Contract Drawings;
 - (8) All addenda issued by the Department, regarding this request for bids, prior to the receipt of bids;
 - (9) All provisions required by law to be inserted in this Contract, whether actually inserted or not;
 - (10) Notice of Award;
 - (11) Insurance Documents;
 - (12) Performance and Payment Bonds; and

- (13) Notice to Proceed with Work (*Also known as the Commence Work Letter*).
- **B.** General Conditions and Specifications. For particulars as to this procurement, including quantity and quality of the purchase, extent of the work or labor to be performed, delivery and performance schedule, and any other special instructions, prospective Bidders are referred to the bid material, the Detailed Specifications/Scope of Work and the General Condition Parts, which are attached to these bid documents.
- C. <u>Deposit for Copy of the Bid Documents</u>. Prospective Bidders may obtain a copy of the bid documents by complying with the conditions set forth in the Advertisement for Bids. A Bid Book deposit is \$25 Dollars, must be in the form of a <u>United States Post Office money order</u> or a <u>certified check</u>, made payable to the order of the Commissioner of Finance, and drawn upon a state or national bank or trust company, or a check of such bank or trust company signed by a duly authorized officer thereof.
- **D.** <u>Additional Copies.</u> Additional copies of the bid documents may be obtained, subject to the conditions set forth in the advertisement for bids.

6. PRE-BID CONFERENCE

A. The Department shall hold a pre-bid conference on the date and time and at the location set forth below:

TIME: DATE:

PLACE: <u>Bulova Corporate Center, Central Office of Procurement, Suite 160, Conf. Rm.</u>
Site Visit will follow Pre-Bid Conference

B. Bidder attendance at this pre-bid conference is:

Mandatory [] Optional [X] But Highly Recommended.

Failure to attend a mandatory pre-bid conference shall be grounds for rejection of a bid.

- C. Nothing stated at the pre-bid conference shall change the terms and conditions of the bid documents unless a change is made by a written amendment as provided in Section 8 below and in accordance with the PPB Rules.
- **D.** Please notify the agency contact person listed in Section 7 below of the number of representatives from your firm that will attend the pre-bid conference when the bid solicitation documents are picked up.

7. AGENCY CONTACT

The agency contact person for this bid shall be:

NAME: Phillip Emmanuel Intatano

TITLE: Contract Manager

ADDRESS: 75-20 Astoria, Blvd., Suite 160

East Elmhurst, New York 11370

PHONE: (718) 546-0692 FAX NO: (718) 278-6205

Any questions or correspondence relating to this bid solicitation shall be addressed to the agency contact person.

8. EXAMINATION OF PROPOSED CONTRACT

- A. Request for Interpretation or Correction. Prospective Bidders must examine the Contract documents carefully and before bidding must request the ACCO in writing for an interpretation or correction of every patent or latent ambiguity, inconsistency or error therein which should have been discovered by a reasonably prudent bidder. Such interpretation or correction, as well as any additional Contract provisions the ACCO may decide to include, will be issued in writing by the ACCO as an addendum to the Contract, which will be sent by mail or delivered to each person recorded as having received a copy of the Contract documents from the Agency Contact, and which also will be posted at the place where the Contract documents are available for the inspection of prospective Bidders. Upon such mailing or delivery and posting, such addendum shall become a part of the Contract documents, and binding on all Bidders, whether or not actual notice of such addendum is shown.
- B. Only the Agency Chief Contracting Officer's Interpretation or Correction Binding. Only the written interpretation or correction given by the ACCO shall be binding, and prospective Bidders are warned that no other officer, agent or employee of the City is authorized to give information concerning, or to explain or interpret, the Contract.

9. FORM OF BID

- A. Part B consists of the prescribed forms that must be submitted and must contain:
 - (1) The name, residence and place of business of the person(s) making the bid;
 - (2) The name of all persons interested therein, and if no other person is so interested, such fact must be distinctly stated;

- (3) A statement to the effect that it is made without any connection with any other person making a bid for the same purpose and that it is in all respects fair and without collusion or fraud;
- (4) A statement that no Council Member or other officer, employee or person whose salary is payable in whole or in part from the City Treasury is directly or indirectly interested therein or in the supplies, materials or equipment and work or labor to which it relates, or in any portion of the profits thereof;
- (5) A statement that the Bidder is not in arrears to the City or to any agency upon a debt, contract or taxes, and is not a defaulter as surety or otherwise upon any obligation to the City or to any agency thereof, except as set forth in the bid.

10. BIDDER'S OATH

- A. The bid shall be properly signed by an authorized representative of the Bidder and shall be verified by the written oath of the authorized representative who signed the bid that the several matters stated and information furnished therein are in all aspects true.
- B. A materially false statement willfully or fraudulently made in connection with the bid or any of the forms completed and submitted with the bid may result in the termination of any contract between the City and the Bidder. As a result, the Bidder may be barred from participating in future City contracts as well as be subject to possible criminal prosecution.
- C. Documents given to a subcontractor for the purpose of soliciting the subcontractor's bid shall include either a copy of the bid cover or a separate information sheet setting forth the project name, the contract number (if available), the contracting agency, and the project location.

11. <u>SITE VISIT</u>

- A. Pre-Bid Investigation: Where the work to be performed involves performance of services on City facilities, all Bidders are urged and expected to inspect the site where services are to be performed and to satisfy themselves as to all general and local conditions that may affect the cost of performance of the Contract. Bidders will be conclusively presumed to have full knowledge of any and all conditions on, about or above the site relating or affecting the performance of the work to be done under this Contract which were or should have been indicated to a reasonably prudent bidder. In no event will a failure to inspect a site constitute grounds for withdrawal of a bid after opening or for a claim after award of the Contract.
- B. Changed Conditions: Should the Contractor encounter during the progress of the work, subsurface conditions at the site materially differing from any shown on the Contract Drawings or as indicated in the specifications, or such subsurface

conditions as could not reasonably have been anticipated by the Contractor and were not anticipated by the City, which conditions will materially affect the cost of the work to be done under the Contract, Contractor must notify the Commissioner immediately and before any such conditions are disturbed. If the Commissioner finds that the conditions do so materially differ, or that they could not reasonably have been anticipated by the Contractor and were not anticipated by the City, the Contract may be modified with the Commissioner's written approval.

12. IRREVOCABILITY OF BID

The prices set forth in the bid cannot be revoked and shall be effective until the award of the Contract, unless the bid is withdrawn as provided for in Sections 16 and 19 below.

13. ACKNOWLEDGMENT OF AMENDMENTS

The receipt of any amendment to the Contract documents shall be acknowledged by the Bidder in its bid submission.

14. <u>BID SAMPLES AND DESCRIPTIVE LITERATURE</u>

Bid samples and descriptive literature shall not be submitted by the Bidder, unless expressly requested elsewhere in the Contract or Contract documents. Any unsolicited bid samples or descriptive literature which are submitted shall not be examined or tested and shall not be deemed to vary any of the provisions of this Contract.

15. PROPRIETARY INFORMATION/TRADE SECRETS

- A. The Bidder shall identify those portions of its bid that it deems to be confidential, or include proprietary information or trade secrets, and shall provide justification why such materials should not be disclosed by the City. The Bidder shall clearly indicate all materials the Bidder desires to remain confidential by stamping the pages on which such information appears, at the top and bottom thereof with the word "Confidential." Such materials stamped "Confidential" must be easily separable from the non-confidential sections of the bid.
- B. All such materials so indicated shall be reviewed by the Department and any decision not to honor a request for confidentiality shall be communicated in writing to the Bidder. For those bids which are unsuccessful, all such confidential materials shall be returned to the Bidder. Prices, makes, models or catalog numbers of the items offered, deliveries, and terms of payment shall be publicly available after bid opening regardless of any designation of confidentiality made by the Bidder.

16. PRE-OPENING MODIFICATION OR WITHDRAWAL OF BIDS

A. A bid may be modified or withdrawn by written notice, received and signed for by the designated agency contact person in Part A, Paragraph 7, at the Central Office of Procurement, 75-20 Astoria Blvd., Suite 160, East Elmhurst, New York 11370, before the time and date set for the bid opening.

B. If a bid is withdrawn in accordance with this Section the bid security, if any, shall be returned to the Bidder.

17. <u>BID EVALUATION AND AWARD</u>

- A. In accordance with the New York City Charter, the PPB Rules and the terms and conditions of the bid documents, this Contract shall be awarded, if at all, to the responsible Bidder whose bid meets the requirements and evaluation criteria set forth in the bid documents, and whose bid price is either the lowest responsive and responsible bid price, or, if the bid documents so state, the lowest responsive and responsible evaluated bid price. A bid may not be evaluated for any requirement or criterion that is not disclosed in the bid documents.
- B. No negotiations with any bidder shall be allowed to take place except under circumstances and in the manner set forth below. Nothing in this Section shall be deemed to permit a Contract award to a bidder submitting a higher quality item than that designated in the Invitation for Bid if that bid is not also the most favorable bid.
- C. Upon determination of the apparent lowest responsive and responsible bidder and prior to award, the ACCO may elect to open negotiations with the selected bidder in an effort to improve the bid to the City with respect to the price only. In the event the apparent lowest responsive and responsible bidder declines to negotiate, the Contracting Officer may elect to either award the contract to the apparent lowest responsive and responsible bidder, or may, upon written approval by the ACCO, reject all bids in accordance with the PPB Rules.

18. LATE BIDS, LATE WITHDRAWAL AND LATE MODIFICATIONS

Any bid received at the place designated in the solicitation after the time and date set for receipt of bids is late and shall not be considered. Any request for withdrawal or modification received at the place designated in the solicitation after the time and date set for receipt of bids is late and shall not be considered.

19. WITHDRAWAL OF BIDS

- A. Except as provided for in Section 16 above, a Bidder may not withdraw its bid before the expiration of forty five (45) days after the date of opening of bids; thereafter, a Bidder may withdraw its bid only in writing and in advance of an actual award.
- B. If within sixty (60) days after the execution of the Contract, the Commissioner fails to fix the date for commencement of work by written notice to the Bidder, the Bidder, at its option, may ask to be relieved of its obligation to perform the work called for by written notice to the Commissioner. If such notice is given, and the request to withdraw is granted, the Bidder waives all claims in connection with this Contract.

20. MISTAKES IN BIDS

- A. <u>Mistakes Discovered Before Bid Opening</u>: A Bidder may correct mistakes discovered before the time and date set for bid opening by withdrawing or correcting the bid as provided in Section 16 above.
- B. <u>Mistakes Discovered Before Award</u>: In accordance with the PPB Rules, if a Bidder alleges a mistake in its bid after bid opening and before award, the bid may be corrected or withdrawn upon written approval of the ACCO if the following conditions are met:
 - (1) <u>Minor Informalities</u>. Minor informalities in bids are matters of form rather than substance evident from the bid document, or insignificant mistakes that can be corrected without prejudice to other Bidders; that is, the effect on price, quantity, quality, delivery, or contractual conditions is negligible. The ACCO may waive such informalities or allow the Bidder to correct them depending on which is in the best interest of the City.
 - (2) <u>Mistakes Where Intended Correct Bid is Evident</u>. If the mistake and the intended correct bid are clearly evident on the face of the bid document, the bid shall be corrected to the intended correct bid and may not be withdrawn.
 - (3) <u>Mistakes Where Intended Correct Bid is Not Evident.</u> Mistakes may not be corrected after bid opening. A bidder may be permitted to withdraw a low bid where a unilateral error or mistake has been discovered in the bid and the ACCO makes the following determination:
 - (a) the mistake was known or made known to the agency prior to bidder selection or within three days after the opening of the bid, whichever period is shorter;
 - (b) the price bid was based on an error of such magnitude that enforcement would be unconscionable;
 - (c) the bid was submitted in good faith and the bidder submits credible evidence that the mistake was a clerical error as opposed to a judgment error;
 - (d) the error in bid is actually due to an unintentional and substantial arithmetic error or unintentional omission of a substantial quantity of work, labor, material, goods, or services made directly in the compilation of the bid, which unintentional arithmetic error or unintentional omission can be clearly shown by objective evidence drawn from inspection of the original work paper, documents, or materials used in the preparation of the bid sought to be withdrawn; and

- (e) it is possible to place the City in the same condition that had existed prior to the receipt of the bid.
- A. Upon the approval of the ACCO, the bid may be withdrawn, and the bid bond or other security returned to the bidder. The contract shall either be awarded to the next lowest bidder or re-solicited pursuant to the PPB Rules. Under no circumstances shall a bid be amended or revised to rectify the error or mistake
- B. <u>Mistakes Discovered After Award</u>. Mistakes shall not be corrected after award of the Contract except where the ACCO, subject to the approval of City Chief Procurement Officer (CCPO), makes a determination that it would be unconscionable not to allow the mistake to be corrected.
- C. <u>Determinations Required.</u> When a bid is corrected or withdrawn, or correction or withdrawal is denied, the ACCO shall prepare a determination showing that the relief was granted or denied in accordance with the PPB Rules

21. TIED LOW BIDS

- A. When two (2) or more low responsive bids from responsible Bidders are identical in price, meeting all the requirements and criteria set forth in the bid documents, the ACCO will break the tie in the following manner in order of priority:
 - (1) Award to a certified New York City small, minority or woman-owned business entity Bidder;
 - (2) Award to a New York City Bidder;
 - (3) Award to a certified New York State small, minority or woman-owned business Bidder;
 - (4) Award to a New York State Bidder.
- B. If two (2) or more Bidders still remain equally eligible after application of Section A above, the award shall be made by a drawing by lot limited to those Bidders. The Bidders involved shall be invited to attend the drawing. A witness shall be present to verify the drawing and shall certify the results on the bid tabulation sheet.

22. REJECTION OF BIDS

- A. Rejection of Individual Bids. The ACCO may reject a bid if:
 - (1) The Bidder fails to furnish any of the information required pursuant to the bid documents; or if

- (2) The Bidder is determined to be not responsible pursuant to the PPB Rules; or if
- (3) The bid is determined to be non-responsive pursuant to the PPB Rules; or if
- (4) The bid, in the opinion of the ACCO contains unbalanced bid prices and is thus non-responsive, unless the Bidder can show that the prices are not unbalanced for the probable required quantity of such items, or if the imbalance is corrected pursuant to the PPB Rules.
- B. <u>Rejection of All Bids</u>. The ACCO may reject all bids and may elect to re-solicit by bid or by other method authorized by the PPB Rules.

23. RIGHT TO APPEAL DETERMINATION OF NON-RESPONSIVENESS OR NON-RESPONSIBILITY AND RIGHT TO PROTEST SOLICITATION AND AWARD

The Bidder has the right to appeal a determination of non-responsiveness or non-responsibility and has the right to protest a solicitation and award, pursuant to the PPB Rules

24. <u>AFFIRMATIVE ACTION AND EQUAL EMPLOYMENT OPPORTUNITY</u>

The bid solicitation is subject to applicable provisions of Federal, State and Local Laws and executive orders requiring affirmative action and equal employment opportunity.

25. <u>VENDEX QUESTIONNAIRE</u>

A. New York City Administrative Code Section 6-116.2 and the PPB Rules established a requirement that VENDEX questionnaires or an Affidavit of No Change, as appropriate, must be completed and submitted by all persons or entities seeking to do business with the City of New York. Generally, if this bid is one hundred thousand dollars (\$100,000) or more, or if this bid, when added to the sum total of all contracts, concessions and franchises the Bidder has received from the City and any subcontracts the Bidder has received from a City Contractor within the past twelve (12) months equals or exceeds one hundred thousand dollars (\$100,000) then VENDEX questionnaires must be completed by the Bidder. The VENDEX questionnaires consist of a Business Entity Questionnaire and a Principal Questionnaire, both of which are either included in the Bid documents or may be obtained by contacting the agency contact person listed in Section 7 above. The VENDEX questionnaire or the Affidavit of No Change must be completed and submitted to the Department before any award of the Contract may be made or before an approval is given for a proposed Detailed instructions regarding the completion of VENDEX questionnaires are included in the VENDEX package. Non-compliance with these submission requirements may result in the disqualification of the bid or vendor, disapproval of a subcontractor, subsequent withdrawal of approval for the use of an approved subcontractor, or the cancellation of the Contract after its award. Questionnaires need be completed only once every three (3) years, so long as a prospective contractor, prior to the award, certifies that there has been no material changes in the information previously submitted. Any questions concerning the VENDEX questionnaires must be submitted to the ACCO or the agency contact person for this Contract.

B. VENDOR NAME CHECK FEE IMPLEMENTATION

Pursuant to Procurement Policy Board Rule 2-08(f)(2), the contractor will be charged a fee for the administration of the VENDEX system, including the Vendor Name Check process, if a Vendor Name Check review is required to be conducted by the Department of Investigation. The contractor shall also be required to pay the applicable required fees for any of its subcontractors for which Vendor Name Check reviews are required.

The fee(s) will be deducted from payments made to the contractor under the contract. For contracts with an estimated value of less than or equal to \$1,000,000, the fee will be \$175. For contracts with an estimated value of greater than \$1,000,000, the fee will be \$350.

26. COMPLAINTS ABOUT BID PROCESS

The New York City Comptroller is charged with the audit of Contracts in New York City. Any vendor who believes that there has been unfairness, favoritism or impropriety in the bid process should inform the Comptroller, Office of Contract Administration, One Centre Street, Room 1005, New York, NY 10007.

27. BID, PERFORMANCE AND PAYMENT SECURITY

- A. <u>General</u>. The ACCO may require bid, performance or payment security, or all three (3), on any contract for goods or services (see Schedule "A" located in Part E).
- B. <u>Bid security.</u>+ Each bid must be accompanied by bid security in an amount and type as specified in Schedule "A" (see Part E). The bid security shall assure the City of New York of the adherence of the Bidder to its bid, the execution of the contract and the furnishing of performance and payment bonds by the Bidder, if required. If a bid does not comply with the bid security requirements of this bid document, the bid may be rejected as non-responsive.
- C. Bid security will be returned to bidders as follows:
 - (1) Within ten (10) days after the bid opening, the Comptroller will be notified to return the bid securities of all but the three (3) lowest Bidders. Within five (5) days after the award, the Comptroller will be notified to return the bid securities of the remaining two (2) unsuccessful Bidders.
 - (2) Within five (5) days after the execution of the Contract and acceptance of the Contractor's bonds, the Comptroller will be notified to return the bid security of the successful Bidder or, if no Performance and Payment bonds

- are required, the Comptroller will be notified to return the bid security only after the sum retained under applicable provisions of the Contract equals the bid security.
- (3) Where all bids are rejected, the Comptroller will be notified to return the bid security of all Bidders at the time of rejection.
- D. <u>Performance and Payment Security.</u> The performance and payment security, if required in the bid documents and in the amounts specified in Schedule "A" (see Part E), shall be delivered by the Contractor to the City within ten (10) days after the receipt of a Notice of Award. If a Contractor fails to deliver the required performance and payment security, then the award shall be rescinded, its bid security shall be enforced and the award of the Contract may be made to the next lowest responsive and responsible Bidder or the Contract may be rebid.
- E. <u>ACCEPTABLE SECURITY</u>. Acceptable security for bids, performance and payment shall be limited to:
 - (1) A one-time bond in a form satisfactory to the City;
 - (2) A bank-certified check or money order; or
 - (3) City bonds.
- F. FORM OF BONDS. Security provided in the form of bonds must be prepared on the form of bonds authorized by the City of New York. Forms for bid, performance and payment bonds are included in the bid documents (see Part B). Such bonds must have as surety thereunder, such company or companies as are approved by the City of New York and authorized to do business in the State of New York.
- G. **POWER OF ATTORNEY.** Attorneys-in-fact who sign bid, performance or payment bonds must file with each bond a certified copy of their power of attorney to sign said bond.

28. INSURANCE

Bidders are advised that the insurance requirements herein are regarded as a material term of this Contract. During performance and up to the date of final acceptance, including any maintenance and guaranty period, the Contractor must effect and maintain with insurance companies authorized and licensed to do business in the State of New York, the types and amounts of insurance specified in Schedule "A" (See Part E) of this Invitation for Bids. Pursuant to Section 57 of the New York State Worker's Compensation Law, the bidder must submit proof of worker's compensation and disability benefits coverage to the ACCO prior to the execution of any contract resulting from this solicitation. ALL other required insurance documentation must also be submitted prior to commencement of work of this Contract.

29. <u>FAILURE TO EXECUTE CONTRACT AND FURNISH SECURITY OR INSURANCE</u>

If the successful Bidder fails to execute the Contract and furnish any required security and insurance, within (10) days after notice of the award of the Contract, the bid security of the successful Bidder or so much thereof as shall be applicable to the amount of the award made, shall be forfeited and retained by the City, and the successful Bidder shall be liable for and hereby agrees to pay on demand the difference between the price bid and the price for which such Contract shall be subsequently awarded, including the cost of any reletting less the amount of such bid security. No plea of mistake in such accepted bid shall be available to the Bidder for the recovery of the bid security or as a defense to any action based upon such accepted bid. Further, should the Bidder's failure to comply with this section cause any funding agency, body or group (Federal, State, City, public, private, etc.) to terminate, cancel or reduce the funding on this project, the Bidder in such event shall be liable also to the City for the amount of actual funding withdrawn by such agency, body or group on this project, less the amount of the forfeited bid security.

30. SALES, EXCISE AND FEDERAL TRANSPORTATION TAXES

Unless this Contract indicates otherwise, the City is exempt from the payment of any sales, excise or Federal transportation taxes. The bid price must be exclusive of such taxes and shall be so construed.

31. <u>BIDDER QUALIFICATIONS - EVIDENCE OF ABILITY AND FINANCIAL QUALIFICATIONS</u>

- A. Before or after Contract award, the City reserves the right to inspect the Bidder's plant or premises.
- B. The Bidder shall, upon request, submit evidence that will prove to the satisfaction of the Commissioner that the Bidder is qualified and able to furnish the services on which it bid and perform the services in the manner and time specified in the Contract. The Bidder shall also furnish evidence that it has secured the necessary licenses, permits or certificates, required by any legislative or regulatory body having jurisdiction, to carry on the business of furnishing the services on which the bid was submitted.
- C. The Bidder shall, upon request, provide complete financial statements prepared by a certified public accountant, which shall include without limitation, a certified balance sheet, revenue and expense sheet, fixed and capital assets, or other information concerning the Bidder's financial status for examination as may be required by the Department to ascertain Bidder's financial qualifications to perform the Contract.
- D. Bids will be accepted from any firm that has been in the business of providing comparable service to that specified herein, for at least the previous 3 years prior to the submission of their bids. Bidders shall further certify that they have performed in a satisfactory or better manner during the above referenced time period. In

- addition, bidders shall certify that they employ a work force qualified to perform the specified services, as referenced in Part C.
- E. For verification purposes, the lowest apparent responsive and responsible Bidder shall submit the following within five (5) business days of receipt of a request for such from the Department:
 - 1. Documentation that the Bidder has been in business for at least the previous 5 years, performing comparable work;
 - 2. Documentation that the Bidder is able to provide specially trained and qualified technicians to service/repair of chilled water riser utility equipment.
 - 3. Business references from at least three clients having comparable premises, serviced by the Bidder, indicating that the work performed was of a satisfactory or better quality; and
 - 4. Information such as resumes, that provides the names and experience of the Bidder's employees and management that will be responsible for the specified work. If new employees are hired during the term of this contract to perform services for this Contract, the Contractor shall be responsible for providing the aforementioned information about said employee(s) to the Department, within five (5) business days of their hiring. All such new hires shall meet the requirements set forth in Part C, if any.
- F. If the evidence required in Sections 31(B) through 31(E) above is not furnished, or if, upon examination of such evidence or other inspection of the Bidder's plant or premises, it is found that the Bidder does not comply with the requirements set forth in this Contract, the Commissioner shall have the right to reject the bid in whole or in part. Should the non-compliance be discovered after the award is made, the Commissioner shall have the right to cancel and terminate this Contract and/or declare the Contractor in default, in addition to any other remedies provided by Contract or at law or equity.
- G. In addition to any other requirement of this Contract, the Commissioner may request the Bidder to submit a sworn statement or submit to an oral examination setting forth such information as may be deemed necessary by the Commissioner to determine the Bidder's ability and responsibility to perform the work and supply the services in accordance with the Contract.

32. <u>DEPARTMENT OF BUSINESS SERVICES, DIVISION OF LABOR SERVICES</u> (EMPLOYMENT REPORT)

A. Who Must File A Complete Employment Report: In accordance with Executive Order No. 50 (1980), as modified by Executive Order No. 108 (1986) and its implementing regulations, the filing of a completed Employment Report (ER) is a requirement of doing business with the City of New York if:

- (1) The Bidder has been identified as the lowest Bidder for a supply or service Contract or his/her proposal for supplies or services has been accepted; and
- (2) The Contract value exceeds fifty thousand dollars (\$50,000); and
- (3) The Bidder's firm employs fifty (50) or more people.

Each successful Bidder must file an ER if it meets each of these conditions. In addition, suppliers, subcontractors or vendors performing on the Contract who meet conditions (2) and (3) above, must also file an ER. The ER will be sent by the low bidder under separate cover.

- B. Who must file a Less Than 50 Employees Certificate?
 - (1) Any Contractor or any of its facilities performing on the Contract that has fewer than fifty (50) employees, although the Contract value exceeds fifty thousand dollars (\$50,000), need only submit a "Less Than 50 Employees Certificate."
 - Any Subcontractor, supplier or vendor to the prime Contractor performing on the Contract and any of its facilities performing on the Contract which have fewer than fifty (50) employees, need only submit the "Less Than 50 Employee Certificate," even if the Subcontract value exceeds fifty thousand dollars (\$50,000).

33. PROMPT PAYMENT

- A. The Prompt Payment provisions set forth in the PPB Rules in effect at the time of this solicitation will be applicable to payments made under a Contract resulting from this solicitation. The provisions require the payment to Contractors of interest on payments made after the required payment date except as set forth in the PPB Rules.
- B. The Contractor must submit a proper invoice to receive payment, except where the Contract provides that the Contractor will be paid at predetermined intervals without having to submit an invoice for each scheduled payment.
- C. Determinations of interest due will be made in accordance with the provisions of the PPB Rules.

34. <u>BIDS SHALL BE TYPEWRITTEN OR WRITTEN LEGIBLY IN INK</u>

A. Each Bidder shall submit its bid typewritten or written legibly in ink and shall sign the bid in ink. The signer shall initial in ink any and all erasures or alterations to the bid.

B. If the bid price has been materially altered, alterations must be initialed in ink by the Bidder. If the alteration has not been initialed in ink, and can be severed from the other items in the bid, then that particular item only may be considered non-responsive.

35. APPROVAL OF CONTRACT

- A. This Agreement shall be neither binding nor effective unless and until it is registered with the Comptroller of the City of New York pursuant to the New York City Charter § 328.
- B. The requirements of this Section shall be in addition to, and not in lieu of, any approval or authorization otherwise required for this Agreement to be effective and for the expenditure of City funds.

36. PERFORMANCE EVALUATIONS

The Contractor is subject to an annual performance evaluation to be conducted by the Agency pursuant to the PPB Rules.

37. BID SHEETS

Please use the Bid Sheets in Part B of this Invitation for Bids document for your unit price quotations and projected total costs for the term of the Contract.

38. MINORITY OWNED AND WOMEN OWNED BUSINESS ENTITY (M/WBE)

If the contract resulting from this Invitation for Bids will be subject to M/WBE participation requirements under Section 6-129 of the Administrative Code of the City of New York, as indicated by the inclusion of Schedule B – M/WBE Utilization Plan (Attachment A) and the Participation Goals indicated in Part I thereof, proposers must complete the Schedule B – M/WBE Utilization Plan and submit it with their proposal. Please refer to the Schedule B - M/WBE Utilization Plan and the Notice to All Prospective Contractors (Attachment A) for information on the M/WBE requirements established for this solicitation and instructions on how to complete the required forms. If the proposer intends to seek a full or partial waiver of the Participation Goals on the grounds described in Section 10 of the Notice to All Prospective Contractors, including but not limited to, proposer's intention to use its own forces to perform any or all of the required contract work would result in a failure to attain the Participation Goals, the proposer must request and obtain from the Agency a full or partial waiver of the Participation Goals (M/WBE Utilization Plan, Part III) in advance of proposal submission and submit the waiver determination with the proposal. Please note that if a partial waiver is obtained, the proposer is required to submit a completed Schedule B-M/WBE Utilization Plan based on the revised Participation Goals in order to be found responsive.

39. NO BLASTING

Unless otherwise permitted in the Plans and/or Specifications, no blasting will be allowed. The Contractor shall use line drilling or other methods acceptable to DOC.

40. LABOR LAW

Section 220 of the New York State Labor Law requires payment of the prevailing rate of wages when a public agency contract involves the employment of laborers, workers, or mechanics and concerns a public work. Public works projects are, as a general matter, public construction projects.

Labor Law 231 requires prevailing wages to be paid to each service employee under a contract in which the "principal purpose" is to furnish services through the use of building service employees. Labor Law 230(1) defines "building service employee" or "employee" as "any person performing work in connection with the care or maintenance of an existing building, or in connection with the transportation of office furniture or equipment to or from such building, or in connection with the transportation and delivery of fossil fuel to such building." Labor Law section 231 does not require the payment of prevailing wages to service employees if the *principal purpose* of the contract is not to furnish services provided by building services employees.

41. <u>IRAN DIVESTMENT ACT COMPLIANCE RIDER FOR NEW YORK CITY CONTRACTORS</u>

- A. The Iran Divestment Act of 2012, effective as of April 12, 2012, is codified at State Finance Law ("SFL") §165-a and General Municipal Law ("GML") §103-9. The Iran Divestment Act, with certain exceptions, prohibits municipalities, including the City' from entering into contracts with persons engaged in investment activities in the energy sector of Iran. Pursuant to the terms set forth in SFL §165-a and GML §103-g, a person engages in investment activities in the energy sector of Iran if:
 - (1) the person provides goods or services of twenty million dollars or more in the energy sector of Iran, including a person that provides oil or liquefied natural gas tankers, or products used to construct or maintain pipelines used to transport oil or liquefied natural gas, for the energy sector of Iran; or
 - (2) the person is a financial institution that extends twenty million dollars or more in credit to another person, for forty-five days or more, if that person will use the credit to provide goods or services in the energy sector in Iran and is identified on a list created pursuant to paragraph (b) of subdivision three of Section 165-a of the State Finance Law and maintained by the Commissioner of the Office of General Services.
- B. A bid or proposal shall not be considered for award nor shall any award be made where the bidder or proposer fails to submit a signed and verified bidder's certification.
- C. Each bidder or proposer must certify that it is not on the list of entities engaged in investment activities in Iran created pursuant to paragraph (b) of subdivision 3 of Section 165-a of the State Finance Law. In any case where the bidder or proposer cannot certify that they are not on such list, the bidder or proposer shall so state

and shall furnish with the bid or proposal a signed statement which sets forth in detail the reasons why such statement cannot be made. The City of New York may award a bid to a bidder who cannot make the certification on a case by case basis if:

- (1) The investment activities in Iran were made before the effective date of this section (i.e., April 12, 2012), the investment activities in Iran have not been expanded or renewed after the effective date of this section and the person has adopted, publicized and is implementing a formal plan to cease the investment activities in Iran and to refrain from engaging in any new investments in Iran: or
- (2) The City makes a determination that the goods or services are necessary for the City to perform its functions and that, absent such an exemption, the City would be unable to obtain the goods or services for which the contract is offered. Such determination shall be made in writing and shall be a public document.

42. SUBCONTRACTOR REPORTING

- A. As of March 2013 the City has implemented a new web based subcontractor reporting system through the City's Payee Information Portal (PIP), available at www.nyc.gov/pip. In order to use the new system, a PIP account will be required. Detailed instructions on creating a PIP account and using the new system are also available at that site. Additional assistance with PIP may be received by emailing the Financial Information Services Agency Help Desk at pip@fisa.nyc.gov.
- B. In order to obtain subcontractor approval under Article 11 of Part D or Article 17 of the Standard Construction Contract and PPB Rule § 4-13, Contractor is required to list the subcontractor in the system. For each subcontractor listed, Contractor is required to provide the following information: maximum contract value, description of subcontractor work, start and end date of the subcontract and identification of the subcontractor's industry. Thereafter, Contractor will be required to report in the system the payments made to each subcontractor within 30 days of making the payment. If any of the required information changes throughout the term of the contract, Contractor will be required to revise the information in the system.
- C. Failure of the Contractor to list a subcontractor and/or to report subcontractor payments in a timely fashion may result in the Agency declaring the Contractor in default of the Contract and will subject Contractor to liquidated damages in the amount of \$100 per day for each day that the Contractor fails to identify a subcontractor along with the required information about the subcontractor and/or fails to report payments to a subcontractor, beyond the time frames set forth herein or in the notice from the City. For construction contracts, the provisions of Article 15 of the Standard Construction Contract shall govern the issue of liquidated damages.
- D. Contractor hereby agrees to these provisions.

PART B: BID FORMS

- I. BIDDER INFORMATION
- II. BIDDER REPRESENTATION AND WARRANTIES
- III. BID SCHEDULE OF PRICES AND SIGNATURE OF BIDDER AND AFFIDAVIT
- IV TAX AFFIRMATION
- V. IRAN DIVESTMENT ACT CERTIFICATION
- VI BID BOND FORMS

NOTICE

• Before bidding, Bidders must review, by personal examination or such other means as they may prefer, the nature and extent of the work required, detailed specifications, plans, agreement and location(s) of the proposed work. Bidders must determine and allow for all difficulties which may be encountered in the prosecution of the work.

FAILURE TO COMPLETE THIS PART B IN DETAIL WILL RESULT IN REJECTION OF YOUR BID

No Further Text on This Page.

EPIN: 07218B0009

The City of New York Department of Correction Bid for Furnishing All Labor and Material Necessary and Required For:

	for Furnishing All Labor and Material Necessary and Required For:
	NUMBER: 072201821CPD
Date	of Bid:
I.	BIDDER INFORMATION Name of Bidder:
	Contact Person:
	Address:
	Telephone Number: ()
	Fax Number: ()
	of Organization (Check one of the following boxes) o Individual o Unincorporated organization (e.g. partnership or joint-venture) o Corporation e of Business of Bidder:
1 lacc	STREET ADDRESS
CIT	Y STATE ZIP CODE
If Bio	dder is a Corporation Corporate Tax ID Number: Jurisdiction of Incorporation: Year of Incorporation:
Nam	es and Home Addresses of the Following Officers: President: NAME: ADDRESS:

Secretary: NAME:		
ADDRESS:		
ADDDECC.		
If Bidder is an individual		
Residence of Bidder:	EET ADDDECC	
SIRI	EET ADDRESS	
CITY	STATE	ZIP CODE
* Social Security Number:		_
social security number will not result is security numbers to identify bidders to in enforcement of laws and to provide that seek City Contracts. If Bidder is a partnership	ensure their compliance	e with laws, to assist the C
Employer Identification Number: Names of Partners		Residence
		Kesidence
		Kesidence
If Bidder is a Joint Venture Employer Identification Number:		Kesidence
		Residence

EPIN: 07218B0009

II. BIDDER REPRESENTATIONS AND WARRANTIES

Each of the above-named Bidders hereby certifies, affirms and declares:

A.	This Bidder is of lawful age and the only one interested in this bid and that reperson, corporation or organization other than hereinabove named has any intere in this bid or in the Contract.		
B.		idder and each person bidding on the Bidder's behalf do hereby certify, penalty of perjury, that to the best of each such persons knowledge and	
		The prices in this bid have been arrived at independently without collusion, consultation, communication or agreement for the purpose of restricting competition, as to any matter relating to such prices with any other bidder or with any competitor or potential competitor; and	
		Unless otherwise required by law, the prices quoted in this bid have not been knowingly disclosed by the Bidder and will not knowingly be disclosed by the Bidder prior to the bid opening, directly or indirectly, to any other Bidder or to any competitor; and	
		No attempt has been made or will be made by the Bidder to induce any other person, partnership, corporation or organization to submit or not to submit a bid for the purpose of restricting competition; and	
		No member of the City Council, or other officer, employee or person whose salary is payable in whole or in part from the City Treasury is directly or indirectly interested in this bid or in the supplies, materials, equipment, work or labor to which it relates or in any of the profits thereof; and	
		This Bidder is not in arrears to the City of New York upon any debt, contract or taxes and is not a defaulter, as surety or otherwise, upon any obligations to the City of New York, and has not been declared not responsible, or disqualified by any agency of the City of New York or the State of New York, nor is there any proceeding pending relating to the responsibility or qualification of this Bidder to receive public contracts except	

C. The Bidder has examined all parts of this Bid document, including but not limited to the Contract and the terms and conditions thereof, and if this bid is accepted as submitted, this Bidder shall execute the Contract as set forth herein.

EPIN: 07218B0009

D. This Bidder has inspected the site where the services are to be performed and is satisfied as to all general and local conditions that may affect the cost of performance of the Contract.

- E. This Bidder is duly licensed to do business in the City of New York and the State of New York and the Bidder currently holds or agrees to obtain all necessary permits and other authorization required by law or regulation for performance of the Contract.
- F. This Bidder's attention has been specifically drawn to the equal employment provisions of the Contract and this Bidder warrants that it will comply with all the terms and provisions prescribed therein.
- G. This Bidder as an individual or as a member, partner, director or officer of the Bidder, if the same be a firm, partnership or corporation executes this document expressly warranting and representing that should this bid be accepted by the City and the Contract awarded to him, he and his subcontractors engaged in the performance of this Contract:
 - Will comply with the provisions of Section 6-108 of the Administrative Code of the City of New York and the non-discrimination provisions of Section 220-e of the New York State Labor Law; and
 Have complied with the provisions of the aforesaid laws since its effective date; and
 Will post notices setting forth the requirements of the aforesaid laws, to be furnished by the City, in prominent and conspicuous places in each and every plant, factory, building and structure where employees engaged in the performance of the Contract can readily review them, and will continue to keep such notices posted until the supplies, materials, equipment, work labor and services required to be furnished or rendered by the Contractor have been finally accepted by the City.
- H. The Bidder, as an individual, or as a member, partner, director or officer of the Bidder, if the same be a firm, partnership or corporation, executes this document expressly warranting and representing that the Bidder is not disqualified under the provisions of Section 6-109 of the Administrative Code of the City of New York for the award of this Contract and that should this bid be accepted by the City and this Contract awarded to the Bidder, the Bidder and his subcontractors engaged in the performance of this Contract:

EPIN: 07218B0009

Will comply with the provisions of Section 6-109 of the Administration Code of the City of New York in relation to minimum wages and other stipulations and rules and regulations applicable thereto; and		
Have complied with the provisions of said Section 6-109 and said rules and regulations since their respective enforcement date insofar as applicable to the bidder and to his subcontractors.		

- I. The Bidder as an individual, or as a member, partner, director or officer of the Bidder, by executing this document on behalf of such firm, partnership or corporation, represents and warrants that no payment, gift or thing of value has been made, given or promised to obtain this or any other Contract between the parties. The Bidder makes such representations and warranties to induce the City to enter into this Contract and the City relies upon such representations and warranties in the execution hereof. For breach or violation of such representations and warranties, the Commissioner shall have the right to annul this Contract without liability, entitling the City to recover all monies paid hereunder and the Bidder/Contractor shall not make claims for, or be entitled to recover any sum or sums due under this Contract. This remedy, if effected shall not constitute the sole remedy afforded the City for the falsity or breach nor shall it constitute a waiver of the City's right to claim damages or refuse payment or to take any other action provided for by law or pursuant to this Contract.
- J. The Bidder has visited and examined the site of the work and has examined the Contract in the form approved by the Corporation Counsel, and will execute the Contract and perform all its items, covenants and conditions and will provide, furnish and deliver all work, materials, supplies, equipment and all labor and material necessary or required for the completion of the Contract work, all in strict conformity with the Contract, in accordance with the schedule of prices appended hereto.
- K. The Bidder represents and warrants that it will not utilize tropical hardwoods as defined in Section 167-b of the New York State Finance Law in the performance of this Contract except as expressly permitted by the foregoing provisions of law.

All material, fixtures, supplies and equipment furnished under the Contract shall be new and unused, except as approved by the Agency or as specified and of standard first-grade quality and the best workmanship and design. The City encourages use of recycled products where practicable.

EPIN: 07218B0009

The Engineer's Estimate of Quantities included above is approximate only and is not to be considered as a binding feature of the Contract. Bidders are required to submit their bids upon the following express conditions which apply to and become part of every bid received. Bidders must satisfy themselves as to the accuracy of the foregoing estimate by personal examination of the location of the proposed work and surroundings thereof, and by such other means as they may prefer, and shall not, at any time after submission of their bids, dispute or complain of such estimate of Quantities of the Engineer's, nor assert that there was any misunderstanding in regard to quantity or kind of material to be furnished or work to be done. No error or misunderstanding of the Bidder shall affect the validity of the bid made or the Contract entered into hereunder.

The prices included in the bid sheets above are to be paid for the actual quantities of the several classes of Work covered in this Contract, and they cover the cost of all work, labor, material, tools, plant and appliances of every description necessary and required to complete the entire Work, as specified, and the removal of debris, temporary work and appliances. Should the dimensions of any part of the Work or the materials be less than those required by the Plans, the actual quantities only will be allowed for payment purposes.

EPIN: 07218B0009

III. BID SCHEDULE OF PRICES AND SIGNATURE OF BIDDER AND AFFIDAVIT

BID WORKSHEET

Vernon C. Bain Center (VCBC)
Chilled Water Risers Replacement
Budget ID: C75VRISER

Pin: 072201821CPD

The following itemization is a general breakdown of the scope of work included in the attached drawings, specifications, and any subsequent addenda and bulletins.

GENERAL CONSTRUCTION DEMOLITION:

1.	Remove pumps bases	C1.1	
2.	Demo areas at bulkhead to access piping	C1.2	
3.	Clean up.		
GEN	NERAL CONSTRUCTION INSTALLATION:		
4.	Secure pumps to steel platform	C1.4	
5.	Fire stopping	C1.5	
6.	Priming and painting	C1.6	
ME	CHANICAL DEMOLITION:		
7.	Disconnect and remove (3) chilled water pumps.	C1.7	
8.	Replace chilled water supply and return branches.		

		C1.8
9.	Remove expansion tank	C1.9
10.	Remove chilled water risers	C1.10
11.	Clean up.	C1.11
ME	CHANICAL INSTALLATION:	
12.	Install (3) chilled water pumps with VFD's	C1.12
13	Install new expansion tank	C1.l3
14.	Install new isolation valves, one per chiller with a tot	al of 6 valves
		C1.14
15.	Install new chilled water risers and branches through	out the facility. C1.15
16.	Install marine grade hydronic components and insula	tion. C1.16
17.	Flush, fill, purge, testing, balance of six (3) pumps ar	nd AHU branches system.
		C1.17
18.	Training of NYCDOC personnel.	C1.18
19.	Interlock new pumps to existing BMS system.	
		C1.19
20.	Clean up.	C1.20

21.	Obtain all required permitting.	C1.21
ELE	CCTRICAL DEMOLITION:	
22.	Disconnect power to chilled water pumps.	C1.22
23.	Remove disconnect switches for the pumps	C1.23
24.	Disconnect and remove conduit from the disconnect s	witches to the pumps. C1.24
25.	Remove wiring from the disconnect switches to the p	umps C1.25
26.	Clean up.	C1.26
ELE	CTRICAL INSTALLATION:	
27.	Provide power to the new pumps by extending the exi	sting circuitry. C1.27
28.	Provide new VFDs with integral disconnect switches	
		C1.28
29.	Provide new conduit, hangers and supports as require	d to extend the existing circuit C1.29
30.	Provide new wiring as required to extend the existing	
31.	Clean up.	C1.31

Total Bid Amount (Cost C.1.1 to Cost C.1.31):		
Total Bid Amount in Words:		
Notes:		
(1) For further explanations of the above cost, see the appropriate sector technical requirement document.	ctions of the	
(2) The respondent vendor is not to alter the bid format from that req Any such alterations of the bid format will result in a determination respondent being "nonresponsive".		
(3) Inclusion of disclaimers which contradict the requirements of this will also result in a determination of the respondent being "nonrespondent being".		
Bidder's Company Name:		
Bidder's Representative:	_	
(Print Name)	(Title)	
Signature of Bidder's Representative:		
Date:		

Bidder's Company Name:			
Bidder's Representative:			
(Print Name)	(Title)		
Signature of Bidder's Representative:			
Date:			

EPIN: 07218B0009

SIGNATURE OF BIDDER AND AFFIDAVIT

Зу: <u> </u>	D	
	Partner or Authorized Corporate Office	r
	Print Name	
	Print Title	
Date:		
FOR CORPORATIONS ONLY:		(Corporate Seal):

Affidavit on following page must be subscribed and sworn to before a Notary Public.

PIN: 072201821CPD

EPIN: 07218B0009

AFFIDAVIT

STA	TE OF NEW	YORK, COUNTY OF	SS:
		being duly sworn, say	s:
Note to Bidders: complete)		Choose only one (1) of the following three (3) options	. (Check box and
0		Bidder: the person described in and who executed the foregoing beers therein stated are in all respects true.	oid and the several
O	at	the of the above named of	corporation bing bid. I resident
O	I an unin subs	ated Organization (e.g. Partnership or Joint Venture) Bidden a member of corporated organization described in and which executed the cribed the name of the unincorporated organization thereto nization and the several matters therein stated are in all responses.	, the ne foregoing bid. It on behalf of such
(Sign	nature of the p	erson who signed the bid)	
	t Name: t Title:		
	Subscribed	and sworn to before me this day of	_, 20
	Notary Pub	olic	

EPIN: 07218B0009

IV. <u>TAX AFFIRMATION</u>

The undersigned Bidder affirms and declares that said Bidder is not in arrears to the City of New York upon debt, contract or taxes and is not a defaulter, as surety or otherwise, upon any obligation to the City of New York, and has not been declared not responsible or disqualified by any agency of the City of New York, nor is there any proceeding pending relating to the responsibility or qualification of the proposer or Bidder to receive public contracts except

City:	State:	Zip Code:
	AND INCLUDE APPROPRIATE dual or Sole Proprietorship * NUMBER:	
	rship, Joint Venture or other Non-Inc IFICATION NUMBER:	1 0
*	ration (<i>If a corporation place seal bed</i> IFICATION NUMBER:	,
By:		
Si	gnature	Title

* Under the Federal Privacy Act, 5 USC § 552a (1996), as amended from time to time, the furnishing of Social Security Numbers by bidders on City Contracts is voluntary. Failure to provide a Social Security Number will not result in a Bidder's disqualification. Social Security Numbers will be used to identify Bidders, Proposers or Vendors to ensure their compliance with laws, to assist the City in enforcement of laws as well as to provide the

City a means of identifying businesses which seek City Contracts.

EPIN: 07218B0009

V. BIDDER'S CERTIFICATION OF COMPLIANCE WITH IRAN DIVESTMENT ACT

Pursuant to General Municipal Law §103-g, which generally prohibits the City from entering into contracts with persons engaged in investment activities in the energy sector of Iran, the bidder/proposer submits the following certification:

[Please Check One]

Notary Public

Dated

BIDDER'S CERTIFICATION		
	By submission of this bid or proposal, each behalf of any bidder/proposer certifies, and certifies as to its own organization, under knowledge and belief, that each bidder/proparagraph (b) of subdivision 3 of Section 165	in the case of a joint bid each party thereto penalty of perjury, that to the best of its poser is not on the list created pursuant to
	I am unable to certify that my name and the on the list created pursuant to paragraph (b) of Finance Law. I have attached a signed state certify.	of subdivision 3 of Section 165-a of the State
Dated	, New York	
	·	SIGNATURE
	<u>-</u>	PRINTED NAME
Sworn	to before me this	TITLE
	day of, 20	

EPIN: 07218B0009

VI. <u>BID BOND FORMS</u>

- **1.** Each executed Bid Bond shall be accompanied by:
 - a) appropriate acknowledgments of the respective parties; and
 - an appropriate duly certified copy of the Power of Attorney or other certificate of authority where the bond is executed by agent, officer or other representative of the Principal and Surety; and
 - c) a duly certified extract from the by-laws or resolution of Surety under which Power of Attorney or other certificate of authority of its agent, officer or representative was issued; and
 - a duly certified copy of the latest published financial statement of assets and liabilities of the Surety.
- **2.** Affix Acknowledgments and Justification of Sureties.

EPIN: 07218B0009

BID BOND FORM

WE	
	hereinafter
referred to as the "Principal," and	
hereinafter referred to as the "Surety" are held and firmly bound to the CITY	OF NEW YORK,
hereinafter referred to as the "City," or to its successors and assigns, in the p	enal sum of
(\$) Dollars, lawful money of the United Sta	tes of America, for
the payment of which said sum of money well and truly to be made, we and	each of us bind
ourselves, our heirs, executors, administrators, successors and assigns, jointl	y and severally,
firmly by these presents.	
WHEREAS, the Principal is about to submit (or has submitted) to the City	the accompanying
bid, hereby made a part hereof, to enter into, a contract in writing for	

NOW, THEREFORE, the conditions of this obligation are such that if the Principal shall not withdraw said bid without the consent of the City for a period of forty-five (45) days after the opening of bids and, in the event of acceptance of the Principal's bid by the City the Principal shall:

A. Within ten (10) days after notification by the City, execute in triplicate and deliver to the City all the executed counterparts of the Contract in the form set forth in the Contract Documents, in accordance with the bid as accepted, and

EPIN: 07218B0009

B. Furnish a Performance Bond and a Payment Bond, as may be required by the City for the faithful performance and proper fulfillment of the Contract, which bonds shall be satisfactory in all respects to the City and shall be executed by good and sufficient Sureties, and

C. In all respects perform the Contract created by the acceptance of the bid as provided in the Information for Bidders, which is incorporated herein by reference or if the City shall reject the aforesaid bid then this obligation shall be null and void; otherwise it remains in full force and effect and the Surety shall fulfill its obligations under this Bid Bond.

In the event that the Principal's bid shall be accepted by the City and the Contract awarded to him, then the Surety hereunder agrees, subject only to the payment by the Principal of the premium therefore, if requested by the City, to write the aforementioned performance and payment bonds in the form set forth in the Contract documents.

It is expressly understood and agreed that the liability of the Surety for any and all claims under this Bid Bond shall in no event exceed the penal amount of this bid as stated herein.

In the event that the City accepts the Principal's bid, and either a Performance Bond, Payment Bond or both will not be required by the City on or before the thirtieth day after the date on which the City signs the Contract, there shall be no liability under the Bid Bond as to such Performance Bond or Payment Bond.

The Surety, for value received, hereby stipulates and agrees that the obligations of the Surety and its bond shall in no way be impaired or affected by any postponements of the date upon which the City will receive or open bids, or by any extensions of the time within which the City may accept the Principal's bid, or by any waiver by the City of any of the requirements in the bid documents. The Surety hereby waives notice of any such postponements, extensions, or waivers.

EPIN: 07218B0009

IN WITNESS WHEREOF, the P and such of them as are corporation these presents to be signed by their	ons have caused their	corporate seals to be her	eto affixed and
(Seal)	By:	Principal	(LS)
(Seal)	By:	Surety	

PIN: 072201821CPD EPIN: 07218B0009

ACKNOWLEDGMENT OF CONTRACTOR—IF A CORPORATION

State of	County of	SS:
On this day of	, 20, before me personally appeared	
	to me known, who being by me duly swe	orn, did depose and say
that he /she resides at		, that he/she is
	of	
seal of said corporation;	and which executed the foregoing instrument that one of the seals affixed to said instrument order of the directors of said corporation, and r.	nent is such corporate seal
	Notary Pu	ıblic
	EDGMENT OF CONTRACTOR—IF A PA	
State of	County of	ss:
	, 20, before me personally ap to me known and known to	
the firm described in and	who executed the foregoing instrument and h	ne/she acknowledged to me
that he/she executed the s	ame as and for the act and deed of said firm.	
	Notary Pu	ıblic

EPIN: 07218B0009

ACKNOWLEDGMENT OF CONTRACTOR—IF AN INDIVIDUAL

State of	County of	ss:
On this day of _		e me personally appeared
	o me to be the person described in and nowledged to me that he/she executed s	
	Notary I	Public

EPIN: 07218B0009

	PART C:	DETAILED	SPECIFICAT	IONS/SCOPE	OF WORK
--	---------	-----------------	-------------------	------------	----------------

(Note: See also Part E and Schedule "A" which contains the bonding and insurance requirements)

THE CITY OF NEW YORK DEPARTMENT OF CORRECTION 75-20 ASTORIA BOULEVARD, SUITE 160 EAST ELMHURST, NEW YORK 11370



CYNTHIA BRANN ACTING COMMISSIONER

Vernon C. Bain Center (VCBC) Chilled Water Risers and Pumps Replacement

Technical Specification

Budget ID: C75VRISER PIN 072201821CPD

Advertised Bid:

Vernon C. Bain Center (VCBC) Chilled Water Risers and Pumps Replacement 1 Halleck Street Bronx, New York 10474

Frank Doka Deputy Commissioner Frank Eilam Assistant Commissioner



TABLE OF CONTENTS

Section

I.	INT	RODUCTION	PAGE#
	A.	Project Objective	4
	B.	Contents of Technical Requirements	4
	C.	Contract Type	4
	D.	Quality Assurance	4
	E.	Start Work Date	5
II.	SCC	OPE OF WORK	5
	A.	Construction Services	6
	B.	Materials and Required Submissions	9
	C.	Construction Phasing	10
	D.	Daily Work Logs	10
	E.	Construction Staffing	10
III.	GEN	NERAL INFORMATION AND REQUIREMENTS	
	A.	Pre-Cost Proposal Conference and Site Visit	10
	B.	Review of Contract and Site	10
	C.	Representations	11
	D.	Time of Completion	11
	E.	Conformance to Requirements	11
	F.	Discrepancies	11
	G.	Department of Correction Contact	11
	H.	Definitions	12
	I.	Liability for Damage	13
	J.	Liquidated Damages	13
	K.	Guaranty-Warranty	13
	L.	Deviation from Scope of Work	13
	M.	Labor Law	14
	N.	Prompt Payment/Payment Procedure	14

IV.	BID ADMINISTRATION A. Basis of Awarding	15
	B. Bidding Procedure	15
	C. Bid Submission Deadline	16
	D. Fairness in the Bidding Process	16
v.	TECHNICAL SECTIONS	
	GENERAL REQUIREMENTS	
	01310 – Project Meetings	18
	01330 – Submittals	20
	01600 - Materials and Equipment	22
	01730 - Removals, Cutting, and Patching	24
	01770 – Contract Closeout	26
	01900 – Existing Premise Work	30
	GENERAL CONSTRUCTION SPECIFICATIONS	
	23000 - Basic Heating, Ventilation and Air Conditioning Requirements	40
	23001 – HVAC Piping	50
	23050 – Valves	57
	23070 – Piping Insulation	61
	23131 – Pumps	67
	23185 – Hydronic Specialties	70
	23230 – Thermometers and Gauges	73
	23550 – Pipe and Valve Identification	76
	23590 – Cleaning and Testing	80
	23940 – Balancing of System	85
	23965 – Sequence of Operation	87
	260519 – Wiring Systems	89
	260533 – Raceways, Fittings, Supporting Devices, Boxes and Accessories	96

VI. LIST OF DRAWININGS

T-001	TTTLE SHEET
C-001	SITE PLAN AND ELEVATIONS REFERENCE ONLY
M-01	GENERAL NOTES, LEGEND AND ABBREVIATIONS
DM-01	DEMO. CHILLED WATER FLOW SCHEMATIC DIAGRAM
DM-02	BOILER/TANK DECK DEMOLITION & INSTALLATION
DM-03	DEMO. MAIN DECK & TANK TOP CHILLED WATER PIPING PLAN
DM-04	DEMO. FIRST & SECOND DECK CHILLED WATER PIPING PLAN
DM-05	DEMO. 3^{RD} & 4^{TH} DECK & ABOVE CHILLED WATER PIPING PLAN
M-02	NEW INSTALLATION CHILLER PLANT FLOW DIAGRAM AND P&ID
M-03	NEW INTALLATION BOILER/TANK DECK
M-04 NEW	INSTALLATION MAIN DECK & TANK TOP CHILLED WATER PIPING PLAN
M-05	NEW INSTALLATION $1^{\rm ST}$ & $2^{\rm ND}$ DECK CHILLED WATER PIPING PLAN
M-06 NEW 1	INSTALLATION 3 RD & 4 TH DECK & ABOVE CHILLED WATER PIPING PLAN
M-07	SCHEDULES AND DETAILS

SECTION I <u>INTRODUCTION</u>

A. Project Objective

It is the objective of the Department of Correction, Division of Capital Policy and Development, to secure qualified Mechanical Contractors to provide construction for the Installation of Chiller Water Riser at Vernon C. Bain Center (VCBC) located at 1 Halleck Street, Bronx, NY 10474 as hereinafter described in these Technical Requirements.

The work is to be conducted at:

Vernon C. Bain Center (VCBC) Department of Correction 1 Halleck Street Bronx, NY 10474

The recipient of this Contract shall fully understand that it is of the utmost importance to the Department that the Work specified herein be completed within the time allotted.

The Contractor who is awarded the subject Contract shall furnish all labor, materials, equipment, paving, tools, implements, rigging, hoisting, shoring, cutting and patching, waste disposal, transportation, testing, utility surveys and protection necessary and/or required to complete all required rehabilitation and construction services as described in these Technical Requirements.

B. Content of Technical Requirements

The Technical Requirements consist of a cover, table of contents, project specification and drawings.

C. Contract Type:

The Contract work shall be carried out via a competitive sealed bid process. The award shall be made to the contractor after evaluation of the submitted responsive and responsible lowest bid cost for the complete requirement of the work items noted in the specifications and drawings.

D. Quality Assurance

- 1. The Contractor that is to be the recipient of this work must be fully qualified, having all licenses required by all agencies having jurisdiction over the work required under this Contract, and must have prior documented experience of having satisfactorily completed work of similar scope and magnitude to that specified herein for at least three (3) years.
- 2. Workmanship and Material (General)

Where any material or construction is required for the completion of the Contract, but the sizes of the material or the kinds of material are not clearly indicated or specified, they shall be of the size and kind required in the best interest of the City and as approved by the DOC Engineer.

The Contractor shall furnish and install all special construction that will be necessary to meet any unusual conditions as though specifically called forth herein.

All materials are to be of the best quality of their respective kinds and in ample quantities. Workmanship is to be of the best grade in every respect and all work must be executed in the best, most thorough, substantial and workmanship like manner.

Only persons experienced in their respective trades, and holding all necessary licenses as applicable, shall be employed in this work.

Any unfaithful or imperfect work or materials discovered shall be removed and corrected immediately after being condemned, and other work and materials furnished satisfactory to the Department at the Contractor's expense.

All materials furnished shall be entirely new, of the best grade and quality, free from defects and entirely satisfactory for the purpose intended.

E. Start Work Date

The Contractor shall begin work on the date instructed on the "Order to Proceed" from the Department. The start of work shall be coordinated with the Department of Correction Construction Management Unit Representative

SECTION II SCOPE OF WORK

The below description only provides a general overview of the scope of work. It will be the contractor's responsibility to review each and every document for actual scope of work.

General Construction

Demolition:

- 1. Remove pump bases
- 2. Demo areas at bulkhead to access piping
- 3. Clean up.

Installation:

- 4. Secure pumps to steel platform
- 5. Fire stopping
- 6. Priming and Painting

Mechanical

Demolition:

- 7. Disconnect and remove (3) chilled water pumps.
- 8. Replace chilled water supply and return branches.
- 9. Remove expansion tank
- 10. Remove chilled water risers
- 11. Clean up.

Installation:

- 12. Install (3) chilled water pumps with VFD's
- 13. Install new expansion tank
- 14. Install new isolation valves, one per chiller with a total of six (6) valves
- 15. Install new chilled water risers and branches throughout the facility.
- 16. Install marine grade hydronic components and insulation.
- 17. Flush, fill, purge, testing, balance of six (3) pumps and AHU branches system.
- 18. Training of NYCDOC personnel.
- 19. Interlock new pumps to existing BMS system
- 20. Clean up.
- 21. Obtain all required permitting.

Electrical

Demolition:

- 22. Disconnect power to chilled water pumps.
- 23. Remove disconnect switches for the pumps
- 24. Disconnect and remove conduit from the disconnect switches to the pumps.
- 25. Remove wiring from the disconnect switches to the pumps
- 26. Clean up

Installation:

- 27. Provide power to the new pumps by extending the existing circuitry
- 28. Provide new VFDs with integral disconnect switches
- 29. Provide new conduit, hangers and supports as required to extend the existing circuit
- 30. Provide new wiring as required to extend the existing circuit.
- 31. Clean Up

A. CONSTRUCTION SERVICES

After obtaining the required construction permits and approvals, the Contractor shall proceed with the Work. The Contractor shall observe the following requirements while carrying out the construction work.

- 1. The Contractor shall provide all materials, labor, tools, appliances necessary to complete all work required for the Installation of Chiller Plant at Vernon C. Bain Center (VCBC) located at 1 Halleck Street, Bronx, NY as noted in the Technical Requirements and as required by jurisdictional agencies.
- 2. <u>Asbestos Requirement</u>: The Contractor shall stop work and notify DOC of any suspected asbestos contaminated areas encountered during the course of the site investigation. The Contractor is not responsible for any asbestos investigation or

- abatement work. The DOC will perform an asbestos investigation and abatement (if needed) of the involved areas prior to the Contractor beginning work in those areas.
- 3. <u>Safeguards</u>: The Contractor shall provide during the performance of the work, and in accordance with OSHA and all other applicable regulations, proper safeguards at the worksite for the prevention of any accidents, injury, or damage to persons or property.
- 4. Removal of Debris: The Contractor shall remove from the facility and legally dispose of all debris resulting from the work required under this Contract. This shall include: construction debris, demolition debris, excavated soils, packaging, etc. Regarding site cleanliness, at the end of each workday the site shall be left in a condition which is acceptable to the Department.
- 5. <u>Utilities</u>: The Contractor shall be permitted to utilize the 120 volt electric supply at the facility, if available. However, the Contractor shall be responsible for providing all necessary extensions, switches, etc. to facilitate the usage of such electric power.

Regarding water for site work, the Contractor shall provide and utilize at its own expense, fresh water of a non-potable grade.

The Contractor shall be responsible for providing all other utilities not noted herein, including compressed air, generator power, etc. as required to fulfill the requirements of the Contract.

The Contractor shall provide temporary sanitary facilities for the Contract workers.

- 6. <u>Daily work schedule</u>: Normally, work is performed, Monday through Friday between the hours of 7AM to 3 PM. However, arrangements can be made as needed to permit the Contractor to work extended hours on-site. Note that the Contractor may work overtime to complete the project within the time allotted. However, there shall be no extra payment by the City for overtime differential wages. The shutdowns for this work shall be nights and weekends with prior arrangements with the facility.
- 7. Prior to beginning construction, the Contractor shall carefully lay out all its work. Where cutting, channeling, chasing, excavating and backfilling or drilling is necessary for the proper installation, support or anchorage of the Work specified under this Contract, the Work shall be carefully done by the Contractor. All cutting and patching shall be restored, by this Contractor, to no less than its former condition after the required installation.
- 8. <u>Covering of Work</u>: No device, or other work of any kind shall be covered or hidden from view before it has been examined or approved by the engineer, architect, and/or other authority having jurisdiction over the same. Any unfaithful or

- imperfect work or materials discovered shall be removed and corrected immediately after being condemned, and other work and materials furnished satisfactory to DOC.
- 9. <u>Painting</u>: All exposed piping, steel hangers, and supports are to be painted primed and finish coated.
- 10. The Contractor shall be responsible for: work and equipment until finally inspected, tested, and accepted by DOC; protecting work against theft, injury or damage; carefully storing material and equipment received on-site which is not immediately installed; closing open ends of work with temporary covers or plugs during construction to prevent entry of obstructing material.
- 11. Protection of Property: The Contractor shall be responsible for the preservation of all public and private property, along and adjacent to the work, and shall use every precaution necessary to prevent damage or injury thereto. The Contractor shall use suitable precautions to prevent damage to pipes, conduits and other underground structures or utilities, and shall carefully protect from disturbance or damage all property marks until an authorized agent has witnessed or otherwise referenced their location, and shall not remove them until so directed by the Department.

Any damages to public or private property resulting from the work of the Contractor shall be repaired by the Contractor at no additional cost to the City. If such damages are not repaired by the Contractor forthwith, then the City shall employ other means to repair the damages, and the Contractor shall be held responsible for all associated costs incurred by the City in facilitating the repairs.

- 12. <u>Coordination of utility connections</u>: The scheduling of all connections to existing facility utilities shall be coordinated with, and approved in advance by DOC.
- 13. <u>Construction Progress Meetings</u>: The Contractor is required to be represented at all construction progress meetings by personnel possessing full knowledge of the project. The frequency and scheduling of the meetings shall be determined by DOC, but shall occur no less than four times each month for the duration of the project.
- 14. <u>Site Responsibility</u>: The Contractor shall be responsible for work and equipment until finally inspected, tested, and accepted; protecting work against theft, injury or damage; and carefully storing material and equipment received on-site which is not immediately installed. The Contractor shall close open ends of work with temporary covers or plugs during construction to prevent entry of obstructing material.

The Contractor shall be fully responsible for all construction site health and safety. The Contractor shall be fully responsible for securing the work site in order to protect vehicular and pedestrian traffic in the vicinity. The Contractor shall observe all safety regulations of the Department of Transportation (DOT) and OSHA when working.

15. Operations of Others: During the time that the Contractor is performing the Contract, other trade contractors (electrical, mechanical, general contractors, etc ...) will be engaged in other operations on or about the site, including vehicular traffic which shall remain uninterrupted.

The Contractor shall so plan and conduct its operations as to work in harmony with others engaged in the area of the site and not to delay, endanger or interfere with the operations of others, all in the best interests of the City and the public and as may be directed by the Engineer.

No portion of the infrastructure systems, including but not limited to, gas distribution, storm sewer, sanitary sewer, potable water, steam, electric power, may be interrupted or curtailed by the Contractor without prior approval of the Department of Correction for the specific systems and time periods involved.

16. <u>Interference</u>: If the Contractor installs work so as to cause interference with the work of other trades or the normal operation of the facility, the Contractor shall make the necessary changes in its work to correct the condition, at no extra cost to the Department.

B. Materials and Required Submissions

- 1. All materials installed by the Contractor shall be new, of good quality, and suited for their intended applications in accordance with the requirements of all jurisdictional agencies, the requirements of the Technical Specifications, and the generally accepted practices of the industry.
- 2. Prior to beginning construction, the Contractor shall make all required submittals as noted in the 'SUBMITTALS' sections of the individual sections of the Technical Specifications.

For material items which are not specifically identified in the Technical Specifications, but which are required components of the subject systems, the Contractor shall be required to submit catalog cuts of the proposed items to the Department of Correction for approval. The Contractor shall not proceed with the purchasing and installing of material items which have not been approved by DOC. Additionally, cost data for the items shall be provided at the time of submission of each catalog cut.

- 3. The Contractor is not to proceed with the installation of materials without the written approval of the DOC. If any such materials are rejected by the DOC, the Contractor is to resubmit an alternate plan until approval is obtained.
- 4. To substitute another material for one after it has been approved, a written request must be submitted to the Department's project manager or engineer along with descriptive literature for the parts or materials which the contractor wishes to

substitute for those previously approved. Only upon receiving written approval of the latter submission from the Department may the Contractor proceed to install the substituted item.

C. Construction Phasing

Prior to beginning the Work, the Contractor shall coordinate construction phasing with the Department's Construction Management Unit project manager or engineer. All construction phasing shall be subject to the approval of the Construction Management Unit.

D. Daily Work Logs

During the course of the construction, the Contractor shall coordinate its daily work assignments with the DOC Construction Management Unit. In addition, daily work logs shall be kept for all work done by the Contractor.

E. Construction Staffing

All Contractor and Subcontractor staff shall have expertise in their respective areas of work. All Contractors/Subcontractors conducting work on this Project shall hold all licenses required by jurisdictional agencies necessary for performing the Contract work in which they are engaged or equivalent education and experience qualification.

SECTION III GENERAL INFORMATION AND REQUIREMENTS

A. Pre-Bid Conference and Site visit

A site visit shall be conducted with the Contractor at the site of the proposed work and the contractor shall note all conditions that affect the work to be done at the time of the pre-bid site visit.

B. Review of Contract Documents and Site

The Contractor shall acknowledge that it has examined the Specifications and site, and that from its own investigations it is satisfied as to the nature and location of the Work; the general and local conditions, particularly those bearing upon transportation, disposal, handling and storage of materials; availability of labor, water, electric power, roads and certainties of weather; the character of equipment and facilities needed preliminary to and during the execution of the Work; all federal, state, county, and municipal laws, ordinances and regulations, particularly those relating to employment of labor rates of wages, and construction methods; and all other matters which can in any way affect the Work or the cost thereof under this Contract. Any failure by the Contractor concerning

these conditions will not relieve it from the responsibility for estimating properly the difficulty or cost of successfully performing the work.

C. Representations

DOC assumes no responsibility for any understanding or representation made during or prior to any negotiation and execution of this Contract unless such understanding or representation is expressly stated in the Contract, and the Contract expressly provides that the responsibility is assumed by DOC.

D. Time for Completion

The Contractor shall complete all work required or specified by 365 CCD's. The Contractor shall be solely responsible for making the required submittals and receiving the necessary approvals on a timely basis.

Once the work has begun, the Contractor shall make every reasonable effort to ensure that the work proceeds to completion without interruption or unnecessary delay.

E. Conformance to Requirements

- 1. All work shall be conducted in accordance with the requirements of the NYC Building Code and all other agencies having jurisdiction. This shall include, but not be limited to, requirements for materials, installation procedures, and system/equipment tests.
- 2. All persons performing work on this project shall hold all appropriate licenses and permits as required by the NYC Department of Buildings and all other agencies having jurisdiction.

F. Discrepancies

Should any discrepancies be found between the field conditions and/or Contract documents, the Contractor shall be required to follow that which will result in a better installation. The Department of Correction's Engineer shall be the sole judge of what shall constitute the better installation.

G. Department of Correction Contact

Prior to the awarding of the Contract, all inquiries regarding the contents of these Requirements can be directed to the following persons:

1) For all contract related inquiries

Ava Rice
Agency Chief Contracting Officer
NYC Department of Correction
Central Office of Procurement

75-20 Astoria Blvd, Suite 160 East Elmhurst, NY 11370 (718) 546-0690

Email: ava.rice@doc.nyc.gov

H. Definitions

The following definitions are to apply to all sections of the Contract documents in their entirety:

"Commissioner" means the Commissioner of the Department of Correction, or any of her representatives.

"CCD" means consecutive calendar days.

"Contractor" means the entity which is the recipient of this Contract or any of that Contractor's agents.

"Department" means the Department of Correction, or any of its representatives.

"DOC" refers to the Department of Correction.

"Engineer" refers to any of the Department of Correction's engineering project manager.

"Engineering Unit" refers to the Engineering Unit of the Department of Correction Division of Capital Policy and Development.

"OTW" means "Order To Work"; the date on which the Contractor is given a written directive by the Department to proceed with the project.

"Project" means the Work required under this Contract in its entirety.

"Provide" means purchase and/or manufacture, deliver and install in an acceptable manner.

"Replace" means remove subject item(s) and install new, similar item(s), as required, in approximate same location.

"Supply" has the same meaning as "provide".

"Vendor" means the entity which is the recipient of this Contract or any of that party's agents.

I. Liability for Damage

The Contractor shall be responsible for the preservation of all public and private property, along and adjacent to the Work, and shall use every precaution necessary to prevent damage or injury thereto. The Contractor shall use suitable precautions to prevent damage to pipes, conduits and other underground structures or utilities, and shall carefully protect from disturbance or damage all property marks until an authorized agent has witnessed or otherwise referenced their location, and shall not remove them until directed to do so by the Department.

Any damage to public or private property resulting from the work of the Contractor shall be repaired by the Contractor at no additional cost to the City. If such damage is not repaired by the Contractor forthwith, then the City shall employ other means to repair the damages, and the Contractor shall be held responsible for all associated costs incurred by the City in facilitating the repairs.

J. Liquidated Damages

In the event the Contractor shall fail to complete the work within the term of the contract, plus authorized time extensions, or if the Contractor, in the sole determination of the Commissioner, has abandoned the work, the Contractor must pay to the city the amount of \$250.00 (Two Hundred and Fifty Dollars) for each day and part thereof that completion of the work exceeds the time allowed.

K. Guaranty-Warranty

The Contractor shall guarantee its work, free of defects in materials, installation and operation (excluding routine maintenance) for a period of two (2) years after completion of the work. During this period the Contractor shall replace any such defective materials promptly and free of charge to the Department.

L. Deviation from Scope of Work

If, for any reason, the Contractor has cause to believe that work in addition to that specified herein is required to put any or all of the subject systems in satisfactorily operating condition, then the Contractor is to notify the Engineer of the work entailed and the reason the Contractor believes such additional work is required. The Contractor is to proceed with the additional work only if written direction from the Department is provided. The written direction must be in the form of an approved change order.

The Contractor is to note that all work performed under this Contract, including additional change order work, is subject to audit by the City.

M. Labor Law

1. Compliance

The Contractor and any Sub-Contractors must comply strictly with all applicable provisions of the New York State Labor Law, including but not limited to Section 220 thereof with respect to the payment of prevailing rates of wages as amended and supplemented.

The Contractor or Sub-Contractor shall not have work performed or labor or means employed in the carrying out of this Contract that would in any manner cause or result in a suspension or delay of, or strike upon the work to be performed hereunder of any of the trades performing in or about other buildings or premises of the City of New York.

Failure to comply with these conditions shall place the Contractor in a default on this Contract. Upon notification of such default, the Contractor shall cease all work under this Contract. The City may then proceed to complete the work under the Contract, charging the Contractor with any loss or additional costs it may suffer by reason of such default.

2. Labor Law Provisions

The Contractor and any Sub-Contractor shall not employ on the work:

- a. Anyone who is not competent, faithful and skilled in the work for which he/she shall be employed, and whenever the Commissioner shall inform the Contractor in writing that an employee is, in his/her opinion, incompetent, unfaithful or disobedient, such employee shall be discharged from the work forthwith and shall not again be employed on this contract.
- b. Any labor, materials or means whose employment, or utilization during the course of this Contract, may tend to or in any way cause or result in strikes, work stoppages, delays, suspensions of work, or similar troubles by workers employed by the Contractor or any Sub-Contractors, or by any of the trades working in or about the buildings and premises where the Work is being performed under this Contract, or by other Contractors, or their Sub-Contractors pursuant to other contracts, or on any other building or premises owned or operated by the City of New York, its agencies, Departments, boards or authorities. Any violation by the Contractor of these requirements may, upon certification of Engineer to the Commissioner, be considered as proper and sufficient cause for declaring the Contractor to be in default and for the City to take action against him as set forth in the Contract, or such other action as the Commissioner may deem proper.

N. Prompt Payment Procedure

- 1. The prompt payment provisions set forth in the Procurement Policy Board Rules in effect at the time of this solicitation shall be applicable to payments made under a Contract resulting from this solicitation.
- 2. Partial Payments: The Contractor shall be entitled to monthly partial payments for completing specified portions of the work. Monthly partial payments shall be payable upon completion of the various parts of the project as shown on an approved Construction Payment Schedule submitted by the vendor at the beginning of the Project and as approved by the Department.
- 3. Invoicing for Payments: To request payment for construction services the Contractor shall submit all invoices to the Director of the DOC Construction Management Unit. All requests for payment must be accompanied by invoices and must include audit-compliant paper work which may be required by the Department's Engineering Audit Officer.
- 4. Final Payment: After approval and acceptance by the Department of the work, any remaining balance of the not-to-exceed lump sum cost(s) (except for the cost of items deleted from the Contract work) shall become due and payable to the Contractor and shall constitute the Final Payment under this Contract. Monies retained from partial payments shall be released upon completion of the work as part of the Final Payment, as approved by the Department.

In order to receive final acceptance of the required work and final payment for the same under the Contract, THE CONTRACTOR MUST FIRST OBTAIN THE WRITTEN APPROVAL OF THE PERTINENT CODE ENFORCEMENT AGENCIES FOR THE WORK AND FULFILL ALL PENDING WORK AS REQUIRED BY THE CONTRACT DOCUMENTS.

SECTION IV <u>BID ADMINISTRATION</u>

A. Basis of Awarding Contract

This awarding of this Contract will be by means of competitive sealed bid. Bidders shall submit a completed Bid Work Sheet which shall include the Total Bid amount for completing all work required herein in its entirety.

The Contract will be awarded to the qualified responsive Bidder that submits the lowest lump sum Total Bid Cost, and who has been determined to be a responsive responsible bidder.

B. Bidding Procedure

It is recommend that bidders attend the pre-bid meeting. It is not mandatory. All bidders are required to submit a Bid, which states that the Bidder will provide to the Department, for the submitted Total Bid Cost, all materials and services as required in the Specifications and that the Bid includes all costs associated with satisfactorily fulfilling the requirements of the Specifications and drawings. The Bid must be signed by a duly authorized representative of the company.

The Bid is to be submitted, by the specified time, IN A SEALED ENVELOPE, to:

New York City Department of Correction Central Office of Procurement 75-20 Astoria Blvd, Suite 160 East Elmhurst, NY 11370

Identify the Bid as a "BID" and indicate on the envelope the project's PIN: 072201734CPD and the Project's name: Vernon C. Bain Center (VCBC) Chilled Water Risers Replacement

C. Bid Submission Deadline

All bids are to be received at the location indicated above no later than the date and time indicated in the public advertisement of the Invitation for Bids, or as indicated in the Bid Schedule of this bid book, as amended, if appropriate.

D. Fairness in the Bidding Process

The New York City Comptroller is charged with the audit of contracts in New York City. Any Contractor who believes that there has been unfairness, favoritism or impropriety in the bid process, or as indicated in the bid schedule of this bid book as subsequently amended, if applicable, should inform the Comptroller, Office of Contract Administration, 1 Center Street, Room 835, New York, NY 10007; Telephone number (212) 669-300

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 01310 PROJECT MEETINGS

PART 1 GENERAL

1.01 <u>INITIAL JOB MEETING</u>

A. NYCDOC's Representative will notify all parties concerned of the time and place of the initial job meeting.

1.02 <u>CONSTRUCTION PROGRESS MEETINGS</u>

- A. Progress meetings will be held at a time and place agreed upon by NYCDOC's Representative and the Contractor as per Section II, A: Construction Services. Other interested parties may attend when needed, e.g., subcontractors and representatives from suppliers, public utilities, and local government.
- B. The meetings will be conducted by NYCDOC's Representative for the following purposes:
 - 1. Review job progress, quality of Work, and approval and delivery of materials.
 - 2. Identify and resolve problems which impede planned progress.
 - 3. Coordinate the efforts of all concerned so that the project progresses on schedule to on time completion.
 - 4. Maintain a sound working relationship between the Contractor and NYCDOC's Representative and a mutual understanding of the project requirements.
 - 5. Maintain sound working procedures.

1.03 PRE-INSTALLATION MEETINGS

- A. Pre-installation meetings will be held to review the specifications, drawings and approved submittals in preparation for start of a particular activity.
- B. The meetings shall be attended by NYCDOC's Representative, a Design Representative and the Contractor's Representative including installer and representatives of manufacturers & fabricators involved in or affected by the installation and its coordination with other materials/trades.
- C. NYCDOC's Representative shall schedule the meetings prior to the start of the work. The goal of these meetings is to ensure the quality of construction and to maintain the schedule.

1.04 <u>ATTENDANCE</u>

A. A Contractor's Representative shall be required to attend all meetings scheduled by NYCDOC's Representative.

- B. The Contractor's Representative shall be a competent supervisor familiar with the work and have authority to act for the Contractor.
- C. If the Contractor's Representative fails to attend two (2) scheduled meetings without prior approval, the Contractor will be directed to replace the current Contractor's Representative. Further incidents of non-attendance by the Contractor's Representative, will form the basis for review of the Contractor's responsible bidder status.

PART 2 PRODUCTS (Not Used)

PART 3 EXECUTION (Not Used)

END OF SECTION

SECTION 01330 SUBMITTALS

PART 1 GENERAL

1.01 RELATED REQUIREMENTS SPECIFIED ELSEWHERE

A. Other requirements pertaining to submittals are included in the General Conditions and in various sections of the Specifications.

1.02 DEVIATIONS FROM REQUIREMENTS OF THE CONTRACT DOCUMENTS

A. If, for any reason, the Contractor has cause to believe that work in addition to that specified herein is required to put any or all of the subject systems in satisfactorily operating condition, then the Contractor is to notify the Engineer of the work entailed and the reason the Contractor believes such additional work is required. The Contractor is to proceed with the additional work only if written direction from the Department is provided. The written direction must be in the form of an approved change order.

The Contractor is to note that all work performed under this Contract, including additional change order work, is subject to audit by the City.

1.03 SUBSTITUTIONS

A. Whenever a product is specified by brand name, a substitute brand, equal to that named, may be submitted for approval subject to the requirements under Section II, B: Materials and Required Submissions.

1.04 SHOP DRAWINGS

- A. Submit six (6) copies of each shop drawing required by the Specifications. Show the information, dimensions, connections, and other details necessary to insure that the shop drawings accurately interpret the Contract Documents. Show adjoining construction in such detail as required indicating proper connections. Where adjoining connected construction requires shop drawings or product data, submit such information for approval at the same time so that connections can be accurately checked.
- B. The shop drawings will be reviewed and two (2) stamped copies returned. If returned copies are stamped "DISAPPROVED" or "RETURNED FOR CORRECTION", promptly resubmit six (6) copies of shop drawings meeting Contract requirements.

1.05 PRODUCT DATA

- A. Submit six (6) copies of each item of product data required by the Specifications. Modify product data by deleting information that is not applicable to the project or by marking each copy to identify pertinent products. Supplement standard information, if necessary, to provide additional information applicable to the project.
- B. The product data will be reviewed and two (2) stamped copies returned. If returned copies are stamped "DISAPPROVED" or "RETURNED FOR CORRECTION", promptly resubmit six (6) copies of product data meeting Contract requirements.

1.06 PAYMENT SUBMITTAL

A. Prepare and submit an application for payment as directed by NYCDOC-Construction Management Unit. Payments will be made based on the determination of percentage of Work completed unless otherwise directed by NYCDOC's Representative and/or the Contracting Officer.

1.07 SUBMITTAL REQUIREMENTS

- A. Identify all submittals by project title and number. Include Contractor's name, date, and revision date. On shop drawings, product data, and samples, also include name of supplier and subcontractor (if any), and applicable specification section number. Stamp each submittal and initial or sign the stamp to certify review and approval of submittal.
- B. If a submittal is based on, or the result of, a change order or field order to the Contract documents include copies of applicable change order or field order with the submittal.
- C. Transmit each submittal to:

Mr. Hardee Saini NYC Department of Correction Engineering Unit 75-20 Astoria Boulevard, Suite 160 East Elmhurst, NY 11370

Enclose an original and two (2) copies of transmittal letter with each submittal.

D. Send one additional copy of each transmittal letter to NYCDOC's Representative at the site.

END OF SECTION

SECTION 01600 MATERIALS AND EQUIPMENT

PART 1 - GENERAL

1.01 RELATED REQUIREMENTS SPECIFIED ELSEWHERE

A. Specific requirements pertaining to materials and equipment specified elsewhere are additional to the provisions of this Section.

1.02 PRODUCT LABELS

A. When materials or equipment are specified to conform to American Society for Testing and Materials (ASTM), Federal or other reference specifications, the materials delivered to the site shall bear the manufacturer's printed labels stating that the materials meet the requirements of such referenced specifications.

1.03 TRANSPORTATION AND HANDLING

- A. Deliver factory packaged materials and equipment in the manufacturer's original containers.
- B. Transport and handle materials and equipment in such a manner as to prevent their damage.
- C. Arrange for delivery of materials and equipment during the hours of the day established by NYCDOC's Representative.
- D. Have workers available to receive and unload materials and equipment delivered to the site. Do not deliver, or have delivered, any materials and equipment to the site unless such forces are available.
- E. Facility personnel are not authorized to sign for receipt of Contractor's material or equipment.

1.04 STORAGE AND PROTECTION

- A. Neatly pile, store, protect, and secure materials and equipment in locations where directed.
- B. Protect materials and equipment subject to damage by temperature or other weather conditions.
- C. Do not store volatile liquids in a NYCDOC building.

PART 2 PRODUCTS (Not Used)

PART 3 EXECUTION (Not Used)

END OF SECTION

SECTION 01730 REMOVALS, CUTTING, AND PATCHING

PART 1 GENERAL

1.01 PROJECT CONDITIONS

- A. Do not disturb existing structures, construction, materials or equipment unless required by the Contract.
 - 1. Do not cut, drill or remove structural members such as joists, beams or columns supporting construction that is to remain unless expressly required by the Contract Documents.
- B. Existing Paint: If paint is believed to be lead based paint, contact NYCDOC immediately and stop work until further notice.

PART 2 PRODUCTS

2.01 MATERIALS

A. Match the appearance and performance of existing corresponding materials as closely as practicable, unless otherwise indicated.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Prior to cutting, drilling or removal, investigate both sides of the surface involved. Determine the exact location of structural members.
- B. If unforeseen obstructions are encountered, take precautions necessary to prevent damage and obtain instructions from the NYCDOC's Representative before proceeding with the Work.

3.02 PREPARATION

- A. Provide temporary shoring and other supports necessary to prevent settlement or other damage to existing construction which is to remain.
- B. Prepare existing surfaces properly to receive and, where required, bond with the Work.

3.03 <u>REMOVALS, CUTTING, AND ALTERING</u>

A. In addition to the items indicated to be removed on the Drawings, remove existing construction superseded by the Work except items such as pipes, conduits, recessed boxes, and ducts which are built into existing construction that is to remain. Cut off

- and conceal such items at face of remaining construction. Provide cover plates on recessed boxes.
- B. Remove and alter existing construction as required to install and connect the Work to adjacent construction in an approved manner.
- C. Cut and alter existing materials as required to perform the Work. Limit cutting to the smallest amount necessary. Core drill round holes and saw cut other openings where possible.
- D. Perform cutting, drilling, and removals in a manner which will prevent damage to construction which is to remain.
- E. Perform removal of items to remain the property of the State with such care as necessary to prevent damage to these items.

3.04 PATCHING

- A. Patch existing construction and finishes defaced, damaged, or left incomplete due to alterations and removals. Patching, except as otherwise indicated, shall be limited to the areas which have been cut or altered. Finish patched surfaces to match existing adjacent surfaces as closely as practicable.
- B. Perform patching around items penetrating existing construction in a manner that will maintain the water and fire resistive capability of the existing construction.
- C. Paint patched areas and cover plates to match existing adjacent surfaces as closely as practicable using same type of paint. Painting, except as otherwise indicated, shall be limited to the areas which have been patched.
- D. Where surfaces exposed by removals are to remain as exposed surfaces, paint such areas to match existing adjacent surfaces as closely as practicable using same type of paint.

3.05 REINSTALLATION

A. Where reinstallation of removed items is indicated, reinstall them to a condition equal to or better than their condition before removal.

END OF SECTION

SECTION 01770 CONTRACT CLOSEOUT

PART 1 - GENERAL

1.01 CONTRACT CLOSEOUT INSPECTIONS

- A. The following three (3) inspections will be made in addition to the normal inspections to ensure that all Contract requirements are met and that the Work is complete and acceptable. The purpose of each of these inspections is to furnish the Contractor a written list of Contract exceptions, omissions, and incompletions so that the Work can be progressed to timely completion in accordance with the Contract Documents.
 - 1. Detailed Inspection: The "Detailed Inspection" will be made when the Work is substantially complete. A copy of the detailed inspection list will be furnished to the Contractor. When this inspection progresses over any length of time, copies of the list will be furnished as the inspection progresses so that the Contractor may proceed with the required Work without delay.
 - 2. Final Inspection: The Contractor will be advised by letter of the date and time of final inspection. A copy of the final inspection list containing all incomplete or unsatisfactory items and the time allowed to complete the Work will be furnished to the Contractor.
 - 3. Joint Inspection for Physical Completion: The joint inspection for physical completion may be made to verify completion of the exception items listed on the final inspection list so that the physical completion date may be established.

1.02 FINAL CLEANING

- A. Perform final cleaning prior to joint inspection for physical completion. Leave the premises in a neat, unobstructed condition, the work areas broom clean (except where more thorough cleaning is specified), and everything in perfect repair and adjustment.
- B. Clean site.
- C. Remove tools, equipment, waste and surplus materials, rubbish, and construction facilities from the premises as soon as possible upon completion of the Work.

1.03 PROJECT RECORD DOCUMENTS

- A. Maintain on site, two (2) sets of the following record documents; record actual revisions to the Work:
 - 1. Contract Drawings.
 - 2. Project Manual.
 - 3. Addenda.
 - 4. Change Orders and other modifications to the Contract.
 - 5. Reviewed shop drawings, product data, and samples.

- B. Store record documents separate from documents used for construction.
- C. Record information concurrent with construction progress.
- D. Project Manual: Legibly mark and record in Part two (2) of each Section of the Specifications, a description of the actual products installed, including the following:
 - 1. Manufacturer's name and product model and number.
 - 2. Product substitutions or alternates utilized.
 - 3. Changes made by addenda and modifications.
- E. Record Documents and Shop Drawings: Legibly mark each item to record actual construction including:
 - 1. Measured depths of foundations in relation to finish (first) (main) floor datum.
 - 2. Measured horizontal and vertical locations of underground utilities and appurtenances, referenced to permanent surface improvements.
 - 3. Measured locations of internal utilities and appurtenances concealed in construction, referenced to visible and accessible features of the Work.
 - 4. Field changes of dimension and detail.
 - 5. Details not on original Contract Drawings.
- F. Upon completion of the work, create electronic versions of the project record documents. Black and white documents are to be scanned into Tag Image File Format (TIFF) using Consultative Committee for International Telephony and Telegraphy (CCIT) Group 4 compression. Documents with color, which include black line documents with color notations, are to be scanned into TIFF format using a minimum of eight (8) colors and "packbit" compression.
 - 1. The scanned images are to be put on a compact disc (CD) using ISO 9660 format. Name the electronic files with the same name as the drawing. Create a folder on the CD for each trade and one for Shop Drawings.
 - 2. Label the CD with the project number, name, and title as it appears on the project manual cover. If there is more than one CD include notation to that effect on the label; i.e., 1 of 3, 2 of 3, 3 of 3. The project record documents and CD(s) are to be turned over to NYCDOC's Representative.
- G. Applications for progress payments will not be approved if the record documents are not kept current. Application for final payment will not be approved until the project record documents are delivered to NYCDOC's Representative.

1.04 OPERATION AND MAINTENANCE DATA

A. Prepare two (2) sets comprised of 8-1/2 x 11 inch text pages bound in capacity expansion binders with durable plastic covers identified with printed title "OPERATION AND MAINTENANCE INSTRUCTIONS", title of project, and subject matter of binder when multiple binders are required. Prepare a printed Table of Contents for each volume, with each product or system description identified. Internally subdivide the binder contents with permanent page dividers, logically organized as described below, with tab titles clearly printed under reinforced laminated plastic tabs:

- <u>Part 1</u>: Directory, listing names, addresses, and telephone numbers of Architect/Engineer, Contractor, subcontractors, and major equipment suppliers.
- <u>Part 2</u>: Operation and maintenance instructions, arranged by system and subdivided by specification section. For each category, identify names, addresses, and telephone numbers of subcontractors and suppliers. Identify the following:
 - 1. Significant design criteria.
 - 2. List of equipment.
 - 3. Parts list for each component.
 - 4. Operating instructions.
 - 5. Maintenance instructions for equipment and systems.
 - Maintenance instructions for finishes, including recommended cleaning methods and materials and special precautions identifying detrimental agents.

<u>Part 3</u>: Project documents and certificates, including the following:

- 1. Shop drawings and product data
- 2. Certificates, affidavits and approvals.
- 3. Test reports for and including, but not limited to air and water balance reports
- 4. Photocopies of warranties
- B. Submit one copy of completed volumes in final form 15 days prior to final inspection. This copy will be returned after final inspection, with the NYCDOC's comments. Revise content of documents as required prior to final submittal.
- C. Submit 2 volumes prior to final Application for Payment.

1.05 WARRANTIES

- A. In addition to the warranties outlined in the General Conditions, all Labor Warranties shall be for two (2) years.
- B. Furnish warranty certification and copies of warranties that extend beyond the one year period required by the General Conditions. Warranties submitted without warranty certification will not be accepted.
 - 1. Warranty Certification: Written certification from the warrantor that invoices for installation, service, supplies, and warranty fees have been paid in full to persons or firms due payment, and that the warranty is in effect and non-retractable due to any of the specified conditions.
- C. Prepare printed Table of Contents and assemble warranty certifications and warranty copies in a binder with a durable plastic cover.
- D. Deliver the binder to NYCDOC's Representative prior to final Application for Payment.

- E. For items of Work delayed beyond date of Substantial Completion, provide updated submittal within 10 days after acceptance, indicating date of acceptance as start of warranty period.
- F. Applications for final payment will not be approved until the warranty certification and warranty documents are delivered to NYCDOC's Representative.

1.06 SPARE PARTS AND MAINTENANCE MATERIALS

- A. Label and deliver spare parts, maintenance items, and extra materials to the Site. Place in locations as directed.
 - 1. Include "NOT FOR WARRANTY REPAIRS" on the labels.
 - 2. Obtain receipt prior to final payment.
- B. Do not use the spare parts and maintenance materials required by the Contract Documents to remedy defects during the two-year period except when approved otherwise by authorized NYCDOC's Representative. In such cases, replace items used.
- C. Furnish the names, business addresses, and telephone numbers of fully equipped authorized service organizations to NYCDOC's Representative.
- D. Applications for final payment will not be approved until these items are delivered to the NYCDOC's Representative.

END OF SECTION

SECTION 01900 EXISTING PREMISES WORK

1.01 PROTECTION

A. General Safety Restrictions

- 1. The operation of the fire alarm telegraph, the interior fire alarm system, gongs, bells and telephones shall not be interfered with.
- 2. Nothing shall be done to in any way block the streets at or about exits, or the exits themselves.
- 3. There shall be no unauthorized interference with the free and unobstructed use of hallways, stairways, toilets and rooms.
- 4. Whenever work is carried on during facility hours use not more than one stairway shall be closed off from free and safe use at any time, and this only after the written permission of the NYCDOC has been obtained.
- 5. No part of the building or premises shall be closed to the use of the occupants without the permission of the NYCDOC. When such permission has been given, erect temporary partitions and barriers wherever required to ensure the absolute safety of the occupants of the building and premises.
- 6. Maintain on the premises a complete file of Material Safety Data Sheets for all materials, arranged by specifications section number. The file shall be available to NYCDOC's Representative for reference at all times.

B. Precautions Against Fire

- 1. Take every precaution in the performance of the Work to prevent fires.
- 2. Smoking shall not be permitted within the premises at any time.
- 3. N.Y.C. Fire Department regulations shall govern the storage and use of flammable materials. Flammable materials and fire-producing equipment shall not be left unattended about the premises in locations accessible to building occupants. All polyethylene sheeting shall be flame retardant in accordance with NFPA 701.
- 4. Rubbish shall be removed as hereinafter specified.
- 5. Fire extinguishers and other protective equipment shall be provided as required by regulations.
- 6. During all interruptions of Work, flammable mixtures shall be stored in designated locations.

C. Fire Watch

When open flame or spark-producing tools and equipment such as heating kettles on roofs, blow torches and welding rods are being used, the Contractor shall provide fire guards to maintain a fire watch over the operation of these items at all times during the use and until all materials have cooled sufficiently to no longer constitute a fire hazard. Provide additional fire guards required by Fire Department as determined by the Local Fire Department inspector after Work is under way.

D. Asbestos, Lead Paint and Other Hazardous Conditions

1. Contractor is to stop work and immediately notify the NYCDOC of any suspected contaminated areas including but not limited to: asbestos, lead paint, PCB caulking, PCB containing ballasts or mercury containing light blubs, encountered during the course of work.

E. Temporary Maintenance of Hazardous Conditions

- 1. Upon receipt of the Notice to Proceed, carefully inspect all existing work which is required to be repaired, altered or removed. Any such work which is found to be weakened, structurally unsafe or otherwise hazardous, shall be immediately put in a safe condition and so maintained until such time as the permanent work in connection therewith is completed.
- 2. Any restrictions regarding sequence of operations and locations of work do not apply to the elimination of hazardous conditions; all parts of the premises will be available at all times for the performance of such work.

F. Protection of Property

- 1. The Contractor shall be responsible for all damage to all new and existing work on the premises due to the Contractor's operations, and shall provide and maintain adequate protection against such damage.
- 2. The premises shall not be used as a work shop to the detriment of any portion thereof.
- 3. Any furniture and equipment shall not be used as workbenches; neither shall materials and furniture be piled thereon without proper protection. All furniture shall be protected by drop cloths or 6-mil polyethylene sheeting. The sheeting shall not be removed until clean-up is complete.
- 4. Provide decking on floors, steps, platforms, pavements and roofs where subject to damage from heavy traffic.
- 5. Provide protection of existing roofing and flashing and limit traffic to prevent any damage to the existing work. As a minimum provide a protective compressible layer of polyisocyanurate roof insulation board, 1" minimum thickness, over the existing membrane, and cover this cushion layer with a layer of hard protective board.
 - Where there is a warranty in effect the protection shall be acceptable to the roofing manufacturer such that the existing roof warranty is not jeopardized. Obtain the manufacturer's written approval of the protection methods and submit the approval letter to the NYCDOC prior to beginning work on the roof.
- 6. Protect doors and door jambs when conveying rubbish and materials.
- 7. Provide and maintain barricades to confine dust to work areas.
- 8. Provide watertight enclosures over openings at roof and walls; provide watertight protection where tank houses, bulkheads and other roof structures are removed; remove temporary waterproofing protection for installation of new permanent work.
- 9. All damage to adjoining work due to failure to provide adequate protection shall be corrected by the Contractor at the Contractor's expense.

10. After completion of the Work, the Contractor shall thereafter protect Work until it is accepted.

G. Protection of Building Occupants

- 1. The Contractor shall be responsible for all injury to persons due to the Contractor's operations and shall provide and maintain adequate protection against such injury.
- 2. Provide guards, rails, barricades, fences, sidewalk sheds, catch-platforms, decking, night lighting, and all other items as required by New York City Building Laws and as further required to provide adequate protection.
- 3. Provide barricades around work areas as required to prevent unauthorized persons from entering therein.
- 4. Provide plumbing and temporary drainage as required to keep all pits, trenches and other excavations, and the adjoining areas of the premises, dry during the course of the work.
- 5. Prevent exposure of persons to hazardous materials, offensive odors, noxious or toxic fumes or gases. Ensure that such contaminants are not recirculated through the ventilation systems, or through windows and openings, to occupied areas. Ventilate work areas prior to re-occupancy, to make certain that odors and gases are properly dissipated. Notify NYCDOC's Representative to conduct an inspection of the affected areas prior to re-occupancy.

H. Stability and Integrity of Existing Structures

- 1. Shoring of members and protection of the existing structure during construction is the responsibility of the Contractor and shall comply with the requirements of the NYC Building Code.
- 2. The most stringent requirements of the Building Code, Contract Drawings, Specifications, or any authorities having jurisdiction shall govern this Work.
- 3. Coordinate Work of this Section with Work of all other Divisions so as to properly, and completely, install all Work as indicated on Drawings or specified.

1.02 NON-INTERFERENCE WITH FACILITY FUNCTIONS

- A. Perform the Work in such a manner that normal facility functions may be carried on throughout the period of work with a minimum of interference. Before commencing work in any portion of the premises normally used for facility functions, meet with NYCDOC's Representative and perfect a working agreement. Noise shall be kept to a minimum.
- B. In general, the Contractor shall not use or work in rooms, corridors, stairs, or elevators designated for facility personnel.
- C. NYCDOC may assign a stair for Contractor use during working hours. Refer to the Phasing Exhibit. The Contractor shall only use the stair for access to floors and

shall not in any way obstruct the stair or make it unsuitable for use as an exit by occupants.

1.03 FRATERNIZATION

A. Contractor shall prohibit all contact between Contractor's employees (including Subcontractor's employees and visitors to the site) and the occupants.

1.04 WORK SCHEDULE AND PHASING

A. General:

1. All Work must be performed according to a Work schedule coordinated by the Contractor and the Department's Construction Management Unit as described in Section II, C: Construction Phasing that will not disrupt facility activities.

All decisions affecting the normal operation of the facility shall be coordinated with the NYCDOC's Representative.

- B. Work that shall be performed only when the building is totally unoccupied shall be as follows:
 - 1. Structural Work critical to the integrity of the building.
 - 2. Any Work generating dust, offensive odors, noxious or toxic fumes or gases (including but not limited to those containing chemicals or mineral dusts listed in Section 1910.1000 Air Contaminants, Tables Z-1, Z-2, and Z-3, OSHA Standards for General Industry, latest edition) that cannot be contained within an isolated Work area.
 - 3. Boiler start-up and testing.
 - 4. Ventilation system start-up and testing.
 - 5. Burning, welding, brazing, sweating

C. Voluntary Overtime Work:

When permission to perform overtime or alternate shift Work is requested by the Contractor for the Contractor's own purposes, in order to meet schedules or for the Contractor's own convenience, the Overtime Work shall be considered to have been included in the Contract Price and no increase in the Contract Price, or Extra, will be granted for the Overtime Work. Contractor shall pay all costs necessary to maintain the construction operation including but not limited to permits, temporary heat, temporary lighting, and temporary power.

D. Mandatory Overtime Work

If at any time, in the judgment of the NYCDOC, any item of Work is behind the established construction progress schedule, or is causing a delay that will affect the contract completion date, the NYCDOC may order the Contractor to increase The Contractor's Work force or to work the Contractor's forces and the forces of any Subcontractor overtime, at the Contractor's expense, until such time as all items of

work have progressed to be in accordance with the accepted construction progress schedule. The Contractor shall pay all costs necessary to maintain the construction operation including but not limited to permits, temporary heat, temporary lighting, and temporary power.

E. Ordered Premium Overtime Work:

- 1. The NYCDOC reserves the right to order and pay for rescheduling any regularly scheduled Work (other than that Work hereinbefore classified under Voluntary and Mandatory Overtime Provisions) as Premium Work or to add Premium Work to the regularly scheduled Work.
- 2. Such Premium Work will be made by Change Order of Extra Work as identified elsewhere in the Contract Documents.
- 3. Extra payment for Change Order of Extra Work shall be paid only for the actual difference between "regular labor rates" and "overtime labor rates," and the cost of any additional labor, material, permits, custodial and ancillary services (if any); plus an amount in accordance with the provisions of the Contract for any and all other costs, overhead, and profits that might be incurred by the Contractor, as determined by the NYCDOC.
- F. Contractor's Procedure for Performing Overtime or Ordered Premium Work To Be Done Prior To Commencing Work:
 - 1. Make immediate arrangements to provide such ancillary services, if any, as may be required by Working Men, and Community, including, but not limited to:
 - a. Sanitary facilities and drinking water.
 - b. Power and light.
 - c. Heating, Ventilating and Air Conditioning.
 - d. Fire Protection.
 - e. Security.
 - f. Dust Protection.
 - g. Clean-up and debris removal.
 - h. Obtain permit from Supervisory bureau.
- G. Contractor's Procedure During Overtime and Ordered Premium Work periods:
 - 1. Proceed expeditiously with Work.
 - 2. Do not begin any Work in any space unless all of the required materials and labor to complete that Work are at the job when Overtime or Ordered Premium work is scheduled to begin.
 - 3. Complete all Work in each phase by all trades that have Work to be accomplished in each phase and inside each defined area.
 - 4. All other limitations and restrictions governing Contract Work during building use shall apply to Overtime and Ordered Premium Work.

- H. Opening Permits (For Work Involving Wet Mopping & Wiping)
 - 1. For work that must be performed on holidays, and weekends the Contractor shall obtain from the Department of Buildings an "After-Hour Work Permit", and shall arrange to schedule.

1.05 CHANGE IN LEVELS

A. Where finished floor levels are raised or lowered as a result of Work specified, the Contractor shall make corresponding adjustments to existing floor registers, trap screws, plugs, catch basins, covers to cesspools and dry wells, coal holes, fresh air inlets, grates, fences, railings, tracks and all other work adversely affected by the change in levels, as required to restore proper relationship between these articles and the new floor surface.

1.06 WATER

A. Refer to Section II, A: Construction Services, #5.

1.07 ELECTRIC CURRENT

A. Refer to Section II, A: Construction Services, #5.

1.08 STORAGE SPACE

A. Storage space, if available, will be designated or assigned by the NYCDOC. Interior space will be assigned for storage of material liable to damage by weather. Provide any additional protection required and assume all responsibility for damage to materials. Do not store or temporarily leave materials in locations other than those assigned for storage.

1.09 MECHANICAL WORK

- A. The removing of sanitary, heating and ventilating and electric work, including plumbing fixtures, pipes, metal ducts, radiators, lighting fixtures, wires, bells, telephones, and other incidental removals, and the repairing, altering, extending and replacing of such work will be done by the Contractor, as required for the completion of the Work.
- B. All work damaged, disturbed or otherwise affected by the alterations shall be repaired.

1.10 MOVING OF FURNITURE, ARTICLES, AND FIXTURES

A. When the moving of furniture, shades, clocks, pictures, maps, plaster casts and other articles or fixtures is made necessary in the carrying on of the alterations, repair work, painting, cutting of openings through or removing of existing walls and partitions, or for any other such reason, the removing, resetting and relocating

together with the necessary repairing, shall be carefully done as a part of this Contract.

- B. Existing window shades, toilet accessories and other appliances shall be replaced and left in good condition; those which cannot be replaced shall be left in care of the NYCDOC Maintenance.
- C. All removed work shall be protected.

1.11 TEMPORARY DUST PARTITIONS AND BARRIERS

A. Dust Partitions (non-Fire-rated)

Provide temporary dust-tight partitions and doors complying with all requirements of the City of New York City Building Code and all authorities having jurisdiction.

- 1. Partitions shall extend tightly between walls and partitions, and tightly from floor to ceiling, at locations indicated on the Drawings.
- 2. Partitions shall be of 2"x4" stud framing, 16" on center with 2"x 4" sill and cap members. Framing shall be entirely covered both sides with 5/8", gypsum wall boards. Provide 3" sound attenuation mineral fire blankets between studs. Both sides of the partition shall be finished with 1/4" x 2" tempered hardboard batten strips over all joints, horizontal and vertical.
- 3. Provide continuous neoprene gasketing at juncture of Partition with walls, floor and ceilings or underside of structure.
- 4. Provide at least one, hollow metal door and frame assembly in each partition, where required for access. Door shall be 36" wide by 84" high and each door shall be equipped with hardware as specified in Section 08710 Finish Hardware: 1-1/2 pairs of butts; a closer; pulls (2 required); rim latch operable by knob-release from work area, key-operated from the other side (furnish three (3) keys); and sill protection sweep.

B. Dust Partitions (Fire-rated)

1. Construct same as in A., above, except provide for 1-hour fire-rated construction: use Type X gypsum board; use 1-hour rated steel door and frame.

C. Dust Barriers

- 1. Construct of PVC piping framework, telescoping, with holes and pegs to allow adjustment of heights. Cover framework completely with polyethylene film, 6-mils minimum thickness, with flap for access. Install at doorways to form vestibule between work area and other areas. Tape junctures to obtain dust-tight barrier. Construct in manner to provide easy assembly and disassembly.
- 2. Closet doors, cabinets, drawers, etc. which remain in the work area during demolition shall, at minimum, be sealed with duct tape (or equivalent) at all openings where dust may penetrate. As an alternative, the Contractor may completely cover the object and all openings in one layer of 6-mil polyethylene sheeting, sealed on all edges to prevent the penetration of dust.

3. The Contractor shall continuously inspect adjacent non-work areas and ensure that these areas are free of any dust or debris generated by the work.

1.12 REMOVAL OF RUBBISH

- A. Remove all rubbish (e.g., dirt, refuse, empty containers and packages, removed materials that become property of Contractor) from the premises as the work. No rubbish of any kind shall be stored in any rooms, halls, passageways or yards and no accumulation of rubbish shall be allowed to remain in or about the premises at any time during the course of the work for more than 24 hours.
- B. Should the Contractor fail to keep the building, premises and surrounding sidewalks and streets clean and free from rubbish resulting from the Work, then NYCDOC may have such rubbish removed by others in accordance with the terms of the Contract. In such event, there shall be withheld from any payment to the Contractor a sum determined by NYCDOC sufficient to cover the cost of removal by other parties.

1.13 CLEAN-UP

A. Daily Cleaning

- 1. The site shall be left in a condition which is acceptable to the NYCDOC.
- 2. The Contractor shall provide daily wet mopping of floors subject to construction dust in all areas affected by the Work.
- 3. All vertical and horizontal surfaces shall be cleaned and have a polished appearance and have no accumulation of dust, dirt, marks, streaks, smudges or fingerprints. All lighting fixtures and related work shall be clean.
- B. Upon completion of the Work, the Contractor shall provide thorough clean-up, performed by professional cleaning service, of all areas affected by the Work as follows:
 - 1. In general, clean-up requirements are limited to the removal of all rubbish, spatters, stains, smears, finger marks, foot tracks, from finish surfaces and the broom cleaning of floors, yards, sidewalks, and other areas on the premises that are affected by the Work.
 - 2. Where work that causes the dissemination of dust has been performed, clean-up operations shall include, in addition to the operations herein before specified, the washing of windows, the mopping of floors and the dusting and washing of walls, sills, furniture, and other surfaces, and the HEPA vacuuming of these same surfaces, all as required to restore work areas to the same state of cleanliness existing before work began.
 - 3. In performing dust-creating work, provide dust enclosures and foot mats to minimize the spread of dust and foot marks. Refer to part. 1.11 of this Section.
 - 4. This final clean-up is in addition to the required daily removal of rubbish.

C. Wet Wiping and HEPA Vacuuming

The Contractor shall provide wet wiping, and HEPA vacuuming by professional cleaning service, of all surfaces (including furniture) in all areas affected by the Work, immediately prior to the releasing of the areas for facility use.

END OF SECTION

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 23000

BASIC HEATING, VENTILATING AND AIR CONDITIONING REQUIREMENTS

PART 1 - GENERAL

1.01 SCOPE OF WORK

A. Provide labor, materials, tools, machinery, equipment, and services necessary to complete the HVAC Work under this Contract. All systems and equipment shall be complete in every aspect and all items of material, equipment and labor shall be provided for a fully operational system and ready for use. Coordinate the work with the work of the other trades in order to resolve all conflicts without impeding the job progress.

Examine the Architectural, Structural, Plumbing and Electrical Drawings and other Divisions, and Sections of the Specifications in order to determine the extent of the Work required to be completed under this Division. Failure to examine all the Contract Documents for this Project will not relieve the Contractor of his/her responsibilities to perform the Work required for a complete fully operational and satisfactory installation.

C. The Work includes but is not limited to the following systems, equipment and services:

Mechanical

a) Refer to Section II – Scope of work - Mechanical

1.02 RELATED WORK

- A. Division 1 General Requirements
 - B. Division 2, 3, 4, 5, 7 (Structural Sections)
 - C. Division 16 Electrical Sections

1.03 SUBMITTALS

- A. General: Unless indicated otherwise in the specific technical section, if a particular product specified in the technical section is being provided, manufacturer's qualifications and samples (except as listed below), are not required to be submitted. Manufacturer's product data, installation instructions, samples requiring color or texture approval, samples showing thickness and type of material, shop drawings, and calculations are to be submitted. Schedules, startup manuals, operation and maintenance manuals, and shop drawings are always required to be submitted.
- B. The following Submittals are required for all Sections of Division 15-Heating, Ventilating, and Air Conditioning. Specific "Supplemental Submittals" or additional information to that listed below that are required to be submitted are defined in each individual technical section.
 - 1. Product Data: Submit manufacturer's product data for equipment including catalog sheets or cuts, specifications, capacity, performance charts, test data, materials, dimensions, weights,

- furnished specialties and accessories; and installation instructions. Submit start-up instructions where applicable.
- 2. Shop Drawings: Submit manufacturer's shop drawings detailing equipment assemblies and indicating dimensions, weight, loadings, required clearances, method of field assembly, components, location and size of each field connection.
- C. Where indicated in the Supplemental Submittals of the technical sections, the following submittals are defined as follows:
 - 1. Maintenance Data: Submit maintenance data and parts list. Include this data and the product data in the maintenance manual in accordance with the requirements of Division 1.
 - 2. Test Report: Submit factory certified test results prior to shipping.
 - 3. Certificates: Submit written affidavit stating that the Contractor has started up and demonstrated (in the presence of the NYCDOC's Representative and required Department of Correction personnel, including a Maintenance Representative) that the equipment is operating properly as designed.
- D. Piping, Ductwork, and Wiring Diagrams: Submit a complete wiring diagram, ductwork layout, and piping layout of all equipment. All parts of the installation shall be indicated exactly as installed and shall be properly identified. Valve identification numbers shall agree with valve tags of Section 23550: Identification and all piping shall be clearly shown and labeled.
- E. Coordination Drawings: Provide complete coordination Drawings showing interface of all mechanical trades with the Architecture of the Building. All copies are to be signed. The Contractor is to keep a copy of the signed coordination drawing on the site.

1.04 QUALITY ASSURANCE

A. Manufacturer's Qualifications: If a particular product specified in the technical section is not being provided, provide manufacturer's qualifications.

Provide manufacturer's qualifications that indicate that the firms are regularly engaged in manufacture of equipment, of types, materials, and sizes required, whose products have been in satisfactory use in similar service for not less than five years.

B. Codes and Standards: All equipment furnished and installed shall meet or exceed the referenced Standards and Codes in all respects – installation, performance, etc.

References and industry standards listed herein and in other HVAC Sections are applicable to the Work specified in the Section. Unless more restrictive criteria is explicitly called-out for in other HVAC Specifications or mandated by the Building Code, the requirements described in the referenced standards below shall be deemed applicable to the Work. This includes language in the documents in the form of a recommendation or suggestion, which shall be deemed as mandatory.

- 1. NFPA
- 2. NYC BUILDING CODE

- 3. ASHRAE
- 4. SMACNA
- 5. ELECTRICAL IEEE STANDARDS
- 6. STATE DEC REGULATIONS
- 7. NYCDEP DEPARTMENT OF AIR RESOURCES CRITERIA
- 8. ASME
- 9. ANSI
- 10. NY INDUSTRIAL CODE RULE 4
- 11. ABMA
- 12. UL
- 13. LOCAL LAWS
- 14. NCPWB
- 15. FCI
- 16. EJMA
- 17. MSS
- 18. ABMA
- 19. IRI
- 20. MEA
- 21. AABC
- 22. NEBB
- 23. ARI
- 24. AMCA
- 25. ADC
- 26. NEMA
- 27. NEC
- 28. ASTM
- 29. FCI

1.05 ACCESSIBILITY

- A. Install access for servicing and maintenance. Coordinate the final location of concealed equipment and devices requiring access with final location of access panels and doors. Allow ample space for removal of all parts that require replacement or servicing.
- B. For access doors to valves, dampers and all other HVAC type of items, accessories and equipment, concealed in walls, furring's and hung ceilings; Door shall permit full access to the equipment.

1.06 ROUGHING-IN

A. Verify final locations for roughing work with field measurements and with the requirements of the actual equipment being connected. Coordinate with General Construction drawings.

1.07 MECHANICAL INSTALLATIONS

- A. Coordinate HVAC equipment and materials installation with other building components.
- B. Verify all dimensions by field measurements.
- C. Arrange for chases, slots, and openings in other building components to allow for HVAC installations.

- D. Sequence, coordinate, and integrate installations of HVAC materials and equipment for efficient flow of the Work. Give particular attention to large equipment requiring positioning and entrance prior to the close of the building.
- E. Coordinate the cutting and patching of building components to accommodate the installation of HVAC equipment and materials.
- F. Where mounting heights are not detailed or dimensioned, install HVAC services and overhead equipment to provide the maximum headroom possible.
- G. Install HVAC equipment to facilitate maintenance and repair or replacement of equipment components. As much as practical, connect equipment for ease of disconnecting and minimum of interference with other installations.
- H. Coordinate the installation of HVAC materials and equipment above ceilings with suspension system, light fixtures, and all other installations and accessories.
- I. Provide all rigging, disassembly and reassembly of equipment including the furnishing and installation of dunnage and all other required and necessary accessories.

1.08 COORDINATION DRAWINGS

- A. Provide coordination drawings. Coordination drawings shall be completed so as not to delay the progress of the Project.
- B. The coordination drawings shall be prepared in the following manner: HVAC Subcontractor shall prepare a set of mylars drawn to the scale of 3/8"=1'-0", indicating thereon ductwork, steam and return piping, refrigerant piping, and sprinkler work, plus structural and architectural background details. HVAC Subcontractor shall deliver this set of mylars to Plumbing and Drainage, who will draw the P&D work to scale on the mylars. Then the HVAC Subcontractor shall deliver the set of mylars to Electrical, who will superimpose the Electrical work on the drawings. The elevation, location, support points, and size of all lines shall be indicated. All beam and slab penetrations shall be indicated and sizes shall be coordinated. HVAC Contractor shall provide shop drawings for all roof openings required for installation of HVAC systems. Roof opening shop drawings shall be dimensioned from the centerline of the nearest structural column and coordinated with the approved HVAC equipment, sheet metal shop drawings, framing plan, etc. The specified order in which the Subcontractors impose their work on the mylars is not intended to grant priority to any one Subcontractor in the allocation of space. At the completion of this phase, hold a coordination meeting to eliminate any interference among the trades that the drawings indicate and to avoid any conflicts in installing the Work. Should any problems of coordination require architectural or structural change of design, this change shall be submitted to the NYCDOC for approval.
- C. If any trade installs any Work before coordinating with the Work of other trades, that Trade shall make necessary changes to correct the condition without extra cost to the NYCDOC. This requirement for "Coordination Drawings" shall not be construed as authorization to make any unauthorized changes to the Drawings. All Design Drawings space allocations shall be maintained, such as ceiling height, chase walls, equipment room size, and all other items and accessories, unless prior written authorization is received from the NYCDOC to change them.

- D. After the set of mylars has been coordinated, and all necessary changes have been made, each Subcontractor shall sign the coordination drawings, attesting to the agreement that the work is clear.
- E. Furnish (in writing, with copies to the Engineer and the NYCDOC) any information necessary to permit the Work to be installed satisfactorily and with the least possible interference or delay.

1.09 <u>CUTTING AND PATCHING</u>

- A. Do not endanger or damage installed Work through procedures and processes of cutting and patching.
- B. Arrange for repairs required to restore the work, because of damage caused as a result of HVAC installations.
- C. No additional compensation will be authorized for cutting and patching Work that is necessitated by defective or non-conforming installations.
- D. Perform cutting, fitting, and patching of HVAC equipment and materials required to:
 - 1. Remove and replace defective work.
 - 2. Remove and replace work not conforming to requirements of the Contract Documents.
 - 3. Remove samples of installed work as specified for testing.
 - 4. Install equipment and materials in existing structures.
 - 5. Cut, remove and legally dispose of selected HVAC equipment, components, and materials as indicated, including, but not limited to removal of HVAC piping, heating units and trim and other HVAC items made obsolete by the new work.
 - 6. Protect the structure, furnishings, finishes, and adjacent materials not indicated or scheduled to be removed.

1.10 EQUIPMENT NOISE AND VIBRATION

- A. Provide equipment and systems that, as defined herein, shall be quiet and free of apparent vibration in operation.
- B. The vibration shall not be apparent in occupied areas of the building. Both the balancing of rotating machinery and the installation of vibration isolation at various locations are required.
- C. Obtain equipment that is quiet in operation as compared to other available equipment of its size, capacity, and type; install equipment so that a minimum amount of noise and/or vibration is transmitted to the building; and fabricate the duct system so that air noises generated in the system are held to an absolute minimum.

D. Adjust all the equipment RPM, noise production and vibration in order to avoid any production of resonance in any system.

1.11 EQUIPMENT GUARDS

A. Provide easily removable expanded metal guards for all belts, couplings, exposed fan inlets and outlets, and other moving parts of machinery. Provide tachometer openings in the guards at least 2" in diameter, for all belt-driven or variable speed machinery. Equipment guards shall comply with OSHA requirements.

1.12 <u>ELECTRICAL CHANGES TO MECHANICAL EQUIPMENT</u>

A. If any changes made in equipment submitted are approved especially as to the sizes of the motors, notify Electrical.

1.13 <u>DELIVERY, STORAGE, AND HANDLING</u>

- A. Handle equipment carefully to prevent damage, breaking, denting, and scoring. Do not install damaged units or components; replace with new.
- B. Store equipment in clean dry place. Protect from weather, dirt, fumes, water, construction debris, and physical damage.
- C. Comply with manufacturer's rigging and installation instructions for unloading equipment, and moving them to final location.

1.14 GUARANTEES, WARRANTIES, BONDS, AND MAINTENANCE CONTROL

- A. Refer to General Sections for procedures and submittal requirements for warranties. Refer to individual equipment specifications for warranty requirements.
 - 1. Compile and assemble the warranties specified for HVAC work into a separated set of documents, tabulated and indexed for easy reference.
 - 2. Provide complete warranty information for each item to include product or equipment including duration of warranty or bond; and names, addresses, and telephone numbers and procedures for filing a claim and obtaining warranty services.
 - 3. Unless otherwise noted in the specific sections, warranties for the equipment, workmanship and materials shall be provided for the period of one year. Exceptions include, but are not limited to, the five-(5) year warranty provided for the refrigeration compressors.
 - 4. Manufacturers', not Contractors' warranties, shall be provided for all HVAC equipment and accessories.
 - 5. All warranties are to start from the date of Substantial Completion.

1.15 OPERATIONS, TRAINING, AND MANUAL

- A. Refer to General Sections for procedures and requirements for preparation and submittal of operation and maintenance manuals of each HVAC equipment. Refer to individual equipment specifications for maintenance manual additional requirements. In addition, include the following information:
 - 1. Description of function, normal operating characteristics and limitations, performance curves, engineering data and tests, and complete nomenclature and commercial numbers of all replaceable parts.
 - 2. Manufacturer's printed operating procedures to include start-up, break-in, routine and normal operating instructions; regulation, control, stopping, shut-down, and emergency instructions; and summer and winter operating instructions.
 - 3. Maintenance procedures for routine preventative maintenance and troubleshooting; disassembly, repair, and reassemble; aligning and adjusting instructions.
 - 4. Servicing instructions and lubrication charts and schedules.
- B. Bind all the other Sections maintenance manuals in a single final Operating and Maintenance Manual.

1.16 PAINTING

A. Painting Schedule

- 1. No on-site painting is required on the following items unless specifically indicated otherwise:
 - a. Concealed metal and piping.
 - b. Piping or ductwork to be insulated.
 - c. Insulation on piping or ductwork in unfinished spaces or concealed.
 - d. Mechanical equipment with a factory applied baked on enamel finish, not specified to be insulated or provided with an enameled steel insulated jacket.

2. Paint the following:

- a. Hangers, Supports, Restraints and Accessories:
 - 1) All black steel or iron pipe hangers, rods, inserts, brackets, restraints, and accessories for supporting piping systems and duct systems: 1 coat of primer and 2 coats of latex semi-gloss enamel. Paint black steel hanger rods, threaded on the job site, with a primer immediately after installation.

B. Color Coding:

1. Apply finish paints of colors indicated opposite the various items listed below where such items are installed in Mechanical Equipment Rooms:

Piping, Exposed - Bare and Insulated on Unfinished Spaces and Rooms:

Refrigerants Green

Sprinkler Systems Red

Steam Supply (all pressures) Yellow

Steam Condensate Returns Yellow

1.17 ADJUSTING AND CLEANING

A. Perform final cleaning prior to joint inspection for physical completion. Leave the premises in a neat, unobstructed condition, the work areas shall be broom cleaned (except where more thorough cleaning is specified).

- B. Clean site.
- C. Remove tools, equipment, waste, surplus materials, rubbish, and construction facilities from the premises as soon as possible upon completion of the Work.
- B. Alignment/adjustment: Check alignment, and where necessary, realign equipment within recommended tolerances by the manufacturer and in presence of manufacturer's service representative and the NYCDOC.

1.18 TORCH BURNING OPERATION

- A. The storing and use of oxygen and combustible gases in conjunction with torch burning apparatus is subject to the Rules and Regulations of the Division of Fire Prevention of the Fire Department of the City of New York, latest Fire Prevention (F.P.) Directive. Fire watches shall be provided during all operations using torches for burning, cutting or welding.
- B. Contractor shall apply for and obtain permits for the use and storage of such equipment on premises. The operator of such equipment shall have a certificate of fitness issued by the Fire Department.
- C. The cost of permits, certificates, fire watches, apparatus and other items required in the torch burning operation shall be borne by the Contractor at no additional cost to the NYCDOC.

PART 2 - PRODUCTS - NOT APPLICABLE

PART 3 - EXECUTION

3.01 INSPECTION

A. Examine areas and conditions under which equipment is to be installed. Do not proceed with work until conditions are suitable.

3.02 INSTALLATION

- A. Install equipment in accordance with manufacturer's installation instructions. Install units plumb and level, firmly anchored in locations indicated, and maintain manufacturer's recommended clearances.
- B. Support: Install equipment on 4" high concrete pad when installed on floor, with vibration isolators and restraints as required.
- C. Accessories: Install equipment accessories not installed at factory and shown on the Drawings.
- D. Connections: Connect all equipment and accessories as recommended by manufacturer for a complete installation.
- E. Contractor shall not leave sharp exposed metal edges (bottom of threaded rods, mechanical equipment supports, etc.) that could otherwise present safety hazards to the building's occupants/work staff.

3.03 <u>START-UP AND DEMONSTRATION/TRAINING/SERVICE</u>

- A. Start-Up and Demonstration/Training: The Contractor shall start-up and demonstrate, in the presence of the NYCDOC's Representative including Maintenance Representative, the proper operation of all equipment provided in this Contract. The Contractor shall also provide training to the NYCDOC's designated Representatives.
- B. Service: Provide the services of a competent field service representative to furnish service to the facility during construction and during the warranty period. Service must be performed within 48 hours from the time of notification (24 hours for emergencies).

3.04 ADJUSTING AND CLEANING

A. Cleaning: Clean factory-finished surfaces. Repair any marred or scratched surfaces with manufacturer's touch-up paint.

3.05 SPARE PARTS

A. Provide a set of spare parts that may be normally required, such as belts, filters, etc. that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

<u>TESTING</u>

A. The Contractor shall furnish energy, fuel, oil, water, air, light and electrical instruments as required for all testing. Reference Section of Cleaning and Testing.

END OF SECTION

SECTION 23001 HVAC PIPING

PART 1 GENERAL

1.01 RELATED WORK SPECIFIED ELSEWHERE

N/A

1.02 **SUBMITTALS**

A. Product Data:

- Catalog sheets and specifications indicating manufacturer name, type, 1. applicable reference standard, schedule, or class for specified pipe and fittings.
- 2. Material Schedule: Itemize pipe and fitting materials for each specified application in Pipe and Fittings Schedule in Part 3 of this Section. Where optional materials are specified indicate option selected.

B. **Quality Control Submittals:**

- Installers Qualification Data:
 - Welder Qualification Data: Copies of certification; include names, a. home addresses.
 - b. Welding Procedures:
 - Copy of QW-482 "Suggested Format for Welding 1) Procedure Specification (WPS)" for all welders for all weld types.
 - Copy of QW-483 "Suggested Format for Procedure 2) Qualification Record (PQR)" as specified in Welding Quality Assurance below for all weld types.
 - Welders' Certificates: c.
 - Copy of QW-484 "Suggested Format for Manufacturer's 1) Record of Welder or Welding Operator Qualification Tests (WPO)" for all welders for all weld types.
- C. Welding Procedure Submittals: Submit the following:
- Welding Procedure Specifications: Provide for each weld type.

 a. Recommended to use ASME Form E00006, QW-482 "Suggested Format for Welding Procedure Specification (WPS)".

 Procedure Qualification Records: Provide for each weld type.

 a. Recommended to use ASME Form E00007, QW-483 "Suggested Format for Procedure Qualification Records".
 - 2.
 - Format for Procedure Qualification Record (PQR)".

D. **Contract Closeout Submittals:**

Copy of Final Hydrostatic Testing Record Log.

1.03 **QUALITY ASSURANCE**

A. Qualifications of Welding Procedures, Welders and Welding Operators: Comply with the following:

B. Welding Procedures:

- 1. Record in detail, and qualify the Welding Procedure Specifications for every welding procedure that is proposed to be used for the Project.
- 2. Develop procedures for all metals included in the work.
- 3. Qualify the procedures for making transition welds between different materials, or between plates or pipes of different wall thickness.
- 4. Qualification for each welding procedure shall conform to the requirements of ASME B31.1, and as specified herein.
- 5. Describe the method for each system including the number of beads, the volts, the amperes, and the welding rod for various pipe thicknesses and materials.
- 6. The welding procedures shall specify end preparation for butt welds including cleaning, alignment, and root openings.
- 7. Preheat, interpass temperature control, and postheat treatment of welds shall be as required by approved welding procedures, unless otherwise indicated or specified.
- 8. Approval of any procedure does not relieve the Contractor of the sole responsibility for producing acceptable welds.
- 9. Welding procedures shall be identified individually and shall be clearly referenced to the type of welding required for this project.
- 10. These procedures shall be the same as those used for all pipe welder qualification tests, all shop welds, and all field welds.
- 11. Provide procedure qualification records for all proposed Welding Procedure Specifications (WPS).

C. Welder Qualification:

1. WPOs:

3.

- a. Provide welder qualifications for each welder for each weld type.
- b. Recommended to use ASME Form E00008, QW-484 "Suggested Format for Manufacturer's Record of Welder or Welding Procedure Qualification Tests (WPQ)."
- 2. Perform WPQs under the witness of an independent agency.
 - a. The witness shall be a representative of an independent testing agency, Authorized Inspector, or consultant, any of which must be approved by the National Certified Pipe Welding Bureau.
 - b. The qualifying test segment must be a 2 inch nominal pipe size with wall thickness within range of the WPS.
 - c. Tests position shall be "6G" per ASME Section IX. Evidence of Continuity: Welder qualifications must be current.
 - a. If the qualification test is more than 6 months old, provide record of welding continuity for each welder.

- b. Record of welding continuity shall show that the welder in question has performed welding to the procedure in question without a 6 month continuous span of inactivity since the date that the welder qualification test was passed for the submitted welding procedure.
- c. Record of welding continuity shall include, at a minimum, the welder's employer name and address, the date the welder qualification test was passed, and the dates indicating welding continuity including welding procedure for each date.

D. Weld Records:

- 1. For all welding within the scope of ASME B31.1, submit for approval an administrative procedure for recording, locating, monitoring, and maintaining the quality of all welds to be performed on the project.
 - a. The weld record shall include but not be limited to drawings and schedules identifying location of each weld by individual number, identification of welder who performed each weld by individual welder's name, stamp number, date and WPS used.
- 2. After achieving qualification, but before being assigned work, each qualified person shall be assigned an identifying number by the Contractor to be used to identify all of his welds.
 - A list of qualified persons with their respective numbers shall be submitted and maintained accurately with deletions and additions reported promptly.
- 3. Upon completing a joint, the welder shall mark the pipe not more than 6 inches from the weld with the identifying number and the last two digits of the year in which the work was performed.
 - a. Make identification marks with a rubber stamp or felt-tipped marker with permanent, weatherproof ink or other methods approved by the Director's Representative that do not deform the metal.
 - b. Place identification marks for seam welds adjacent to the welds at 3-foot intervals.
 - c. Identification by die stamps or electric etchers is not acceptable.
 - d. Provide required markers. Substitution of a map of welds with welders' names is not acceptable.
- 4. Maintain a constantly updated log available to the Director's Representative at all times.

1.05 <u>DELIVERY, STORAGE, AND HANDLING</u>

A. Pipe Storage:

- 1. Upon the receipt of each shipment of pipe on the job, maintain the pipe marking, and store pipe in accordance with ASTM material specifications, and method of manufacture (seamless, etc.) of each length of pipe.
- 2. Pipe markings shall be clearly readable at the time of pipe installation.

- 3. If at the time of its installation, any length of pipe not readily identifiable will be subject to rejection, or arbitrary downgrading by the Director's Representative to the lowest grade which has been received on the job to that date.
- 4. Provide factory-applied plastic end-caps on each length of pipe and tube, except for concrete, corrugated metal, bell and-spigot, and clay pipe.
 - a. Maintain end-caps through shipping, storage and handling to prevent pipe-end damage and prevent entrance of dirt, debris, and moisture.

PART 2 PRODUCTS

2.01 STEEL PIPE AND FITTINGS

- A. Standard Weight Schedule 40 or Extra Heavy Weight Schedule 80, Black.
- B. Flanges, Welding Neck Type, Same Pressure Rating as Adjoining Pipe: ASME B16.5.
- C. Weld Fittings, Carbon Steel:
 - 1. Butt Welding Type: ASME B16.9.
 - a. Allied Piping Products Co., Inc.'s Branchlets, Type 1 or 2.
 - b. Bonney Forge Corp.'s Weldolets.
 - c. or approved equal.
- D. Malleable Iron, Steam Pattern Threaded Fittings:
 - 1. 150 lb Class: ASME B16.3.
- E. Unions: Malleable iron, 250 lb class, brass to iron or brass to brass seats.
- F. Couplings: Same material and pressure rating as adjoining pipe, conforming to standards for fittings in such pipe. Use taper tapped threaded type in screwed pipe systems operating in excess of 15 psig.
- G. Nipples: Same material and strength as adjoining pipe, except nipples having a length of less than one inch between threads shall be extra heavy.

2.02 <u>DIELECTRIC CONNECTORS</u>

- A. Dielectric Fitting: Bronze ball valve with end connections and pressure rating to match associated piping.
 - 1. Nipples with inert non-corrosive thermoplastic linings are not acceptable.

PART 3 EXECUTION

3.01 <u>INSTALLATION - GENERAL</u>

A. Install piping at approximate locations indicated, and at maximum height.

- B. Install piping clear of door swings, and above sash heads.
- C. Make allowances for expansion and contraction.
- D. Allow for a minimum of one inch free air space around pipe or pipe covering, unless otherwise specified.
- E. Install vertical piping plumb.
- F. Use fittings for offsets and direction changes, except for Type K soft annealed copper tube.
- G. Cut pipe and tubing ends square; ream before joining.
- H. Threading: Use American Standard Taper Pipe Thread Dies.
 - 1. Thread brass pipe with special threading dies.
- I. Make final connections to equipment with unions, flanges, or mechanical type joint couplings.

3.02 WATER AND PROPYLENE GLYCOL PIPING SYSTEMS

A. Pitch:

- 1. Pitch horizontal piping 1/8 inch per 10 feet in direction indicated on drawings. When direction of flow is not indicated, pitch supply piping up in direction of flow and return piping downward in direction of flow.
- 2. Pitch single pipe systems up in direction of flow 1/8 inch per 10 feet.
- B. Air Vents: Install air vents at locations indicated on the drawings, and at each high point in system. Use manually operated air vents, unless otherwise indicated.

C. Drains:

- 1. Install piping to be completely drainable. Provide drains at low points, consisting of a 1/2 inch valve with a hose bibb connection, and at the following locations and equipment:
 - a. In each section of piping separated by valves.
 - b. For each riser, where riser or runout to riser has a valve installed.
 - c. For each heating cooling unit, having valves in supply and return connections.
 - d. In low point of piping to each down fed convector or radiator.
- D. Runouts: Connect runouts to upfeed risers to top of mains, and runouts to downfeed risers to bottom of mains.

3.03 PIPE AND FITTING SCHEDULE

A. Abbreviations: The following abbreviations are applicable to the Pipe and Fitting Schedule:

BS Black steel.

ST Steel.

SW Standard weight.

WE Weld end.

XH Extra heavy weight.

- B. Where options are given, choose only one option for each piping service. No deviations from selected option will be allowed.
- C. Schedule of Pipe and Fittings for the different piping services is as follows:
 - 1. Chilled Water (CWS & CWR) 125 psig and less:
 - a. 3 inch and less: SW BS pipe with SW fittings.
 - b. 4 inch Size: SW BS pipe, with SE SW fittings, or WE SW ST fittings.
 - c. 5 inch and Up: SW BS pipe, with WE SW ST fittings.
 - d. Chilled Water (CWS & CWR) 126 psi to 250 psi:

END OF SECTION

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 23050 VALVES

PART 1 GENERAL

1.01 ABBREVIATIONS

A. IBBM: Iron body, bronze mounted.

1.02 **SUBMITTALS**

- A. Product Data: Manufacturer's catalog sheets and specifications for each valve type.
- B. Valve Schedule: List type of valve, manufacturer's model number, and size for each service application.

1.03 MAINTENANCE

- A. Special Tools:
 - 1. One wrench for each type and size wrench operated plug valve.
 - 2. Two insert changing tools, and one spare insert for each self contained thermostatic radiator control valve.

PART 2 PRODUCTS

2.01 <u>VALVES - GENERAL</u>

- A. Valve Standardization: Valves from one or more manufacturers may be used, however valves supplied for each specific valve type shall be the product of one manufacturer.
- B. Vales to be Marine grade and have marine grade coating.
- C. Valves shall be first quality, free from all imperfections and defects, with body markings indicating manufacturer and rating.
- D. Valve parts of same manufacturer, size and type shall be interchangeable.
- E. Manually operated globe valves shall be of rising stem type, unless otherwise specified.
- F. Valves which use packing shall be capable of being packed when wide open and under full working pressure.

G. Size valves the same size as the piping in which they are installed, unless specified otherwise.

2.02 GLOBE

A. Type K: Marine grade,125 psig WSP, 200 psig, IBBM, bolted bonnet, and flanged ends depending on size. Acceptable Valves: Crane 351 & 353, Hammond IR116, Jenkins 613C & 615C, Milwaukee F2981, Nibco F718B & F818B, Stockham G512, & G515 or approved equal.

2.03 BUTTERFLY VALVES

- A. Type BF: Marine grade, Iron body, flangeless wafer or lugged type, (lug for each bolt hole, drilled and tapped for cap screws), with replaceable reinforced resilient EPT (EPDM) seats, bronze or nickel plated ductile iron discs, phosphate coated steel or stainless steel stems, and raised necks able to accommodate 2 inches of insulation. Acceptable Manufacturers: Crane, Demco, De Zurik, Hammond, Keystone, Milwaukee, Nibco, Stockham, Watts or approved equal.
 - 1. Pressure Ratings:
 - a. 12 inch size and Less: 150 psig at 275 degrees F.
 - b. 14 inch size and Up: 150 psig at 275 degrees F.

B. Operators:

- 1. 6 inch size and Less: Manual actuator handles with external indication of disc position, and suitable means of locking actuator in any fixed position.
- 2. 8 inch size and Up: Worm gear operator.

2.04 GAGE COCKS

A. Gage Cocks: Marine grade, All brass construction, "T" or lever handles, threaded ends, built for 300 psig hydraulic pressure. Acceptable Manufacturers: Marsh Instrument Company, Mueller Instruments Co., H.O. Trerice Co., Weksler Instruments Corp or approved equal.

2.05 BALL VALVES

A. Type BV: Marine grade,150 psig WSP, 600 psig WOG, 2 piece bronze body, solid blow-out proof stem, teflon seats, chrome plated brass ball, teflon seals, corrosion resistant steel lever handles with vinyl grips, balancing stop, and threaded or solder ends. Acceptable Manufacturers: Conbraco, Hammond, Milwaukee, Nibco, Watts or approved equal.

2.06 GATE VALVES

- A. Type A: Marine grade, 125 psig, bronze body, union bonnet, solid wedge disc, and threaded ends. Acceptable Valves: Crane428UB, Hammond IB617, Jenkins 47CU, Milwaukee 1152, Nibco T134, Stockham B105 or approved equal.
- B. Type C: Marine grade, 125 psig, up to 16 inch size; bolted bonnet, solid wedge disc, and threaded or flanged ends depending on size. Acceptable Valves: Crane 464-1/2 & 465-1/2, Hammond IR1140, Milwaukee F2885, Nibco T6170 & F6170, Stockham G620 & G623 or approved equal.

2.07 ACTUATORS

- A. Install as indicated on contract documents.
- B. Marine grade.
- C. Electric; 120v, 1 phase.
- D. Torque; as specific valve required
- E. Temperature range; -13 F to 131 F
- F. Housing; NEMA 4X
- G. Manufacture; Crane, Rotork, or approved equal.

PART 3 EXECUTION

3.01 <u>INSTALLATION</u>

A. General: Install valves at locations noted on the drawings or specified.

3.02 <u>VALVE APPLICATION SCHEDULE</u>

- A. Schedule of valve applications for the different services is as follows:
 - 1. Chilled Water (CWS & CWR) 125 psig and Less:
 - a. 3 inch and Less: A -BV balls, K globes.
 - b. 4 inch and Up: BF butterflys, K globes

END OF SECTION

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 23070 PIPING INSULATION

PART 1 GENERAL

1.01 RELATED WORK SPECIFIED ELSEWHERE

N/A

1.02 <u>ABBREVIATIONS</u>

- A. FS: Federal Specification.
- B. K: Thermal Conductivity, i.e., maximum Btu per inch thickness per hour per square foot.
- C. pcf: Pounds per cubic foot.
- D. PVC: Polyvinylchloride.

1.03 SUBMITTALS

- A. Product Data: Manufacturer's catalog sheets, specifications and installation instructions for the following:
 - 1. Insulation Materials.
 - 2. Jacket Materials.
- B. Quality Control Submittals:
 - 1. Installers Qualification Data:
 - a. Name of each person who will be performing the Work, and their employer's name, business address and telephone number.
 - b. Furnish names and addresses of the required number of similar projects that each person has worked on which meet the qualifications.

1.04 **QUALITY ASSURANCE**

- A. Qualifications: The persons installing the Work of this Section and their Supervisor shall be personally experienced in mechanical insulation work and shall have been regularly employed by a company installing mechanical insulation for a minimum of 5 years.
- B. Regulatory Requirements:
 - 1. Insulation installed inside buildings, including laminated jackets, mastics, sealants and adhesives shall have a Fire Spread/Smoke Developed Rating of 25/50 or less based on ASTM E 84.

PART 2 PRODUCTS

2.01 PIPING INSULATION

- A. Flexible Elastomeric Foam Insulation:
 - 1. FM tested and approved, meeting the following:
 - a. Maximum Water Vapor Transmission: 0.10 perm inch based on ASTM E 96, Procedure A.
 - b. K of 0.27 at 75 degrees F based on ASTM C 518 or C 177.
 - c. Fire Spread/Smoke Developed Rating: 25/50 or less based on ASTM E 84.
 - 2. Pipe Insulation: ASTM C 534, Type I.
 - 3. Polyethylene and polyolefin insulation is not acceptable.
- B. High Density Jacketed Insulation Inserts for Hangers and Supports:
 - 1. For Use with Fibrous Glass Insulation:
 - a. Cold Service Piping:
 - 1) Polyurethane Foam: Minimum density 4 pcf, K of 0.13 at 75 degrees F, minimum compressive strength of 125 psi.
 - 2) For Use with Flexible Elastomeric Foam Insulation: Hardwood dowels and blocks, length or thickness equal to insulation thickness, other dimensions as specified or required.

C. Cements:

- 1. Fibrous Glass Thermal Insulating Cement: Asbestos free; ASTM C 195.
- 2. Fibrous Glass Hydraulic Setting Thermal Insulating and Finishing Cement: ASTM C 449/C 449M.

2.02 <u>INSULATION JACKETS</u>

- A. Laminated Vapor Barrier Jackets for Piping: Factory applied by insulation manufacturer, conforming to ASTM C 1136, Type I.
 - 1. Type I: Reinforced white kraft and aluminum foil laminate with kraft facing out.
 - a. Pipe Jackets: Furnished with integral 1-1/2 inch self sealing longitudinal lap, and separate 3 inch wide adhesive backed butt strips.
 - 2. Laminated vapor barrier jackets are not required for flexible elastomeric foam insulation.
- B. Canvas Jackets: Cotton duck, fire retardant, complying with NFPA 701, 4 oz or 6 oz per sq yd as specified.
- C. Premolded PVC Fitting Jackets:
 - 1. Constructed of high impact, UV resistant PVC.
 - a. ASTM D 1784, Class 14253-C.
 - b. Working Temperature: 0-150 degrees F.
- D. Metal Jacketing:
 - 1. Aluminum: ASTM B 209, Alloys 1100, 30003, 3105 or 5005, Temper H14, 0.016 inch thick.

- a. Factory Pre-formed Sectional Pipe Jacketing:
- 1) Smooth outer finish with integral bonded laminated polyethylene film kraft paper moisture barrier underside.
- 2) Pittsburgh or modified Pittsburgh longitudinal lock seams.
- 3) 2 inch overlapping circumferential joints with integral locking clips, or butt joints sealed with 2 inch wide mastic backed aluminum snap bands.
 - b. Fastening Devices:
- 1) Strapping: Type 18-8 stainless steel, 0.020 inch thick, 1/2 and 3/4 inch wide as specified.
- 2) Wing Seals: Type 18-8 stainless steel, 0.032 inch thick.
- 3) Sheet Metal Screws: Panhead, Type A, hardened aluminum, and stainless steel.

2.03 ADHESIVES, MASTICS, AND SEALERS

- A. Lagging Adhesive (Canvas Jackets): Childers' CP-50A, Epolux's Cadalag 336, Foster's 30-36 or approved equal.
- B. Vapor Seal Adhesive (Fibrous Glass Insulation): Childers' CP-82, Epolux's Cadoprene 400, Foster's 85-75 or 85-20 or approved equal.
- C. Vapor Barrier Mastic/Joint Sealer (Fibrous Glass Insulation): Childers' CP-30, Epolux's Cadalar 670, Foster's 95-44 or 30-35 or approved equal.
- D. Adhesive (Flexible Elastomeric Foam): Armstrong's 520, Childers' CP-80, Epolux's Cadoprene 488, Foster's 82-40 or approved equal.
- E. Adhesive (Reinforcing Membrane): Childers' Chil-Spray WB CP-56 or approved equal.
- F. Mastic (Reinforcing Membrane): Childers' AK-CRYL CP-9 or approved equal.
- G. Sealant (Metal Pipe Jacket): One-part silicone sealant for high temperatures; Dow Corning's Silastic 736 RTV or General Electric's RTV 106 or approved equal.

2.04 MISCELLANEOUS MATERIALS

- A. Pressure Sensitive Tape for Sealing Laminated Jackets:
 - 1. Acceptable Manufacturers: Alpha Associates, Childers, Ideal Tape, Morgan Adhesive or approved equal.
 - 2. Type: Same construction as jacket.
- B. Wire, Bands, and Wire Mesh:
 - 1. Binding and Lacing Wire: Nickel copper alloy or copper clad steel, gage as specified.

- 2. Bands: Galvanized steel, 1/2 inch wide x 0.015 inch thick, with 0.032 inch thick galvanized wing seals.
- 3. Wire Mesh: Woven 20 gage steel wire with 1 inch hexagonal openings, galvanized after weaving.
- C. Reinforcing Membrane: Glass or Polyester, 10 x 10 mesh. Alpha Associates Style 59, Childer's Chil-Glas, Foster's MAST-A-FAB or approved equal.

PART 3 EXECUTION

3.01 PREPARATION

- A. Perform the following before starting insulation Work:
 - 1. Install hangers, supports and appurtenances in their permanent locations.
 - 2. Complete testing of piping.
 - 3. Clean and dry surfaces to be insulated.

3.02 <u>INSTALLATION, GENERAL</u>

- A. Install the Work of this Section in accordance with the manufacturer's printed installation instructions unless otherwise specified.
- B. Provide continuous piping insulation and jacketing when passing thru interior wall, floor, and ceiling construction.
 - 1. At Through Penetration Firestops: Coordinate insulation densities with the requirements of approved firestop system being installed.
 - a. Insulation densities required by approved firestop system may vary with the densities specified in this Section. When this occurs use the higher density insulation.
- C. Do not intermix different insulation materials on individual runs of piping.

3.03 <u>INSTALLATION AT HANGERS AND SUPPORTS</u>

- A. Reset and realign hangers and supports if they are displaced while installing insulation.
- B. Install high density jacketed insulation inserts at hangers and supports for insulated piping.
- C. Insulation Inserts For Use with Flexible Elastomeric Foam Insulation:
 - 1. Where clevis hangers are used, install insulation shields with hardwood filler pieces, same thickness as adjoining insulation, inserted in undersized die cut or slotted holes in insulation at support points.
 - 2. Contour hardwood blocks to match the curvature of pipe, and shield.
 - 3. Coat dowels and blocks with insulation adhesive, and insert while still wet.

- 4. Vapor seal outer surfaces of dowels and blocks with adhesive after insertion.
- 5. Install filler pieces as follows:

PIPE/TUBING SIZE	FILLER PIECES	POSITION
Thru 1-1/2"	2 dowel plugs	6 o'clock; in tandem
2" thru 4"	1 block, 2 dowel plugs	6 o'clock, and 4 & 8 o'clock respectively
6" thru 10"	2 blocks, 4 dowel plugs	6 o'clock; in tandem and 4 & 8 o'clock; in tandem

3.04 <u>INSTALLATION OF FLEXIBLE ELASTOMERIC FOAM INSULATION</u>

- A. Where possible, slip insulation over the pipe, and seal butt joints with adhesive.
 - 1. Where the slip-on technique is not possible, slit the insulation and install.
 - 2. Re-seal with adhesive, making sure the mating surfaces are completely joined.
- B. Insulate fittings and valves with miter cut sections. Use templates provided by the manufacturer, and assemble the cut sections in accordance with the manufacturer's printed instructions.
 - 1. Insulate threaded fittings and valves with sleeved fitting covers. Over lap and seal the covers to the adjoining pipe insulation with adhesive.
- C. Carefully mate and seal with adhesive all contact surfaces to maintain the integrity of the vapor barrier of the system.
- D. Piping Exposed Exterior to a Building, Totally Exposed to the Elements:
 - 1. Apply flexible elastomeric foam insulation to piping with adhesive.
 - 2. Apply reinforcing membrane around piping insulation with adhesive or mastic.
 - 3. Adhesive Applied System: Apply 2 coats of finish. See Section 099103.
 - 4. Mastic Applied System: Apply another coat of mastic over reinforcing membrane.

3.05 <u>INSTALLATION OF SHEET METAL JACKETING ON PIPING</u>

- A. Secure jacketing to insulated piping with preformed aluminum snap straps and stainless steel strapping installed with special banding wrench.
- B. Jacket exposed insulated fittings, valves and flanges with mitred sections of aluminum jacketing.
 - 1. Seal joints with sealant and secure with preformed aluminum bands.

3.06 PIPING INSULATION SCHEDULE

A. Insulate all cold service and hot service piping, and appurtenances except where otherwise specified.

3.07 COLD SERVICE INSULATION MATERIAL SCHEDULE

ТҮРЕ	SERVICE AND TEMPERATURES	INSULATION MATERIAL	PIPE SIZES (INCHES	MINIMUM (NOMINAL) INSULATION THICKNESS (INCHES)
С	Chilled Water and other fluids (except domestic cold water) 40 F to 80 F.	Flex. Elastomeric Foam	1-1/2 & less Over 6"	1 1-1/2

END OF SECTION

SECTION 23131 PUMPS

PART 1 – GENERAL

1.01 RELATED WORK SPECIFIED ELSEWHERE

1. Wiring Systems: Section 260519.

1.02 SUBMITTALS

- A. Product Data: Catalog sheets and installation instructions for each type or size pump.
- B. Schedule: Pump schedule showing pump specifications and application.
- C. Quality Control Submittals:
 - 1. Performance curves for each pump, showing gpm, brake HP and efficiency from free delivery to shut-off. Chart curves on manufacturer's factory tests shall be conducted in accordance with the recommended procedures of the Hydraulic Institute, and certified thereto by the manufacturer.

D. Contract Close Out Submittals:

1. Operation, Maintenance Data, and Parts Lists: Deliver 2 copies, for each type of pump or pumping apparatus, to the Director's Representative.

1.03 MAINTENANCE

A. Spare Parts: Deliver one spare set of mechanical seals for each size and type of pump equipped with mechanical seals, to the Director's Representative, who will sign receipt for same. Furnish seals of type as required for the particular pump application and the chemical water treatment being utilized. Suitably box and label spare seals as to their usage.

PART 2 PRODUCTS

2.01 PUMPS – GENERAL

- A. Design pumps to operate continuously without overheating bearings or motors at every condition of operation on the pump curve, or produce noise audible outside the room or space in which installed.
- B. Equip pumps complete with electric motor and drive assembly, unless otherwise indicated. Design pump casings for the indicated working pressure and factory

- test at 1-1/2 times the designed pressure.
- C. Provide pumps as complete factory assembled and prewired packaged units, each complete with integral pump controls and VFD.
- D. Pumps of the same type, shall be the product of a single manufacturer, with pump parts of the same size and type interchangeable.
- E. Equip base mounted pumps with OSHA compliant metal guards over the moving drive assembly. Fabricate from expanded galvanized metal or galvanized sheet metal. Secure guards as required and approved.
- F. Pump shall be provided with factory VFD
- G. Provide pump with Hex Guard enclosure around coupling.

PART 3 – EXECUTION

3.01 <u>INSTALLATION</u>

A. Install base mounted pumps on steel deck floor. Level, and align pump and weld to steel base.

3.02 FIELD QUALITY CONTROL

- A. Preliminary System Tests:
 - 1. Preparation: Adjust the completed system and then operate it long enough to assure that it is performing properly.
 - 2. Run a preliminary test for the purpose of:
 - a. Determining whether the system is in a suitable condition to conduct the acceptance test.
 - b. Checking control equipment.
 - c. Training Facility personnel.
- B. System Acceptance Test:
 - 1. Preparation: Notify the Director's Representative at least 3 working days prior to the test so arrangements can be made to have a Facility Representative witness the test.
 - 2. Make the following tests:
 - a. Individually test control devices.
 - b. Test alarm indicating devices.
 - c. Test each system function step by step.
 - 3. Supply equipment necessary for system adjustment and testing.

4. Submit a typewritten report of the test results. Enclose a copy of the report in a metal frame covered with clear acrylic glazing and mount it adjacent to the pump control panel.

END OF SECTION

SECTION 23185 HYDRONIC SPECIALTIES

PART 1 – GENERAL

1.01 RELATED WORK SPECIFIED ELSEWHERE

A. Piping: Section 23070.

1.02 **SUBMITTALS**

- A. Product Data: Catalog sheets, specifications, and installation instructions for each item specified.
- B. Contract Closeout Submittals:
 - 1. Operation and Maintenance Data: Deliver 2 copies, covering the installed products, to the Director's Representative.

PART 2 – PRODUCTS

2.01 EXPANSION TANKS

- A. Type A Expansion Tank: Welded steel (ASME Boiler and Pressure Vessel Code Section VIII, Division I) with air control tank fittings, and gage glass tappings.
 - 1. Maximum Working Pressure: 125 psig.
 - 2. Maximum Operating Temperature: 250 degrees F.
- B. Type B Expansion Tank: Pre-pressurized, welded steel (ASME Boiler and Pressure Vessel Code Section VIII, Division I) with heavy duty butyl rubber diaphragm, air charging valve, and plugged drain.
 - 1. Maximum Working Pressure: 125 psig.
 - 2. Maximum Operating Temperature: 200 degrees F.

2.02 AIR VENTS

- A. Type B: Automatic Float Operated Vent; ITT Hoffman Model 78 or approved equal.
 - 1. Construction: Brass body with stainless steel ball check, and 1/8 inch safety drain connection.
 - 2. Maximum Working Pressure: 150 psig.
 - 3. Maximum Operating Temperature: 250 degrees F.
- B. Type C: Automatic Float Operated Vent; ITT Hoffman Model 79 or approved equal.
 - 1. Construction: Brass body with stainless steel ball check, and 1/8 inch

safety drain connection.

- C. Maximum Working Pressure: 75 psig.
- D. Maximum Operating Temperature: 250 degrees F.
- E. Type D: Automatic High Capacity Float Operated Vent; Sarco Model 13W, or ITT Bell and Gossett Model 107 or approved equal.
 - 1. Construction: Cast iron body with bolted and gasketed cover, and stainless steel float mechanism, and 3/8 inch drain connection.
- F. Maximum Working Pressure: 150 psig.
- G. Maximum Operating Temperature: 250 degrees F.
- H. Type E: Automatic High Pressure Float Operated Vent; ITT Hoffman Model 792 or approved equal.
 - 1. Construction: Cast iron body (30,000 psi tensile strength) with heat treated stainless steel internal parts, and stainless steel float.
- I. Maximum Working Pressure: 250 psig.
- J. Maximum Operating Temperature: 300 degrees F.
- K. Maximum Hydrostatic Pressure: 350 psig.

PART 3 – EXECUTION

3.01 INSTALLATION

L. Install the Work of this Section in accordance with the manufacturer's printed installation instructions.

END OF SECTION

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 23230 THERMOMETERS AND GAUGES

PART 1 GENERAL

1.01 RELATED WORK SPECIFIED ELSEWHERE

A. Valves: Section 23050.

1.02 **SUBMITTALS**

A. Product Data: Manufacturer's catalog sheets, specifications and installation instructions for each item specified.

1.03 QUALITY ASSURANCE

A. Regulatory Requirements: Where Federal, NSF, ASME or other standards are indicated or required, products shall meet or exceed the standards established for material, quality, manufacture and performance.

PART 2 PRODUCTS

2.01 MANUFACTURERS/COMPANIES

- A. Dresser Instruments.
- B. Marsh Bellofram.
- C. Moeller Instrument Co.
- D. Taylor Precision Products.
- E. H.O. Trerice Co.
- F. Weksler Instruments Corp.
- G. or approved equal

2.02 THERMOMETERS

- A. General Design Features:
 - 1. Scale Ranges: 1-1/2 times actual working temperature required for the particular application, as approved.
 - a. Maximum of two degrees between graduations and ten degrees between numerals.
 - b. When scale ranges are in excess of 100 degrees, maximum range between numerals may be 20 degrees, or as otherwise approved for the particular application.

- 2. Direct Reading Thermometers: Bimetallic actuated, dial type, straight pattern, angle pattern, or adjustable angle pattern as required.
- 3. Remote Reading Thermometers: Vapor tension actuated, or gas actuated type, with extension capillary tube of length as required for the particular application.
- a. Case type as required for the particular mounting application.
 4. Thermometers for Sensing Liquid Temperature: Furnish with separable sockets.
 - a. Sockets for Use in Insulated Piping, Insulated Tanks or Similar Equipment: Extension lagging neck type, of length as required to compensate for insulation thickness, and proper immersion.

2.03 THERMOMETERS FOR MEASURING LIQUID TEMPERATURE

- A. Bimetallic Actuated Thermometers: Comply with ASME B40.3, Accuracy Grade
 - 1. Construction: Type 304 stainless steel, all welded construction, with clear acrylic plastic or shatterproof glass crystal. Marine Grade application.
 - 2. Dial: White enamel background with bold black figures and graduations.
 - 3. Head Size:
 - a. Installation in Piping: 3inch diameter.
 - b. Installation in Tanks and Similar Equipment: 5 inch diameter.
 - 4. Stem: Length as required for proper immersion, and to compensate for insulation thickness, with threaded connection for socket.
 - 5. External Calibration Device.
 - 6. Separable Socket:
 - a. Water Service: Brass or bronze. Marine Grade

2.04 PRESSURE AND COMPOUND GAUGES

- A. Type: Adjustable dial type with micrometer type pointer, or external calibration device, bronze bourdon tube, and bronze bushed rotary movement. Marine Grade application.
- B. Dial: White enameled background, and bold black graduations, numerals and pointer; 3-1/2 inch diameter.
 - 1. Scale Range:
 - a. Standard Gauges: Double normal operating pressure.
 - b. Compound Gauges: From 30" Hg vacuum to double normal operating pressure.
- C. Case: Stainless Steel, Marine Grade application.
- D. Accuracy: Guaranteed of within 1 percent in middle third of dial range.

PART 3 EXECUTION

3.01 INSTALLATION

- A. Thermometers:
 - 1. Install in accordance with the manufacturer's printed installation instructions.
 - 2. Install direct reading thermometers, when the application requires installation 6 feet or less above the floor or bottom of space in which installed, and remote reading type when the installation is over 6 feet.

B. Pressure:

- 1. Install in accordance with the manufacturer's printed installation instructions.
- 2. For Measuring Liquid Pressure: Install gauges complete with stop cocks and drain cocks.

END OF SECTION

SECTION 23550 PIPE AND VALVE IDENTIFICATION

PART 1 GENERAL

1.01 REFERENCES

A. ANSI A13.1 - Scheme for Identification of Piping Systems.

1.02 SUBMITTALS

A. Product Data: Catalog sheets, specifications and installation instructions for each item specified.

PART 2 PRODUCTS

2.01 ACCEPTABLE MANUFACTURERS

- A. W.H. Brady Co., Milwaukee, WI.
- B. Emed Co., Buffalo, NY.
- C. Panduit Corp., Tinley Park, IL.
- D. Seton Nameplate Corp., New Haven, CT.
- E. or approved equal

2.02 PIPE MARKERS AND ACCESSORIES

- A. Snap-on Marker: One piece wrap around type constructed of precoiled acrylic plastic with clear polyester coating, integral flow arrows, legend printed in alternating directions, 3/4 inch adhesive strip on inside edge, and 360 degree visibility.
- B. Strap-On Marker: Strip type constructed of precoiled acrylic plastic with clear polyester coating, integral flow arrows, legend printed in alternating directions, factory applied grommets, and pair of stainless steel spring fasteners.
- C. Stick-On Marker: Pressure sensitive adhesive backed type constructed of vinyl with clear polyester coating, and integral flow arrows for applications where flow arrow banding tape is not being used.

D. Pipe Marker Legend and Color Field Sizes:

OUTSIDE DIAMETER OF PIPE OR INSULATION (Inches)	LETTER SIZE (Inches)	LENGTH OF COLOR FIELD (Inches)
3/4 to 1-1/4	1/2	8
1-1/2 to 2	3/4	8
2-1/2 to 6	1-1/4	12
8 to 10	2-1/2	24
Over 10	3-1/2	32

- E. Banding Tapes: Pressure sensitive adhesive backed type constructed of vinyl with clear polyester coating.
 - 1. Plain Tape: Unprinted type; color to match pipe marker background.
 - 2. Flow Arrow Tape: Printed type with integral flow arrows; color to match pipe marker background.
- F. Pipe Size Labels: Pressure sensitive adhesive backed type constructed of vinyl with clear polyester coating, vertical reading pipe size in inches, and legend size matching adjacent pipe marker.

2.03 PIPE SERVICE IDENTIFICATION TAGS

- A. Type: No. 19 B & S gage brass, with 1/4 inch high pipe service abbreviated legend on one line, over 1/2 inch high pipe size legend in inches, both deep stamped and black filled; and 3/16 inch top hole for fastener.
- B. Size: 2 inch square tag.
- C. Fasteners: Brass "S" hook or brass jack chain of size as required for pipe to which tag is attached.

2.04 VALVE SERVICE IDENTIFICATION TAGS

- A. Type: No. 19 B & S gage brass, with 1/4 inch high valve service abbreviated lettering on one line over 1/2 inch high valve service chart number, both deep stamped and black filled; and with 3/16 inch top hole for fastener.
- B. Sizes:
 - 1. HVAC Use: 1-1/2 inch dia round.
- C. Fasteners: Brass "S" hook or brass jack chain of size as required for valve stem or handle to which tag is attached.

2.05 VALVE SERVICE IDENTIFICATION CHART FRAMES

A. Type: Satin finished extruded aluminum frame with rigid clear plastic glazing, size to fit 8-1/2 x 11 inches valve chart.

PART 3 EXECUTION

3.01 PREPARATION

- A. Complete testing, insulation and finish painting work prior to completing the Work of this Section.
- B. Clean pipe surfaces with cleaning solvents prior to installing piping identification.
- C. Remove dust from insulation surfaces with clean cloths prior to installing piping identification.

3.02 INSTALLATION

- A. Install the Work of this Section in accordance with the manufacturer's printed installation instructions, unless otherwise specified.
- B. Stick-On Pipe Markers:
 - 1. Install minimum of 2 markers at each specified location, 90 degrees apart on visible side of pipe.
 - 2. Encircle ends of pipe markers around pipe or insulation with banding tape with one inch lap. Use plain banding tape on markers with integral flow arrows, and flow arrow banding tape on markers without integral flow arrows.
- C. Pipe Size Labels: Install labels adjacent to each pipe marker and upstream from flow arrow. Install a minimum of 2 pipe size labels at each specified location, 90 degrees apart on visible side of pipe.
- D. Pipe Service Identification Tags: Attach tags to piping being identified with "S" hooks or jack chains.

3.03 PIPING IDENTIFICATION SCHEDULE

- A. Piping Identification Types:
 - 1. Piping or Insulation under 3/4 inch od: Pipe identification tags.
 - 2. Piping or Insulation 3/4 inch to 5-7/8 inch od: Snap-on marker or stick-on marker.
 - 3. Piping or Insulation 6 inch od and Larger: Strap-on marker or stick-on marker.
- B. Identify exposed piping, bare or insulated, as to content, size of pipe and direction of flow, with the following exceptions:

- 1. Piping in non-walk-in tunnels or underground conduits between manholes.
- 2. Piping in furred spaces or suspended ceilings, except at valve access panels where valves and piping shall be identified as specified for exposed piping systems.
- 3. Piping in finished spaces such as offices, class rooms, wards, toilet rooms, shower rooms and spaces as specified.
- C. Locate piping identification to be visible from exposed points of observation.
 - 1. Locate piping identification at valve locations; at points where piping enters and leaves a partition, wall, floor or ceiling, and at intervals of 20 feet on straight runs.
 - 2. Where 2 or more pipes run in parallel, place printed legend and other markers in same relative location.

3.04 <u>VALVE IDENTIFICATION SCHEDULE</u>

- A. Valve Service Identification Tags:
 - 1. Tag control valves, except valves at equipment, with a brass tag fastened to the valve handle or stem, marked to indicate service and numbered in sequence for the following applications:
 - a. Domestic water valves controlling mains, risers and branch runouts.
 - b. Gas valves controlling mains, risers, and branch runouts.
 - c. Valves in heating, ventilating, air conditioning and refrigeration systems.
- B. Valve Service Identification Charts:
 - 1. Provide 2 framed valve charts for each piping system specified to be provided with valve identification tags. Type charts on 8-1/2 x 11 inches heavy white bond paper, indicating valve number, service and location.
 - 2. Hang framed charts at locations as directed.

END OF SECTION

SECTION 23590 CLEANING AND TESTING

PART 1 GENERAL

1.01 RELATED WORK SPECIFIED ELSEWHERE

A. Balancing of Systems: Section 23940.

1.02 **SUBMITTALS**

- A. Quality Control Submittals
 - 1. Test Reports (Field Tests):
 - a. Propylene Glycol System Test: Submit test results in a format acceptable to the Director's Representative.
 - b. Submit data for each system tested, and/or disinfected; include date performed, description, and test results for each system.

1.03 QUALITY ASSURANCE

- A. Regulatory Requirements:
 - 1. Perform factory testing of factory fabricated equipment in complete accordance with the agencies having jurisdiction.
 - 2. Perform field testing of piping systems in complete accordance with the local utilities and other agencies having jurisdiction and as specified.

1.04 PROJECT CONDITIONS

A. Protection: During test Work, protect controls, gages and accessories which are not designed to withstand test pressures. Do not utilize permanently installed gages for field testing of systems.

1.05 <u>SEQUENCING AND SCHEDULING</u>

- A. Transmit written notification of proposed date and time of operational tests to the Director's Representative at least 5 days in advance of such tests.
- B. Perform cleaning and testing Work in the presence of the Director's Representative.
- C. Pressure test piping systems, at the roughing-in stage of installation, before piping is enclosed by construction Work, and at other times as directed. Perform test operations in sections as required and directed, to progress the Work in a satisfactory manner and not delay the general construction of the building. Valve or cap-off sections of piping to be tested, utilizing valves required to be installed in the permanent piping systems, or temporary valves or caps as required to perform the Work.

PART 2 PRODUCTS

2.01 MATERIALS

- A. Test Equipment and Instruments: Type and kind as required for the particular system under test.
- B. Test Media (water): As specified for the particular piping or system under test.
- C. Cleaning Agent (chemical solution, steam, water): As specified for the particular piping, apparatus or system being cleaned.
- D. Propylene Glycol: Permanent type anti-freeze solution as manufactured by Dow Chemical Co. or Union Carbide.
 - 1. Percentage of Propylene Glycol: 35 percent.

PART 3 EXECUTION

3.01 PRELIMINARY WORK

A. Thoroughly clean pipe and tubing prior to installation. During installation, prevent foreign matter from entering systems. Prevent if possible and remove stoppages or obstructions from piping and systems.

3.02 PRESSURE TESTING OF PIPING

A. Piping shall be tight under test and shall not show loss in pressure or visible leaks, during test operations or after the minimum duration of time as specified.
 Remove piping which is not tight under test; remake joints and repeat test until no leaks occur.

B. General:

- 1. Pressure test piping systems inside buildings, at the roughing-in stage of installation, before piping is enclosed by construction Work, and at other times as directed.
- 2. Perform test operations in sections as required and directed, to progress the Work in a satisfactory manner and not delay the general construction of the building.
- 3. Valve or cap-off sections of piping to be tested, utilizing valves required to be installed in the permanent piping systems, or temporary valves or caps as required to perform the Work.
- 4. Isolate existing piping from pressure testing.
- 5. Pressure test only new piping unless otherwise specified or directed by Director's Representative.

6. Water Systems:

1. Circulating water systems, including propylene glycol solution systems and cold water make-up piping connections to heating, ventilating, air conditioning and refrigeration systems, unless otherwise specified:

- a. Before final connections are made perform hydrostatic test at 1-1/2 times the maximum working pressure, but not less than 125 psig, for 4 hours.
- b. After final connections are made perform hydrostatic retest at a pressure equal to maximum operating system design pressure, but not less than 30 psig, for 4 hours.

3.03 <u>HEATING, VENTILATING AND AIR CONDITIONING SYSTEMS - CLEANING AND OPERATIONAL TESTING</u>

- A. Circulating Chilled Water Systems in ship:
 - 1. Cleaning:
 - a. Flush systems and apparatus, upon completion of pressure test(s).
 - b. Completely open valves and flush each system with clean water, prior to chemical cleaning.
 - c. Repeatedly flush at short intervals until twice the system water capacity has been flushed through.
 - d. Chemically clean systems immediately following flushing operations.
 - e. Circulate a solution consisting of trisodium phosphate, in a proportion of one pound of chemical to every 50 gallons of water in the system.
 - f. Completely fill system with cleaning solution; vent as required, and place in operation, with automatic controls operating and valves fully open.
 - g. Allow system to reach design operating temperature or an operating temperature designated by the Director's Representative.
 - h. Circulate the solution through the system for a minimum of 4 consecutive hours; immediately drain system and flush with clean water until the pH at the farthest drain matches the clean water input.
 - i. Provide temporary pipe and /or hose required to drain system.
 - j. Keep strainers unplugged during cleaning operations. Remove and clean strainer screens prior to operational test.
 - k. Refill system with clean water and correct pH to 7.
 - 1. Upon completion of flushing, remove temporary piping and reconnect steam coil.
 - 2. Operational Test:
 - a. Run system in an automatic mode for a minimum of 120 consecutive hours.
 - b. During this time, make final adjustments, including the setting of the balancing valves.
- B. Propylene Glycol Systems:
 - 1. Clean as specified for circulating water systems.

2. Perform operational test as specified for circulating water systems with propylene glycol solution in system.

END OF SECTION

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 23940 BALANCING OF SYSTEMS

PART 1 GENERAL

1.01 RELATED WORK SPECIFIED ELSEWHERE

A. Cleaning and Testing: Section 23590.

1.02 **SUBMITTALS**

A. Quality Control Submittals:

- 1. Testing, Adjustment and Balancing Reports:
 - a. Hydronic Systems: Submit results on Form BDC-374, which can be obtained from the Director's Representative or use a similar test report form which includes all of the items and data included on Form BDC-374.

1.03 QUALITY ASSURANCE

A. Qualifications:

- 1. Provide the services of a certified independent agency for the testing, adjustment and balancing of all air distribution and hydronic distribution systems complete with all connected apparatus and equipment. The agency shall be certified by the Associated Air Balance Council Bureau AABC, Los Angeles, Cal. 90026 or by National Environmental Balancing Bureau NEBB, Arlington, Va. 22209.
- 2. The Work shall be performed by skilled mechanical technicians under the direct supervision of certified personnel in the employ of the independent agency. The supervisor shall be personally certified by the national council or bureau, as approved by the Director.

1.04 SEQUENCING AND SCHEDULING

A. Scheduling:

- 1. Perform environmental systems testing and balancing after cleaning, miscellaneous testing, adjustment and operational testing Work has been completed.
- 2. Test and balance system during a period of time when outside temperature conditions will impose a significant load on the system; i.e., summer months for air conditioning system, winter months for heating system. Balance and adjust systems accordingly.
- 3. Send written notification to the Director a minimum of five days prior to the performance of testing and balancing Work. Perform testing and balancing Work in the presence of the Director's Representative.

PART 2 PRODUCTS

2.01 TEST EQUIPMENT

- A. General Information: Test instruments are included in this specification for information only. Balancing of air and hydronic systems shall be performed by qualified personnel utilizing company owned test instruments, which will remain the property of the company. Use test instruments which are in first class operating condition, with individual calibration histories to guarantee their accuracy. Test instruments shall be of type and kind as required by the type of system installed. Trade names and manufacturer's names are mentioned in this section for descriptive purposes only; instruments of equivalent range and capabilities may be utilized.
- B. Hydronic Balancing Instruments:
 - 1. Calibrated Test Gages: Ranges 0 to 30 lbs., 0 to 60 lbs., 0 to 200 lbs.
 - 2. Calibrated Test Gages (Compound Type): Ranges from -30 inches to 30 lbs. and -30 inches to 60 lbs.
 - 3. U Tube Manometer: 36 inches.

PART 3 EXECUTION

3.01 PRELIMINARY WORK

A. Circulating Water Systems: Prior to balancing the system, bleed all air vents so as to completely flood the system; check pumps for proper rotation; clean strainers and set balancing and system stop valves in the full-open position.

3.02 FIELD QUALITY CONTROL

- A. Inspection: Prior to the environmental testing and balancing of hydronic and air distribution systems, the certified supervisor in the employ of the testing and balancing agency shall inspect the installations and notify the Director's Representative of any Work which must be performed or modified prior to initiating testing and balancing procedures.
- B. Performance: Test and balance environmental hydronic and air distribution systems, including all connected equipment and apparatus, so as to conform to the design conditions. Perform the Work of this section in accordance with the published standards of the balancing council or bureau, which is certifying the member firm. Record all test readings, calculations and results.

END OF SECTION

SECTION 23965 SEQUENCE OF OPERATION

PART 1 GENERAL

The Chiller Plant consists of 2 groups of 3 Air Cooled Chillers with 3 Chilled Water pumps, 1 per chiller group with one standby. The Cooling Load is initially carried by one group of (3) Chillers and (1) Chilled Water Pump. All chillers have automatic isolation valves to load and unload one chiller at the time.

The Chillers to be provided with BACnet communication capability and Chiller Controls with LCD displays.

A system controller (SC) shall communicate with the Chillers and a Chiller Water Plant Controller (UC) via BACnet.

The following Control Devices to be provided:

Chilled Water Pump Start/Stop (3) DO

Chilled Water Pump Run Status Current Switch (3) DI

Alarm Station - Sonalert with Red Pilot Light and Silence Pushbutton (1)

The Chiller Plant shall be enabled when Outside Air Temperature rises above 55 Degrees (Adjustable) or by operator manual input at the UC Panel LCD touchscreen.

The Lead Chiller and Lead CHW Pump shall be determined based on least run hours.

The Lead Chilled Water Pump shall start and the Current Switch shall indicate run status.

If Run Status is not achieved in a predetermined time the Lead Pump will be disabled, an alarm shall be sounded and the Lag Pump shall be started.

The Lead Chiller shall be enabled through their individual Chilled Water Flow Switch.

The Chiller with start in sequence to limit electrical demand and load equally to maintain their individual CHW Supply Temperature Setpoint and Loop Setpoint of 42 Degrees (Adjustable).

When the Chilled Water Loop setpoint is achieved, 42 Degrees (Adjustable) the UC Controller will operate only as many Chillers in the group as need to operate efficiently and maintain the CHWS loop setpoint as reset by the CHW Return flow demand. The UC Controller shall operate the Chillers with the least run hours to maintain the Loop Setpoint.

As the Space Conditions are satisfied the Air Handler Cooling Coil two way valves shall modulate closed. On an increase in CHW Loop Differential Pressure the Differential

Pressure Bypass Valve shall modulate open to maintain system minimum flow through chiller via chiller flow switch.

If after a predetermined time the CHW Loop temperature setpoint is not achieved an alarm will be sounded and the Lag Group of Chillers will be enabled and operate as described previously.

An alarm shall be sounded if any temperature or pressure sensing device is beyond set high or low limits as well as chiller common alarms. Chiller diagnostics will be at the individual Chiller Control Panel LCD Displays.

END OF SECTION

SECTION 260519 WIRING SYSTEMS

PART 1 - GENERAL

1.01 <u>DESCRIPTION OF WORK</u>

A. Install all conductors as required for the proper operation of the various systems specified. All connections shall be made complete, and all systems shall be energized and tested for proper operation.

1.02 QUALITY ASSURANCE

- A. Wire and marine type shipboard cables manufactured over one year prior to delivery to the site will not be accepted.
- B. Tapes for splices or termination shall be dated by the tape manufacturer to indicate that they have been manufactured no longer than six months prior to use in the Work of this Section.

1.03 <u>DELIVERY, STORAGE, AND HANDLING</u>

- A. Conductors shall be delivered at the building in original packages or on reels, and shall have the tag of the manufacturer attached thereto indicating: Contractor's name, Project title and number, Date of manufacturing.
- B. Store material in a clean, dry space and protect from weather.

1.04 <u>SUPPLEMENTAL SUBMITTALS</u>

A. Submit a Product Schedule indicating the item description and manufacturer name. The Schedule will be accepted by the D.O.C for record purposes only, provided that the items are in full compliance with the Specifications.

B. Certificates

Provide affidavit stating that all items used are UL listed and meet the specifications.

C. Submit field test results for wires and cables, including "Megger" readings with the method used.

PART 2 - PRODUCTS

2.01 WIRES AND CABLES

A. General

- 1. Conductors shall conform to A.S.T.M., MILL Standards for Shipboard Cable, and I.P.C.E.A. standards, and be UL listed and labeled.
- 2. Conductors shall have 600 volts insulation and shall be of soft-annealed-uncoated copper of 98% conductivity. Copper clad conductors are not acceptable.
- 3. All conductors shall have identifiable lettering on the insulator jacket as to voltage rating, wire type, A.W.G. size, insulation, and manufacturer I.D.

B. Wire/Cable Description

- 1. Type THHN/THWN: 75°C, THHN: 90°C shall have a thermo-plastic polyvinyl chloride insulation with nylon jacket for 600 volts, and shall comply with ASTM, IPCEA S-61-402 (latest edition) and NEMA WC5 (latest edition).
- 2. TFFN (stranded) shall be thermoplastic insulated, jacketed by abrasion and oil resistant nylon, and rated at 105°C.
- 3. XLPO marine type cable insulation material, Silicon Rubber/Glass, Braid/Braid covering, Jacket Halogen-Free (LSZH) Cross-Link Polyolefin (XLPO) Water Tight Cable.

4. Lightweight Low Smoke Watertight Wire Cable. Jacket: Irradiation Cross-Linked Modified Low Smoke Polyolefin, compounded without Halogens. Cable shall be of multi-strands, twisted pairs, shielded with an outer jacket.

2.02 SPLICES AND TERMINATIONS

A. General

- 1. All materials for making splices and terminations shall be specifically designed for use with the type of wire, the cable insulation, the installation and the operating conditions of the specific application and be UL listed.
- 2. Grounding conductors and bonding jumpers shall be connected by exothermic welding, listed pressure connectors, listed clamps, or other listed means.

PART 3 - EXECUTION

3.01 PREPARATION

A. Prior to pulling wires and cable, clean raceway systems (if installed) of all foreign matter and perform all operations necessary so as not to cause damage to wires and cables while pulling.

3.02 INSTALLATION

A. General

1. At least 6 inches of free conductor, measured from the point in the box where it emerges from its raceway or cable sheath, shall be left at each outlet, junction and switch point for splices or the connection of luminaries or devices. Where the opening of an outlet, junction or switch point is less than 8 inches in any dimension, each conductor shall be long enough to extend at least 3 inches outside the opening.

2. Use approved lubrication when installing cables in conduits and raceways. Any pulling compounds shall be compatible with the finish of the wires and cables furnished.

B. Type THHN/THWN wire

- 1. For extending and/or re-using any branch wiring, that contains existing THHN/THWN wire.
- C. Shipboard cable, Cross-Link Polyolefin (ALPO) Water tight Cable / Lightweight Low Smoke Watertight Wire Cable.
 - 1. Feeder, Branch Circuits, and Power Distribution.
 - 2. Remote-Control Signaling and Power-Limited Circuits: Circuit Classes 1, 2, or 3, unless otherwise indicated.

D. Terminations

- 1. For Conductor Sizes Larger than Terminal Capacity on Equipment: Reduce the larger conductor to the maximum conductor size that terminal can accommodate (reduce section no longer than 1 ft.). Cutting of cable strands to fit terminal is not acceptable.
- E. Identifications of Wire and Cable
- 1. For Conductor Sizes Larger than Terminal Capacity on Equipment: Reduce the larger conductor to the maximum conductor size that terminal can accommodate (reduce section no longer than 1 ft.). Cutting of cable strands to fit terminal is not acceptable.

3.03 COMMON NEUTRAL CONDUCTOR

A. Common neutral shall not be used.

3.04 EQUIPMENT GROUNDING CONDUCTOR

Note that equipment-grounding conductors are not shown on the Contract Drawings but it shall be provided when and as required by code.

3.05 FIELD TESTS

A. Test all feeder cables installed under this Contract with a 1000-volt Megohmmeter. Furnish the D.O.C's Representative with a copy of the "Megger" test report, together with an outline of the method used. Any cable not attaining the minimum reading established in the code shall be replaced.

END OF SECTION

LIST OF SUBMITTALS

SUBMITTAL	DATE SUBMITTED	DATE APPROVED
Product Schedule		
Certificates		
Field test report		

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 260533 RACEWAYS, FITTINGS, SUPPORTING DEVICES, BOXES AND ACCESSORIES

PART 1 - GENERAL

1.01 <u>DESCRIPTION OF WORK</u>

- A. Provide raceways, fittings, supporting devices, boxes and accessories required for a complete system and its proper operation.
- B. Coordinate layout and installation of raceways, boxes, enclosures, cabinets, and suspension system with other construction that penetrates ceilings or is supported by them, including light fixtures, HVAC equipment, fire-suppression system, new security cabinetry, and partition assemblies.

1.02 RELATED SECTIONS

A.	Firestopping	Section 078400
----	--------------	----------------

B. Painting Section 099000

1.03 SUPPLEMENTAL SUBMITTALS

- C. Submit a Product Schedule indicating the item description and manufacturer name. The schedule will be accepted by the D.O.C. for record purposes only, provided that the items are in full compliance with the Specifications.
- D. Certificates

Provide affidavit stating that all items used are UL listed and meet the specifications.

E. Provide conduit routing plan, drawn to scale, showing structural members, architectural features, Elevator, HVAC and P&D items.

PART 2 - PRODUCTS

2.01 RACEWAYS

A. Rigid Galvanized Conduit (RGC/RGS)

Steel conduit, Schedule 40, hot dipped galvanized, with Underwriters Laboratories label stamped on each length.

2.02 SUPPORTING DEVICES

A. Hangers

- 1. Separate hangers shall be installed for supporting conduits. Wherever possible, hangers shall be supported from concrete slab by inserts.
- 2. Hangers and piping installed by other trades shall not be used for supporting electric conduits.
- B. Individual and multiple pipe hangers and riser clamps including all parts and hardware shall be hot-dipped galvanized throughout. All U-bolts, clamps, attachments and hardware for hanger assembly and conduits shall be provided. Each multiple hanger shall be designed to support a load equal to or greater than the sum of the weights of the conduits, wires and hanger itself, plus 200 pounds.
- C. Use pipe straps and specified method of attachment where conduit is installed proximate to surface of steel stud or masonry construction.
 - 1. Use hangers secured to surface with specified method of attachment where conduit is suspended from the surfaces.

- D. Use "C" beam clamps and hangers where conduit is supported from steel beams.
- E. Use deck clamps and hangers to support conduits from steel decking having hanger tabs. One conduit per tab is permitted.
 - 1. Where conduit is supported from steel decking which does not have hanger tabs, use clamps and hangers secured to decking, utilizing specified method of attachment.
- F. Use channel support system supported from structural steel for multiple parallel conduit runs.
- G. Where conduits are installed above ceiling, do not rest conduit directly on runners bars, T-Bars, etc.
 - 1. Conduit Sizes 2-1/2" and Smaller: Support conduit form ceiling supports or from construction above ceiling.
 - 2. Conduit Sizes Over 2-1/2": Support conduit from beams, joist, or trusses above ceiling.
- H. Conduits shall be supported within three (3) feet of any kind of fitting and at every outlet or junction box, panel, etc. This shall apply to both horizontal and vertical runs.

2.03 BOXES AND ENCLOSURES

- A. The Contractor shall provide outlet boxes and enclosures appropriate for the purpose at all locations where the Drawings require the installation of electrical devices or electrical equipment. For exposed conduit systems, the contractor shall use cast outlet boxes in all locations below 8'-0" with number of threaded hubs equal to the number of conduits, except when installing surface metal raceway contractor shall provide boxes from the same manufacturer of the surface metal raceway.
- B. Where the Contractor selects and installs an item of equipment that requires additional boxes, fittings, etc., or a modification of the conduit system indicated on the Drawings, such additional boxes, fittings, etc. shall be furnished and

installed and such modifications shall be performed by the Contractor as part of this Contract, without extra compensation from the NYCDOC.

C. Unless otherwise noted on the drawings the contractor is required to utilize weatherproof boxes and enclosures.

2.04 FITTINGS AND ACCESSORIES

A. All fittings and accessories must be UL listed and compatible with selected raceways and suitable for use location.

2.05 CONDUIT SIZES

- A. Where conduit is required to be installed, its nominal diameter shall be not less than 3/4 inch.
- B. Where/If conduit size is specified on the drawings, contractor is permitted to install larger conduit gauge, to incorporate multiple home runs within the same location. This "means and methods" installation will solely be the cost of the contractor for all necessary material and labor. The conduit fill should not exceed industry standards. Contractor is not permitted to not install smaller gauge conduit then what is specified on the drawings/specifications.

2.06 <u>SLEEVES FOR CONDUIT</u>

- A. Provide sleeves, Schedule 40, galvanized steel, for all electrical conduits and shipboard type cable passing through foundation walls.
- B. Provide sleeves, Schedule 10, galvanized steel, for all electrical conduits and shipboard type cable passing through partitions and slabs. Proprietary sleeves that are part of an NYC approved fire stopping assembly are also acceptable.

PART 3 – EXECUTION

3.01 RACEWAY SCHEDULE

A. Rigid Galvanized Steel Conduit (RGC)

Provide RGC as follows:

- 1. Provide RGC for concealing all exterior power runs.
- 2. If existing conduit is installed, and the drawings call for relocation, temporary supporting, extending, etc, the contractor is required to install additional conduit, as required to complete the installation.

3.02 RACEWAY INSTALLATION

A. General

- 1. Keep raceways at least 6 inches away from parallel runs of flues and steam or hot-water pipes. Install horizontal raceway runs above water and steam piping.
- 2. All conduit systems shall be mechanically and electrically continuous.
- 3. The ends of all conduit shall be square, carefully reamed out to full size, shouldered in the fittings, and bushed or capped wherever stubbed clear of the building.
- 4. Not more than four (4) 90 degree ells or bends or the equivalent shall be used in any single run of conduit. Conduits for telephone, television, video surveillance or data cable shall not have more than three (3) 90 degree bends or the equivalent. Where more bends are necessary, provide suitable code size pull boxes or fittings. All conduits for telephone, television, video surveillance or data systems cable shall have large radius bends. Pull boxes shall be installed in accessible locations.
- 5. Conduit installed on equipment shall not obstruct any removable panel, access door, or control. Control apparatus, outlet, junction, and pull boxes shall be installed so as not to interfere with any piping, fixtures, or equipment.
- 6. Complete raceway installation before starting conductor installation.
- 7. Conduits installed across seismic separations (expansion joints) shall include, but not limited to, the following:
 - a. The conduit shall be securely anchored on each side of the seismic separation with a pipe hanger per SMACNA details.
 - b. The spacing between conduit ends shall be 36" minimum.
 - c. A liquid-tight flexible metal conduit of the same size shall be installed between the conduit ends spanning the seismic separation.

d. The liquid-tight flexible metal conduit shall be of sufficient length to provide for a longitudinal and axial deflection of two (2)-inches minimum in all directions.

8. Terminations:

- a. Where raceways are terminated with locknuts and bushings, align raceways to enter squarely and install locknuts with dished part against box. Use two locknuts, one inside and one outside box.
- b. Where raceways are terminated with threaded hubs, screw raceways or fittings tightly into hub so end bears against wire protection shoulder. Where chase nipples are used, align raceways so coupling is square to box tighten chase nipple so no threads are exposed.
- 9. Install pull wires in empty raceways. Use polypropylene or monofilament plastic line with not less than 200-lb (90-kg) tensile strength. Leave at least 12 inches (300 mm) of slack at each end of pull wire.
- 10. Rooftop conduits (rigid steel) shall be neatly grouped and installed parallel to the building lines. Support conduits on minimum 4 inches x 6 inches on pressure treated lumber sleepers at minimum 5 feet spacing.

B. Exposed conduits

Exposed conduits shall be rigidly fastened to structure, or to rigid hangers or angle irons connected to structure at intervals not exceeding eight feet. Where the conduits or surface metal raceways are installed exposed, they shall follow the architectural lines of the enclosure and shall be run as to be as inconspicuous as possible. Conduits or surface metal raceways shall not be installed diagonally on ceilings, walls or columns.

C. Conduit Installed Concealed in Existing Building

Where new partition walls and new hung or furred ceilings are being erected or where existing walls are to have a new tile finish, the conduits and related equipment shall be installed concealed in walls and in hung or furred ceilings.


- D. Raceways passing through fire-rated walls, floors, roofs, ceilings, and other areas where indicated: the space between sleeve and pipe/conduit shall be fire stopped in accordance with Section 078400 to comply with fire-rating of assembly through which it passes.
- E. Raceways passing through foundation walls shall be of watertight utilizing "Link-Seal" type gasketing.

3.03 PAINTING

A. All exposed raceways and boxes in finished parts of the building shall be painted. Painting shall consist of a prime coat and a finished coat, color as selected by project architect. Factory painting will be accepted as a prime coat.

END OF SECTION

PART D: STANDARD CONSTRUCTION CONTRACT 2017



CITY OF NEW YORK STANDARD CONSTRUCTION CONTRACT

TABLE OF CONTENTS

CHAPTER I: THE CONTRACT AND DEFINITIONS	
ARTICLE 1. THE CONTRACT	1
ARTICLE 2. DEFINITIONS	
CHAPTER II: THE WORK AND ITS PERFORMANCE	
ARTICLE 3. CHARACTER OF THE WORK	
ARTICLE 4. MEANS AND METHODS OF CONSTRUCTI	ION4
ARTICLE 5. COMPLIANCE WITH LAWS	
ARTICLE 6. INSPECTION	
ARTICLE 7. PROTECTION OF WORK AND OF PERSON	NS AND PROPERTY: NOTICES AND
INDEMNIFICATION	
CHAPTER III: TIME PROVISIONS	
ARTICLE 8. COMMENCEMENT AND PROSECUTION (
ARTICLE 9. PROGRESS SCHEDULES	
ARTICLE 10. REQUESTS FOR INFORMATION OR APP	
ARTICLE 11. NOTICE OF CONDITIONS CAUSING DEL	AY AND DOCUMENTATION OF
DAMAGES CAUSED BY DELAY	14
ARTICLE 12. COORDINATION WITH OTHER CONTRA	ACTORS18
ARTICLE 13. EXTENSION OF TIME FOR PERFORMAN	NCE19
ARTICLE 14. COMPLETION AND FINAL ACCEPTANCE	E OF THE WORK21
ARTICLE 15. LIQUIDATED DAMAGES	23
ARTICLE 16. OCCUPATION OR USE PRIOR TO COMP	LETION23
CHAPTER IV: SUBCONTRACTS AND ASSIGNMENTS.	24
ARTICLE 17. SUBCONTRACTS	24
ARTICLE 18. ASSIGNMENTS	26
CHAPTER V: CONTRACTOR'S SECURITY AND GUAR	ANTEE26
ARTICLE 19. SECURITY DEPOSIT	26
ARTICLE 20. PAYMENT GUARANTEE	
ARTICLE 21. RETAINED PERCENTAGE	
ARTICLE 22. INSURANCE	30
ARTICLE 23. MONEY RETAINED AGAINST CLAIMS	36
ARTICLE 24. MAINTENANCE AND GUARANTY	37
CHAPTER VI: CHANGES, EXTRA WORK, AND DOCUM	MENTATION OF CLAIM38
ARTICLE 25. CHANGES	38
ARTICLE 26. METHODS OF PAYMENT FOR OVERRUN	NS AND EXTRA WORK38
ARTICLE 27. RESOLUTION OF DISPUTES	
ARTICLE 28. RECORD KEEPING FOR EXTRA OR DISP	PUTED WORK OR WORK ON A TIME &
MATERIALS BASIS	45
ARTICLE 29. OMITTED WORK	
ARTICLE 30. NOTICE AND DOCUMENTATION OF CO	STS AND DAMAGES; PRODUCTION OF
FINANCIAL RECORDS	46
CHAPTER VII: POWERS OF THE RESIDENT ENGINEER	R,THE ENGINEER OR ARCHITECT AND
THE COMMISSIONER	48
ARTICLE 31. THE RESIDENT ENGINEER	
ARTICLE 32. THE ENGINEER OR ARCHITECT OR PRO	
ARTICLE 33. THE COMMISSIONER	
ARTICLE 34. NO ESTOPPEL	
CHAPTER VIII: LABOR PROVISIONS	
ARTICLE 35. EMPLOYEES	
ARTICLE 36. NO DISCRIMINATION	
ARTICLE 37. LABOR LAW REQUIREMENTS	59
CITY OF NEW YORK i	STANDARD CONSTRUCTION CONTRACT

ARTICLE 38. PAYROLL REPORTS	64
ARTICLE 39. DUST HAZARDS	64
CHAPTER IX: PARTIAL AND FINAL PAYMENTS	65
ARTICLE 40. CONTRACT PRICE	65
ARTICLE 41. BID BREAKDOWN ON LUMP SUM	65
ARTICLE 42. PARTIAL PAYMENTS	65
ARTICLE 43. PROMPT PAYMENT	
ARTICLE 44. SUBSTANTIAL COMPLETION PAYMENT	66
ARTICLE 45. FINAL PAYMENT	
ARTICLE 46. ACCEPTANCE OF FINAL PAYMENT	
ARTICLE 47. APPROVAL BY PUBLIC DESIGN COMMISSION	69
CHAPTER X: CONTRACTOR'S DEFAULT	69
ARTICLE 48. COMMISSIONER'S RIGHT TO DECLARE CONTRACTOR IN DEFAULT	69
ARTICLE 49. EXERCISE OF THE RIGHT TO DECLARE DEFAULT	
ARTICLE 50. QUITTING THE SITE	71
ARTICLE 51. COMPLETION OF THE WORK	71
ARTICLE 52. PARTIAL DEFAULT	
ARTICLE 53. PERFORMANCE OF UNCOMPLETED WORK	72
ARTICLE 54. OTHER REMEDIES	72
CHAPTER XI: MISCELLANEOUS PROVISIONS	72
ARTICLE 55. CONTRACTOR'S WARRANTIES	
ARTICLE 56. CLAIMS AND ACTIONS THEREON	
ARTICLE 57. INFRINGEMENT	
ARTICLE 58. NO CLAIM AGAINST OFFICIALS, AGENTS OR EMPLOYEES	74
ARTICLE 59. SERVICE OF NOTICES	74
ARTICLE 60. UNLAWFUL PROVISIONS DEEMED STRICKEN FROM CONTRACT	
ARTICLE 61. ALL LEGAL PROVISIONS DEEMED INCLUDED	74
ARTICLE 62. TAX EXEMPTION	74
ARTICLE 63. INVESTIGATION(S) CLAUSE	76
ARTICLE 64. TERMINATION BY THE CITY	
ARTICLE 65. CHOICE OF LAW, CONSENT TO JURISDICTION AND VENUE	80
ARTICLE 66. PARTICIPATION IN AN INTERNATIONAL BOYCOTT	
ARTICLE 67. LOCALLY BASED ENTERPRISE PROGRAM	82
ARTICLE 68. ANTITRUST	
ARTICLE 69. MACBRIDE PRINCIPLES PROVISIONS	
ARTICLE 70. ELECTRONIC FILING/NYC DEVELOPMENT HUB	
ARTICLE 71. PROHIBITION OF TROPICAL HARDWOODS	
ARTICLE 72. CONFLICTS OF INTEREST	85
ARTICLE 73. MERGER CLAUSE	85
ARTICLE 74. STATEMENT OF WORK	
ARTICLE 75. COMPENSATION TO BE PAID TO CONTRACTOR	
ARTICLE 76. ELECTRONIC FUNDS TRANSFER	
ARTICLE 77. RECORDS RETENTION	86
ARTICLE 78. EXAMINATION AND VIEWING OF SITE, CONSIDERATION OF OTHER SO	
OF INFORMATION AND CHANCED SITE CONDITIONS	96

WITNESSETH:

The parties, in consideration of the mutual agreements contained herein, agree as follows:

CHAPTER I: THE CONTRACT AND DEFINITIONS

ARTICLE 1. THE CONTRACT

- 1.1 Except for titles, subtitles, headings, running headlines, tables of contents and indices (all of which are printed herein merely for convenience), the following, except for such portions thereof as may be specifically excluded, shall be deemed to be part of this **Contract**:
 - 1.1.1 All provisions required by law to be inserted in this **Contract**, whether actually inserted or not;
 - 1.1.2 The Contract Drawings and Specifications;
 - 1.1.3 The General Conditions and Special Conditions, if any;
 - 1.1.4 The Contract:
 - 1.1.5 The Information for Bidders; Request for Proposals; Notice of Solicitation and Proposal For Bids; Bid or Proposal, and, if used, the Bid Booklet;
 - 1.1.6 All Addenda issued prior to the receipt of the bids; the Notice of Award; Performance and Payment Bonds, if required; and the Notice to Proceed or the Order to Work.
- 1.2 Should any conflict occur in or between the Drawings and Specifications, the **Contractor** shall be deemed to have estimated the most expensive way of doing the **Work**, unless the **Contractor** shall have asked for and obtained a decision in writing from the **Commissioner** of the **Agency** that is entering into this **Contract**, before the submission of its bid, as to what shall govern.

ARTICLE 2. DEFINITIONS

- 2.1 The following words and expressions, or pronouns used in their stead, shall, wherever they appear in this Contract, be construed as follows, unless a different meaning is clear from the context:
 - 2.1.1 "Addendum" or "Addenda" shall mean the additional Contract provisions and/or technical clarifications issued in writing by the Commissioner prior to the receipt of bids.
 - 2.1.2 "Agency" shall mean a city, county, borough or other office, position, department, division, bureau, board or commission, or a corporation, institution or agency of government, the expenses of which are paid in whole or in part from the City treasury.
 - 2.1.3 "Agency Chief Contracting Officer" (ACCO) shall mean a person delegated authority by the Commissioner to organize and supervise the procurement activity of subordinate Agency staff in conjunction with the CCPO, or his/her duly authorized representative.

- 2.1.4 "Allowance" shall mean a sum of money which the Agency may include in the total amount of the Contract for such specific contingencies as the Agency believes may be necessary to complete the Work, *e.g.*, lead or asbestos remediation, and for which the Contractor will be paid on the basis of stipulated unit prices or a formula set forth in the Contract or negotiated between the parties provided, however, that if the Contractor is not directed to use the Allowance, the Contractor shall have no right to such money and it shall be deducted from the total amount of the Contract.
- 2.1.5 "City" shall mean the City of New York.
- 2.1.6 "City Chief Procurement Officer" (CCPO) shall mean a person delegated authority by the Mayor to coordinate and oversee the procurement activity of Mayoral agency staff, including the ACCO and any offices which have oversight responsibility for the procurement of construction, or his/her duly authorized representative.
- 2.1.7 **"Commissioner"** shall mean the head of the Agency that has entered into this Contract, or his/her duly authorized representative.
- 2.1.8 "Comptroller" shall mean the Comptroller of the City of New York.
- 2.1.9 "Contract" or "Contract Documents" shall mean each of the various parts of the contract referred to in Article 1 hereof, both as a whole and severally.
- 2.1.10 "Contract Drawings" shall mean only those drawings specifically entitled as such and listed in the Specifications or in any Addendum, or any drawings furnished by the Commissioner, pertaining or supplemental thereto.
- 2.1.11 "Contract Work" shall mean everything required to be furnished and done by the Contractor by any one or more of the parts of the Contract referred to in Article 1, except Extra Work as hereinafter defined.
- 2.1.12 "Contractor" shall mean the entity which executed this Contract, whether a corporation, firm, partnership, joint venture, individual, or any combination thereof, and its, their, his/her successors, personal representatives, executors, administrators, and assigns, and any person, firm, partnership, joint venture, individual, or corporation which shall at any time be substituted in the place of the Contractor under this Contract.
- 2.1.13 "Days" shall mean calendar days, except where otherwise specified.
- 2.1.14 "Engineer" or "Architect" or "Project Manager" shall mean the person so designated in writing by the Commissioner in the Notice to Proceed or the Order to Work to act as such in relation to this Contract, including a private Architect or Engineer or Project Manager, as the case may be. Subject to written approval by the Commissioner, the Engineer, Architect or Project Manager may designate an authorized representative.
- 2.1.15 **"Engineering Audit Officer"** (**EAO**) shall mean the person so designated by the Commissioner to perform responsible auditing functions hereunder.
- 2.1.16 **"Extra Work"** shall mean Work other than that required by the Contract at the time of award which is authorized by the Commissioner pursuant to Chapter VI of this Contract.

- 2.1.17 **"Federal-Aid Contract"** shall mean a contract in which the United States (federal) Government provides financial funding as so designated in the Information for Bidders.
- 2.1.18 **"Final Acceptance"** shall mean final written acceptance of all the Work by the Commissioner, a copy of which shall be sent to the Contractor.
- 2.1.19 **"Final Approved Punch List"** shall mean a list, approved pursuant to Article 14.2.2, specifying those items of Work to be completed by the Contractor after Substantial Completion and dates for the completion of each item of Work.
- 2.1.20 "Law" or "Laws" shall mean the Constitution of the State of New York, the New York City Charter, the New York City Administrative Code, a statute of the United States or of the State of New York, a local law of the City of New York, any ordinance, rule or regulation having the force of law, or common law.
- 2.1.21 "Materialman" shall mean any corporation, firm, partnership, joint venture, or individual, other than employees of the Contractor, who or which contracts with the Contractor or any Subcontractor, to fabricate or deliver, or who actually fabricates or delivers, plant, materials or equipment to be incorporated in the Work.
- 2.1.22 "Means and Methods of Construction" shall mean the labor, materials, temporary structures, tools, plant, and construction equipment, and the manner and time of their use, necessary to accomplish the result intended by this Contract.
- 2.1.23"Notice to Proceed" or "Order to Work" shall mean the written notice issued by the Commissioner specifying the time for commencement of the Work and the Engineer, Architect or Project Manager.
- 2.1.24 "Other Contractor(s)" shall mean any contractor (other than the entity which executed this Contract or its Subcontractors) who or which has a contract with the City for work on or adjacent to the building or Site of the Work.
- 2.1.25 **"Payroll Taxes"** shall mean State Unemployment Insurance (SUI), Federal Unemployment Insurance (FUI), and payments pursuant to the Federal Insurance Contributions Act (FICA).
- 2.1.26 "**Project**" shall mean the public improvement to which this Contract relates.
- 2.1.27 "Procurement Policy Board" (PPB) shall mean the Agency of the City of New York whose function is to establish comprehensive and consistent procurement policies and rules which shall have broad application throughout the City.
- 2.1.28 **"Required Quantity"** in a unit price Contract shall mean the actual quantity of any item of Work or materials which is required to be performed or furnished in order to comply with the Contract.
- 2.1.29 **"Resident Engineer"** shall mean the representative of the Commissioner duly designated by the Commissioner to be his/her representative at the site of the Work.
- 2.1.30 "Site" shall mean the area upon or in which the Contractor's operations are carried on, and such other areas adjacent thereto as may be designated as such by the Engineer.

- 2.1.31 "Small Tools" shall mean items that are ordinarily required for a worker's job function, including but not limited to, equipment that ordinarily has no licensing, insurance or substantive storage costs associated with it; such as circular and chain saws, impact drills, threaders, benders, wrenches, socket tools, etc.
- 2.1.32 "Specifications" shall mean all of the directions, requirements, and standards of performance applying to the Work as hereinafter detailed and designated under the Specifications.
- 2.1.33 "Subcontractor" shall mean any person, firm or corporation, other than employees of the Contractor, who or which contracts with the Contractor or with its subcontractors to furnish, or actually furnishes labor, or labor and materials, or labor and equipment, or superintendence, supervision and/or management at the Site. Wherever the word Subcontractor appears, it shall also mean sub-Subcontractor.
- 2.1.34 "Substantial Completion" shall mean the written determination by the Engineer that the Work required under this Contract is substantially, but not entirely, complete and the approval of the **Final Approved Punch List**.
- 2.1.35 "Work" shall mean all services required to complete the Project in accordance with the Contract Documents, including without limitation, labor, material, superintendence, management, administration, equipment, and incidentals, and obtaining any and all permits, certifications and licenses as may be necessary and required to complete the Work, and shall include both Contract Work and Extra Work.

CHAPTER II: THE WORK AND ITS PERFORMANCE

ARTICLE 3. CHARACTER OF THE WORK

3.1 Unless otherwise expressly provided in the **Contract Drawings**, **Specifications**, and **Addenda**, the **Work** shall be performed in accordance with the best modern practice, utilizing, unless otherwise specified in writing, new and unused materials of standard first grade quality and workmanship and design of the highest quality, to the satisfaction of the **Commissioner**.

ARTICLE 4. MEANS AND METHODS OF CONSTRUCTION

- 4.1 Unless otherwise expressly provided in the **Contract Drawings**, **Specifications**, and **Addenda**, the **Means and Methods of Construction** shall be such as the **Contractor** may choose; subject, however, to the **Engineer's** right to reject the **Means and Methods of Construction** proposed by the **Contractor** which in the opinion of the **Engineer**:
 - 4.1.1 Will constitute or create a hazard to the Work, or to persons or property; or
 - 4.1.2 Will not produce finished **Work** in accordance with the terms of the **Contract**; or
 - 4.1.3 Will be detrimental to the overall progress of the **Project**.
- 4.2 The **Engineer's** approval of the **Contractor's Means and Methods of Construction**, or his/her failure to exercise his/her right to reject such means or methods, shall not relieve the **Contractor**

of its obligation to complete the **Work** as provided in this **Contract**; nor shall the exercise of such right to reject create a cause of action for damages.

ARTICLE 5. COMPLIANCE WITH LAWS

- 5.1 The **Contractor** shall comply with all **Laws** applicable to this **Contract** and to the **Work** to be done hereunder.
- 5.2 Procurement Policy Board Rules: This **Contract** is subject to the Rules of the **PPB** ("**PPB** Rules") in effect at the time of the bid opening for this **Contract**. In the event of a conflict between the **PPB** Rules and a provision of this **Contract**, the **PPB** Rules shall take precedence.
 - 5.3 Noise Control Code provisions.
 - 5.3.1 In accordance with the provisions of Section 24-216(b) of the Administrative Code of the **City** ("Administrative Code"), Noise Abatement Contract Compliance, devices and activities which will be operated, conducted, constructed or manufactured pursuant to this **Contract** and which are subject to the provisions of the **City** Noise Control Code shall be operated, conducted, constructed, or manufactured without causing a violation of the Administrative Code. Such devices and activities shall incorporate advances in the art of noise control development for the kind and level of noise emitted or produced by such devices and activities, in accordance with regulations issued by the **Commissioner** of the **City** Department of Environmental Protection.
 - 5.3.2 The Contractor agrees to comply with Section 24-219 of the Administrative Code and implementing rules codified at 15 Rules of the City of New York ("RCNY") Section 28-100 et seq. In accordance with such provisions, the Contractor, if the Contractor is the responsible party under such regulations, shall prepare and post a Construction Noise Mitigation Plan at each Site, in which the Contractor shall certify that all construction tools and equipment have been maintained so that they operate at normal manufacturers operating specifications. If the Contractor cannot make this certification, it must have in place an Alternative Noise Mitigation Plan approved by the City Department of Environmental Protection. In addition, the Contractor's certified Construction Noise Mitigation Plan is subject inspection by the City Department of Environmental Protection in accordance with Section 28-101 of Title 15 of RCNY. No Contract Work may take place at a **Site** unless there is a Construction Noise Mitigation Plan or approved Alternative Noise Mitigation Plan in place. In addition, the Contractor shall create and implement a noise mitigation training program. Failure to comply with these requirements may result in fines and other penalties pursuant to the applicable provisions of the Administrative Code and RCNY.
- 5.4 Ultra Low Sulfur Diesel Fuel: In accordance with the provisions of Section 24-163.3 of the Administrative Code, the **Contractor** specifically agrees as follows:
 - 5.4.1 Definitions. For purposes of this Article 5.4, the following definitions apply:
 - 5.4.1(a) "Contractor" means any person or entity that enters into a Public Works Contract with a **City Agency**, or any person or entity that enters into an agreement with such person or entity, to perform work or provide labor or services related to such Public Works Contract.

- 5.4.1(b) "Motor Vehicle" means any self-propelled vehicle designed for transporting persons or property on a street or highway.
- 5.4.1(c) "Nonroad Engine" means an internal combustion engine (including the fuel system) that is not used in a Motor Vehicle or a vehicle used solely for competition, or that is not subject to standards promulgated under Section 7411 or Section 7521 of Title 42 of the United States Code, except that this term shall apply to internal combustion engines used to power generators, compressors or similar equipment used in any construction program or project.
- 5.4.1(d) "Nonroad Vehicle" means a vehicle that is powered by a Nonroad Engine, fifty (50) horsepower and greater, and that is not a Motor Vehicle or a vehicle used solely for competition, which shall include, but not be limited to, excavators, backhoes, cranes, compressors, generators, bulldozers, and similar equipment, except that this term shall not apply to horticultural maintenance vehicles used for landscaping purposes that are powered by a Nonroad Engine of sixty-five (65) horsepower or less and that are not used in any construction program or project.
- 5.4.1(e) "Public Works Contract" means a contract with a **City Agency** for a construction program or project involving the construction, demolition, restoration, rehabilitation, repair, renovation, or abatement of any building, structure, tunnel, excavation, roadway, park or bridge; a contract with a **City Agency** for the preparation for any construction program or project involving the construction, demolition, restoration, rehabilitation, repair, renovation, or abatement of any building, structure, tunnel, excavation, roadway, park or bridge; or a contract with a **City Agency** for any final work involved in the completion of any construction program or project involving the construction, demolition, restoration, rehabilitation, repair, renovation, or abatement of any building, structure, tunnel, excavation, roadway, park or bridge.
- 5.4.1(f) "Ultra Low Sulfur Diesel Fuel" means diesel fuel that has a sulfur content of no more than fifteen parts per million (15 ppm).

5.4.2 Ultra Low Sulfur Diesel Fuel

- 5.4.2(a) All **Contractors** shall use Ultra Low Sulfur Diesel Fuel in diesel-powered Nonroad Vehicles in the performance of this **Contract**.
- 5.4.2(b) Notwithstanding the requirements of Article 5.4.2(a), **Contractors** may use diesel fuel that has a sulfur content of no more than thirty parts per million (30 ppm) to fulfill the requirements of this Article 5.4.2, where the Commissioner of the **City** Department of Environmental Protection ("DEP Commissioner") has issued a determination that a sufficient quantity of Ultra Low Sulfur Diesel Fuel is not available to meet the needs of **Agencies** and **Contractors**. Any such determination shall expire after six (6) months unless renewed.
- 5.4.2(c) **Contractors** shall not be required to comply with this Article 5.4.2 where the **City Agency** letting this **Contract** makes a written finding, which is approved, in writing, by the DEP Commissioner, that a sufficient quantity of Ultra Low Sulfur Diesel Fuel, or diesel fuel that has a sulfur content of no more than thirty parts per million (30 ppm) is not available to meet the requirements of Section 24-163.3 of the Administrative Code, provided that such **Contractor** in its fulfillment of the

requirements of this **Contract**, to the extent practicable, shall use whatever quantity of Ultra Low Sulfur Diesel Fuel or diesel fuel that has a sulfur content of no more than thirty parts per million (30 ppm) is available. Any finding made pursuant to this Article 5.4.2(c) shall expire after sixty (60) **Days**, at which time the requirements of this Article 5.4.2 shall be in full force and effect unless the **City Agency** renews the finding in writing and such renewal is approved by the DEP Commissioner.

- 5.4.2(d) **Contractors** may check on determinations and approvals issued by the DEP Commissioner pursuant to Section 24-163.3 of the Administrative Code, if any, at www.dep.nyc.gov or by contacting the **City Agency** letting this **Contract**.
- 5.4.2(e) The requirements of this Article 5.4.2 do not apply where they are precluded by federal or State funding requirements or where the **Contract** is an emergency procurement.

5.4.3 Best Available Technology

- 5.4.3(a) All **Contractors** shall utilize the best available technology for reducing the emission of pollutants for diesel-powered Nonroad Vehicles in the performance of this **Contract**. For determinations of best available technology for each type of diesel-powered Nonroad Vehicle, **Contractors** shall comply with the regulations of the **City** Department of Environmental Protection, as and when adopted, Chapter 14 of Title 15 of the Rules of the City of New York (RCNY). The **Contractor** shall fully document all steps in the best available technology selection process and shall furnish such documentation to the **City Agency** or the DEP Commissioner upon request. The **Contractor** shall retain all documentation generated in the best available technology selection process for as long as the selected best available technology is in use.
- 5.4.3(b) No **Contractor** shall be required to replace best available technology for reducing the emission of pollutants or other authorized technology utilized for a diesel-powered Nonroad Vehicle in accordance with the provisions of this Article 5.4.3 within three (3) years of having first utilized such technology for such vehicle.
- 5.4.3(c) This Article 5.4.3 shall not apply to any vehicle used to satisfy the requirements of a specific Public Works Contract for fewer than twenty (20) **Days**.
- 5.4.3(d) The **Contractor** shall not be required to comply with this Article 5.4.3 with respect to a diesel-powered Nonroad Vehicle under the following circumstances:
 - 5.4.3(d)(i) Where the **City Agency** makes a written finding, which is approved, in writing, by the DEP Commissioner, that the best available technology for reducing the emission of pollutants as required by this Article 5.4.3 is unavailable for such vehicle, the **Contractor** shall use whatever technology for reducing the emission of pollutants, if any, is available and appropriate for such vehicle.
 - 5.4.3(d)(ii) Where the DEP Commissioner has issued a written waiver based upon the **Contractor** having demonstrated to the DEP Commissioner that the use of the best available technology for reducing the emission of pollutants might endanger the operator of such vehicle or those working near such vehicle, due to engine malfunction, the **Contractor** shall use whatever technology for

reducing the emission of pollutants, if any, is available and appropriate for such vehicle, which would not endanger the operator of such vehicle or those working near such vehicle.

- 5.4.3(d)(iii) In determining which technology to use for the purposes of Articles 5.4.3(d)(i) and 5.4.3(d)(ii) above, the **Contractor** shall primarily consider the reduction in emissions of particulate matter and secondarily consider the reduction in emissions of nitrogen oxides associated with the use of such technology, which shall in no event result in an increase in the emissions of either such pollutant.
- 5.4.3(d)(iv) The **Contractor** shall submit requests for a finding or a waiver pursuant to this Article 5.4.3(d) in writing to the DEP Commissioner, with a copy to the **ACCO** of the **City Agency** letting this **Contract**. Any finding or waiver made or issued pursuant to Articles 5.4.3(d)(i) and 5.4.3(d)(ii) above shall expire after one hundred eighty (180) **Days**, at which time the requirements of Article 5.4.3(a) shall be in full force and effect unless the **City Agency** renews the finding, in writing, and the DEP Commissioner approves such finding, in writing, or the DEP Commissioner renews the waiver, in writing.
- 5.4.3(e) The requirements of this Article 5.4.3 do not apply where they are precluded by federal or State funding requirements or where the **Contract** is an emergency procurement.
- 5.4.4 Section 24-163 of the Administrative Code. The **Contractor** shall comply with Section 24-163 of the Administrative Code related to the idling of the engines of motor vehicles while parking.

5.4.5 Compliance

- 5.4.5(a) The **Contractor's** compliance with Article 5.4 may be independently monitored. If it is determined that the **Contractor** has failed to comply with any provision of Article 5.4, any costs associated with any independent monitoring incurred by the **City** shall be reimbursed by the **Contractor**.
- 5.4.5(b) Any **Contractor** who violates any provision of Article 5.4, except as provided in Article 5.4.5(c) below, shall be liable for a civil penalty between the amounts of one thousand (\$1,000) and ten thousand (\$10,000) dollars, in addition to twice the amount of money saved by such **Contractor** for failure to comply with Article 5.4.
- 5.4.5(c) No **Contractor** shall make a false claim with respect to the provisions of Article 5.4 to a **City Agency**. Where a **Contractor** has been found to have done so, such **Contractor** shall be liable for a civil penalty of twenty thousand (\$20,000) dollars, in addition to twice the amount of money saved by such **Contractor** in association with having made such false claim.

5.4.6 Reporting

5.4.6(a) For all Public Works Contracts covered by this Article 5.4, the **Contractor** shall report to the **City Agency** the following information:

- 5.4.6(a)(i) The total number of diesel-powered Nonroad Vehicles used to fulfill the requirements of this Public Works Contract;
- 5.4.6(a)(ii) The number of such Nonroad Vehicles that were powered by Ultra Low Sulfur Diesel Fuel;
- 5.4.6(a)(iii) The number of such Nonroad Vehicles that utilized the best available technology for reducing the emission of pollutants, including a breakdown by vehicle model and the type of technology;
- 5.4.6(a)(iv) The number of such Nonroad Vehicles that utilized such other authorized technology in accordance with Article 5.4.3, including a breakdown by vehicle model and the type of technology used for each such vehicle:
 - 5.4.6(a)(v) The locations where such Nonroad Vehicles were used; and
- 5.4.6(a)(vi) Where a determination is in effect pursuant to Article 5.4.2(b) or 5.4.2(c), detailed information concerning the **Contractor's** efforts to obtain Ultra Low Sulfur Diesel Fuel or diesel fuel that has a sulfur content of no more than thirty parts per million (30 ppm).
- 5.4.6(b) The **Contractor** shall submit the information required by Article 5.4.6(a) at the completion of **Work** under the Public Works Contract and on a yearly basis no later than August 1 throughout the term of the Public Works Contract. The yearly report shall cover **Work** performed during the preceding fiscal year (July 1 June 30).
- 5.5 Ultra Low Sulfur Diesel Fuel. In accordance with the Coordinated Construction Act for Lower Manhattan, as amended:
 - 5.5.1 Definitions. For purposes of this Article 5.5, the following definitions apply:
 - 5.5.1(a) "Lower Manhattan" means the area to the south of and within the following lines: a line beginning at a point where the United States pierhead line in the Hudson River as it exists now or may be extended would intersect with the southerly line of West Houston Street in the Borough of Manhattan extended, thence easterly along the southerly side of West Houston Street to the southerly side of Houston Street, thence easterly along the southerly side of Houston Street to the southerly side of East Houston Street, thence northeasterly along the southerly side of East Houston Street to the point where it would intersect with the United States pierhead line in the East River as it exists now or may be extended, including tax lots within or immediately adjacent thereto.
 - 5.5.1(b) "Lower Manhattan Redevelopment Project" means any project in Lower Manhattan that is funded in whole or in part with federal or State funding, or any project intended to improve transportation between Lower Manhattan and the two air terminals in the **City** known as LaGuardia Airport and John F. Kennedy International Airport, or between Lower Manhattan and the air terminal in Newark known as Newark Liberty International Airport, and that is funded in whole or in part with federal funding.

- 5.5.1(c) "Nonroad Engine" means an internal combustion engine (including the fuel system) that is not used in a Motor Vehicle or a vehicle used solely for competition, or that is not subject to standards promulgated under Section 7411 or Section 7521 of Title 42 of the United States Code, except that this term shall apply to internal combustion engines used to power generators, compressors or similar equipment used in any construction program or project.
- 5.5.1(d) "Nonroad Vehicle" means a vehicle that is powered by a Nonroad Engine, fifty (50) horsepower (HP) and greater, and that is not a Motor Vehicle or a vehicle used solely for competition, which shall include, but not be limited to, excavators, backhoes, cranes, compressors, generators, bulldozers, and similar equipment, except that this terms shall not apply to horticultural maintenance vehicles used for landscaping purposes that are powered by a Nonroad Engine of sixty-five (65) HP or less and that are not used in any construction program or project.
- 5.5.1(e) "Ultra Low Sulfur Diesel Fuel" means diesel fuel that has a sulfur content of no more than fifteen parts per million (15 ppm).
- 5.5.2 Requirements. **Contractors** and **Subcontractors** are required to use only Ultra Low Sulfur Diesel Fuel to power the diesel-powered Nonroad Vehicles with engine HP rating of fifty (50) HP and above used on a Lower Manhattan Redevelopment Project and, where practicable, to reduce the emission of pollutants by retrofitting such Nonroad Vehicles with oxidation catalysts, particulate filters, or technology that achieves lowest particulate matter emissions.
- 5.6 Pesticides. In accordance with Section 17-1209 of the Administrative Code, to the extent that the **Contractor** or any **Subcontractor** applies pesticides to any property owned or leased by the **City**, the **Contractor**, and any **Subcontractor** shall comply with Chapter 12 of the Administrative Code.
- 5.7 Waste Treatment, Storage, and Disposal Facilities and Transporters. In connection with the **Work**, the **Contractor** and any **Subcontractor** shall use only those waste treatment, storage, and disposal facilities and waste transporters that possess the requisite license, permit or other governmental approval necessary to treat, store, dispose, or transport the waste, materials or hazardous substances.
- 5.8 Environmentally Preferable Purchasing. The **Contractor** shall ensure that products purchased or leased by the **Contractor** or any **Subcontractor** for the **Work** that are not specified by the **City** or are submitted as equivalents to a product specified by the **City** comply with the requirements of the New York City Environmentally Preferable Purchasing Program contained in Chapter 11 of Title 43 of the RCNY, pursuant to Chapter 3 of Title 6 of the Administrative Code.

ARTICLE 6. INSPECTION

- 6.1 During the progress of the **Work** and up to the date of **Final Acceptance**, the **Contractor** shall at all times afford the representatives of the **City** every reasonable, safe, and proper facility for inspecting all **Work** done or being done at the **Site** and also for inspecting the manufacture or preparation of materials and equipment at the place of such manufacture or preparation.
- 6.2 The **Contractor's** obligation hereunder shall include the uncovering or taking down of finished **Work** and its restoration thereafter; provided, however, that the order to uncover, take down and restore shall be in writing, and further provided that if **Work** thus exposed proves satisfactory, and if the **Contractor** has complied with Article 6.1, such uncovering or taking down and restoration shall be

considered an item of **Extra Work** to be paid for in accordance with the provisions of Article 26. If the **Work** thus exposed proves unsatisfactory, the **City** has no obligation to compensate the **Contractor** for the uncovering, taking down or restoration.

- 6.3 Inspection and approval by the **Commissioner**, the **Engineer**, **Project Manager**, or **Resident Engineer**, of finished **Work** or of **Work** being performed, or of materials and equipment at the place of manufacture or preparation, shall not relieve the **Contractor** of its obligation to perform the **Work** in strict accordance with the **Contract**. Finished or unfinished **Work** not found to be in strict accordance with the **Contract** shall be replaced as directed by the **Engineer**, even though such **Work** may have been previously approved and paid for. Such corrective **Work** is **Contract Work** and shall not be deemed **Extra Work**.
- 6.4 Rejected **Work** and materials shall be promptly taken down and removed from the **Site**, which must at all times be kept in a reasonably clean and neat condition.

ARTICLE 7. PROTECTION OF WORK AND OF PERSONS AND PROPERTY; NOTICES AND INDEMNIFICATION

- 7.1 During the performance of the **Work** and up to the date of **Final Acceptance**, the **Contractor** shall be under an absolute obligation to protect the finished and unfinished **Work** against any damage, loss, injury, theft and/or vandalism and in the event of such damage, loss, injury, theft and/or vandalism, it shall promptly replace and/or repair such **Work** at the **Contractor's** sole cost and expense, as directed by the **Resident Engineer**. The obligation to deliver finished **Work** in strict accordance with the **Contract** prior to **Final Acceptance** shall be absolute and shall not be affected by the **Resident Engineer's** approval of, or failure to prohibit, the **Means and Methods of Construction** used by the **Contractor**.
- 7.2 During the performance of the **Work** and up to the date of **Final Acceptance**, the **Contractor** shall take all reasonable precautions to protect all persons and the property of the **City** and of others from damage, loss or injury resulting from the **Contractor's**, and/or its **Subcontractors'** operations under this **Contract.** The **Contractor's** obligation to protect shall include the duty to provide, place or replace, and adequately maintain at or about the **Site** suitable and sufficient protection such as lights, barricades, and enclosures.
- 7.3 The **Contractor** shall comply with the notification requirements set forth below in the event of any loss, damage or injury to **Work**, persons or property, or any accidents arising out of the operations of the **Contractor** and/or its **Subcontractors** under this **Contract**.
 - 7.3.1 The **Contractor** shall make a full and complete report in writing to the **Resident Engineer** within three (3) **Days** after the occurrence.
 - 7.3.2 The **Contractor** shall also send written notice of any such event to all insurance carriers that issued potentially responsive policies (including commercial general liability insurance carriers for events relating to the **Contractor**'s own employees) no later than twenty (20) days after such event and again no later than twenty (20) days after the initiation of any claim and/or action resulting therefrom. Such notice shall contain the following information: the number of the insurance policy, the name of the Named Insured, the date and location of the incident, and the identity of the persons injured or property damaged. For any policy on which the **City** and/or the **Engineer**, **Architect**, or **Project Manager** are Additional Insureds, such notice shall expressly specify that "this notice is

being given on behalf of the City of New York as Additional Insured, such other Additional Insureds, as well as the Named Insured."

- 7.3.2(a) Whenever such notice is sent under a policy on which the **City** is an Additional Insured, the **Contractor** shall provide copies of the notice to the **Comptroller**, the **Commissioner** and the **City** Corporation Counsel. The copy to the **Comptroller** shall be sent to the Insurance Unit, NYC Comptroller's Office, 1 Centre Street Room 1222, New York, New York, 10007. The copy to the **Commissioner** shall be sent to the address set forth in Schedule A of the General Conditions. The copy to the **City** Corporation Counsel shall be sent to Insurance Claims Specialist, Affirmative Litigation Division, New York City Law Department, 100 Church Street, New York, New York 10007.
- 7.3.2(b) If the **Contractor** fails to provide any of the foregoing notices to any appropriate insurance carrier(s) in a timely and complete manner, the **Contractor** shall indemnify the **City** for all losses, judgments, settlements, and expenses, including reasonable attorneys' fees, arising from an insurer's disclaimer of coverage citing late notice by or on behalf of the **City**.
- 7.4 To the fullest extent permitted by law, the **Contractor** shall defend, indemnify, and hold the City, its employees, and officials (the "Indemnitees") harmless against any and all claims (including but not limited to claims asserted by any employee of the Contractor and/or its Subcontractors) and costs and expenses of whatever kind (including but not limited to payment or reimbursement of attorneys' fees and disbursements) allegedly arising out of or in any way related to the operations of the Contractor and/or its Subcontractors in the performance of this Contract or from the Contractor's and/or its Subcontractors' failure to comply with any of the provisions of this Contract or of the Law. Such costs and expenses shall include all those incurred in defending the underlying claim and those incurred in connection with the enforcement of this Article 7.4 by way of cross-claim, third-party claim, declaratory action or otherwise. The parties expressly agree that the indemnification obligation hereunder contemplates (1) full indemnity in the event of liability imposed against the Indemnitees without negligence and solely by reason of statute, operation of Law or otherwise; and (2) partial indemnity in the event of any actual negligence on the part of the Indemnitees either causing or contributing to the underlying claim (in which case, indemnification will be limited to any liability imposed over and above that percentage attributable to actual fault whether by statute, by operation of Law, or otherwise). Where partial indemnity is provided hereunder, all costs and expenses shall be indemnified on a pro rata basis.
 - 7.4.1 Indemnification under Article 7.4 or any other provision of the **Contract** shall operate whether or not **Contractor** or its **Subcontractors** have placed and maintained the insurance specified under Article 22.
- 7.5 The provisions of this Article 7 shall not be deemed to create any new right of action in favor of third parties against the **Contractor** or the **City**.

CHAPTER III: TIME PROVISIONS

ARTICLE 8. COMMENCEMENT AND PROSECUTION OF THE WORK

8.1 The **Contractor** shall commence the **Work** on the date specified in the **Notice to Proceed** or the **Order to Work**. The time for performance of the **Work** under the **Contract** shall be computed from

the date specified in the **Notice to Proceed** or the **Order to Work**. **TIME BEING OF THE ESSENCE** to the **City**, the **Contractor** shall thereafter prosecute the **Work** diligently, using such **Means and Methods of Construction** as are in accord with Article 4 herein and as will assure its completion not later than the date specified in this Contract, or on the date to which the time for completion may be extended.

ARTICLE 9. PROGRESS SCHEDULES

- 9.1 To enable the **Work** to be performed in an orderly and expeditious manner, the **Contractor**, within fifteen (15) **Days** after the **Notice to Proceed** or **Order to Work**, unless otherwise directed by the **Engineer**, shall submit to the **Engineer** a proposed progress schedule based on the Critical Path Method in the form of a bar graph or in such other form as specified by the **Engineer**, and monthly cash flow requirements, showing:
 - 9.1.1 The anticipated time of commencement and completion of each of the various operations to be performed under this **Contract**; and
 - 9.1.2 The sequence and interrelation of each of these operations with the others and with those of other related contracts; and
 - 9.1.3 The estimated time required for fabrication or delivery, or both, of all materials and equipment required for the **Work**, including the anticipated time for obtaining required approvals pursuant to Article 10; and
 - 9.1.4 The estimated amount in dollars the **Contractor** will claim on a monthly basis.
- 9.2 The proposed schedule shall be revised as directed by the **Engineer**, until finally approved by the **Engineer**, and after such approval, subject to the provisions of Article 11, shall be strictly adhered to by the **Contractor**.
- 9.3 If the **Contractor** shall fail to adhere to the approved progress schedule, or to the schedule as revised pursuant to Article 11, it shall promptly adopt such other or additional **Means and Methods of Construction**, at its sole cost and expense, as will make up for the time lost and will assure completion in accordance with the approved progress schedule. The approval by the **City** of a progress schedule which is shorter than the time allotted under the **Contract** shall not create any liability for the **City** if the approved progress schedule is not met.
- 9.4 The **Contractor** will not receive any payments until the proposed progress schedule is submitted.

ARTICLE 10. REQUESTS FOR INFORMATION OR APPROVAL

10.1 From time to time as the **Work** progresses and in the sequence indicated by the approved progress schedule, the **Contractor** shall submit to the **Engineer** a specific request in writing for each item of information or approval required by the **Contractor**. These requests shall state the latest date upon which the information or approval is actually required by the **Contractor**, and shall be submitted in a reasonable time in advance thereof to provide the **Engineer** a sufficient time to act upon such submissions, or any necessary re-submissions thereof.

10.2 The **Contractor** shall not have any right to an extension of time on account of delays due to the **Contractor's** failure to submit requests for the required information or the required approval in accordance with the above requirements.

ARTICLE 11. NOTICE OF CONDITIONS CAUSING DELAY AND DOCUMENTATION OF DAMAGES CAUSED BY DELAY

- 11.1 After the commencement of any condition which is causing or may cause a delay in completion of the **Work**, including conditions for which the **Contractor** may be entitled to an extension of time, the following notifications and submittals are required:
 - 11.1.1 Within fifteen (15) **Days** after the **Contractor** becomes aware or reasonably should be aware of each such condition, the **Contractor** must notify the **Resident Engineer** or **Engineer**, as directed by the **Commissioner**, in writing of the existence, nature and effect of such condition upon the approved progress schedule and the **Work**, and must state why and in what respects, if any, the condition is causing or may cause a delay. Such notice shall include a description of the construction activities that are or could be affected by the condition and may include any recommendations the **Contractor** may have to address the delay condition and any activities the **Contractor** may take to avoid or minimize the delay.
 - 11.1.2 If the **Contractor** shall claim to be sustaining damages for delay as provided for in this Article 11, within forty-five (45) **Days** from the time such damages are first incurred for each such condition, the **Contractor** shall submit to the **Commissioner** a verified written statement of the details and estimates of the amounts of such damages, including categories of expected damages and projected monthly costs, together with documentary evidence of such damages as the **Contractor** may have at the time of submission ("statement of delay damages"), as further detailed in Article 11.6. The **Contractor** may submit the above statement within such additional time as may be granted by the **Commissioner** in writing upon written request therefor.
 - 11.1.3 Articles 11.1.1 and 11.1.2 do not relieve the **Contractor** of its obligation to comply with the provisions of Article 44.
- 11.2 Failure of the **Contractor** to strictly comply with the requirements of Article 11.1.1 may, in the discretion of the **Commissioner**, be deemed sufficient cause to deny any extension of time on account of delay arising out of such condition. Failure of the **Contractor** to strictly comply with the requirements of both Articles 11.1.1 and 11.1.2 shall be deemed a conclusive waiver by the **Contractor** of any and all claims for damages for delay arising from such condition and no right to recover on such claims shall exist.
- 11.3 When appropriate and directed by the **Engineer**, the progress schedule shall be revised by the **Contractor** until finally approved by the **Engineer**. The revised progress schedule must be strictly adhered to by the **Contractor**.

11.4 Compensable Delays

11.4.1 The **Contractor** agrees to make claim only for additional costs attributable to delay in the performance of this **Contract** necessarily extending the time for completion of the **Work** or resulting from acceleration directed by the **Commissioner** and required to maintain the progress schedule, occasioned solely by any act or omission to act of the **City** listed below. The **Contractor** also agrees that delay from any other cause shall be

compensated, if at all, solely by an extension of time to complete the performance of the **Work**.

- 11.4.1.1 The failure of the **City** to take reasonable measures to coordinate and progress the **Work** to the extent required by the **Contract**, except that the City shall not be responsible for the **Contractor's** obligation to coordinate and progress the **Work** of its **Subcontractors**.
- 11.4.1.2 Unreasonable delays attributable to the review of shop drawings, the issuance of change orders, or the cumulative impact of change orders that were not brought about by any act or omission of the **Contractor**.
- 11.4.1.3 The unavailability of the **Site** caused by acts or omissions of the **City**...
- 11.4.1.4 The issuance by the **Engineer** of a stop work order that was not brought about through any act or omission of the **Contractor**.
- 11.4.1.5 Differing site conditions or environmental hazards that were neither known nor reasonably ascertainable on a pre-bid inspection of the **Site** or review of the bid documents or other publicly available sources, and that are not ordinarily encountered in the **Project**'s geographical area or neighborhood or in the type of **Work** to be performed.
- 11.4.1.6 Delays caused by the **City's** bad faith or its willful, malicious, or grossly negligent conduct;
- 11.4.1.7 Delays not contemplated by the parties;
- 11.4.1.8 Delays so unreasonable that they constitute an intentional abandonment of the **Contract** by the **City**; and
- 11.4.1.9 Delays resulting from the **City's** breach of a fundamental obligation of the **Contract**.
- 11.4.2 No claim may be made for any alleged delay in **Substantial Completion** of the **Work** if the **Work** will be or is substantially completed by the date of **Substantial Completion** provided for in Schedule A unless acceleration has been directed by the **Commissioner** to meet the date of **Substantial Completion** set forth in Schedule A, or unless there is a provision in the **Contract** providing for additional compensation for early completion.
- 11.4.3 The provisions of this Article 11 apply only to claims for additional costs attributable to delay and do not preclude determinations by the **Commissioner** allowing reimbursements for additional costs for **Extra Work** pursuant to Articles 25 and 26 of this **Contract**. To the extent that any cost attributable to delay is reimbursed as part of a change order, no additional claim for compensation under this Article 11 shall be allowed.
- 11.5 Non-Compensable Delays. The **Contractor** agrees to make no claim for, and is deemed to have included in its bid prices for the various items of the **Contract**, the extra/additional costs attributable to any delays caused by or attributable to the items set forth below. For such items, the **Contractor** shall be compensated, if at all, solely by an extension of time to complete the performance of the **Work**, in accordance with the provisions of Article 13. Such extensions of time will be granted, if at all, pursuant to the grounds set forth in Article 13.3.
 - 11.5.1 The acts or omissions of any third parties, including but not limited to **Other Contractors**, public/ governmental bodies (other than **City Agencies**), utilities or private enterprises, who are disclosed in the **Contract Documents** or are ordinarily encountered or generally recognized as related to the **Work**;

- 11.5.2 Any situation which was within the contemplation of the parties at the time of entering into the **Contract**, including any delay indicated or disclosed in the **Contract Documents** or that would be generally recognized by a reasonably prudent contractor as related to the nature of the **Work**, and/or the existence of any facility or appurtenance owned, operated or maintained by any third party, as indicated or disclosed in the **Contract Documents** or ordinarily encountered or generally recognized as related to the nature of the **Work**:
- 11.5.3 Restraining orders, injunctions or judgments issued by a court which were caused by a Contractor's submission, action or inaction or by a Contractor's **Means and Methods of Construction**, or by third parties, unless such order, injunction or judgment was the result of an act or omission by the **City**;
- 11.5.4 Any labor boycott, strike, picketing, lockout or similar situation;
- 11.5.5 Any shortages of supplies or materials, or unavailability of equipment, required by the **Contract Work**;
- 11.5.6 Climatic conditions, storms, floods, droughts, tidal waves, fires, hurricanes, earthquakes, landslides or other catastrophes or acts of God, or acts of war or of the public enemy or terrorist acts, including the **City's** reasonable responses thereto; and
- 11.5.7 **Extra Work** which does not significantly affect the overall completion of the **Contract**, reasonable delays in the review or issuance of change orders or field orders and/or in shop drawing reviews or approvals.
- 11.6 Required Content of Submission of Statement of Delay Damages
 - 11.6.1 In the verified written statement of delay damages required by Article 11.1.2, the following information shall be provided by the **Contractor**:
 - 11.6.1.1 For each delay, the start and end dates of the claimed periods of delay and, in addition, a description of the operations that were delayed, an explanation of how they were delayed, and the reasons for the delay, including identifying the applicable act or omission of the City listed in Article 11.4.
 - 11.6.1.2 A detailed factual statement of the claim providing all necessary dates, locations and items of **Work** affected by the claim.
 - 11.6.1.3 The estimated amount of additional compensation sought and a breakdown of that amount into categories as described in Article 11.7.
 - 11.6.1.4 Any additional information requested by the **Commissioner**.

11.7 Recoverable Costs

- 11.7.1 Delay damages may be recoverable for the following costs actually and necessarily incurred in the performance of the **Work**:
 - 11.7.1.1 Direct labor, including payroll taxes (subject to statutory wage caps) and supplemental benefits, based on time and materials records;
 - 11.7.1.2 Necessary materials (including transportation to the **Site**), based on time and material records;

- 11.7.1.3 Reasonable rental value of necessary plant and equipment other than small tools, plus fuel/energy costs according to the applicable formula set forth in Articles 26.2.4 and/or 26.2.8, based on time and material records:
- 11.7.1.4 Additional insurance and bond costs;
- 11.7.1.5 Extended **Site** overhead, field office rental, salaries of field office staff, on-site project managers and superintendents, field office staff vehicles, **Project-**specific storage, field office utilities and telephone, and field office consumables;
- 11.7.1.6 Labor escalation costs based on actual costs;
- 11.7.1.7 Materials and equipment escalation costs based on applicable industry indices unless documentation of actual increased cost is provided;
- 11.7.1.8 Additional material and equipment storage costs based on actual documented costs and additional costs necessitated by extended manufacturer warranty periods; and
- 11.7.1.9 Extended home office overhead calculated based on the following formula:
 - (1) Subtract from the original **Contract** amount the amount earned by original contractual **Substantial Completion** date (not including change orders);
 - (2) Remove 15% overhead and profit from the calculation in item (1) by dividing the results of item (1) by 1.15;
 - (3) Multiply the result of item (2) by 7.25% for the total home office overhead;
 - (4) Multiply the result of item (3) by 7.25% for the total profit; and
 - (5) The total extended home office overhead will be the total of items (3) and (4).
- 11.7.2 Recoverable Subcontractor Costs. When the **Work** is performed by a **Subcontractor**, the **Contractor** may be paid the actual and necessary costs of such subcontracted **Work** as outlined above in Articles 11.7.1.1 through 11.7.1.8, and an additional overhead of 5% of the costs outlined in Articles 11.7.1.1 through 11.7.1.3.
- 11.7.3 Non-Recoverable Costs. The parties agree that the **City** will have no liability for the following items and the **Contractor** agrees it shall make no claim for the following items:
 - 11.7.3.1Profit, or loss of anticipated or unanticipated profit, except as provided in Article 11.7.1.9;
 - 11.7.3.2Consequential damages, including, but not limited to, construction or bridge loans or interest paid on such loans, loss of bonding capacity, bidding opportunities, or interest in investment, or any resulting insolvency;
 - 11.7.3.3 Indirect costs or expenses of any nature except those included in Article 11.7.1:
 - 11.7.3.4 Direct or indirect costs attributable to performance of **Work** where the **Contractor**, because of situations or conditions within its control, has not progressed the **Work** in a satisfactory manner; and
 - 11.7.3.5 Attorneys' fees and dispute and claims preparation expenses.

- 11.8 Any claims for delay under this Article 11 are not subject to the jurisdiction of the Contract Dispute Resolution Board pursuant to the dispute resolution process set forth in Article 27.
- 11.9 Any compensation provided to the **Contractor** in accordance with this Article 11 will be made pursuant to a claim filed with the **Comptroller**. Nothing in this Article 11 extends the time for the **Contractor** to file an action with respect to a claim within six months after **Substantial Completion** pursuant to Article 56.

ARTICLE 12. COORDINATION WITH OTHER CONTRACTORS

- 12.1 During the progress of the **Work**, **Other Contractors** may be engaged in performing other work or may be awarded other contracts for additional work on this **Project**. In that event, the **Contractor** shall coordinate the **Work** to be done hereunder with the work of such **Other Contractors** and the **Contractor** shall fully cooperate with such **Other Contractors** and carefully fit its own **Work** to that provided under other contracts as may be directed by the **Engineer**. The **Contractor** shall not commit or permit any act which will interfere with the performance of work by any **Other Contractors**.
- 12.2 If the **Engineer** determines that the **Contractor** is failing to coordinate its **Work** with the work of **Other Contractors** as the **Engineer** has directed, then the **Commissioner** shall have the right to withhold any payments otherwise due hereunder until the **Contractor** completely complies with the **Engineer's** directions.
- 12.3 The Contractor shall notify the Engineer in writing if any Other Contractor on this Project is failing to coordinate its work with the Work of this Contract. If the Engineer finds such charges to be true, the Engineer shall promptly issue such directions to the Other Contractor with respect thereto as the situation may require. The City shall not, however, be liable for any damages suffered by any Other Contractor's failure to coordinate its work with the Work of this Contract or by reason of the Other Contractor's failure to promptly comply with the directions so issued by the Engineer, or by reason of any Other Contractor's default in performance, it being understood that the City does not guarantee the responsibility or continued efficiency of any contractor. The Contractor agrees to make no claim against the City for any damages relating to or arising out of any directions issued by the Engineer pursuant to this Article 12 (including but not limited to the failure of any Other Contractor to comply or promptly comply with such directions), or the failure of any Other Contractor to coordinate its work, or the default in performance of any Other Contractor.
- 12.4 The **Contractor** shall indemnify and hold the **City** harmless from any and all claims or judgments for damages and from costs and expenses to which the **City** may be subjected or which it may suffer or incur by reason of the **Contractor's** failure to comply with the **Engineer's** directions promptly; and the **Comptroller** shall have the right to exercise the powers reserved in Article 23 with respect to any claims which may be made for damages due to the **Contractor's** failure to comply with the **Engineer's** directions promptly. Insofar as the facts and **Law** relating to any claim would preclude the **City** from being completely indemnified by the **Contractor**, the **City** shall be partially indemnified by the **Contractor** to the fullest extent provided by **Law**.
- 12.5 Should the **Contractor** sustain any damage through any act or omission of any **Other Contractor** having a contract with the **City** for the performance of work upon the **Site** or of work which may be necessary to be performed for the proper prosecution of the **Work** to be performed hereunder, or through any act or omission of a subcontractor of such **Other Contractor**, the **Contractor** shall have no claim against the **City** for such damage, but shall have a right to recover such damage from the **Other**

Contractor under the provision similar to the following provisions which apply to this **Contract** and have been or will be inserted in the contracts with such **Other Contractors**:

- 12.5.1 Should any **Other Contractor** having or who shall hereafter have a contract with the **City** for the performance of work upon the **Site** sustain any damage through any act or omission of the **Contractor** hereunder or through any act or omission of any **Subcontractor** of the **Contractor**, the **Contractor** agrees to reimburse such **Other Contractor** for all such damages and to defend at its own expense any action based upon such claim and if any judgment or claim (even if the allegations of the action are without merit) against the **City** shall be allowed the **Contractor** shall pay or satisfy such judgment or claim and pay all costs and expenses in connection therewith and agrees to indemnify and hold the **City** harmless from all such claims. Insofar as the facts and **Law** relating to any claim would preclude the **City** from being completely indemnified by the **Contractor**, the **City** shall be partially indemnified by the **Contractor** to the fullest extent provided by **Law**.
- 12.6 The **City's** right to indemnification hereunder shall in no way be diminished, waived or discharged by its recourse to assessment of liquidated damages as provided in Article 15, or by the exercise of any other remedy provided for by **Contract** or by **Law**.

ARTICLE 13. EXTENSION OF TIME FOR PERFORMANCE

- 13.1 If performance by the **Contractor** is delayed for a reason set forth in Article 13.3, the **Contractor** may be allowed a reasonable extension of time in conformance with this Article 13 and the **PPB** Rules.
- 13.2 Any extension of time may be granted only by the **ACCO** or by the Board for the Extension of Time (hereafter "Board") (as set forth below) upon written application by the **Contractor**.
- 13.3 Grounds for Extension: If such application is made, the **Contractor** shall be entitled to an extension of time for delay in completion of the **Work** caused solely:
 - 13.3.1 By the acts or omissions of the **City**, its officials, agents or employees; or
 - 13.3.2 By the act or omissions of **Other Contractors** on this **Project**; or
 - 13.3.3 By supervening conditions entirely beyond the control of either party hereto (such as, but not limited to, acts of God or the public enemy, excessive inclement weather, war or other national emergency making performance temporarily impossible or illegal, or strikes or labor disputes not brought about by any act or omission of the **Contractor**).
 - 13.3.4 The **Contractor** shall, however, be entitled to an extension of time for such causes only for the number of **Days** of delay which the **ACCO** or the Board may determine to be due solely to such causes, and then only if the **Contractor** shall have strictly complied with all of the requirements of Articles 9 and 10.
- 13.4 The **Contractor** shall not be entitled to receive a separate extension of time for each of several causes of delay operating concurrently, but, if at all, only for the actual period of delay in completion of the **Work** as determined by the **ACCO** or the Board, irrespective of the number of causes contributing to produce such delay. If one of several causes of delay operating concurrently results from any act, fault or omission of the **Contractor** or of its **Subcontractors** or **Materialmen**, and would of itself (irrespective

of the concurrent causes) have delayed the **Work**, no extension of time will be allowed for the period of delay resulting from such act, fault or omission.

- 13.5 The determination made by the **ACCO** or the Board on an application for an extension of time shall be binding and conclusive on the **Contractor**.
- 13.6 The **ACCO** or the Board acting entirely within their discretion may grant an application for an extension of time for causes of delay other than those herein referred.
- 13.7 Permitting the **Contractor** to continue with the **Work** after the time fixed for its completion has expired, or after the time to which such completion may have been extended has expired, or the making of any payment to the **Contractor** after such time, shall in no way operate as a waiver on the part of the **City** of any of its rights under this **Contract**.
 - 13.8 Application for Extension of Time:
 - 13.8.1 Before the **Contractor's** time extension request will be considered, the **Contractor** shall notify the **ACCO** of the condition which allegedly has caused or is causing the delay, and shall submit a written application to the **ACCO** identifying:
 - 13.8.1(a) The **Contractor**; the registration number; and **Project** description;
 - 13.8.1(b) Liquidated damage assessment rate, as specified in the **Contract**;
 - 13.8.1(c) Original total bid price;
 - 13.8.1(d) The original **Contract** start date and completion date;
 - 13.8.1(e) Any previous time extensions granted (number and duration); and
 - 13.8.1(f) The extension of time requested.
 - 13.8.2 In addition, the application for extension of time shall set forth in detail:
 - 13.8.2(a) The nature of each alleged cause of delay in completing the **Work**;
 - 13.8.2(b) The date upon which each such cause of delay began and ended and the number of **Days** attributable to each such cause;
 - 13.8.2(c) A statement that the **Contractor** waives all claims except for those delineated in the application, and the particulars of any claims which the **Contractor** does not agree to waive. For time extensions for **Substantial Completion** and final completion payments, the application shall include a detailed statement of the dollar amounts of each element of claim item reserved; and
 - 13.8.2(d) A statement indicating the **Contractor's** understanding that the time extension is granted only for purposes of permitting continuation of **Contract** performance and payment for **Work** performed and that the **City** retains its right to conduct an investigation and assess liquidated damages as appropriate in the future.
 - 13.9 Analysis and Approval of Time Extensions:

- 13.9.1 For time extensions for partial payments, a written determination shall be made by the **ACCO** who may, for good and sufficient cause, extend the time for the performance of the **Contract** as follows:
 - 13.9.1(a) If the **Work** is to be completed within six (6) months, the time for performance may be extended for sixty (60) **Days**;
 - 13.9.1(b) If the **Work** is to be completed within less than one (1) year but more than six (6) months, an extension of ninety (90) **Days** may be granted;
 - 13.9.1(c) If the **Contract** period exceeds one (1) year, besides the extension granted in Article 13.9.1(b), an additional thirty (30) **Days** may be granted for each multiple of six (6) months involved beyond the one (1) year period; or
 - 13.9.1(d) If exceptional circumstances exist, the **ACCO** may extend the time for performance beyond the extensions in Articles 13.9.1(a), 13.9.1(b), and 13.9.1(c). In that event, the **ACCO** shall file with the Mayor's Office of Contract Services a written explanation of the exceptional circumstances.
- 13.9.2 For extensions of time for **Substantial Completion** and final completion payments, the **Engineer**, in consultation with the **ACCO**, shall prepare a written analysis of the delay (including a preliminary determination of the causes of delay, the beginning and end dates for each such cause of delay, and whether the delays are excusable under the terms of this **Contract**). The report shall be subject to review by and approval of the Board, which shall have authority to question its analysis and determinations and request additional facts or documentation. The report as reviewed and made final by the Board shall be made a part of the **Agency** contract file. Neither the report itself nor anything contained therein shall operate as a waiver or release of any claim the **City** may have against the **Contractor** for either actual or liquidated damages.
- 13.9.3 Approval Mechanism for Time Extensions for **Substantial Completion** or Final Completion Payments: An extension shall be granted only with the approval of the Board which is comprised of the **ACCO** of the **Agency**, the **City** Corporation Counsel, and the **Comptroller**, or their authorized representatives.
- 13.9.4 Neither the granting of any application for an extension of time to the **Contractor** or any **Other Contractor** on this **Project** nor the papers, records or reports related to any application for or grant of an extension of time or determination related thereto shall be referred to or offered in evidence by the **Contractor** or its attorneys in any action or proceeding.
- 13.10 No Damage for Delay: The **Contractor** agrees to make no claim for damages for delay in the performance of this **Contract** occasioned by any act or omission to act of the **City** or any of its representatives, except as provided for in Article 11.

ARTICLE 14. COMPLETION AND FINAL ACCEPTANCE OF THE WORK

14.1 Date for **Substantial Completion**: The **Contractor** shall substantially complete the **Work** within the time fixed in Schedule A of the General Conditions, or within the time to which such **Substantial Completion** may be extended.

- 14.2 Determining the Date of **Substantial Completion**: The **Work** will be deemed to be substantially complete when the two conditions set forth below have been met.
 - 14.2.1 Inspection: The **Engineer** or **Resident Engineer**, as applicable, has inspected the **Work** and has made a written determination that it is substantially complete.
 - 14.2.2 Approval of **Final Approved Punch List** and Date for **Final Acceptance**: Following inspection of the **Work**, the **Engineer/Resident Engineer** shall furnish the **Contractor** with a final punch list, specifying all items of **Work** to be completed and proposing dates for the completion of each specified item of **Work**. The **Contractor** shall then submit in writing to the **Engineer/Resident Engineer** within ten (10) **Days** of the **Engineer/Resident Engineer** furnishing the final punch list either acceptance of the dates or proposed alternative dates for the completion of each specified item of **Work**. If the **Contractor** neither accepts the dates nor proposes alternative dates within ten (10) **Days**, the schedule proposed by the **Engineer/Resident Engineer** shall be deemed accepted. If the **Contractor** proposes alternative dates, then, within a reasonable time after receipt, the **Engineer/Resident Engineer**, in a written notification to the **Contractor**, shall approve the **Contractor's** completion dates or, if they are unable to agree, the **Engineer/Resident Engineer** shall establish dates for the completion of each item of **Work**. The latest completion date specified shall be the date for **Final Acceptance** of the **Work**.
- 14.3 Date of **Substantial Completion**. The date of approval of the **Final Approved Punch List**, shall be the date of **Substantial Completion**. The date of approval of the **Final Approved Punch List** shall be either (a) if the **Contractor** approves the final punch list and proposed dates for completion furnished by the **Engineer/Resident Engineer**, the date of the **Contractor**'s approval; or (b) if the **Contractor** neither accepts the dates nor proposes alternative dates, ten (10) **Days** after the **Engineer/Resident Engineer** furnishes the **Contractor** with a final punch list and proposed dates for completion; or (c) if the **Contractor** proposes alternative dates, the date that the **Engineer/Resident Engineer** sends written notification to the **Contractor** either approving the **Contractor**'s proposed alternative dates or establishing dates for the completion for each item of **Work**.
- 14.4 Determining the Date of **Final Acceptance**: The **Work** will be accepted as final and complete as of the date of the **Engineer**'s/**Resident Engineer**'s inspection if, upon such inspection, the **Engineer/Resident Engineer** finds that all items on the **Final Approved Punch List** are complete and no further **Work** remains to be done. The **Commissioner** will then issue a written determination of **Final Acceptance**.
- 14.5 Request for Inspection: Inspection of the **Work** by the **Engineer/Resident Engineer** for the purpose of **Substantial Completion** or **Final Acceptance** shall be made within fourteen (14) **Days** after receipt of the **Contractor's** written request therefor.
- 14.6 Request for Re-inspection: If upon inspection for the purpose of **Substantial Completion** or **Final Acceptance**, the **Engineer/Resident Engineer** determines that there are items of **Work** still to be performed, the **Contractor** shall promptly perform them and then request a re-inspection. If upon reinspection, the **Engineer/Resident Engineer** determines that the **Work** is substantially complete or finally accepted, the date of such re-inspection shall be the date of **Substantial Completion** or **Final Acceptance**. Re-inspection by the **Engineer/Resident Engineer** shall be made within ten (10) **Days** after receipt of the **Contractor's** written request therefor.

14.7 Initiation of Inspection by the **Engineer/Resident Engineer**: If the **Contractor** does not request inspection or re-inspection of the **Work** for the purpose of **Substantial Completion** or **Final Acceptance**, the **Engineer/Resident Engineer** may initiate such inspection or re-inspection.

ARTICLE 15. LIQUIDATED DAMAGES

- 15.1 In the event the **Contractor** fails to substantially complete the **Work** within the time fixed for such **Substantial Completion** in Schedule A of the General Conditions, plus authorized time extensions, or if the **Contractor**, in the sole determination of the **Commissioner**, has abandoned the **Work**, the **Contractor** shall pay to the **City** the sum fixed in Schedule A of the General Conditions, for each and every **Day** that the time consumed in substantially completing the **Work** exceeds the time allowed therefor; which said sum, in view of the difficulty of accurately ascertaining the loss which the **City** will suffer by reason of delay in the **Substantial Completion** of the **Work** hereunder, is hereby fixed and agreed as the liquidated damages that the **City** will suffer by reason of such delay, and not as a penalty. This Article 15 shall also apply to the **Contractor** whether or not the **Contractor** is defaulted pursuant to Chapter X of this **Contract**. Neither the failure to assess liquidated damages nor the granting of any time extension shall operate as a waiver or release of any claim the **City** may have against the **Contractor** for either actual or liquidated damages.
- 15.2 Liquidated damages received hereunder are not intended to be nor shall they be treated as either a partial or full waiver or discharge of the **City's** right to indemnification, or the **Contractor's** obligation to indemnify the **City**, or to any other remedy provided for in this **Contract** or by **Law**.
- 15.3 The **Commissioner** may deduct and retain out of the monies which may become due hereunder, the amount of any such liquidated damages; and in case the amount which may become due hereunder shall be less than the amount of liquidated damages suffered by the **City**, the **Contractor** shall be liable to pay the difference.

ARTICLE 16. OCCUPATION OR USE PRIOR TO COMPLETION

- 16.1 Unless otherwise provided for in the **Specifications**, the **Commissioner** may take over, use, occupy or operate any part of the **Work** at any time prior to **Final Acceptance**, upon written notification to the **Contractor**. The **Engineer** or **Resident Engineer**, as applicable, shall inspect the part of the **Work** to be taken over, used, occupied, or operated, and will furnish the **Contractor** with a written statement of the **Work**, if any, which remains to be performed on such part. The **Contractor** shall not object to, nor interfere with, the **Commissioner's** decision to exercise the rights granted by Article 16. In the event the **Commissioner** takes over, uses, occupies, or operates any part of the **Work**:
 - 16.1.1 the **Engineer/Resident Engineer** shall issue a written determination of **Substantial Completion** with respect to such part of the **Work**;
 - 16.1.2 the **Contractor** shall be relieved of its absolute obligation to protect such part of the unfinished **Work** in accordance with Article 7;
 - 16.1.3 the **Contractor's** guarantee on such part of the **Work** shall begin on the date of such use by the **City**; and;
 - 16.1.4 the **Contractor** shall be entitled to a return of so much of the amount retained in accordance with Article 21 as it relates to such part of the **Work**, except so much thereof as may be retained under Articles 24 and 44.

CHAPTER IV: SUBCONTRACTS AND ASSIGNMENTS

ARTICLE 17. SUBCONTRACTS

- 17.1 The **Contractor** shall not make subcontracts totaling an amount more than the percentage of the total **Contract** price fixed in Schedule A of the General Conditions, without prior written permission from the **Commissioner**. All subcontracts made by the **Contractor** shall be in writing. No **Work** may be performed by a **Subcontractor** prior to the **Contractor** entering into a written subcontract with the **Subcontractor** and complying with the provisions of this Article 17.
- 17.2 Before making any subcontracts, the **Contractor** shall submit a written statement to the **Commissioner** giving the name and address of the proposed **Subcontractor**; the portion of the **Work** and materials which it is to perform and furnish; the cost of the subcontract; the VENDEX questionnaire if required; the proposed subcontract if requested by the **Commissioner**; and any other information tending to prove that the proposed **Subcontractor** has the necessary facilities, skill, integrity, past experience, and financial resources to perform the **Work** in accordance with the terms and conditions of this **Contract**.
- 17.3 In addition to the requirements in Article 17.2, **Contractor** is required to list the **Subcontractor** in the web based Subcontractor Reporting System through the City's Payee Information Portal (PIP), available at www.nyc.gov/pip. For each **Subcontractor** listed, **Contractor** is required to provide the following information: maximum contract value, description of **Subcontractor's** Work, start and end date of the subcontract and identification of the **Subcontractor's** industry. Thereafter, **Contractor** will be required to report in the system the payments made to each **Subcontractor** within 30 days of making the payment. If any of the required information changes throughout the Term of the **Contract, Contractor** will be required to revise the information in the system.

Failure of the **Contractor** to list a **Subcontractor** and/or to report **Subcontractor** payments in a timely fashion may result in the **Commissioner** declaring the **Contractor** in default of the **Contract** and will subject **Contractor** to liquidated damages in the amount of \$100 per day for each day that the **Contractor** fails to identify a **Subcontractor** along with the required information about the **Subcontractor** and/or fails to report payments to a **Subcontractor**, beyond the time frames set forth herein or in the notice from the **City**. Article 15 shall govern the issue of liquidated damages.

- 17.4 If an approved **Subcontractor** elects to subcontract any portion of its subcontract, the proposed sub-subcontract shall be submitted in the same manner as directed above.
- 17.5 The **Commissioner** will notify the **Contractor** in writing whether the proposed **Subcontractor** is approved. If the proposed **Subcontractor** is not approved, the **Contractor** may submit another proposed **Subcontractor** unless the **Contractor** decides to do the **Work**. No **Subcontractor** shall be permitted to enter or perform any work on the **Site** unless approved.
- 17.6 Before entering into any subcontract hereunder, the **Contractor** shall provide the proposed **Subcontractor** with a complete copy of this document and inform the proposed **Subcontractor** fully and completely of all provisions and requirements of this **Contract** relating either directly or indirectly to the **Work** to be performed and the materials to be furnished under such subcontract, and every such

-

¹ In order to use the new system, a PIP account will be required. Detailed instructions on creating a PIP account and using the new system are also available at www.nyc.gov/pip. Additional assistance with PIP may be obtained by emailing the Financial Information Services Agency Help Desk at pip@fisa.nyc.gov.

Subcontractor shall expressly stipulate that all labor performed and materials furnished by the **Subcontractor** shall strictly comply with the requirements of this **Contract**.

- 17.7 Documents given to a prospective **Subcontractor** for the purpose of soliciting the **Subcontractor's** bid shall include either a copy of the bid cover or a separate information sheet setting forth the **Project** name, the **Contract** number (if available), the **Agency** (as noted in Article 2.1.6), and the **Project's** location.
- 17.8 The **Commissioner's** approval of a **Subcontractor** shall not relieve the **Contractor** of any of its responsibilities, duties, and liabilities hereunder. The **Contractor** shall be solely responsible to the **City** for the acts or defaults of its **Subcontractor** and of such **Subcontractor's** officers, agents, and employees, each of whom shall, for this purpose, be deemed to be the agent or employee of the **Contractor** to the extent of its subcontract.
- 17.9 If the **Subcontractor** fails to maintain the necessary facilities, skill, integrity, past experience, and financial resources (other than due to the **Contractor's** failure to make payments where required) to perform the **Work** in accordance with the terms and conditions of this **Contract**, the **Contractor** shall promptly notify the **Commissioner** and replace such **Subcontractor** with a newly approved **Subcontractor** in accordance with this Article 17.
- 17.10 The **Contractor** shall be responsible for ensuring that all **Subcontractors** performing **Work** at the **Site** maintain all insurance required by **Law**.
- 17.11 The **Contractor** shall promptly, upon request, file with the **Engineer** a conformed copy of the subcontract and its cost. The subcontract shall provide the following:
 - 17.11.1 Payment to **Subcontractors**: The agreement between the **Contractor** and its **Subcontractor** shall contain the same terms and conditions as to method of payment for **Work**, labor, and materials, and as to retained percentages, as are contained in this **Contract**.
 - 17.11.2 Prevailing Rate of Wages: The agreement between the **Contractor** and its **Subcontractor** shall include the prevailing wage rates and supplemental benefits to be paid in accordance with Labor Law Section 220.
 - 17.11.3 Section 6-123 of the Administrative Code: Pursuant to the requirements of Section 6-123 of the Administrative Code, every agreement between the **Contractor** and a **Subcontractor** in excess of fifty thousand (\$50,000) dollars shall include a provision that the **Subcontractor** shall not engage in any unlawful discriminatory practice as defined in Title VIII of the Administrative Code (Section 8-101 *et seq.*).
 - 17.11.4 All requirements required pursuant to federal and/or state grant agreement(s), if applicable to the **Work**.
- 17.12 The **Commissioner** may deduct from the amounts certified under this **Contract** to be due to the **Contractor**, the sum or sums due and owing from the **Contractor** to the **Subcontractors** according to the terms of the said subcontracts, and in case of dispute between the **Contractor** and its **Subcontractor**, or **Subcontractors**, as to the amount due and owing, the **Commissioner** may deduct and withhold from the amounts certified under this **Contract** to be due to the **Contractor** such sum or sums as may be claimed by such **Subcontractor**, or **Subcontractors**, in a sworn affidavit, to be due and owing until such time as such claim or claims shall have been finally resolved.

- 17.13 On contracts where performance bonds and payment bonds are executed, the **Contractor** shall include on each requisition for payment the following data: **Subcontractor's** name, value of the subcontract, total amount previously paid to **Subcontractor** for **Work** previously requisitioned, and the amount, including retainage, to be paid to the **Subcontractor** for **Work** included in the requisition.
- 17.14 On **Contracts** where performance bonds and payment bonds are not executed, the **Contractor** shall include with each requisition for payment submitted hereunder, a signed statement from each and every **Subcontractor** and/or **Materialman** for whom payment is requested in such requisition. Such signed statement shall be on the letterhead of the **Subcontractor** and/or **Materialman** for whom payment is requested and shall (i) verify that such **Subcontractor** and/or **Materialman** has been paid in full for all **Work** performed and/or material supplied to date, exclusive of any amount retained and any amount included on the current requisition, and (ii) state the total amount of retainage to date, exclusive of any amount retained on the current requisition.

ARTICLE 18. ASSIGNMENTS

- 18.1 The **Contractor** shall not assign, transfer, convey or otherwise dispose of this **Contract**, or the right to execute it, or the right, title or interest in or to it or any part thereof, or assign, by power of attorney or otherwise any of the monies due or to become due under this **Contract**, unless the previous written consent of the **Commissioner** shall first be obtained thereto, and the giving of any such consent to a particular assignment shall not dispense with the necessity of such consent to any further or other assignments.
- 18.2 Such assignment, transfer, conveyance or other disposition of this **Contract** shall not be valid until filed in the office of the **Commissioner** and the **Comptroller**, with the written consent of the **Commissioner** endorsed thereon or attached thereto.
- 18.3 Failure to obtain the previous written consent of the **Commissioner** to such an assignment, transfer, conveyance or other disposition, may result in the revocation and annulment of this **Contract**. The **City** shall thereupon be relieved and discharged from any further liability to the **Contractor**, its assignees, transferees or sublessees, who shall forfeit and lose all monies therefor earned under the **Contract**, except so much as may be required to pay the **Contractor's** employees.
- 18.4 The provisions of this clause shall not hinder, prevent, or affect an assignment by the **Contractor** for the benefit of its creditors made pursuant to the **Laws** of the State of New York.
- 18.5 This **Contract** may be assigned by the **City** to any corporation, agency or instrumentality having authority to accept such assignment.

CHAPTER V: CONTRACTOR'S SECURITY AND GUARANTEE

ARTICLE 19. SECURITY DEPOSIT

19.1 If performance and payment bonds are required, the **City** shall retain the bid security to ensure that the successful bidder executes the **Contract** and furnishes the required payment and performance security within ten (10) **Days** after notice of the award of the **Contract**. If the successful bidder fails to execute the **Contract** and furnish the required payment and performance security, the **City** shall retain such bid security as set forth in the Information for Bidders. If the successful bidder executes the

Contract and furnishes the required payment and performance security, the **City** shall return the bid security within a reasonable time after the furnishing of such bonds and execution of the **Contract** by the **City**.

- 19.2 If performance and payment bonds are not required, the bid security shall be retained by the **City** as security for the **Contractor**'s faithful performance of the **Contract**. If partial payments are provided, the bid security will be returned to the **Contractor** after the sum retained under Article 21 equals the amount of the bid security, subject to other provisions of this **Contract**. If partial payments are not provided, the bid security will be released when final payment is certified by the **City** for payment.
- 19.3 If the **Contractor** is declared in default under Article 48 prior to the return of the deposit, or if any claim is made such as referred to in Article 23, the amount of such deposit, or so much thereof as the **Comptroller** may deem necessary, may be retained and then applied by the **Comptroller**:
 - 19.3.1 To compensate the **City** for any expense, loss or damage suffered or incurred by reason of or resulting from such default, including the cost of re-letting and liquidated damages; or
 - 19.3.2 To indemnify the **City** against any and all claims.

ARTICLE 20. PAYMENT GUARANTEE

- 20.1 On **Contracts** where one hundred (100%) percent performance bonds and payment bonds are executed, this Article 20 does not apply.
- 20.2 In the event the terms of this **Contract** do not require the **Contractor** to provide a payment bond or where the **Contract** does not require a payment bond for one hundred (100%) percent of the **Contract** price, the **City** shall, in accordance with the terms of this Article 20, guarantee payment of all lawful claims for:
 - 20.2.1 Wages and compensation for labor performed and/or services rendered; and
 - 20.2.2 Materials, equipment, and supplies provided, whether incorporated into the **Work** or not, when demands have been filed with the **City** as provided hereinafter by any person, firm, or corporation which furnished labor, material, equipment, supplies, or any combination thereof, in connection with the **Work** performed hereunder (hereinafter referred to as the "beneficiary") at the direction of the **City** or the **Contractor**.
 - 20.3 The provisions of Article 20.2 are subject to the following limitations and conditions:
 - 20.3.1 If the **Contractor** provides a payment bond for a value that is less than one hundred (100%) percent of the value of the **Contract Work**, the payment bond provided by the **Contractor** shall be primary (and non-contributing) to the payment guarantee provided under this Article 20.
 - 20.3.2 The guarantee is made for the benefit of all beneficiaries as defined in Article 20.2 provided that those beneficiaries strictly adhere to the terms and conditions of Article 20.3.4 and 20.3.5.

- 20.3.3 Nothing in this Article 20 shall prevent a beneficiary providing labor, services or material for the **Work** from suing the **Contractor** for any amounts due and owing the beneficiary by the **Contractor**.
- 20.3.4 Every person who has furnished labor or material, to the **Contractor** or to a Subcontractor of the Contractor, in the prosecution of the Work and who has not been paid in full therefor before the expiration of a period of ninety (90) **Days** after the date on which the last of the labor was performed or material was furnished by him/her for which the claim is made, shall have the right to sue on this payment guarantee in his/her own name for the amount, or the balance thereof, unpaid at the time of commencement of the action; provided, however, that a person having a direct contractual relationship with a Subcontractor of the Contractor but no contractual relationship express or implied with the **Contractor** shall not have a right of action upon the guarantee unless he/she shall have given written notice to the **Contractor** within one hundred twenty (120) **Days** from the date on which the last of the labor was performed or the last of the material was furnished, for which his/her claim is made, stating with substantial accuracy the amount claimed and the name of the party to whom the material was furnished or for whom the labor was performed. The notice shall be served by delivering the same personally to the Contractor or by mailing the same by registered mail, postage prepaid, in an envelope addressed to the Contractor at any place where it maintains an office or conducts its business; provided, however, that where such notice is actually received by the **Contractor** by other means, such notice shall be deemed sufficient.
- 20.3.5 Except as provided in Labor Law Section 220-g, no action on this payment guarantee shall be commenced after the expiration of the one-year limitations period set forth in Section 137(4)(b) of the State Finance Law.
- 20.3.6 The **Contractor** shall promptly forward to the **City** any notice or demand received pursuant to Article 20.3.4. The **Contractor** shall inform the **City** of any defenses to the notice or demand and shall forward to the **City** any documents the **City** requests concerning the notice or demand.
- 20.3.7 All demands made against the **City** by a beneficiary of this payment guarantee shall be presented to the **Engineer** along with all written documentation concerning the demand which the **Engineer** deems reasonably appropriate or necessary, which may include, but shall not be limited to: the subcontract; any invoices presented to the **Contractor** for payment; the notarized statement of the beneficiary that the demand is due and payable, that a request for payment has been made of the **Contractor** and that the demand has not been paid by the **Contractor** within the time allowed for such payment by the subcontract; and copies of any correspondence between the beneficiary and the **Contractor** concerning such demand. The **City** shall notify the **Contractor** that a demand has been made. The **Contractor** shall inform the **City** of any defenses to the demand and shall forward to the **City** any documents the **City** requests concerning the demand.
- 20.3.8 The **City** shall make payment only if, after considering all defenses presented by the **Contractor**, it determines that the payment is due and owing to the beneficiary making the demand.
- 20.3.9 No beneficiary shall be entitled to interest from the **City**, or to any other costs, including, but not limited to, attorneys' fees, except to the extent required by State Finance Law Section 137.

- 20.4 Upon the receipt by the **City** of a demand pursuant to this Article 20, the **City** may withhold from any payment otherwise due and owing to the **Contractor** under this **Contract** an amount sufficient to satisfy the demand.
 - 20.4.1 In the event the **City** determines that the demand is valid, the **City** shall notify the **Contractor** of such determination and the amount thereof and direct the **Contractor** to immediately pay such amount to the beneficiary. In the event the **Contractor**, within seven (7) **Days** of receipt of such notification from the **City**, fails to pay the beneficiary, such failure shall constitute an automatic and irrevocable assignment of payment by the **Contractor** to the beneficiary for the amount of the demand determined by the **City** to be valid. The **Contractor**, without further notification or other process, hereby gives its unconditional consent to such assignment of payment to the beneficiary and authorizes the **City**, on its behalf, to take all necessary actions to implement such assignment of payment, including without limitation the execution of any instrument or documentation necessary to effectuate such assignment.
 - 20.4.2In the event that the amount otherwise due and owing to the **Contractor** by the **City** is insufficient to satisfy such demand, the **City** may, at its option, require payment from the **Contractor** of an amount sufficient to cover such demand and exercise any other right to require or recover payment which the **City** may have under **Law** or **Contract**.
 - 20.4.3 In the event the **City** determines that the demand is invalid, any amount withheld pending the **City**'s review of such demand shall be paid to the **Contractor**; provided, however, no lien has been filed. In the event a claim or an action has been filed, the terms and conditions set forth in Article 23 shall apply. In the event a lien has been filed, the parties will be governed by the provisions of the Lien Law of the State of New York.
- 20.5 The provisions of this Article 20 shall not prevent the **City** and the **Contractor** from resolving disputes in accordance with the **PPB** Rules, where applicable.
- 20.6 In the event the **City** determines that the beneficiary is entitled to payment pursuant to this Article 20, such determination and any defenses and counterclaims raised by the **Contractor** shall be taken into account in evaluating the **Contractor's** performance.
- 20.7 Nothing in this Article 20 shall relieve the **Contractor** of the obligation to pay the claims of all persons with valid and lawful claims against the **Contractor** relating to the **Work**.
- 20.8 The **Contractor** shall not require any performance, payment or other bonds of any **Subcontractor** if this **Contract** does not require such bonds of the **Contractor**.
- 20.9 The payment guarantee made pursuant to this Article 20 shall be construed in a manner consistent with Section 137 of the State Finance Law and shall afford to persons furnishing labor or materials to the **Contractor** or its **Subcontractors** in the prosecution of the **Work** under this **Contract** all of the rights and remedies afforded to such persons by such section, including but not limited to, the right to commence an action against the **City** on the payment guarantee provided by this Article 20 within the one-year limitations period set forth in Section 137(4)(b).

ARTICLE 21. RETAINED PERCENTAGE

21.1 If this **Contract** requires one hundred (100%) percent performance and payment security, then as further security for the faithful performance of this **Contract**, the **Commissioner** shall deduct, and

retain until the substantial completion of the **Work**, five (5%) percent of the value of **Work** certified for payment in each partial payment voucher.

- 21.2 If this **Contract** does not require one hundred (100%) percent performance and payment security and if the price for which this **Contract** was awarded does not exceed one million (\$1,000,000) dollars, then as further security for the faithful performance of this **Contract**, the **Commissioner** shall deduct, and retain until the substantial completion of the **Work**, five (5%) percent of the value of **Work** certified for payment in each partial payment voucher.
- 21.3 If this **Contract** does not require one hundred (100%) percent performance and payment security and if the price for which this **Contract** was awarded exceeds one million (\$1,000,000) dollars, then as further security for the faithful performance of this **Contract**, the **Commissioner** shall deduct, and retain until the substantial completion of the **Work**, up to ten (10%) percent of the value of **Work** certified for payment in each partial payment voucher. The percentage to be retained is set forth in Schedule A of the General Conditions.

ARTICLE 22. INSURANCE

- 22.1 Types of Insurance: The **Contractor** shall procure and maintain the following types of insurance if, and as indicated, in Schedule A of the General Conditions (with the minimum limits and special conditions specified in Schedule A). Such insurance shall be maintained from the date the **Contractor** is required to provide Proof of Insurance pursuant to Article 22.3.1 through the date of completion of all required **Work** (including punch list work as certified in writing by the **Resident Engineer**), except for insurance required pursuant to Article 22.1.4, which may terminate upon **Substantial Completion** of the **Contract**. All insurance shall meet the requirements set forth in this Article 22. Wherever this Article requires that insurance coverage be "at least as broad" as a specified form (including all ISO forms), there is no obligation that the form itself be used, provided that the **Contractor** can demonstrate that the alternative form or endorsement contained in its policy provides coverage at least as broad as the specified form.
 - 22.1.1Commercial General Liability Insurance: The **Contractor** shall provide Commercial General Liability Insurance covering claims for property damage and/or bodily injury, including death, which may arise from any of the operations under this **Contract**. Coverage under this insurance shall be at least as broad as that provided by the latest edition of Insurance Services Office ("ISO") Form CG 0001. Such insurance shall be "occurrence" based rather than "claims-made" and include, without limitation, the following types of coverage: premises operations; products and completed operations; contractual liability (including the tort liability of another assumed in a contract); broad form property damage; independent contractors; explosion, collapse and underground (XCU); construction means and methods; and incidental malpractice. Such insurance shall contain a "per project" aggregate limit, as specified in Schedule A, that applies separately to operations under this **Contract**.
 - 22.1.1(a) Such Commercial General Liability Insurance shall name the **City** as an Additional Insured. Coverage for the City shall specifically include the **City's** officials and employees, be at least as broad as the latest edition of ISO Form CG 20 10 and provide completed operations coverage at least as broad as the latest edition of ISO Form CG 20 37.
 - 22.1.1(b) Such Commercial General Liability Insurance shall name all other entities designated as additional insureds in Schedule A but only for claims arising from the

Contractor's operations under this **Contract**, with coverage at least as broad as the latest edition of ISO Form CG 20 26.

- 22.1.1(c) If the **Work** requires a permit from the Department of Buildings pursuant to 1 RCNY Section 101-08, the **Contractor** shall provide Commercial General Liability Insurance with limits of at least those required by 1 RCNY section 101-08 or greater limits required by the Agency in accordance with Schedule A. If the **Work** does not require such a permit, the minimum limits shall be those provided for in Schedule A.
- 22.1.1(d) If any of the **Work** includes repair of a waterborne vessel owned by or to be delivered to the **City**, such Commercial General Liability shall include, or be endorsed to include, Ship Repairer's Legal Liability Coverage to protect against, without limitation, liability arising from navigation of such vessels prior to delivery to and acceptance by the **City**.
- 22.1.2 Workers' Compensation Insurance, Employers' Liability Insurance, and Disability Benefits Insurance: The **Contractor** shall provide, and shall cause its **Subcontractors** to provide, Workers Compensation Insurance, Employers' Liability Insurance, and Disability Benefits Insurance in accordance with the **Laws** of the State of New York on behalf of all employees providing services under this **Contract** (except for those employees, if any, for which the **Laws** require insurance only pursuant to Article 22.1.3).
- 22.1.3 United States Longshoremen's and Harbor Workers Act and/or Jones Act Insurance: If specified in Schedule A of the General Conditions or if required by **Law**, the **Contractor** shall provide insurance in accordance with the United States Longshoremen's and Harbor Workers Act and/or the Jones Act, on behalf of all qualifying employees providing services under this **Contract**.
- 22.1.4 Builders Risk Insurance: If specified in Schedule A of the General Conditions, the Contractor shall provide Builders Risk Insurance on a completed value form for the total value of the Work through Substantial Completion of the Work in its entirety. Such insurance shall be provided on an All Risk basis and include coverage, without limitation, for windstorm (including named windstorm), storm surge, flood and earth movement. Unless waived by the Commissioner, it shall include coverage for ordinance and law, demolition and increased costs of construction, debris removal, pollutant clean up and removal, and expediting costs. Such insurance shall cover, without limitation, (a) all buildings and/or structures involved in the Work, as well as temporary structures at the Site, and (b) any property that is intended to become a permanent part of such building or structure, whether such property is on the Site, in transit or in temporary storage. Policies shall name the Contractor as Named Insured and list the City as both an Additional Insured and a Loss Payee as its interest may appear.
 - 22.1.4(a) Policies of such insurance shall specify that, in the event a loss occurs at an occupied facility, occupancy of such facility is permitted without the consent of the issuing insurance company.
 - 22.1.4(b) Such insurance may be provided through an Installation Floater, at the **Contractor's** option, if it otherwise conforms with the requirements of this Article 22.1.4.
- 22.1.5 Commercial Automobile Liability Insurance: The **Contractor** shall provide Commercial Automobile Liability Insurance for liability arising out of ownership,

maintenance or use of any owned (if any), non-owned and hired vehicles to be used in connection with this **Contract**. Coverage shall be at least as broad as the latest edition of ISO Form CA0001. If vehicles are used for transporting hazardous materials, the Automobile Liability Insurance shall be endorsed to provide pollution liability broadened coverage for covered vehicles (endorsement CA 99 48) as well as proof of MCS 90.

22.1.6 Contractors Pollution Liability Insurance: If specified in Schedule A of the General Conditions, the **Contractor** shall maintain, or cause the **Subcontractor** doing such **Work** to maintain, Contractors Pollution Liability Insurance covering bodily injury and property damage. Such insurance shall provide coverage for actual, alleged or threatened emission, discharge, dispersal, seepage, release or escape of pollutants (including asbestos), including any loss, cost or expense incurred as a result of any cleanup of pollutants (including asbestos) or in the investigation, settlement or defense of any claim, action, or proceedings arising from the operations under this **Contract**. Such insurance shall be in the **Contractor's** name and list the **City** as an Additional Insured and any other entity specified in Schedule A. Coverage shall include, without limitation, (a) loss of use of damaged property or of property that has not been physically injured, (b) transportation, and (c) nonowned disposal sites.

22.1.6(a) Coverage for the **City** as Additional Insured shall specifically include the **City's** officials and employees and be at least as broad as provided to the **Contractor** for this **Project**.

22.1.6(b) If such insurance is written on a claims-made policy, such policy shall have a retroactive date on or before the effective date of this **Contract**, and continuous coverage shall be maintained, or an extended discovery period exercised, for a period of not less than three (3) years from the time the **Work** under this **Contract** is completed.

22.1.7 Marine Insurance:

22.1.7(a) Marine Protection and Indemnity Insurance: If specified in Schedule A of the General Conditions or if the **Contractor** engages in marine operations in the execution of any part of the **Work**, the **Contractor** shall maintain, or cause the **Subcontractor** doing such Work to maintain, Marine Protection and Indemnity Insurance with coverage at least as broad as Form SP-23. The insurance shall provide coverage for the **Contractor** or **Subcontractor** (whichever is doing this **Work**) and for the **City** (together with its officials and employees) and any other entity specified in Schedule A as an Additional Insured for bodily injury and property damage arising from marine operations under this **Contract**. Coverage shall include, without limitation, injury or death of crew members (if not fully provided through other insurance), removal of wreck, damage to piers, wharves and other fixed or floating objects and loss of or damage to any other vessel or craft, or to property on such other vessel or craft.

22.1.7(b) Hull and Machinery Insurance: If specified in Schedule A of the General Conditions or if the **Contractor** engages in marine operations in the execution of any part of the **Work**, the **Contractor** shall maintain, or cause the **Subcontractor** doing such **Work** to maintain, Hull and Machinery Insurance with coverage for the **Contractor** or **Subcontractor** (whichever is doing this Work) and for the **City** (together with its officials and employees) as Additional Insured at least as broad as the latest edition of American Institute Tug Form for all tugs used under this

Contract and Collision Liability at least as broad as the latest edition of American Institute Hull Clauses.

- 22.1.7(c) Marine Pollution Liability Insurance: If specified in Schedule A of the General Conditions or if the **Contractor** engages in marine operations in the execution of any part of the **Work**, the **Contractor** shall maintain, or cause the **Subcontractor** doing such Work to maintain, Marine Pollution Liability Insurance covering itself (or the Subcontractor doing such Work) as Named Insured and the **City** (together with its officials and employees) and any other entity specified in Schedule A as an Additional Insured. Coverage shall be at least as broad as that provided by the latest edition of Water Quality Insurance Syndicate Form and include, without limitation, liability arising from the discharge or substantial threat of a discharge of oil, or from the release or threatened release of a hazardous substance including injury to, or economic losses resulting from, the destruction of or damage to real property, personal property or natural resources.
- 22.1.8 The **Contractor** shall provide such other types of insurance, at such minimum limits and with such conditions, as are specified in Schedule A of the General Conditions.
- 22.2 General Requirements for Insurance Coverage and Policies:
 - 22.2.1 All required insurance policies shall be maintained with companies that may lawfully issue the required policy and have an A.M. Best rating of at least A-/VII or a Standard and Poor's rating of at least A, unless prior written approval is obtained from the **City** Corporation Counsel.
 - 22.2.2 The **Contractor** shall be solely responsible for the payment of all premiums for all required policies and all deductibles and self-insured retentions to which such policies are subject, whether or not the **City** is an insured under the policy.
 - 22.2.3 In his/her sole discretion, the **Commissioner** may, subject to the approval of the **Comptroller** and the **City** Corporation Counsel, accept Letters of Credit and/or custodial accounts in lieu of required insurance.
 - 22.2.4 The **City's** limits of coverage for all types of insurance required pursuant to Schedule A of the General Conditions shall be the greater of (i) the minimum limits set forth in Schedule A or (ii) the limits provided to the **Contractor** as Named Insured under all primary, excess, and umbrella policies of that type of coverage.
 - 22.2.5 The **Contractor** may satisfy its insurance obligations under this Article 22 through primary policies or a combination of primary and excess/umbrella policies, so long as all policies provide the scope of coverage required herein.
 - 22.2.6 Policies of insurance provided pursuant to this Article 22 shall be primary and non-contributing to any insurance or self-insurance maintained by the **City**.

22.3 Proof of Insurance:

22.3.1 For all types of insurance required by Article 22.1 and Schedule A, except for insurance required by Articles 22.1.4 and 22.1.7, the **Contractor** shall file proof of insurance in accordance with this Article 22.3 within ten (10) **Days** of award. For insurance

provided pursuant to Articles 22.1.4 and 22.1.7, proof shall be filed by a date specified by the **Commissioner** or ten (10) **Days** prior to the commencement of the portion of the **Work** covered by such policy, whichever is earlier.

- 22.3.2 For Workers' Compensation Insurance provided pursuant to Article 22.1.2, the **Contractor** shall submit one of the following forms: C-105.2 Certificate of Workers' Compensation Insurance; U-26.3 State Insurance Fund Certificate of Workers' Compensation Insurance; Request for WC/DB Exemption (Form CE-200); equivalent or successor forms used by the New York State Workers' Compensation Board; or other proof of insurance in a form acceptable to the **Commissioner**. For Disability Benefits Insurance provided pursuant to Article 22.1.2, the Contractor shall submit DB-120.1 Certificate Of Insurance Coverage Under The NYS Disability Benefits Law, Request for WC/DB Exemption (Form CE-200); equivalent or successor forms used by the New York State Workers' Compensation Board; or other proof of insurance in a form acceptable to the **Commissioner**. ACORD forms are not acceptable.
- 22.3.3 For policies provided pursuant to all of Article 22.1 other than Article 22.1.2, the **Contractor** shall submit one or more Certificates of Insurance on forms acceptable to the **Commissioner**. All such Certificates of Insurance shall certify (a) the issuance and effectiveness of such policies of insurance, each with the specified minimum limits (b) for insurance secured pursuant to Article 22.1.1 that the **City** and any other entity specified in Schedule A is an Additional Insured thereunder; (c) in the event insurance is required pursuant to Article 22.1.6 and/or Article 22.1.7, that the City is an Additional Insured thereunder; (d) the company code issued to the insurance company by the National Association of Insurance Commissioners (the NAIC number); and (e) the number assigned to the **Contract** by the **City**. All such Certificates of Insurance shall be accompanied by either a duly executed "Certification by Insurance Broker or Agent" in the form contained in Part III of Schedule A or copies of all policies referenced in such Certificate of Insurance as certified by an authorized representative of the issuing insurance carrier. If any policy is not available at the time of submission, certified binders may be submitted until such time as the policy is available, at which time a certified copy of the policy shall be submitted.
- 22.3.4 Documentation confirming renewals of insurance shall be submitted to the **Commissione**r prior to the expiration date of coverage of policies required under this **Contract**. Such proofs of insurance shall comply with the requirements of Articles 22.3.2 and 22.3.3.
- 22.3.5 The **Contractor** shall be obligated to provide the **City** with a copy of any policy of insurance provided pursuant to this Article 22 upon the demand for such policy by the **Commissioner** or the **City** Corporation Counsel.

22.4 Operations of the **Contractor**:

- 22.4.1 The **Contractor** shall not commence the **Work** unless and until all required certificates have been submitted to and accepted by the **Commissioner**. Acceptance by the **Commissioner** of a certificate does not excuse the **Contractor** from securing insurance consistent with all provisions of this Article 22 or of any liability arising from its failure to do so.
- 22.4.2 The **Contractor** shall be responsible for providing continuous insurance coverage in the manner, form, and limits required by this **Contract** and shall be authorized to perform **Work** only during the effective period of all required coverage.

- 22.4.3 In the event that any of the required insurance policies lapse, are revoked, suspended or otherwise terminated, for whatever cause, the **Contractor** shall immediately stop all **Work**, and shall not recommence **Work** until authorized in writing to do so by the **Commissioner**. Upon quitting the **Site**, except as otherwise directed by the **Commissioner**, the **Contractor** shall leave all plant, materials, equipment, tools, and supplies on the **Site**. **Contract** time shall continue to run during such periods and no extensions of time will be granted. The **Commissioner** may also declare the **Contractor** in default for failure to maintain required insurance.
- 22.4.4 In the event the **Contractor** receives notice, from an insurance company or other person, that any insurance policy required under this Article 22 shall be cancelled or terminated (or has been cancelled or terminated) for any reason, the **Contractor** shall immediately forward a copy of such notice to both the **Commissioner** and the New York City Comptroller, attn: Office of Contract Administration, Municipal Building, One Centre Street, room 1005, New York, New York 10007. Notwithstanding the foregoing, the **Contractor** shall ensure that there is no interruption in any of the insurance coverage required under this Article 22.
- 22.4.5 Where notice of loss, damage, occurrence, accident, claim or suit is required under an insurance policy maintained in accordance with this Article 22, the **Contractor** shall notify in writing all insurance carriers that issued potentially responsive policies of any such event relating to any operations under this **Contract** (including notice to Commercial General Liability insurance carriers for events relating to the **Contractor**'s own employees) no later than 20 days after such event. For any policy where the **City** is an Additional Insured, such notice shall expressly specify that "this notice is being given on behalf of the City of New York as Insured as well as the Named Insured." Such notice shall also contain the following information: the number of the insurance policy, the name of the named insured, the date and location of the damage, occurrence, or accident, and the identity of the persons or things injured, damaged or lost. The **Contractor** shall simultaneously send a copy of such notice to the City of New York c/o Insurance Claims Specialist, Affirmative Litigation Division, New York City Law Department, 100 Church Street, New York, New York 10007.
- 22.4.6 In the event of any loss, accident, claim, action, or other event that does or can give rise to a claim under any insurance policy required under this Article 22, the **Contractor** shall at all times fully cooperate with the **City** with regard to such potential or actual claim.
- 22.5 **Subcontractor** Insurance: In the event the **Contractor** requires any **Subcontractor** to procure insurance with regard to any operations under this **Contract** and requires such **Subcontractor** to name the **Contractor** as an **Additional Insured** thereunder, the **Contractor** shall ensure that the **Subcontractor** name the **City**, including its officials and employees, as an Additional Insured with coverage at least as broad as the most recent edition of ISO Form CG 20 26.
- 22.6 Wherever reference is made in Article 7 or this Article 22 to documents to be sent to the **Commissioner** (e.g., notices, filings, or submissions), such documents shall be sent to the address set forth in Schedule A of the General Conditions. In the event no address is set forth in Schedule A, such documents are to be sent to the **Commissioner's** address as provided elsewhere in this **Contract**.
- 22.7 Apart from damages or losses covered by insurance provided pursuant to Articles 22.1.2, 22.1.3, or 22.1.5, the **Contractor** waives all rights against the **City**, including its officials and employees, for any damages or losses that are covered under any insurance required under this Article 22 (whether or

not such insurance is actually procured or claims are paid thereunder) or any other insurance applicable to the operations of the **Contractor** and/or its employees, agents, or **Subcontractors**.

- 22.8 In the event the **Contractor** utilizes a self-insurance program to satisfy any of the requirements of this Article 22, the **Contractor** shall ensure that any such self-insurance program provides the **City** with all rights that would be provided by traditional insurance under this Article 22, including but not limited to the defense and indemnification obligations that insurers are required to undertake in liability policies.
- 22.9 Materiality/Non-Waiver: The **Contractor's** failure to secure policies in complete conformity with this Article 22, or to give an insurance company timely notice of any sort required in this **Contract** or to do anything else required by this Article 22 shall constitute a material breach of this **Contract**. Such breach shall not be waived or otherwise excused by any action or inaction by the **City** at any time.
- 22.10 Pursuant to General Municipal Law Section 108, this **Contract** shall be void and of no effect unless **Contractor** maintains Workers' Compensation Insurance for the term of this **Contract** to the extent required and in compliance with the New York State Workers' Compensation Law.
- 22.11 Other Remedies: Insurance coverage provided pursuant to this Article 22 or otherwise shall not relieve the **Contractor** of any liability under this **Contract**, nor shall it preclude the **City** from exercising any rights or taking such other actions available to it under any other provisions of this **Contract** or **Law**.

ARTICLE 23. MONEY RETAINED AGAINST CLAIMS

- 23.1 If any claim shall be made by any person or entity (including **Other Contractors** with the **City** on this **Project**) against the **City** or against the **Contractor** and the **City** for any of the following:
 - (a) An alleged loss, damage, injury, theft or vandalism of any of the kinds referred to in Articles 7 and 12, plus the reasonable costs of defending the **City**, which in the opinion of the **Comptroller** may not be paid by an insurance company (for any reason whatsoever); or
 - (b) An infringement of copyrights, patents or use of patented articles, tools, etc., as referred to in Article 57; or
 - (c) Damage claimed to have been caused directly or indirectly by the failure of the **Contractor** to perform the **Work** in strict accordance with this **Contract**,

the amount of such claim, or so much thereof as the **Comptroller** may deem necessary, may be withheld by the **Comptroller**, as security against such claim, from any money due hereunder. The **Comptroller**, in his/her discretion, may permit the **Contractor** to substitute other satisfactory security in lieu of the monies so withheld.

23.2 If an action on such claim is timely commenced and the liability of the **City**, or the **Contractor**, or both, shall have been established therein by a final judgment of a court of competent jurisdiction, or if such claim shall have been admitted by the **Contractor** to be valid, the **Comptroller** shall pay such judgment or admitted claim out of the monies retained by the **Comptroller** under the provisions of this Article 23, and return the balance, if any, without interest, to the **Contractor**.

ARTICLE 24. MAINTENANCE AND GUARANTY

- 24.1 The **Contractor** shall promptly repair, replace, restore or rebuild, as the **Commissioner** may determine, any finished **Work** in which defects of materials or workmanship may appear or to which damage may occur because of such defects, during the one (1) year period subsequent to the date of **Substantial Completion** (or use and occupancy in accordance with Article 16), except where other periods of maintenance and guaranty are provided for in Schedule A.
- 24.2 As security for the faithful performance of its obligations hereunder, the **Contractor**, upon filing its requisition for payment on **Substantial Completion**, shall deposit with the **Commissioner** a sum equal to one (1%) percent of the price (or the amount fixed in Schedule A of the General Conditions) in cash or certified check upon a state or national bank and trust company or a check of such bank and trust company signed by a duly authorized officer thereof and drawn to the order of the **Comptroller**, or obligations of the **City**, which the **Comptroller** may approve as of equal value with the sum so required.
- 24.3 In lieu of the above, the **Contractor** may make such security payment to the **City** by authorizing the **Commissioner** in writing to deduct the amount from the **Substantial Completion** payment which shall be deemed the deposit required above.
- 24.4 If the **Contractor** has faithfully performed all of its obligations hereunder the **Commissioner** shall so certify to the **Comptroller** within five (5) **Days** after the expiration of one (1) year from the date of **Substantial Completion** and acceptance of the **Work** or within thirty (30) **Days** after the expiration of the guarantee period fixed in the **Specifications**. The security payment shall be repaid to the **Contractor** without interest within thirty (30) **Days** after certification by the **Commissioner** to the **Comptroller** that the **Contractor** has faithfully performed all of its obligations hereunder.
- 24.5 Notice by the **Commissioner** to the **Contractor** to repair, replace, rebuild or restore such defective or damaged **Work** shall be timely, pursuant to this article, if given not later than ten (10) **Days** subsequent to the expiration of the one (1) year period or other periods provided for herein.
- 24.6 If the **Contractor** shall fail to repair, replace, rebuild or restore such defective or damaged **Work** promptly after receiving such notice, the **Commissioner** shall have the right to have the **Work** done by others in the same manner as provided for in the completion of a defaulted **Contract**, under Article 51.
- 24.7 If the security payment so deposited is insufficient to cover the cost of such **Work**, the **Contractor** shall be liable to pay such deficiency on demand by the **Commissioner**.
- 24.8 The **Engineer's** certificate setting forth the fair and reasonable cost of repairing, replacing, rebuilding or restoring any damaged or defective **Work** when performed by one other than the **Contractor**, shall be binding and conclusive upon the **Contractor** as to the amount thereof.
- 24.9 The **Contractor** shall obtain all manufacturers' warranties and guaranties of all equipment and materials required by this **Contract** in the name of the **City** and shall deliver same to the **Commissioner**. All of the **City**'s rights and title and interest in and to said manufacturers' warranties and guaranties may be assigned by the **City** to any subsequent purchasers of such equipment and materials or lessees of the premises into which the equipment and materials have been installed.

CHAPTER VI: CHANGES, EXTRA WORK, AND DOCUMENTATION OF CLAIM

ARTICLE 25. CHANGES

- 25.1 Changes may be made to this **Contract** only as duly authorized in writing by the **Commissioner** in accordance with the **Law** and this **Contract**. All such changes, modifications, and amendments will become a part of the **Contract**. **Work** so ordered shall be performed by the **Contractor**.
- 25.2 **Contract** changes will be made only for **Work** necessary to complete the **Work** included in the original scope of the **Contract** and/or for non-material changes to the scope of the **Contract**. Changes are not permitted for any material alteration in the scope of **Work** in the **Contract**.
- 25.3 The **Contractor** shall be entitled to a price adjustment for **Extra Work** performed pursuant to a written change order. Adjustments to price shall be computed in one or more of the following ways:
 - 25.3.1 By applicable unit prices specified in the **Contract**; and/or
 - 25.3.2 By agreement of a fixed price; and/or
 - 25.3.3 By time and material records; and/or
 - 25.3.4 In any other manner approved by the **CCPO**.
- 25.4 All payments for change orders are subject to pre-audit by the **Engineering Audit Officer** and may be post-audited by the **Comptroller** and/or the **Agency**.

ARTICLE 26. METHODS OF PAYMENT FOR OVERRUNS AND EXTRA WORK

- 26.1 Overrun of Unit Price Item: An overrun is any quantity of a unit price item which the **Contractor** is directed to provide which is in excess of one hundred twenty-five (125%) percent of the estimated quantity for that item set forth in the bid schedule.
 - 26.1.1For any unit price item, the **Contractor** will be paid at the unit price bid for any quantity up to one hundred twenty-five (125%) percent of the estimated quantity for that item set forth in the bid schedule. If during the progress of the **Work**, the actual quantity of any unit price item required to complete the **Work** approaches the estimated quantity for that item, and for any reason it appears that the actual quantity of any unit price item necessary to complete the **Work** will exceed the estimated quantity for that item by twenty-five (25%) percent, the **Contractor** shall immediately notify the **Engineer** of such anticipated overrun. The **Contractor** shall not be compensated for any quantity of a unit price item provided which is in excess of one hundred twenty-five (125%) percent of the estimated quantity for that item set forth in the bid schedule without written authorization from the **Engineer**.
 - 26.1.2 If the actual quantity of any unit price item necessary to complete the **Work** will exceed one hundred twenty five (125%) percent of the estimated quantity for that item set forth in the bid schedule, the **City** reserves the right and the **Contractor** agrees to negotiate a new unit price for such item. In no event shall such negotiated new unit price exceed the unit bid price. If the **City** and **Contractor** cannot agree on a new unit price, then the **City** shall order the **Contractor** and the **Contractor** agrees to provide additional quantities of

the item on the basis of time and material records for the actual and reasonable cost as determined under Article 26.2, but in no event at a unit price exceeding the unit price bid.

- 26.2 **Extra Work:** For **Extra Work** where payment is by agreement on a fixed price in accordance with Article 25.3.2, the price to be paid for such **Extra Work** shall be based on the fair and reasonable estimated cost of the items set forth below. For **Extra Work** where payment is based on time and material records in accordance with Article 25.3.3, the price to be paid for such **Extra Work** shall be the actual and reasonable cost of the items set forth below, calculated in accordance with the formula specified therein, if any.
 - 26.2.1 Necessary materials (including transportation to the **Site**); plus
 - 26.2.2 Necessary direct labor, including payroll taxes (subject to statutory wage caps) and supplemental benefits; plus
 - 26.2.3 Sales and personal property taxes, if any, required to be paid on materials not incorporated into such **Extra Work**; plus
 - 26.2.4 Reasonable rental value of Contractor-owned (or Subcontractor-owned, as applicable), necessary plant and equipment other than **Small Tools**, plus fuel/energy costs. Except for fuel costs for pick-up trucks which shall be reimbursed based on a consumption of five (5) gallons per shift, fuel costs shall be reimbursed based on actual costs or, in the absence of auditable documentation, the following fuel consumption formula per operating hour: (.035) x (HP rating) x (Fuel cost/gallon). Reasonable rental value is defined as the lower of either seventy-five percent of the monthly prorated rental rates established in "The AED Green Book, Rental Rates and Specifications for Construction Equipment" published by Equipment Watch (the "Green Book"), or seventy-five percent of the monthly prorated rental rates established in the "Rental Rate Blue Book for Construction Equipment" published by Equipment Watch (the "Blue Book") (the applicable Blue Book rate being for rental only without the addition of any operational costs listed in the Blue Book). The reasonable rental value is deemed to be inclusive of all operating costs except for fuel/energy consumption and equipment operator's wages/costs. For multiple shift utilization, reimbursement shall be calculated as follows: first shift shall be seventy-five (75%) percent of such rental rates; second shift shall be sixty (60%) percent of the first shift rate; and third shift shall be forty (40%) percent of the first shift rate. Equipment on standby shall be reimbursed at one-third (1/3) the prorated monthly rental rate. Contractor-owned (or Subcontractor-owned, as applicable) equipment includes equipment from rental companies affiliated with or controlled by the Contractor (or Subcontractor, as applicable), as determined by the Commissioner. In establishing cost reimbursement for non-operating Contractor-owned (or Subcontractor-owned, as applicable) equipment (scaffolding, sheeting systems, road plates, etc.), the City may restrict reimbursement to a purchase-salvage/life cycle basis if less than the computed rental costs; plus
 - 26.2.5 Necessary installation and dismantling of such plant and equipment, including transportation to and from the **Site**, if any, provided that, in the case of non-**Contractor**-owned (or non-**Subcontractor**-owned, as applicable) equipment rented from a third party, the cost of installation and dismantling are not allowable if such costs are included in the rental rate; plus
 - 26.2.6 Necessary fees charged by governmental entities; plus

- 26.2.7 Necessary construction-related service fees charged by non-governmental entities, such as landfill tipping fees; plus
- 26.2.8 Reasonable rental costs of non-**Contractor**-owned (or non-**Subcontractor**-owned, as applicable) necessary plant and equipment other than **Small Tools**, plus fuel/energy costs. Except for fuel costs for pick-up trucks which shall be reimbursed based on a consumption of five (5) gallons per shift, fuel costs shall be reimbursed based on actual costs or, in the absence of auditable documentation, the following fuel consumption formula per hour of operation: (.035) x (HP rating) x (Fuel cost/gallon). In lieu of renting, the **City** reserves the right to direct the purchase of non-operating equipment (scaffolding, sheeting systems, road plates, etc.), with payment on a purchase-salvage/life cycle basis, if less than the projected rental costs; plus
- 26.2.9 Workers' Compensation Insurance, and any insurance coverage expressly required by the **City** for the performance of the **Extra Work** which is different than the types of insurance required by Article 22 and Schedule A of the General Conditions. The cost of Workers' Compensation Insurance is subject to applicable payroll limitation caps and shall be based upon the carrier's Manual Rate for such insurance derived from the applicable class Loss Cost ("LC") and carrier's Lost Cost Multiplier ("LCM") approved by the New York State Department of Financial Services, and with the exception of experience rating, rate modifiers as promulgated by the New York Compensation Insurance Rating Board ("NYCIRB"); plus
- 26.2.10 Additional costs incurred as a result of the **Extra Work** for performance and payment bonds; plus
- 26.2.11 Twelve percent (12%) percent of the total of items in Articles 26.2.1 through 26.2.5 as compensation for overhead, except that no percentage for overhead will be allowed on **Payroll Taxes** or on the premium portion of overtime pay or on sales and personal property taxes. Overhead shall include without limitation, all costs and expenses in connection with administration, management superintendence, small tools, and insurance required by Schedule A of the General Conditions other than Workers' Compensation Insurance; plus
- 26.2.12 Ten (10%) percent of the total of items in Articles 26.2.1 through 26.2.5, plus the items in Article 26.2.11, as compensation for profit, except that no percentage for profit will be allowed on **Payroll Taxes** or on the premium portion of overtime pay or on sales and personal property taxes; plus
- 26.2.13 Five (5%) percent of the total of items in Articles 26.2.6 through 26.2.10 as compensation for overhead and profit.
- 26.3 Where the **Extra Work** is performed in whole or in part by other than the **Contractor's** own forces pursuant to Article 26.2, the **Contractor** shall be paid, subject to pre-audit by the **Engineering Audit Officer**, the cost of such **Work** computed in accordance with Article 26.2 above, plus an additional allowance of five (5%) percent to cover the **Contractor's** overhead and profit.
- 26.4 Where a change is ordered, involving both **Extra Work** and omitted or reduced **Contract Work**, the **Contract** price shall be adjusted, subject to pre-audit by the **EAO**, in an amount based on the difference between the cost of such **Extra Work** and of the omitted or reduced **Work**.
- 26.5 Where the **Contractor** and the **Commissioner** can agree upon a fixed price for **Extra Work** in accordance with Article 25.3.2 or another method of payment for **Extra Work** in accordance with

Article 25.3.4, or for **Extra Work** ordered in connection with omitted **Work**, such method, subject to pre-audit by the **EAO**, may, at the option of the **Commissioner**, be substituted for the cost plus a percentage method provided in Article 26.2; provided, however, that if the **Extra Work** is performed by a **Subcontractor**, the **Contractor** shall not be entitled to receive more than an additional allowance of five (5%) percent for overhead and profit over the cost of such **Subcontractor's Work** as computed in accordance with Article 26.2.

ARTICLE 27. RESOLUTION OF DISPUTES

- 27.1 All disputes between the **City** and the **Contractor** of the kind delineated in this Article 27.1 that arise under, or by virtue of, this **Contract** shall be finally resolved in accordance with the provisions of this Article 27 and the **PPB** Rules. This procedure for resolving all disputes of the kind delineated herein shall be the exclusive means of resolving any such disputes.
 - 27.1.1 This Article 27 shall not apply to disputes concerning matters dealt with in other sections of the **PPB** Rules, or to disputes involving patents, copyrights, trademarks, or trade secrets (as interpreted by the courts of New York State) relating to proprietary rights in computer software.
 - 27.1.2 This Article 27 shall apply only to disputes about the scope of **Work** delineated by the **Contract**, the interpretation of **Contract** documents, the amount to be paid for **Extra Work** or disputed work performed in connection with the **Contract**, the conformity of the **Contractor's Work** to the **Contract**, and the acceptability and quality of the **Contractor's Work**; such disputes arise when the **Engineer**, **Resident Engineer**, **Engineering Audit Officer**, or other designee of the **Commissioner** makes a determination with which the **Contractor** disagrees.
- 27.2 All determinations required by this Article 27 shall be made in writing clearly stated, with a reasoned explanation for the determination based on the information and evidence presented to the party making the determination. Failure to make such determination within the time required by this Article 27 shall be deemed a non-determination without prejudice that will allow application to the next level.
- 27.3 During such time as any dispute is being presented, heard, and considered pursuant to this Article 27, the **Contract** terms shall remain in force and the **Contractor** shall continue to perform **Work** as directed by the **ACCO** or the **Engineer**. Failure of the **Contractor** to continue **Work** as directed shall constitute a waiver by the **Contractor** of its claim.

27.4 Presentation of Disputes to **Commissioner**.

Notice of Dispute and Agency Response. The **Contractor** shall present its dispute in writing ("Notice of Dispute") to the **Commissioner** within thirty (30) Days of receiving written notice of the determination or action that is the subject of the dispute. This notice requirement shall not be read to replace any other notice requirements contained in the **Contract**. The Notice of Dispute shall include all the facts, evidence, documents, or other basis upon which the **Contractor** relies in support of its position, as well as a detailed computation demonstrating how any amount of money claimed by the **Contractor** in the dispute was arrived at. Within thirty (30) Days after receipt of the detailed written submission comprising the complete Notice of Dispute, the **Engineer**, **Resident Engineer**, **Engineering Audit Officer**, or other designee of the **Commissioner** shall submit to the **Commissioner** all materials he or she deems pertinent to the dispute. Following initial submissions to the **Commissioner**, either party may demand of the other the production of any document or other material the demanding party believes may be relevant to the dispute. The requested party shall produce all relevant materials that are not otherwise

protected by a legal privilege recognized by the courts of New York State. Any question of relevancy shall be determined by the **Commissioner** whose decision shall be final. Willful failure of the **Contractor** to produce any requested material whose relevancy the **Contractor** has not disputed, or whose relevancy has been affirmatively determined, shall constitute a waiver by the **Contractor** of its claim.

- 27.4.1 **Commissioner** Inquiry. The **Commissioner** shall examine the material and may, in his or her discretion, convene an informal conference with the **Contractor**, the **ACCO**, and the **Engineer**, **Resident Engineer**, **Engineering Audit Officer**, or other designee of the **Commissioner** to resolve the issue by mutual consent prior to reaching a determination. The **Commissioner** may seek such technical or other expertise as he or she shall deem appropriate, including the use of neutral mediators, and require any such additional material from either or both parties as he or she deems fit. The **Commissioner's** ability to render, and the effect of, a decision hereunder shall not be impaired by any negotiations in connection with the dispute presented, whether or not the **Commissioner** participated therein. The **Commissioner** may or, at the request of any party to the dispute, shall compel the participation of any **Other Contractor** with a contract related to the **Work** of this **Contract**, and that **Contractor** shall be bound by the decision of the **Commissioner**. Any **Other Contractor** thus brought into the dispute resolution proceeding shall have the same rights and obligations under this Article 27 as the **Contractor** initiating the dispute.
- 27.4.2 **Commissioner** Determination. Within thirty (30) **Days** after the receipt of all materials and information, or such longer time as may be agreed to by the parties, the **Commissioner** shall make his or her determination and shall deliver or send a copy of such determination to the **Contractor**, the **ACCO**, and **Engineer**, **Resident Engineer**, **Engineering Audit Officer**, or other designee of the **Commissioner**, as applicable, together with a statement concerning how the decision may be appealed.
- 27.4.3 Finality of **Commissioner's** Decision. The **Commissioner's** decision shall be final and binding on all parties, unless presented to the Contract Dispute Resolution Board pursuant to this Article 27. The **City** may not take a petition to the Contract Dispute Resolution Board. However, should the **Contractor** take such a petition, the **City** may seek, and the Contract Dispute Resolution Board may render, a determination less favorable to the **Contractor** and more favorable to the **City** than the decision of the **Commissioner**.
- 27.5 Presentation of Dispute to the **Comptroller**. Before any dispute may be brought by the **Contractor** to the Contract Dispute Resolution Board, the **Contractor** must first present its claim to the **Comptroller** for his or her review, investigation, and possible adjustment.
 - 27.5.1 Time, Form, and Content of Notice. Within thirty (30) **Days** of its receipt of a decision by the **Commissioner**, the **Contractor** shall submit to the **Comptroller** and to the **Commissioner** a Notice of Claim regarding its dispute with the **Agency**. The Notice of Claim shall consist of (i) a brief written statement of the substance of the dispute, the amount of money, if any, claimed and the reason(s) the **Contractor** contends the dispute was wrongly decided by the **Commissioner**; (ii) a copy of the written decision of the **Commissioner**; and (iii) a copy of all materials submitted by the **Contractor** to the **Agency**, including the Notice of Dispute. The **Contractor** may not present to the **Comptroller** any material not presented to the **Commissioner**, except at the request of the **Comptroller**.

- 27.5.2 Response. Within thirty (30) **Days** of receipt of the Notice of Claim, the **Agency** shall make available to the **Comptroller** a copy of all material submitted by the **Agency** to the **Commissioner** in connection with the dispute. The **Agency** may not present to the **Comptroller** any material not presented to the **Commissioner** except at the request of the **Comptroller**.
- 27.5.3 Comptroller Investigation. The Comptroller may investigate the claim in dispute and, in the course of such investigation, may exercise all powers provided in Sections 7-201 and 7-203 of the Administrative Code. In addition, the Comptroller may demand of either party, and such party shall provide, whatever additional material the Comptroller deems pertinent to the claim, including original business records of the Contractor. Willful failure of the Contractor to produce within fifteen (15) Days any material requested by the Comptroller shall constitute a waiver by the Contractor of its claim. The Comptroller may also schedule an informal conference to be attended by the Contractor, Agency representatives, and any other personnel desired by the Comptroller.
- 27.5.4 Opportunity of **Comptroller** to Compromise or Adjust Claim. The **Comptroller** shall have forty-five (45) **Days** from his or her receipt of all materials referred to in Article 27.5.3 to investigate the disputed claim. The period for investigation and compromise may be further extended by agreement between the **Contractor** and the **Comptroller**, to a maximum of ninety (90) **Days** from the **Comptroller's** receipt of all materials. The **Contractor** may not present its petition to the Contract Dispute Resolution Board until the period for investigation and compromise delineated in this Article 27.5.4 has expired. In compromising or adjusting any claim hereunder, the **Comptroller** may not revise or disregard the terms of the **Contract** between the parties.
- 27.6 Contract Dispute Resolution Board. There shall be a Contract Dispute Resolution Board composed of:
 - 27.6.1 The chief administrative law judge of the Office of Administrative Trials and Hearings (OATH) or his/her designated OATH administrative law judge, who shall act as chairperson, and may adopt operational procedures and issue such orders consistent with this Article 27 as may be necessary in the execution of the Contract Dispute Resolution Board's functions, including, but not limited to, granting extensions of time to present or respond to submissions;
 - 27.6.2 The **CCPO** or his/her designee; any designee shall have the requisite background to consider and resolve the merits of the dispute and shall not have participated personally and substantially in the particular matter that is the subject of the dispute or report to anyone who so participated; and
 - 27.6.3 A person with appropriate expertise who is not an employee of the **City**. This person shall be selected by the presiding administrative law judge from a prequalified panel of individuals, established and administered by OATH with appropriate background to act as decision-makers in a dispute. Such individual may not have a contract or dispute with the **City** or be an officer or employee of any company or organization that does, or regularly represents persons, companies, or organizations having disputes with the **City**.
- 27.7 Petition to the Contract Dispute Resolution Board. In the event the claim has not been settled or adjusted by the **Comptroller** within the period provided in this Article 27, the **Contractor**,

within thirty (30) **Days** thereafter, may petition the Contract Dispute Resolution Board to review the **Commissioner's** determination.

- 27.7.1 Form and Content of Petition by **Contractor**. The **Contractor** shall present its dispute to the Contract Dispute Resolution Board in the form of a petition, which shall include (i) a brief written statement of the substance of the dispute, the amount of money, if any, claimed, and the reason(s) the **Contractor** contends the dispute was wrongly decided by the **Commissioner**; (ii) a copy of the written Decision of the **Commissioner**, (iii) copies of all materials submitted by the **Contractor** to the Agency; (iv) a copy of the written decision of the **Comptroller**, if any, and (v) copies of all correspondence with, or written material submitted by the **Contractor**, to the **Comptroller**. The **Contractor** shall concurrently submit four (4) complete sets of the Petition: one set to the **City** Corporation Counsel (Attn: Commercial and Real Estate Litigation Division) and three (3) sets to the Contract Dispute Resolution Board at OATH's offices with proof of service on the **City** Corporation Counsel. In addition, the **Contractor** shall submit a copy of the written statement of the substance of the dispute, cited in (i) above, to both the **Commissioner** and the **Comptroller**.
- 27.7.2 **Agency** Response. Within thirty (30) **Days** of its receipt of the Petition by the **City** Corporation Counsel, the **Agency** shall respond to the brief written statement of the **Contractor** and make available to the Contract Dispute Resolution Board all material it submitted to the **Commissioner** and **Comptroller**. Three (3) complete copies of the **Agency** response shall be provided to the Contract Dispute Resolution Board and one to the **Contractor**. Extensions of time for submittal of the **Agency** response shall be given as necessary upon a showing of good cause or, upon consent of the parties, for an initial period of up to thirty (30) Days.
- 27.7.3 Further Proceedings. The Contract Dispute Resolution Board shall permit the Contractor to present its case by submission of memoranda, briefs, and oral argument. The Contract Dispute Resolution Board shall also permit the Agency to present its case in response to the Contractor by submission of memoranda, briefs, and oral argument. If requested by the City Corporation Counsel, the Comptroller shall provide reasonable assistance in the preparation of the Agency's case. Neither the Contractor nor the Agency may support its case with any documentation or other material that was not considered by the Comptroller, unless requested by the Contract Dispute Resolution Board. The Contract Dispute Resolution Board, in its discretion, may seek such technical or other expert advice as it shall deem appropriate and may seek, on its own or upon application of a party, any such additional material from any party as it deems fit. The Contract Dispute Resolution Board, in its discretion, may combine more than one dispute between the parties for concurrent resolution.
- 27.7.4 Contract Dispute Resolution Board Determination. Within forty-five (45) **Days** of the conclusion of all written submissions and oral arguments, the Contract Dispute Resolution Board shall render a written decision resolving the dispute. In an unusually complex case, the Contract Dispute Resolution Board may render its decision in a longer period, not to exceed ninety (90) **Days**, and shall so advise the parties at the commencement of this period. The Contract Dispute Resolution Board's decision must be consistent with the terms of the **Contract**. Decisions of the Contract Dispute Resolution Board shall only resolve matters before the Contract Dispute Resolution Board and shall not have precedential effect with respect to matters not before the Contract Dispute Resolution Board.

- 27.7.5 Notification of Contract Dispute Resolution Board Decision. The Contract Dispute Resolution Board shall send a copy of its decision to the **Contractor**, the **ACCO**, the Engineer, the **Comptroller**, the **City** Corporation Counsel, the CCPO, and the **PPB**. A decision in favor of the **Contractor** shall be subject to the prompt payment provisions of the **PPB** Rules. The Required Payment Date shall be thirty (30) Days after the date the parties are formally notified of the Contract Dispute Resolution Board's decision.
- 27.7.6 Finality of Contract Dispute Resolution Board Decision. The Contract Dispute Resolution Board's decision shall be final and binding on all parties. Any party may seek review of the Contract Dispute Resolution Board's decision solely in the form of a challenge, filed within four (4) months of the date of the Contract Dispute Resolution Board's decision, in a court of competent jurisdiction of the State of New York, County of New York pursuant to Article 78 of the Civil Practice Law and Rules. Such review by the court shall be limited to the question of whether or not the Contract Dispute Resolution Board's decision was made in violation of lawful procedure, was affected by an error of Law, or was arbitrary and capricious or an abuse of discretion. No evidence or information shall be introduced or relied upon in such proceeding that was not presented to the Contract Dispute Resolution Board in accordance with this Article 27.
- Any termination, cancellation, or alleged breach of the **Contract** prior to or during the pendency of any proceedings pursuant to this Article 27 shall not affect or impair the ability of the **Commissioner** or Contract Dispute Resolution Board to make a binding and final decision pursuant to this Article 27.

ARTICLE 28. RECORD KEEPING FOR EXTRA OR DISPUTED WORK OR WORK ON A TIME & MATERIALS BASIS

- 28.1 While the **Contractor** or any of its **Subcontractors** is performing **Work** on a time and material basis or **Extra Work** on a time and material basis ordered by the **Commissioner** under Article 25, or where the **Contractor** believes that it or any of its **Subcontractors** is performing **Extra Work** but a final determination by **Agency** has not been made, or the **Contractor** or any of its **Subcontractors** is performing disputed **Work** (whether on or off the **Site**), or complying with a determination or order under protest in accordance with Articles 11, 27, and 30, in each such case the **Contractor** shall furnish the **Resident Engineer** daily with three (3) copies of written statements signed by the **Contractor's** representative at the **Site** showing:
 - 28.1.1 The name, trade, and number of each worker employed on such **Work** or engaged in complying with such determination or order, the number of hours employed, and the character of the **Work** each is doing; and
 - 28.1.2 The nature and quantity of any materials, plant and equipment furnished or used in connection with the performance of such **Work** or compliance with such determination or order, and from whom purchased or rented.
- 28.2 A copy of such statement will be countersigned by the **Resident Engineer**, noting thereon any items not agreed to or questioned, and will be returned to the **Contractor** within two (2) **Days** after submission.
- 28.3 The **Contractor** and its **Subcontractors**, when required by the **Commissioner**, or the **Comptroller**, shall also produce for inspection, at the office of the **Contractor** or **Subcontractor**, any and all of its books, bid documents, financial statements, vouchers, records, daily job diaries and reports,

and cancelled checks, and any other documents relating to showing the nature and quantity of the labor, materials, plant and equipment actually used in the performance of such **Work**, or in complying with such determination or order, and the amounts expended therefor, and shall permit the **Commissioner** and the **Comptroller** to make such extracts therefrom, or copies thereof, as they or either of them may desire.

- 28.4 In connection with the examination provided for herein, the **Commissioner**, upon demand therefor, will produce for inspection by the **Contractor** such records as the **Agency** may have with respect to such **Extra Work** or disputed **Work** performed under protest pursuant to order of the **Commissioner**, except those records and reports which may have been prepared for the purpose of determining the accuracy and validity of the **Contractor's** claim.
- 28.5 Failure to comply strictly with these requirements shall constitute a waiver of any claim for extra compensation or damages on account of the performance of such **Work** or compliance with such determination or order.

ARTICLE 29. OMITTED WORK

- 29.1 If any **Contract Work** in a lump sum **Contract**, or if any part of a lump sum item in a unit price, lump sum, or percentage-bid **Contract** is omitted by the **Commissioner** pursuant to Article 33, the **Contract** price, subject to audit by the EAO, shall be reduced by a pro rata portion of the lump sum bid amount based upon the percent of **Work** omitted subject to Article 29.4. For the purpose of determining the pro rata portion of the lump sum bid amount, the bid breakdown submitted in accordance with Article 41 shall be considered, but shall not be the determining factor.
- 29.2 If the whole of a lump sum item or units of any other item is so omitted by the **Commissioner** in a unit price, lump sum, or percentage-bid **Contract**, then no payment will be made therefor except as provided in Article 29.4.
- 29.3 For units that have been ordered but are only partially completed, the unit price shall be reduced by a pro rata portion of the unit price bid based upon the percentage of **Work** omitted subject to Article 29.4.
- 29.4 In the event the **Contractor**, with respect to any omitted **Work**, has purchased any non-cancelable material and/or equipment that is not capable of use except in the performance of this **Contract** and has been specifically fabricated for the sole purpose of this **Contract**, but not yet incorporated into the **Work**, the **Contractor** shall be paid for such material and/or equipment in accordance with Article 64.2.1(b); provided, however, such payment is contingent upon the **Contractor's** delivery of such material and/or equipment in acceptable condition to a location designated by the **City**.
- 29.5 The **Contractor** agrees to make no claim for damages or for loss of overhead and profit with regard to any omitted **Work**.

ARTICLE 30. NOTICE AND DOCUMENTATION OF COSTS AND DAMAGES; PRODUCTION OF FINANCIAL RECORDS

30.1 If the **Contractor** shall claim to be sustaining damages by reason of any act or omission of the **City** or its agents, it shall submit to the **Commissioner** within forty-five (45) **Days** from the time such damages are first incurred, and every thirty (30) **Days** thereafter to the extent additional damages are being incurred for the same condition, verified statements of the details and the amounts of such

damages, together with documentary evidence of such damages. The **Contractor** may submit any of the above statements within such additional time as may be granted by the **Commissioner** in writing upon written request therefor. Failure of the **Commissioner** to respond in writing to a written request for additional time within thirty (30) **Days** shall be deemed a denial of the request. On failure of the **Contractor** to strictly comply with the foregoing provisions, such claims shall be deemed waived and no right to recover on such claims shall exist. Damages that the **Contractor** may claim in any action or dispute resolution procedure arising under or by reason of this **Contract** shall not be different from or in excess of the statements and documentation made pursuant to this Article 30. This Article 30.1 does not apply to claims submitted to the **Commissioner** pursuant to Article 11 or to claims disputing a determination under Article 27.

- 30.2 In addition to the foregoing statements, the **Contractor** shall, upon notice from the **Commissioner**, produce for examination at the **Contractor's** office, by the **Engineer**, **Architect** or **Project Manager**, all of its books of account, bills, invoices, payrolls, subcontracts, time books, daily reports, bank deposit books, bank statements, check books, and cancelled checks, showing all of its acts and transactions in connection with or relating to or arising by reason of this **Contract**, and submit itself and persons in its employment, for examination under oath by any person designated by the **Commissioner** or **Comptroller** to investigate claims made or disputes against the **City** under this **Contract**. At such examination, a duly authorized representative of the **Contractor** may be present.
- 30.3 In addition to the statements required under Article 28 and this Article 30, the **Contractor** and/or its **Subcontractor** shall, within thirty (30) **Days** upon notice from the **Commissioner** or **Comptroller**, produce for examination at the **Contractor's** and/or **Subcontractor's** office, by a representative of either the **Commissioner** or **Comptroller**, all of its books of account, bid documents, financial statements, accountant workpapers, bills, invoices, payrolls, subcontracts, time books, daily reports, bank deposit books, bank statements, check books, and cancelled checks, showing all of its acts and transactions in connection with or relating to or arising by reason of this **Contract**. Further, the **Contractor** and/or its **Subcontractor** shall submit any person in its employment, for examination under oath by any person designated by the **Commissioner** or **Comptroller** to investigate claims made or disputes against the **City** under this **Contract**. At such examination, a duly authorized representative of the **Contractor** may be present.
- 30.4 Unless the information and examination required under Article 30.3 is provided by the **Contractor** and/or its **Subcontractor** upon thirty (30) **Days'** notice from the **Commissioner** or **Comptroller**, or upon the **Commissioner's** or **Comptroller's** written authorization to extend the time to comply, the **City** shall be released from all claims arising under, relating to or by reason of this **Contract**, except for sums certified by the **Commissioner** to be due under the provisions of this **Contract**. It is further stipulated and agreed that no person has the power to waive any of the foregoing provisions and that in any action or dispute resolution procedure against the **City** to recover any sum in excess of the sums certified by the **Commissioner** to be due under or by reason of this **Contract**, the **Contractor** must allege in its complaint and prove, at trial or during such dispute resolution procedure, compliance with the provisions of this Article 30.
- 30.5 In addition, after the commencement of any action or dispute resolution procedure by the **Contractor** arising under or by reason of this **Contract**, the **City** shall have the right to require the **Contractor** to produce for examination under oath, up until the trial of the action or hearing before the Contract Dispute Resolution Board, the books and documents described in Article 30.3 and submit itself and all persons in its employ for examination under oath. If this Article 30 is not complied with as required, then the **Contractor** hereby consents to the dismissal of the action or dispute resolution procedure.

CHAPTER VII: POWERS OF THE RESIDENT ENGINEER, THE ENGINEER OR ARCHITECT AND THE COMMISSIONER

ARTICLE 31. THE RESIDENT ENGINEER

31.1 The **Resident Engineer** shall have the power to inspect, supervise, and control the performance of the **Work**, subject to review by the **Commissioner**. The **Resident Engineer** shall not, however, have the power to issue an **Extra Work** order, except as specifically designated in writing by the **Commissioner**.

ARTICLE 32. THE ENGINEER OR ARCHITECT OR PROJECT MANAGER

- 32.1 The **Engineer** or **Architect** or **Project Manager**, in addition to those matters elsewhere herein delegated to the **Engineer** and expressly made subject to his/her determination, direction or approval, shall have the power, subject to review by the **Commissioner**:
 - 32.1.1 To determine the amount, quality, and location of the **Work** to be paid for hereunder; and
 - 32.1.2 To determine all questions in relation to the **Work**, to interpret the **Contract Drawings**, **Specifications**, and **Addenda**, and to resolve all patent inconsistencies or ambiguities therein; and
 - 32.1.3 To determine how the **Work** of this **Contract** shall be coordinated with **Work** of **Other Contractors** engaged simultaneously on this **Project**, including the power to suspend any part of the **Work**, but not the whole thereof; and
 - 32.1.4 To make minor changes in the **Work** as he/she deems necessary, provided such changes do not result in a net change in the cost to the **City** or to the **Contractor** of the **Work** to be done under the **Contract**; and
 - 32.1.5 To amplify the **Contract Drawings**, add explanatory information and furnish additional **Specifications** and drawings, consistent with this **Contract**.
- 32.2 The foregoing enumeration shall not imply any limitation upon the power of the **Engineer** or **Architect** or **Project Manager**, for it is the intent of this **Contract** that all of the **Work** shall generally be subject to his/her determination, direction, and approval, except where the determination, direction or approval of someone other than the **Engineer** or **Architect** or **Project Manager** is expressly called for herein.
- 32.3 The **Engineer** or **Architect** or **Project Manager** shall not, however, have the power to issue an **Extra Work** order, except as specifically designated in writing by the **Commissioner**.

ARTICLE 33. THE COMMISSIONER

33.1 The **Commissioner**, in addition to those matters elsewhere herein expressly made subject to his/her determination, direction or approval, shall have the power:

- 33.1.1 To review and make determinations on any and all questions in relation to this **Contract** and its performance; and
- 33.1.2 To modify or change this **Contract** so as to require the performance of **Extra Work** (subject, however, to the limitations specified in Article 25) or the omission of **Contract Work**; and
- 33.1.3 To suspend the whole or any part of the **Work** whenever in his/her judgment such suspension is required:
 - 33.1.3(a) In the interest of the City generally; or
 - 33.1.3(b) To coordinate the **Work** of the various contractors engaged on this **Project** pursuant to the provisions of Article 12; or
 - 33.1.3(c) To expedite the completion of the entire **Project** even though the completion of this particular **Contract** may thereby be delayed.

ARTICLE 34. NO ESTOPPEL

- 34.1 Neither the **City** nor any **Agency**, official, agent or employee thereof, shall be bound, precluded or estopped by any determination, decision, approval, order, letter, payment or certificate made or given under or in connection with this **Contract** by the **City**, the **Commissioner**, the **Engineer**, the **Resident Engineer**, or any other official, agent or employee of the **City**, either before or after the final completion and acceptance of the **Work** and payment therefor:
 - 34.1.1 From showing the true and correct classification, amount, quality or character of the **Work** actually done; or that any such determination, decision, order, letter, payment or certificate was untrue, incorrect or improperly made in any particular, or that the **Work**, or any part thereof, does not in fact conform to the requirements of this **Contract**; and
 - 34.1.2 From demanding and recovering from the **Contractor** any overpayment made to it, or such damages as the **City** may sustain by reason of the **Contractor's** failure to perform each and every part of its **Contract**.

CHAPTER VIII: LABOR PROVISIONS

ARTICLE 35. EMPLOYEES

- 35.1 The **Contractor** and its **Subcontractors** shall not employ on the **Work**:
 - 35.1.1 Anyone who is not competent, faithful and skilled in the **Work** for which he/she shall be employed; and whenever the **Commissioner** shall inform the **Contractor**, in writing, that any employee is, in his/her opinion, incompetent, unfaithful or disobedient, that employee shall be discharged from the **Work** forthwith, and shall not again be employed upon it; or

- 35.1.2 Any labor, materials or means whose employment, or utilization during the course of this **Contract**, may tend to or in any way cause or result in strikes, work stoppages, delays, suspension of **Work** or similar troubles by workers employed by the **Contractor** or its **Subcontractors**, or by any of the trades working in or about the buildings and premises where **Work** is being performed under this **Contract**, or by **Other Contractors** or their **Subcontractors** pursuant to other contracts, or on any other building or premises owned or operated by the **City**, its **Agencies**, departments, boards or authorities. Any violation by the **Contractor** of this requirement may, upon certification of the **Commissioner**, be considered as proper and sufficient cause for declaring the **Contractor** to be in default, and for the **City** to take action against it as set forth in Chapter X of this **Contract**, or such other article of this **Contract** as the Commissioner may deem proper; or
- 35.1.3 In accordance with Section 220.3-e of the Labor Law of the State of New York (hereinafter "Labor Law"), the **Contractor** and its **Subcontractors** shall not employ on the **Work** any apprentice, unless he/she is a registered individual, under a bona fide program registered with the New York State Department of Labor. The allowable ratio of apprentices to journey-level workers in any craft classification shall not be greater than the ratio permitted to the **Contractor** as to its work force on any job under the registered program. Any employee listed on a payroll at an apprentice wage rate, who is not registered as above, shall be paid the wage rate determined by the **Comptroller** of the **City** for the classification of **Work** actually performed. The **Contractor** or **Subcontractor** will be required to furnish written evidence of the registration of its program and apprentices as well as all the appropriate ratios and wage rates, for the area of the construction prior to using any apprentices on the **Contract Work**.
- 35.2 If the total cost of the **Work** under this **Contract** is at least two hundred fifty thousand (\$250,000) dollars, all laborers, workers, and mechanics employed in the performance of the **Contract** on the public work site, either by the **Contractor**, **Subcontractor** or other person doing or contracting to do the whole or a part of the **Work** contemplated by the **Contract**, shall be certified prior to performing any **Work** as having successfully completed a course in construction safety and health approved by the United States Department of Labor's Occupational Safety and Health Administration that is at least ten (10) hours in duration.
- 35.3 In accordance with Local Law Nos. 30-2012 and 33-2012, codified at sections 6-132 and 12-113 of the Administrative Code, respectively,
 - 35.3.1 The **Contractor** shall not take an adverse personnel action with respect to an officer or employee in retaliation for such officer or employee making a report of information concerning conduct which such officer or employee knows or reasonably believes to involve corruption, criminal activity, conflict of interest, gross mismanagement or abuse of authority by any officer or employee relating to this **Contract** to (a) the Commissioner of the Department of Investigation, (b) a member of the New York City Council, the Public Advocate, or the **Comptroller**, or (c) the **CCPO**, **ACCO**, **Agency** head, or **Commissioner**.
 - 35.3.2 If any of the **Contractor**'s officers or employees believes that he or she has been the subject of an adverse personnel action in violation of Article 35.3.1, he or she shall be entitled to bring a cause of action against the **Contractor** to recover all relief necessary to make him or her whole. Such relief may include but is not limited to: (a) an injunction to restrain continued retaliation, (b) reinstatement to the position such employee would have had but for the retaliation or to an equivalent position, (c) reinstatement of full fringe benefits and seniority rights, (d) payment of two times back

pay, plus interest, and (e) compensation for any special damages sustained as a result of the retaliation, including litigation costs and reasonable attorney's fees.

- 35.3.3 The **Contractor** shall post a notice provided by the **City** in a prominent and accessible place on any site where work pursuant to the **Contract** is performed that contains information about:
 - 35.3.3(a) how its employees can report to the New York City Department of Investigation allegations of fraud, false claims, criminality or corruption arising out of or in connection with the **Contract**; and
 - 35.3.3(b) the rights and remedies afforded to its employees under Administrative Code sections 7-805 (the New York City False Claims Act) and 12-113 (the Whistleblower Protection Expansion Act) for lawful acts taken in connection with the reporting of allegations of fraud, false claims, criminality or corruption in connection with the **Contract**.
- 35.3.4 For the purposes of this Article 35.3, "adverse personnel action" includes dismissal, demotion, suspension, disciplinary action, negative performance evaluation, any action resulting in loss of staff, office space, equipment or other benefit, failure to appoint, failure to promote, or any transfer or assignment or failure to transfer or assign against the wishes of the affected officer or employee.
- 35.3.5 This Article 35.3 is applicable to all of the **Contractor**'s **Subcontractors** having subcontracts with a value in excess of \$100,000; accordingly, the **Contractor** shall include this rider in all subcontracts with a value a value in excess of \$100,000.
- 35.4 Article 35.3 is not applicable to this **Contract** if it is valued at \$100,000 or less. Articles 35.3.1, 35.3.2, 35.3.4, and 35.3.5 are not applicable to this **Contract** if it was solicited pursuant to a finding of an emergency.
 - 35.5 Paid Sick Leave Law.
 - 35.5.1 Introduction and General Provisions.
 - 35.5.1(a) The Earned Sick Time Act, also known as the Paid Sick Leave Law ("PSLL"), requires covered employees who annually perform more than 80 hours of work in New York City to be provided with paid sick time.² Contractors of the **City** or of other governmental entities may be required to provide sick time pursuant to the PSLL.
 - 35.5.1(b) The PSLL became effective on April 1, 2014, and is codified at Title 20, Chapter 8, of the New York City Administrative Code. It is administered by the City's Department of Consumer Affairs ("DCA"); DCA's rules promulgated under the PSLL are codified at Chapter 7 of Title 6 of the Rules of the City of New York ("Rules").

² Pursuant to the PSLL, if fewer than five employees work for the same employer, as determined pursuant to New York City Administrative Code § 20-912(g), such employer has the option of providing such employees uncompensated sick time.

- 35.5.1(c) The **Contractor** agrees to comply in all respects with the PSLL and the Rules, and as amended, if applicable, in the performance of this **Contract**. The **Contractor** further acknowledges that such compliance is a material term of this **Contract** and that failure to comply with the PSLL in performance of this **Contract** may result in its termination.
- 35.5.1(d) The **Contractor** must notify the **Agency Chief Contracting Officer** of the **Agency** with whom it is contracting in writing within ten (10) days of receipt of a complaint (whether oral or written) regarding the PSLL involving the performance of this **Contract**. Additionally, the **Contractor** must cooperate with DCA's education efforts and must comply with DCA's subpoenas and other document demands as set forth in the PSLL and Rules.
- 35.5.1(e) The PSLL is summarized below for the convenience of the **Contractor**. The **Contractor** is advised to review the PSLL and Rules in their entirety. On the website www.nyc.gov/PaidSickLeave there are links to the PSLL and the associated Rules as well as additional resources for employers, such as Frequently Asked Questions, timekeeping tools and model forms, and an event calendar of upcoming presentations and webinars at which the **Contractor** can get more information about how to comply with the PSLL. The **Contractor** acknowledges that it is responsible for compliance with the PSLL notwithstanding any inconsistent language contained herein.
- 35.5.2 Pursuant to the PSLL and the Rules: Applicability, Accrual, and Use.
 - 35.5.2(a) An employee who works within the City of New York for more than eighty hours in any consecutive 12-month period designated by the employer as its "calendar year" pursuant to the PSLL ("Year") must be provided sick time. Employers must provide a minimum of one hour of sick time for every 30 hours worked by an employee and compensation for such sick time must be provided at the greater of the employee's regular hourly rate or the minimum wage. Employers are not required to provide more than 40 hours of sick time to an employee in any Year.
 - 35.5.2(b) An employee has the right to determine how much sick time he or she will use, provided that employers may set a reasonable minimum increment for the use of sick time not to exceed four hours per **Day**. In addition, an employee may carry over up to 40 hours of unused sick time to the following Year, provided that no employer is required to allow the use of more than forty hours of sick time in a Year or carry over unused paid sick time if the employee is paid for such unused sick time and the employer provides the employee with at least the legally required amount of paid sick time for such employee for the immediately subsequent Year on the first **Day** of such Year.
 - 35.5.2(c) An employee entitled to sick time pursuant to the PSLL may use sick time for any of the following:
 - such employee's mental illness, physical illness, injury, or health condition
 or the care of such illness, injury, or condition or such employee's need for
 medical diagnosis or preventive medical care;
 - ii. such employee's care of a family member (an employee's child, spouse, domestic partner, parent, sibling, grandchild or grandparent, or the child or parent of an employee's spouse or domestic partner) who has a mental

- illness, physical illness, injury or health condition or who has a need for medical diagnosis or preventive medical care;
- iii. closure of such employee's place of business by order of a public official due to a public health emergency; or
- iv. such employee's need to care for a child whose school or childcare provider has been closed due to a public health emergency.
- 35.5.2(d) An employer must not require an employee, as a condition of taking sick time, to search for a replacement. However, an employer may require an employee to provide: reasonable notice of the need to use sick time; reasonable documentation that the use of sick time was needed for a reason above if for an absence of more than three consecutive work days; and/or written confirmation that an employee used sick time pursuant to the PSLL. However, an employer may not require documentation specifying the nature of a medical condition or otherwise require disclosure of the details of a medical condition as a condition of providing sick time and health information obtained solely due to an employee's use of sick time pursuant to the PSLL must be treated by the employer as confidential.
- 35.5.2(e) If an employer chooses to impose any permissible discretionary requirement as a condition of using sick time, it must provide to all employees a written policy containing those requirements, using a delivery method that reasonably ensures that employees receive the policy. If such employer has not provided its written policy, it may not deny sick time to an employee because of noncompliance with such a policy.
- 35.5.2(f) Sick time to which an employee is entitled must be paid no later than the payday for the next regular payroll period beginning after the sick time was used.
- 35.5.3 Exemptions and Exceptions. Notwithstanding the above, the PSLL does not apply to any of the following:
 - 35.5.3(a) an independent contractor who does not meet the definition of employee under section 190(2) of the New York State Labor Law;
 - 35.5.3(b) an employee covered by a valid collective bargaining agreement in effect on April 1, 2014, until the termination of such agreement;
 - 35.5.3(c) an employee in the construction or grocery industry covered by a valid collective bargaining agreement if the provisions of the PSLL are expressly waived in such collective bargaining agreement;
 - 35.5.3(d) an employee covered by another valid collective bargaining agreement if such provisions are expressly waived in such agreement and such agreement provides a benefit comparable to that provided by the PSLL for such employee;
 - 35.5.3(e) an audiologist, occupational therapist, physical therapist, or speech language pathologist who is licensed by the New York State Department of Education and who calls in for work assignments at will, determines his or her own schedule, has the ability to reject or accept any assignment referred to him or her, and is paid an average hourly wage that is at least four times the federal minimum wage;

- 35.5.3(f) an employee in a work study program under Section 2753 of Chapter 42 of the United States Code;
- 35.5.3(g) an employee whose work is compensated by a qualified scholarship program as that term is defined in the Internal Revenue Code, Section 117 of Chapter 20 of the United States Code; or
- 35.5.3(h) a participant in a Work Experience Program (WEP) under section 336-c of the New York State Social Services Law.
- 35.5.4 Retaliation Prohibited. An employer may not threaten or engage in retaliation against an employee for exercising or attempting in good faith to exercise any right provided by the PSLL. In addition, an employer may not interfere with any investigation, proceeding, or hearing pursuant to the PSLL.

35.5.5 Notice of Rights.

- 35.5.5(a) An employer must provide its employees with written notice of their rights pursuant to the PSLL. Such notice must be in English and the primary language spoken by an employee, provided that DCA has made available a translation into such language. Downloadable notices are available on DCA's website at http://www.nyc.gov/html/dca/html/law/PaidSickLeave.shtml.
- 35.5.5(b) Any person or entity that willfully violates these notice requirements is subject to a civil penalty in an amount not to exceed fifty dollars for each employee who was not given appropriate notice.
- 35.5.6 Records. An employer must retain records documenting its compliance with the PSLL for a period of at least three years, and must allow DCA to access such records in furtherance of an investigation related to an alleged violation of the PSLL.

35.5.7 Enforcement and Penalties.

- 35.5.7(a) Upon receiving a complaint alleging a violation of the PSLL, DCA has the right to investigate such complaint and attempt to resolve it through mediation. Within 30 **Days** of written notification of a complaint by DCA, or sooner in certain circumstances, the employer must provide DCA with a written response and such other information as DCA may request. If DCA believes that a violation of the PSLL has occurred, it has the right to issue a notice of violation to the employer.
- 35.5.7(b) DCA has the power to grant an employee or former employee all appropriate relief as set forth in New York City Administrative Code § 20-924(d). Such relief may include, among other remedies, treble damages for the wages that should have been paid, damages for unlawful retaliation, and damages and reinstatement for unlawful discharge. In addition, DCA may impose on an employer found to have violated the PSLL civil penalties not to exceed \$500 for a first violation, \$750 for a second violation within two years of the first violation, and \$1,000 for each succeeding violation within two years of the previous violation.
- 35.5.8 More Generous Polices and Other Legal Requirements. Nothing in the PSLL is intended to discourage, prohibit, diminish, or impair the adoption or retention of a more generous sick time policy, or the obligation of an employer to comply with any contract,

collective bargaining agreement, employment benefit plan or other agreement providing more generous sick time. The PSLL provides minimum requirements pertaining to sick time and does not preempt, limit or otherwise affect the applicability of any other law, regulation, rule, requirement, policy or standard that provides for greater accrual or use by employees of sick leave or time, whether paid or unpaid, or that extends other protections to employees. The PSLL may not be construed as creating or imposing any requirement in conflict with any federal or state law, rule or regulation.

35.6 HireNYC: Hiring and Reporting Requirements. This Article 35.6 applies to construction contracts of \$1,000,000 or more. The **Contractor** shall comply with the requirements of Articles 35.6.1-35.6.5 for all non-trades jobs (e.g., for an administrative position arising out of **Work** ant located in New York City). The **Contractor** shall reasonably cooperate with SBS and the **City** on specific outreach events, including "Hire-on-the-Spot" events, for the hiring of trades workers in connection with the **Work**. If provided elsewhere in this **Contract**, this **Contract** is subject to a project labor agreement.

35.6.1 Enrollment. The **Contractor** shall enroll with the HireNYC system, found at www.nyc.gov/sbs, within thirty (30) days after the registration of this **Contract** pursuant to Section 328 of the New York City Charter. The **Contractor** shall provide information about the business, designate a primary contact and say whether it intends to hire for any entry to mid-level job opportunities arising from this **Contract** and located in New York City, and, if so, the approximate start date of the first hire.

35.6.2 Job Posting Requirements.

35.6.2(a) Once enrolled in HireNYC, the **Contractor** agrees to update the HireNYC portal with all entry to mid-level job opportunities arising from this **Contract** and located in New York City, if any, which shall be defined as jobs requiring no more than an associate degree, as provided by the New York State Department of Labor (see Column F of https://labor.ny.gov/stats/2012-2022- NYS-Employment-Prospects.xls). The information to be updated includes the types of entry and mid-level positions made available from the work arising from the **Contract** and located in New York City, the number of positions, the anticipated schedule of initiating the hiring process for these positions, and the contact information for the **Contractor's** representative charged with overseeing hiring. The **Contractor** must update the HireNYC portal with any hiring needs arising from the contract and located in New York City, and the requirements of the jobs to be filled, no less than three weeks prior to the intended first day of employment for each new position, except with the permission of SBS, not to be unreasonably withheld, and must also update the HireNYC portal as set forth below.

35.6.2(b) After enrollment through HireNYC and submission of relevant information, SBS will work with the **Contractor** to develop a recruitment plan which will outline the candidate screening process, and will provide clear instructions as to when, where, and how interviews will take place. HireNYC will screen applicants based on employer requirements and refer applicants whom it believes are qualified to the **Contractor** for interviews. The **Contractor** must interview referred applicants whom it believes are qualified.

35.6.2(c) After completing an interview of a candidate referred by HireNYC, the **Contractor** must provide feedback via the portal within twenty (20) business days to indicate which candidates were interviewed and hired, if any. In addition, the **Contractor** shall provide the start date of new hires, and additional information

reasonably related to such hires, within twenty (20) business days after the start date. In the event the **Contractor** does not have any job openings covered by this Rider in any given year, the **Contractor** shall be required to provide an annual update to HireNYC to that effect. For this purpose, the reporting year shall run from the date of the registration of the **Contract** pursuant to Charter section 328 and each anniversary date.

35.6.2(d) These requirements do not limit the **Contractor's** ability to assess the qualifications of prospective workers, and to make final hiring and retention decisions. No provision of this Article 35.6 shall be interpreted so as to require the **Contractor** to employ any particular worker.

35.6.2(e) In addition, the provisions of this Article 35.6 shall not apply to positions that the **Contractor** intends to fill with employees employed pursuant to the job retention provision of Section 22-505 of the Administrative Code of the City of New York. The **Contractor** shall not be required to report such openings with HireNYC. However, the **Contractor** shall enroll with the HireNYC system pursuant to Article 35.6.1, above, and, if such positions subsequently become open, then the remaining provisions of this Article 35.6 will apply.

35.6.3 Breach and Liquidated Damages. If the **Contractor** fails to comply with the terms of the **ContrSact** and this Article 35.6 (1) by not enrolling its business with HireNYC; (2) by not informing HireNYC, as required, of open positions; or (3) by failing to interview a qualified candidate, the **Agency** may assess liquidated damages in the amount of two-thousand five hundred dollars (\$2,500) per breach. For all other events of noncompliance with the terms of this Article 35.6, the **Agency** may assess liquidated damages in the amount of five hundred dollars (\$500) per breach. Furthermore, in the event the **Contractor** breaches the requirements of this Article 35.6 during the term of the **Contract**, the **City** may hold the **Contractor** in default of this **Contract**.

35.6.4 Audit Compliance. In addition to the auditing requirements set forth in other parts of the **Contract**, the **Contractor** shall permit SBS and the **City** to inspect any and all records concerning or relating to job openings or the hiring of individuals for work arising from the **Contract** and located in New York City. The **Contractor** shall permit an inspection within seven (7) business days of the request.

35.6.5 Other Reporting Requirements. The **Contractor** shall report to the **City**, on a monthly basis, all information reasonably requested by the **City** that is necessary for the **City** to comply with any reporting requirements imposed by **Law**, including any requirement that the **City** maintain a publicly accessible database. In addition, the **Contractor** agrees to comply with all reporting requirements imposed by **Law**, or as otherwise requested by the **City**.

35.6.6 Federal Hiring Requirements. If this **Contract** is federally funded (as indicated elsewhere in this Contract), the **Contractor** shall comply with all federal hiring requirements as may be set forth in this **Contract**, including, as applicable: (a) Section 3 of the HUD Act of 1968, which requires, to the greatest extent feasible, economic opportunities for 30 percent of new hires be given to low- and very low-income persons, particularly persons who are recipients of HUD assistance for housing and Executive Order 11246, which prohibits discrimination in employment due to race, color, religion, sex or national origin, and requires the implementation of goals for minority and female participation for work involving any construction trade.

ARTICLE 36. NO DISCRIMINATION

- 36.1 The **Contractor** specifically agrees, as required by Labor Law Section 220-e, as amended, that:
 - 36.1.1 In the hiring of employees for the performance of **Work** under this **Contract** or any subcontract hereunder, neither the **Contractor**, **Subcontractor**, nor any person acting on behalf of such **Contractor** or **Subcontractor**, shall by reason of race, creed, color or national origin discriminate against any citizen of the State of New York who is qualified and available to perform the **Work** to which the employment relates;
 - 36.1.2 Neither the **Contractor**, **Subcontractor**, nor any person on its behalf shall, in any manner, discriminate against or intimidate any employee hired for the performance of **Work** under this **Contract** on account of race, creed, color or national origin;
 - 36.1.3 There may be deducted from the amount payable to the **Contractor** by the **City** under this **Contract** a penalty of fifty (\$50.00) dollars for each person for each **Day** during which such person was discriminated against or intimidated in violation of the provisions of this **Contract**; and
 - 36.1.4 This **Contract** may be cancelled or terminated by the **City** and all moneys due or to become due hereunder may be forfeited, for a second or any subsequent violation of the terms or conditions of this Article 36.
 - 36.1.5 This Article 36 covers all construction, alteration and repair of any public building or public work occurring in the State of New York and the manufacture, sale, and distribution of materials, equipment, and supplies to the extent that such operations are performed within the State of New York pursuant to this **Contract**.
- 36.2 The **Contractor** specifically agrees, as required by Section 6-108 of the Administrative Code, as amended, that:
 - 36.2.1 It shall be unlawful for any person engaged in the construction, alteration or repair of buildings or engaged in the construction or repair of streets or highways pursuant to a **Contract** with the **City** or engaged in the manufacture, sale or distribution of materials, equipment or supplies pursuant to a **Contract** with the **City** to refuse to employ or to refuse to continue in any employment any person on account of the race, color or creed of such person.
 - 36.2.2 It shall be unlawful for any person or any servant, agent or employee of any person, described in Article 36.1.2, to ask, indicate or transmit, orally or in writing, directly or indirectly, the race, color or creed or religious affiliation of any person employed or seeking employment from such person, firm or corporation.
 - 36.2.3 Breach of the foregoing provisions shall be deemed a violation of a material provision of this **Contract**.
 - 36.2.4 Any person, or the employee, manager or owner of or officer of such firm or corporation who shall violate any of the provisions of this Article 36.2 shall, upon

conviction thereof, be punished by a fine of not more than one hundred (\$100.00) dollars or by imprisonment for not more than thirty (30) **Days**, or both.

- 36.3 This **Contract** is subject to the requirements of Executive Order No. 50 (1980) ("E.O. 50"), as revised, and the rules and regulations promulgated thereunder. No contract will be awarded unless and until these requirements have been complied with in their entirety. By signing this **Contract**, the **Contractor** agrees that it:
 - 36.3.1 Will not engage in any unlawful discrimination against any employee or applicant for employment because of race, creed, color, national origin, sex, age, disability, marital status or sexual orientation with respect to all employment decisions including, but not limited to, recruitment, hiring, upgrading, demotion, downgrading, transfer, training, rates of pay or other forms of compensation, layoff, termination, and all other terms and conditions of employment; and
 - 36.3.2 Will not engage in any unlawful discrimination in the selection of **Subcontractors** on the basis of the owner's race, color, creed, national origin, sex, age, disability, marital status or sexual orientation; and
 - 36.3.3 Will state in all solicitations or advertisements for employees placed by or on behalf of the **Contractor** that all qualified applicants will receive consideration for employment without unlawful discrimination based on race, creed, color, national origin, sex, age, citizens status, disability, marital status, sexual orientation, or that it is an equal employment opportunity employer; and
 - 36.3.4 Will send to each labor organization or representative of workers with which it has a collective bargaining agreement or other contract or memorandum of understanding, written notification of its equal employment opportunity commitments under E.O. 50 and the rules and regulations promulgated thereunder; and
 - 36.3.5 Will furnish, before the award of the **Contract**, all information and reports, including an employment report, that are required by E.O. 50, the rules and regulations promulgated thereunder, and orders of the **City** Department of Business Services, Division of Labor Services (**DLS**) and will permit access to its books, records, and accounts by the **DLS** for the purposes of investigation to ascertain compliance with such rules, regulations, and orders.
- 36.4 The **Contractor** understands that in the event of its noncompliance with the nondiscrimination clauses of this **Contract** or with any of such rules, regulations, or orders, such noncompliance shall constitute a material breach of this **Contract** and noncompliance with E.O. 50 and the rules and regulations promulgated thereunder. After a hearing held pursuant to the rules of the **DLS**, the Director of the **DLS** may direct the **Commissioner** to impose any or all of the following sanctions:
 - 36.4.1 Disapproval of the Contractor; and/or
 - 36.4.2 Suspension or termination of the Contract; and/or
 - 36.4.3 Declaring the **Contractor** in default; and/or
 - 36.4.4 In lieu of any of the foregoing sanctions, the Director of the **DLS** may impose an employment program.

In addition to any actions taken under this **Contract**, failure to comply with E.O. 50 and the rules and regulations promulgated thereunder, in one or more instances, may result in a **City Agency** declaring the **Contractor** to be non-responsible in future procurements. The **Contractor** further agrees that it will refrain from entering into any **Contract** or **Contract** modification subject to E.O. 50 and the rules and regulations promulgated thereunder with a **Subcontractor** who is not in compliance with the requirements of E.O. 50 and the rules and regulations promulgated thereunder.

- 36.5 The **Contractor** specifically agrees, as required by Section 6-123 of the Administrative Code, that:
 - 36.5.1 The **Contractor** will not engage in any unlawful discriminatory practice in violation of Title 8 of the Administrative Code; and
 - 36.5.2 Any failure to comply with this Article 36.5 may subject the **Contractor** to the remedies set forth in Section 6-123 of the Administrative Code, including, where appropriate, sanctions such as withholding of payment, imposition of an employment program, finding the **Contractor** to be in default, cancellation of the **Contract**, or any other sanction or remedy provided by **Law** or **Contract**.

ARTICLE 37. LABOR LAW REQUIREMENTS

- 37.1 The **Contractor** shall strictly comply with all applicable provisions of the Labor Law, as amended. Such compliance is a material term of this **Contract**.
- 37.2 The **Contractor** specifically agrees, as required by Labor Law Sections 220 and 220-d, as amended, that:
 - 37.2.1 Hours of **Work**: No laborer, worker, or mechanic in the employ of the **Contractor**, **Subcontractor** or other person doing or contracting to do the whole or a part of the **Work** contemplated by this **Contract** shall be permitted or required to work more than eight (8) hours in any one (1) **Day**, or more than five (5) **Days** in any one (1) week, except as provided in the Labor Law and in cases of extraordinary emergency including fire, flood, or danger to life or property, or in the case of national emergency when so proclaimed by the President of the United States of America.
 - 37.2.2 In situations in which there are not sufficient laborers, workers, and mechanics who may be employed to carry on expeditiously the **Work** contemplated by this **Contract** as a result of such restrictions upon the number of hours and **Days** of labor, and the immediate commencement or prosecution or completion without undue delay of the **Work** is necessary for the preservation of the **Site** and/or for the protection of the life and limb of the persons using the same, such laborers, workers, and mechanics shall be permitted or required to work more than eight (8) hours in any one (1) **Day**; or five (5) **Days** in any one (1) week; provided, however, that upon application of any **Contractor**, the **Commissioner** shall have first certified to the Commissioner of Labor of the State of New York (hereinafter "Commissioner of Labor") that such public **Work** is of an important nature and that a delay in carrying it to completion would result in serious disadvantage to the public; and provided, further, that such Commissioner of Labor shall have determined that such an emergency does in fact exist as provided in Labor Law Section 220.2.
 - 37.2.3 Failure of the **Commissioner** to make such a certification to the Commissioner of Labor shall not entitle the **Contractor** to damages for delay or for any cause whatsoever.

- 37.2.4 Prevailing Rate of Wages: The wages to be paid for a legal day's **Work** to laborers, workers, or mechanics employed upon the **Work** contemplated by this **Contract** or upon any materials to be used thereon shall not be less than the "prevailing rate of wage" as defined in Labor Law Section 220, and as fixed by the **Comptroller** in the attached Schedule of Wage Rates and in updated schedules thereof. The prevailing wage rates and supplemental benefits to be paid are those in effect at the time the **Work** is being performed.
- 37.2.5 Requests for interpretation or correction in the Information for Bidders includes all requests for clarification of the classification of trades to be employed in the performance of the **Work** under this **Contract**. In the event that a trade not listed in the **Contract** is in fact employed during the performance of this **Contract**, the **Contractor** shall be required to obtain from the **Agency** the prevailing wage rates and supplementary benefits for the trades used and to complete the performance of this **Contract** at the price at which the **Contract** was awarded.
- 37.2.6 Minimum Wages: Except for employees whose wage is required to be fixed pursuant to Labor Law Section 220, all persons employed by the **Contractor** and any **Subcontractor** in the manufacture or furnishing of the supplies, materials, or equipment, or the furnishing of work, labor, or services, used in the performance of this **Contract**, shall be paid, without subsequent deduction or rebate unless expressly authorized by **Law**, not less than the sum mandated by **Law**.
- 37.3 Working Conditions: No part of the **Work**, labor or services shall be performed or rendered by the **Contractor** in any plants, factories, buildings or surroundings or under working conditions which are unsanitary or hazardous or dangerous to the health and safety of employees engaged in the performance of this **Contract**. Compliance with the safety, sanitary, and factory inspection **Laws** of the state in which the **Work** is to be performed shall be prima facie evidence of compliance with this Article 37.3.
- 37.4 Prevailing Wage Enforcement: The **Contractor** agrees to pay for all costs incurred by the **City** in enforcing prevailing wage requirements, including the cost of any investigation conducted by or on behalf of the **Agency** or the **Comptroller**, where the **City** discovers a failure to comply with any of the requirements of this Article 37 by the **Contractor** or its **Subcontractor(s)**. The **Contractor** also agrees that, should it fail or refuse to pay for any such investigation, the **Agency** is hereby authorized to deduct from a **Contractor's** account an amount equal to the cost of such investigation.
 - 37.4.1 The Labor Law Section 220 and Section 220-d, as amended, provide that this **Contract** shall be forfeited and no sum paid for any **Work** done hereunder on a second conviction for willfully paying less than:
 - 37.4.1(a) The stipulated prevailing wage scale as provided in Labor Law section 220, as amended, or
 - 37.4.1(b) The stipulated minimum hourly wage scale as provided in Labor Law section 220-d, as amended.
 - 37.4.2 For any breach or violation of either working conditions (Article 37.3) or minimum wages (Article 37.2.6) provisions, the party responsible therefor shall be liable to the **City** for liquidated damages, which may be withheld from any amounts due on any contracts with the **City** of such party responsible, or may be recovered in actions brought by the **City**

Corporation Counsel in the name of the **City**, in addition to damages for any other breach of this **Contract**, for a sum equal to the amount of any underpayment of wages due to any employee engaged in the performance of this **Contract**. In addition, the **Commissioner** shall have the right to cancel contracts and enter into other contracts for the completion of the original contract, with or without public letting, and the original **Contractor** shall be liable for any additional cost. All sums withheld or recovered as deductions, rebates, refunds, or underpayment of wages hereunder, shall be held in a special deposit account and shall be paid without interest, on order of the **Comptroller**, directly to the employees who have been paid less than minimum rates of pay as set forth herein and on whose account such sums were withheld or recovered, provided that no claims by employees for such payments shall be entertained unless made within two (2) years from the date of actual notice to the **Contractor** of the withholding or recovery of such sums by the **City**.

- 37.4.3 A determination by the **Comptroller** that a **Contractor** and/or its **Subcontractor** willfully violated Labor Law Section 220 will be forwarded to the **City's** five District Attorneys for review.
- 37.4.4 The **Contractor's** or **Subcontractor's** noncompliance with this Article 37.4 and Labor Law Section 220 may result in an unsatisfactory performance evaluation and the **Comptroller** may also find and determine that the **Contractor** or **Subcontractor** willfully violated the New York Labor **Law**.
 - 37.4.4(a) An unsatisfactory performance evaluation for noncompliance with this Article 37.4 may result in a determination that the **Contractor** is a non-responsible bidder on subsequent procurements with the **City** and thus a rejection of a future award of a contract with the **City**, as well as any other sanctions provided for by **Law**.
 - 37.4.4(b) Labor Law Section 220-b, as amended, provides that when two (2) final determinations have been rendered against a **Contractor** or **Subcontractor** within any consecutive six (6) year period determining that such **Contractor** or **Subcontractor** has willfully failed to pay the prevailing rate of wages or to provide supplements in accordance with the Labor Law and this Article 37.4, whether such failures were concurrent or consecutive and whether or not such final determinations concerning separate public works projects are rendered simultaneously, such **Contractor** or **Subcontractor** shall be ineligible to submit a bid on or be awarded any public works contract with the **City** for a period of five (5) years from the second final determination. If the final determination involves the falsification of payroll records or the kickback of wages or supplements, the **Contractor** or **Subcontractor** shall be ineligible to submit a bid on or be awarded any public works contract with the **City** for a period of five (5) years from the first final determination.
 - 37.4.4(c) Labor Law Section 220, as amended, provides that the **Contractor** or **Subcontractor** found to have violated this Article 37.4 may be directed to make payment of wages or supplements including interest found to be due, and the **Contractor** or **Subcontractor** may be directed to make payment of a further sum as a civil penalty in an amount not exceeding twenty-five (25%) percent of the total amount found to be due.
- 37.5 The **Contractor** and its **Subcontractors** shall within ten (10) **Days** after mailing of a Notice of Award or written order, post in prominent and conspicuous places in each and every plant, factory, building, and structure where employees of the **Contractor** and its **Subcontractors** engaged in the

performance of this **Contract** are employed, notices furnished by the **City**, in relation to prevailing wages and supplements, minimum wages, and other stipulations contained in Sections 220 and 220-h of the Labor Law, and the **Contractor** and its **Subcontractors** shall continue to keep such notices posted in such prominent and conspicuous places until **Final Acceptance** of the supplies, materials, equipment, or **Work**, labor, or services required to be furnished or rendered under this **Contract**.

37.6 The **Contractor** shall strictly comply with all of the provisions of Articles 37.6.1 through 37.6.5, and provide for all workers, laborers or mechanics in its employ, the following:

37.6.1 Notices Posted At **Site**: Post, in a location designated by the **City**, schedules of prevailing wages and supplements for this **Project**, a copy of all re-determinations of such schedules for the **Project**, the Workers' Compensation **Law** Section 51 notice, all other notices required by **Law** to be posted at the **Site**, the **City** notice that this **Project** is a public works project on which each worker is entitled to receive the prevailing wages and supplements for the occupation at which he or she is working, and all other notices which the **City** directs the **Contractor** to post. The **Contractor** shall provide a surface for such notices which is satisfactory to the **City**. The **Contractor** shall maintain and keep current such notices in a legible manner and shall replace any notice or schedule which is damaged, defaced, illegible or removed for any reason. The **Contractor** shall post such notices before commencing any **Work** on the **Site** and shall maintain such notices until all **Work** on the **Site** is complete; and

37.6.2 Daily **Site** Sign-in Sheets: Maintain daily **Site** sign-in sheets, and require that **Subcontractors** maintain daily **Site** sign-in sheets for its employees, which include blank spaces for an employee's name to be both printed and signed, job title, date started and Social Security number, the time the employee began work and the time the employee left work, until **Final Acceptance** of the supplies, materials, equipment, or **Work**, labor, or services to be furnished or rendered under this **Contract** unless exception is granted by the **Comptroller** upon application by the **Agency**. In the alternative, subject to the approval of the **CCPO**, the **Contractor** and **Subcontractor** may maintain an electronic or biometric sign-in system, which provides the information required by this Article 37.6.2; and

37.6.3 Individual Employee Information Notices: Distribute a notice to each worker. laborer or mechanic employed under this **Contract**, in a form provided by the **Agency**, that this **Project** is a public works project on which each worker, laborer or mechanic is entitled to receive the prevailing rate of wages and supplements for the occupation at which he or she is working. If the total cost of the Work under this Contract is at least two hundred fifty thousand (\$250,000) dollars, such notice shall also include a statement that each worker, laborer or mechanic must be certified prior to performing any Work as having successfully completed a course in construction safety and health approved by the United States Department of Labor's Occupational Safety and Health Administration that is at least ten (10) hours in duration. Such notice shall be distributed to each worker before he or she starts performing any Work of this Contract and with the first paycheck after July first of each year. "Worker, laborer or mechanic" includes employees of the Contractor and all Subcontractors and all employees of suppliers entering the Site. At the time of distribution, the Contractor shall have each worker, laborer or mechanic sign a statement, in a form provided by the **Agency**, certifying that the worker has received the notice required by this Article 37.6.3, which signed statement shall be maintained with the payroll records required by this Contract; and

wages for their particular job classification. Such notification shall be given to every worker, laborer, and mechanic on their first pay stub and with every pay stub thereafter; and

- 37.6.4 **Site** Laminated Identification Badges: The **Contractor** shall provide laminated identification badges which include a photograph of the worker's, laborer's or mechanic's face and indicate the worker's, laborer's or mechanic's name, trade, employer's name, and employment starting date (month/day/year). Further, the **Contractor** shall require as a condition of employment on the **Site**, that each and every worker, laborer or mechanic wear the laminated identification badge at all times and that it may be seen by any representative of the **City**. The **Commissioner** may grant a written waiver from the requirement that the laminated identification badge include a photograph if the **Contractor** demonstrates that the identity of an individual wearing a laminated identification badge can be easily verified by another method; and
- 37.6.5 Language Other Than English Used On **Site**: Provide the **ACCO** notice when three (3) or more employees (worker and/or laborer and/or mechanic) on the **Site**, at any time, speak a language other than English. The **ACCO** will then provide the **Contractor** the notices described in Article 37.6.1 in that language or languages as may be required. The **Contractor** is responsible for all distributions under this Article 37; and
- 37.6.6 Provision of Records: The **Contractor** and **Subcontractor**(s) shall produce within five (5) **Days** on the **Site** of the **Work** and upon a written order of the **Engineer**, the **Commissioner**, the **ACCO**, the **Agency EAO**, or the **Comptroller**, such records as are required to be kept by this Article 37.6; and
- 37.6.7 The **Contractor** and **Subcontractor(s)** shall pay employees by check or direct deposit. If this **Contract** is for an amount greater than one million (\$1,000,000) dollars, checks issued by the **Contractor** to covered employees shall be generated by a payroll service or automated payroll system (an in-house system may be used if approved by the **Agency**). For any subcontract for an amount greater than seven hundred fifty thousand (\$750,000) dollars, checks issued by a **Subcontractor** to covered employees shall be generated by a payroll service or automated payroll system (an in-house system may be used if approved by the **Agency**); and
- 37.6.8 The failure of the **Contractor** or **Subcontractor**(s) to comply with the provisions of Articles 37.6.1 through 37.6.7 may result in the **Commissioner** declaring the **Contractor** in default and/or the withholding of payments otherwise due under the **Contract**.
- 37.7 The **Contractor** and its **Subcontractors** shall keep such employment and payroll records as are required by Section 220 of the Labor Law. The failure of the **Contractor** or **Subcontractor(s)** to comply with the provisions of this Article 37.7 may result in the **Commissioner** declaring the **Contractor** in default and/or the withholding of payments otherwise due under the **Contract.**
- 37.8 At the time the **Contractor** makes application for each partial payment and for final payment, the **Contractor** shall submit to the **Commissioner** a written payroll certification, in the form provided by this **Contract**, of compliance with the prevailing wage, minimum wage, and other provisions and stipulations required by Labor Law Section 220 and of compliance with the training requirements of Labor Law Section 220-h set forth in Article 35.2. This certification of compliance shall be a condition precedent to payment and no payment shall be made to the **Contractor** unless and until each such certification shall have been submitted to and received by the **Commissioner**.

- 37.9 This **Contract** is executed by the **Contractor** with the express warranty and representation that the **Contractor** is not disqualified under the provisions of Section 220 of the Labor Law from the award of the **Contract**.
- 37.10 Any breach or violation of any of the foregoing shall be deemed a breach or violation of a material provision of this **Contract**, and grounds for cancellation thereof by the **City**.

ARTICLE 38. PAYROLL REPORTS

- 38.1 The **Contractor** and its **Subcontractor**(s) shall maintain on the **Site** during the performance of the **Work** the original payrolls or transcripts thereof which the **Contractor** and its **Subcontractor**(s) are required to maintain and shall submit such original payrolls or transcripts, subscribed and affirmed by it as true, within thirty (30) **Days** after issuance of its first payroll, and every thirty (30) **Days** thereafter, pursuant to Labor Law Section 220(3-a)(a)(iii). The **Contractor** and **Subcontractor**(s) shall submit such original payrolls or transcripts along with each and every payment requisition. If payment requisitions are not submitted at least once a month, the **Contractor** and its **Subcontractor**(s) shall submit original payrolls and transcripts both along with its payment requisitions and independently of its payment requisitions.
- 38.2 The **Contractor** shall maintain payrolls or transcripts thereof for six (6) years from the date of completion of the **Work** on this **Contract**. If such payrolls and transcripts are maintained outside of New York City after the completion of the **Work** and their production is required pursuant to this Article 38, the **Contractor** shall produce such records in New York City upon request by the City.
- 38.3 The **Contractor** and **Subcontractor**(s) shall comply with any written order, direction, or request made by the **Engineer**, the **Commissioner**, the **ACCO**, the **Agency EAO**, the **Agency Labor Law Investigator**(s), or the **Comptroller**, to provide to the requesting party any of the following information and/or records within five (5) **Days** of such written order, direction, or request:
 - 38.3.1 Such original payrolls or transcripts thereof subscribed and affirmed by it as true and the statements signed by each worker pursuant to this Chapter VIII; and/or
 - 38.3.2 Attendance sheets for each **Day** on which any employee of the **Contractor** and/or any of the **Subcontractor(s)** performed **Work** on the **Site**, which attendance sheet shall be in a form acceptable to the **Agency** and shall provide information acceptable to the **Agency** to identify each such employee; and/or
 - 38.3.3 Any other information to satisfy the **Engineer**, the **Commissioner**, the **ACCO**, the **Agency EAO**, the **Agency Labor Law Investigator(s)** or the **Comptroller**, that this Chapter VIII and the Labor Law, as to the hours of employment and prevailing rates of wages and/or supplemental benefits, are being observed.
- 38.4 The failure of the **Contractor** or **Subcontractor**(s) to comply with the provisions of Articles 38.1 and/or 38.2 may result in the **Commissioner** declaring the **Contractor** in default and/or the withholding of payments otherwise due under the **Contract**.

ARTICLE 39. DUST HAZARDS

39.1 Should a harmful dust hazard be created in performing the **Work** of this **Contract**, for the elimination of which appliances or methods have been approved by the Board of Standards and Appeals

of the City of New York, such appliances and methods shall be installed, maintained, and effectively operated during the continuance of such harmful dust hazard. Failure to comply with this provision after notice shall make this **Contract** voidable at the sole discretion of the **City**.

CHAPTER IX: PARTIAL AND FINAL PAYMENTS

ARTICLE 40. CONTRACT PRICE

40.1 The **City** shall pay, and the **Contractor** agrees to accept, in full consideration for the **Contractor's** performance of the **Work** subject to the terms and conditions hereof, the lump sum price or unit prices for which this **Contract** was awarded, plus the amount required to be paid for any **Extra Work** ordered by the **Commissioner** under Article 25, less credit for any **Work** omitted pursuant to Article 29.

ARTICLE 41. BID BREAKDOWN ON LUMP SUM

- 41.1 Within fifteen (15) **Days** after the commencement date specified in the **Notice to Proceed** or **Order to Work**, unless otherwise directed by the **Resident Engineer**, the **Contractor** shall submit to the **Resident Engineer** a breakdown of its bid price, or of lump sums bid for items of the **Contract**, showing the various operations to be performed under the **Contract**, as directed in the progress schedule required under Article 9, and the value of each of such operations, the total of such items to equal the lump sum price bid. Said breakdown must be approved in writing by the **Resident Engineer**.
- 41.2 No partial payment will be approved until the **Contractor** submits a bid breakdown that is acceptable to the **Resident Engineer**.
- 41.3 The **Contractor** shall also submit such other information relating to the bid breakdown as directed by the **Resident Engineer**. Thereafter, the breakdown may be used only for checking the **Contractor's** applications for partial payments hereunder, but shall not be binding upon the **City**, the **Commissioner**, or the **Engineer** for any purpose whatsoever.

ARTICLE 42. PARTIAL PAYMENTS

- 42.1 From time to time as the **Work** progresses satisfactorily, but not more often than once each calendar month (except where the **Commissioner** approves in writing the submission of invoices on a more frequent basis and for invoices relating to **Work** performed pursuant to a change order), the **Contractor** may submit to the **Engineer** a requisition for a partial payment in the prescribed form, which shall contain an estimate of the quantity and the fair value of the **Work** done during the payment period.
- 42.2 Partial payments may be made for materials, fixtures, and equipment in advance of their actual incorporation in the **Work**, as the **Commissioner** may approve, and upon the terms and conditions set forth in the General Conditions.
- 42.3 The **Contractor** shall also submit to the **Commissioner** in connection with every application for partial payment a verified statement in the form prescribed by the **Comptroller** setting forth the information required under Labor Law Section 220-a.

42.4 Within thirty (30) **Days** after receipt of a satisfactory payment application, and within sixty (60) **Days** after receipt of a satisfactory payment application in relation to **Work** performed pursuant to a change order, the **Engineer** will prepare and certify, and the **Commissioner** will approve, a voucher for a partial payment in the amount of such approved estimate, less any and all deductions authorized to be made by the **Commissioner** under the terms of this **Contract** or by **Law**.

ARTICLE 43. PROMPT PAYMENT

- 43.1 The Prompt Payment provisions of the **PPB** Rules in effect at the time of the bid will be applicable to payments made under this **Contract**. The provisions require the payment to the **Contractor** of interest on payments made after the required payment date, except as set forth in the **PPB** Rules.
- 43.2 The **Contractor** shall submit a proper invoice to receive payment, except where the **Contract** provides that the **Contractor** will be paid at predetermined intervals without having to submit an invoice for each scheduled payment.
 - 43.3 Determination of interest due will be made in accordance with the **PPB** Rules.
- 43.4 If the **Contractor** is paid interest, the proportionate share(s) of that interest shall be forwarded by the **Contractor** to its **Subcontractor**(s).
- 43.5 The **Contractor** shall pay each **Subcontractor** or **Materialman** not later than seven (7) **Days** after receipt of payment out of amounts paid to the **Contractor** by the **City** for **Work** performed by the **Subcontractor** or **Materialman** under this **Contract**.
 - 43.5.1 If **Contractor** fails to make any payment to any **Subcontractor** or **Materialman** within seven (7) **Days** after receipt of payment by the **City** pursuant to this Article 43.5, then the **Contractor** shall pay interest on amounts due to such **Subcontractor** or **Materialman** at the rate of interest in effect on the date such payment is made by the **Contractor** computed in accordance with Section 756-b (1)(b) of the New York General Business Law. Accrual of interest shall commence on the **Day** immediately following the expiration of the seventh **Day** following receipt of payment by the **Contractor** from the **City** and shall end on the date on which payment is made.
- 43.6 The **Contractor** shall include in each of its subcontracts a provision requiring each **Subcontractor** to make payment to each of its **Subcontractors** or **Materialmen** for **Work** performed under this **Contract** in the same manner and within the same time period set forth above.

ARTICLE 44. SUBSTANTIAL COMPLETION PAYMENT

- 44.1 The **Contractor** shall submit with the **Substantial Completion** requisition:
 - 44.1.1 A final verified statement of any pending Article 27 disputes in accordance with the **PPB** Rules and this **Contract** and any and all alleged claims against the **City**, in any way connected with or arising out of this **Contract** (including those as to which details may have been furnished pursuant to Articles 11, 27, 28, and 30) setting forth with respect to each such claim the total amount thereof, the various items of labor and materials included therein, and the alleged value of each item; and if the alleged claim be one for delay, the alleged cause of each such delay, the period or periods of time, giving the dates when the

Contractor claims the performance of the **Work** or a particular part thereof was delayed, and an itemized statement and breakdown of the amount claimed for each such delay.

44.1.1(a) With respect to each such claim, the **Commissioner**, the **Comptroller** and, in the event of litigation, the **City** Corporation Counsel shall have the same right to inspect, and to make extracts or copies of, the **Contractor's** books, vouchers, records, etc., as is referred to in Articles 11, 27, 28, and 30. Nothing contained in this Article 44.1.1(a) is intended to or shall relieve the **Contractor** from the obligation of complying strictly with Articles 11, 27, 28, and 30. The **Contractor** is warned that unless such claims are completely set forth as herein required, the **Contractor** upon acceptance of the **Substantial Completion** payment pursuant to this Article 44, will have waived any such claims.

44.1.2 A Final Approved Punch List.

- 44.1.3 Where required, a request for an extension of time to achieve **Substantial Completion** or final extension of time.
- 44.2 The **Commissioner** shall issue a voucher calling for payment of any part or all of the balance due for **Work** performed under the **Contract**, including monies retained under Article 21, less any and all deductions authorized to be made by the **Commissioner**, under this **Contract** or by **Law**, and less twice the amount the **Commissioner** considers necessary to ensure the completion of the balance of the **Work** by the **Contractor**. Such a payment shall be considered a partial and not a final payment. No **Substantial Completion** payment shall be made under this Article 44 where the **Contractor** failed to complete the **Work** within the time fixed for such completion in the Schedule A of the General Conditions, or within the time to which completion may have been extended, until an extension or extensions of time for the completion of **Work** have been acted upon pursuant to Article 13.
- 44.3 No further partial payments shall be made to the **Contractor** after **Substantial Completion**, except the **Substantial Completion** payment and payment pursuant to any **Contractor's** requisition that were properly filed with the **Commissioner** prior to the date of **Substantial Completion**; however, the **Commissioner** may grant a waiver for further partial payments after the date of **Substantial Completion** to permit payments for change order **Work** and/or release of retainage and deposits pursuant to Articles 21 and 24. Such waiver shall be in writing.
- 44.4 The **Contractor** acknowledges that nothing contained in this Article 44 is intended to or shall in any way diminish the force and effect of Article 13.

ARTICLE 45. FINAL PAYMENT

45.1 After completion and **Final Acceptance** of the **Work**, the **Contractor** shall submit all required certificates and documents, together with a requisition for the balance claimed to be due under the **Contract**, less the amount authorized to be retained for maintenance under Article 24. Such submission shall be within 90 days of the date of the **Commissioner's** written determination of **Final Acceptance**, or within such additional time as may be granted by the **Commissioner** in writing. If the **Contractor** fails to submit all required certificates and documents within the time allowed, no payment of the balance claimed shall be made to the **Contractor** and the **Contractor** shall be deemed to have forfeited its right to payment of any balance claimed. A verified statement similar to that required in connection with applications for partial payments shall also be submitted to the **Commissioner**.

- 45.2 Amended Verified Statement of Claims: The Contractor shall also submit with the final requisition any amendments to the final verified statement of any pending dispute resolution procedures in accordance with the PPB Rules and this Contract and any and all alleged claims against the City, in any way connected with or arising out of this Contract (including those as to which details may have been furnished pursuant to Articles 11, 27, 28, and 30) that have occurred subsequent to Substantial Completion, setting forth with respect to each such claim the total amount thereof, the various items of labor and materials included therein, and the alleged value of each such item; and if the alleged claim be one for delay, the alleged cause of each such delay, the period or periods of time, giving the dates when the Contractor claims the performance of the Work or a particular part thereof was delayed, and an itemized statement and breakdown of the amount claimed for each such delay. With reference to each such claim, the Commissioner, the Comptroller and, in the event of litigation, the City Corporation Counsel shall have the same right to inspect, and to make extracts or copies of, the Contractor's books, vouchers, records, etc., as is referred to in Articles 11, 27, 28, and 30. Nothing contained in this Article 45.2, is intended to or shall relieve the **Contractor** from the obligation of complying strictly with Articles 11, 27, 28, and 30. The Contractor is warned that unless such claims are completely set forth as herein required, the Contractor, upon acceptance of the Final Payment pursuant to Article 46, will have waived any such claims.
- 45.3 Preparation of Final Voucher: Upon determining the balance due hereunder other than on account of claims, the **Engineer** will prepare and certify, for the Commissioner's approval, a voucher for final payment in that amount less any and all deductions authorized to be made by the **Commissioner** under this **Contract** or by **Law**. In the case of a lump sum **Contract**, the **Commissioner** shall certify the voucher for final payment within thirty (30) **Days** from the date of completion and acceptance of the **Work**, provided all requests for extensions of time have been acted upon.
 - 45.3.1 All prior certificates and vouchers upon which partial payments were made, being merely estimates made to enable the **Contractor** to prosecute the **Work** more advantageously, shall be subject to correction in the final voucher, and the certification of the **Engineer** thereon and the approval of the **Commissioner** thereof, shall be conditions precedent to the right of the **Contractor** to receive any money hereunder. Such final voucher shall be binding and conclusive upon the **Contractor**.
 - 45.3.2 Payment pursuant to such final voucher, less any deductions authorized to be made by the **Commissioner** under this **Contract** or by **Law**, shall constitute the final payment, and shall be made by the **Comptroller** within thirty (30) **Days** after the filing of such voucher in his/her office.
- 45.4 The **Contractor** acknowledges that nothing contained in this Article 45 is intended to or shall in any way diminish the force and effect of Article 13.

ARTICLE 46. ACCEPTANCE OF FINAL PAYMENT

46.1 The acceptance by the **Contractor**, or by anyone claiming by or through it, of the final payment, whether such payment be made pursuant to any judgment of any court, or otherwise, shall constitute and operate as a release of the **City** from any and all claims of and liability to the **Contractor** for anything heretofore done or furnished for the **Contractor** relating to or arising out of this **Contract** and the **Work** done hereunder, and for any prior act, neglect or default on the part of the **City** or any of its officials, agents or employees, excepting only a claim against the **City** for the amounts deducted or retained in accordance with the terms and provisions of this **Contract** or by **Law**, and excepting any claims, not otherwise waived, or any pending dispute resolution procedures which are contained in the

verified statement filed with the **Contractor's** substantial and final requisitions pursuant to Articles 44 and 45.

- 46.2 The **Contractor** is warned that the execution by it of a release, in connection with the acceptance of the final payment, containing language purporting to reserve claims other than those herein specifically excepted from the operation of this Article 46, or those for amounts deducted by the **Commissioner** from the final requisition or from the final payment as certified by the **Engineer** and approved by the **Commissioner**, shall not be effective to reserve such claims, anything stated to the **Contractor** orally or in writing by any official, agent or employee of the **City** to the contrary notwithstanding.
- 46.3 Should the **Contractor** refuse to accept the final payment as tendered by the **Comptroller**, it shall constitute a waiver of any right to interest thereon.
- 46.4 The **Contractor**, however, shall not be barred by this Article 46 from commencing an action for breach of **Contract** to the extent permitted by **Law** and by the terms of the **Contract** for any claims that are contained in the verified statement filed with the **Contractor's** substantial and final requisitions pursuant to Articles 44 and 45 or that arose after submission of the final payment requisition, provided that a detailed and verified statement of claim is served upon the contracting **Agency** and **Comptroller** not later than forty (40) **Days** after the making of such final payment by electronic funds transfer (EFT) or the mailing of such final payment. The statement shall specify the items upon which the claim will be based and any such claim shall be limited to such items.

ARTICLE 47. APPROVAL BY PUBLIC DESIGN COMMISSION

47.1 All works of art, including paintings, mural decorations, stained glass, statues, bas-reliefs, and other sculptures, monuments, fountains, arches, and other structures of a permanent character intended for ornament or commemoration, and every design of the same to be used in the performance of this **Contract**, and the design of all bridges, approaches, buildings, gates, fences, lamps, or structures to be erected, pursuant to the terms of this **Contract**, shall be submitted to the Art Commission, d/b/a the Public Design Commission of the City of New York, and shall be approved by the Public Design Commission prior to the erection or placing in position of the same. The final payment shall not become due or payable under this **Contract** unless and until the Public Design Commission shall certify that the design for the **Work** herein contracted for has been approved by the said Public Design Commission, and that the same has been executed in substantial accordance with the design so approved, pursuant to the provisions of Chapter 37, Section 854 of the **City** Charter, as amended.

CHAPTER X: CONTRACTOR'S DEFAULT

ARTICLE 48. COMMISSIONER'S RIGHT TO DECLARE CONTRACTOR IN DEFAULT

- 48.1 In addition to those instances specifically referred to in other Articles herein, the **Commissioner** shall have the right to declare the **Contractor** in default of this **Contract** if:
 - 48.1.1 The **Contractor** fails to commence **Work** when notified to do so by the **Commissioner**; or if
 - 48.1.2 The **Contractor** shall abandon the **Work**; or if

- 48.1.3 The **Contractor** shall refuse to proceed with the **Work** when and as directed by the **Commissioner**: or if
- 48.1.4 The **Contractor** shall, without just cause, reduce its working force to a number which, if maintained, would be insufficient, in the opinion of the **Commissioner**, to complete the **Work** in accordance with the progress schedule; or if
- 48.1.5 The **Contractor** shall fail or refuse to increase sufficiently such working force when ordered to do so by the **Commissioner**; or if
- 48.1.6 The **Contractor** shall sublet, assign, transfer, convert or otherwise dispose of this **Contract** other than as herein specified; or sell or assign a majority interest in the **Contractor**; or if
- 48.1.7 The **Contractor** fails to secure and maintain all required insurance; or if
- 48.1.8 A receiver or receivers are appointed to take charge of the **Contractor's** property or affairs; or if
- 48.1.9 The **Commissioner** shall be of the opinion that the **Contractor** is or has been unnecessarily or unreasonably or willfully delaying the performance and completion of the **Work**, or the award of necessary subcontracts, or the placing of necessary material and equipment orders; or if
- 48.1.10 The **Commissioner** shall be of the opinion that the **Contractor** is or has been willfully or in bad faith violating any of the provisions of this **Contract**; or if
- 48.1.11 The **Commissioner** shall be of the opinion that the **Work** cannot be completed within the time herein provided therefor or within the time to which such completion may have been extended; provided, however, that the impossibility of timely completion is, in the **Commissioner's** opinion, attributable to conditions within the **Contractor's** control; or if
- 48.1.12 The **Work** is not completed within the time herein provided therefor or within the time to which the **Contractor** may be entitled to have such completion extended; or if
- 48.1.13 Any statement or representation of the **Contractor** in the **Contract** or in any document submitted by the **Contractor** with respect to the **Work**, the **Project**, or the **Contract** (or for purposes of securing the **Contract**) was untrue or incorrect when made; or if
- 48.1.14 The **Contractor** or any of its officers, directors, partners, five (5%) percent shareholders, principals, or other persons substantially involved in its activities, commits any of the acts or omissions specified as the grounds for debarment in the **PPB** Rules.
- 48.2 Before the **Commissioner** shall exercise his/her right to declare the **Contractor** in default, the **Commissioner** shall give the **Contractor** an opportunity to be heard, upon not less than two (2) **Days**' notice.

ARTICLE 49. EXERCISE OF THE RIGHT TO DECLARE DEFAULT

- 49.1 The right to declare the **Contractor** in default for any of the grounds specified or referred to in Article 48 shall be exercised by sending the **Contractor** a notice, signed by the **Commissioner**, setting forth the ground or grounds upon which such default is declared (hereinafter referred to as a "Notice of Default").
- 49.2 The **Commissioner's** determination that the **Contractor** is in default shall be conclusive, final, and binding on the parties and such a finding shall preclude the **Contractor** from commencing a plenary action for any damages relating to the **Contract**. If the **Contractor** protests the determination of the **Commissioner**, the **Contractor** may commence an action in a court of competent jurisdiction of the State of New York under Article 78 of the New York Civil Practice Law and Rules.

ARTICLE 50. QUITTING THE SITE

50.1 Upon receipt of such notice the **Contractor** shall immediately discontinue all further operations under this **Contract** and shall immediately quit the **Site**, leaving untouched all plant, materials, equipment, tools, and supplies then on the **Site**.

ARTICLE 51. COMPLETION OF THE WORK

- 51.1 The **Commissioner**, after declaring the **Contractor** in default, may then have the **Work** completed by such means and in such manner, by contract with or without public letting, or otherwise, as he/she may deem advisable, utilizing for such purpose such of the **Contractor's** plant, materials, equipment, tools, and supplies remaining on the **Site**, and also such **Subcontractors**, as he/she may deem advisable.
- 51.2 After such completion, the **Commissioner** shall make a certificate stating the expense incurred in such completion, which shall include the cost of re-letting and also the total amount of liquidated damages (at the rate provided for in the **Contract**) from the date when the **Work** should have been completed by the **Contractor** in accordance with the terms hereof to the date of actual completion of the **Work**. Such certificate shall be binding and conclusive upon the **Contractor**, its sureties, and any person claiming under the **Contractor**, as to the amount thereof.
- 51.3 The expense of such completion, including any and all related and incidental costs, as so certified by the **Commissioner**, and any liquidated damages assessed against the **Contractor**, shall be charged against and deducted out of monies which are earned by the **Contractor** prior to the date of default. Should the expense of such completion, as certified by the **Commissioner**, exceed the total sum which would have been payable under the **Contract** if it had been completed by the **Contractor**, any excess shall be paid by the **Contractor**.

ARTICLE 52. PARTIAL DEFAULT

52.1 In case the **Commissioner** shall declare the **Contractor** in default as to a part of the **Work** only, the **Contractor** shall discontinue such part, shall continue performing the remainder of the **Work** in strict conformity with the terms of this **Contract**, and shall in no way hinder or interfere with any **Other Contractor(s)** or persons whom the **Commissioner** may engage to complete the **Work** as to which the **Contractor** was declared in default.

52.2 The provisions of this Chapter relating to declaring the **Contractor** in default as to the entire **Work** shall be equally applicable to a declaration of partial default, except that the **Commissioner** shall be entitled to utilize for completion of the part of the **Work** as to which the **Contractor** was declared in default only such plant, materials, equipment, tools, and supplies as had been previously used by the **Contractor** on such part.

ARTICLE 53. PERFORMANCE OF UNCOMPLETED WORK

53.1 In completing the whole or any part of the **Work** under the provisions of this Chapter X, the **Commissioner** shall have the power to depart from or change or vary the terms and provisions of this **Contract**, provided, however, that such departure, change or variation is made for the purpose of reducing the time or expense of such completion. Such departure, change or variation, even to the extent of accepting a lesser or different performance, shall not affect the conclusiveness of the **Commissioner's** certificate of the cost of completion referred to in Article 51, nor shall it constitute a defense to an action to recover the amount by which such certificate exceeds the amount which would have been payable to the **Contractor** hereunder but for its default.

ARTICLE 54. OTHER REMEDIES

- 54.1 In addition to the right to declare the **Contractor** in default pursuant to this Chapter X, the **Commissioner** shall have the absolute right, in his/her sole discretion and without a hearing, to complete or cause to be completed in the same manner as described in Articles 51 and 53, any or all unsatisfactory or uncompleted punch list **Work** that remains after the completion date specified in the **Final Approved Punch List**. A written notice of the exercise of this right shall be sent to the **Contractor** who shall immediately quit the **Site** in accordance with the provisions of Article 50.
- 54.2 The expense of completion permitted under Article 54.1, including any and all related and incidental costs, as so certified by the **Commissioner**, shall be charged against and deducted out of monies which have been earned by the **Contractor** prior to the date of the exercise of the right set forth in Article 54.1; the balance of such monies, if any, subject to the other provisions of this **Contract**, to be paid to the **Contractor** without interest after such completion. Should the expense of such completion, as certified by the **Commissioner**, exceed the total sum which would have been payable under the **Contract** if it had been completed by the **Contractor**, any excess shall be paid by the **Contractor**.
- 54.3 The previous provisions of this Chapter X shall be in addition to any and all other remedies available under **Law** or in equity.
- 54.4 The exercise by the **City** of any remedy set forth herein shall not be deemed a waiver by the **City** of any other legal or equitable remedy contained in this **Contract** or provided under **Law**.

CHAPTER XI: MISCELLANEOUS PROVISIONS

ARTICLE 55. CONTRACTOR'S WARRANTIES

55.1 In consideration of, and to induce, the award of this **Contract** to the **Contractor**, the **Contractor** represents and warrants:

- 55.1.1 That it is financially solvent, sufficiently experienced and competent to perform the **Work**: and
- 55.1.2 That the facts stated in its bid and the information given by it pursuant to the Information for Bidders is true and correct in all respects; and
- 55.1.3 That it has read and complied with all requirements set forth in the **Contract**.

ARTICLE 56. CLAIMS AND ACTIONS THEREON

- 56.1 Any claim, that is not subject to dispute resolution under the **PPB** Rules or this **Contract**, against the **City** for damages for breach of **Contract** shall not be made or asserted in any action, unless the **Contractor** shall have strictly complied with all requirements relating to the giving of notice and of information with respect to such claims, as herein before provided.
- 56.2 Nor shall any action be instituted or maintained on any such claims unless such action is commenced within six (6) months after **Substantial Completion**; except that:
 - 56.2.1 Any claims arising out of events occurring after **Substantial Completion** and before **Final Acceptance** of the **Work** shall be asserted within six (6) months of **Final Acceptance** of the **Work**;
 - 56.2.2 If the **Commissioner** exercises his/her right to complete or cause to complete any or all unsatisfactory or uncompleted punch list **Work** that remains after the completion date specified in the **Final Approved Punch List** pursuant to Article 54, any such action shall be commenced within six (6) months from the date the **Commissioner** notifies the **Contractor** in writing that he/she has exercised such right. Any claims for monies deducted, retained or withheld under the provisions of this **Contract** shall be asserted within six (6) months after the date when such monies otherwise become due and payable hereunder; and
 - 56.2.3 If the **Commissioner** exercises his/her right to terminate the **Contract** pursuant to Article 64, any such action shall be commenced within six (6) months of the date the **Commissioner** exercises said right.

ARTICLE 57. INFRINGEMENT

57.1 The **Contractor** shall be solely responsible for and shall defend, indemnify, and hold the **City** harmless from any and all claims (even if the allegations of the lawsuit are without merit) and judgments for damages and from costs and expenses to which the **City** may be subject to or which it may suffer or incur allegedly arising out of or in connection with any infringement by the **Contractor** of any copyright, trade secrets, trademark or patent rights or any other property or personal right of any third party by the **Contractor** and/or its **Subcontractors** in the performance or completion of the **Work**. Insofar as the facts or **Law** relating to any claim would preclude the **City** from being completely indemnified by the **Contractor**, the **City** shall be partially indemnified by the **Contractor** to the fullest extent permitted by **Law**.

ARTICLE 58. NO CLAIM AGAINST OFFICIALS, AGENTS OR EMPLOYEES

58.1 No claim whatsoever shall be made by the **Contractor** against any official, agent or employee of the **City** for, or on account of, anything done or omitted to be done in connection with this **Contract**.

ARTICLE 59. SERVICE OF NOTICES

- 59.1 The **Contractor** hereby designates the business address, fax number, and email address specified in its bid, as the place where all notices, directions or other communications to the **Contractor** may be delivered, or to which they may be mailed. Any notice, direction, or communication from either party to the other shall be in writing and shall be deemed to have been given when (i) delivered personally; (ii) sent by certified mail, return receipt requested; (iii) delivered by overnight or same day courier service in a properly addressed envelope with confirmation; or (iv) sent by fax or email and, unless receipt of the fax or e-mail is acknowledged by the recipient by fax or e-mail, deposited in a post office box regularly maintained by the United States Postal Service in a properly addressed, postage prepaid envelope.
- 59.2 **Contractor's** notice address, email address, or fax number may be changed at any time by an instrument in writing, executed and acknowledged by the **Contractor**, and delivered to the **Commissioner**.
- 59.3 Nothing herein contained shall, however, be deemed to preclude or render inoperative the service of any notice, direction or other communication upon the **Contractor** personally, or, if the **Contractor** is a corporation, upon any officer thereof.

ARTICLE 60. UNLAWFUL PROVISIONS DEEMED STRICKEN FROM CONTRACT

60.1 If this **Contract** contains any unlawful provision not an essential part of the **Contract** and which shall not appear to have been a controlling or material inducement to the making thereof, the same shall be deemed of no effect and shall, upon notice by either party, be deemed stricken from the **Contract** without affecting the binding force of the remainder.

ARTICLE 61. ALL LEGAL PROVISIONS DEEMED INCLUDED

61.1 It is the intent and understanding of the parties to this **Contract** that each and every provision of **Law** required to be inserted in this **Contract** shall be and is inserted herein. Furthermore, it is hereby stipulated that every such provision is to be deemed to be inserted herein, and if, through mistake or otherwise, any such provision is not inserted, or is not inserted in correct form, then this **Contract** shall forthwith upon the application of either party be amended by such insertion so as to comply strictly with the **Law** and without prejudice to the rights of either party hereunder.

ARTICLE 62. TAX EXEMPTION

62.1 The **City** is exempt from payment of Federal, State, and local taxes, including sales and compensating use taxes of the State of New York and its cities and counties on all tangible personal property sold to the **City** pursuant to the provisions of this **Contract**. These taxes are not to be included in bids. However, this exemption does not apply to tools, machinery, equipment or other property leased by or to the **Contractor**, **Subcontractor** or **Materialman** or to tangible personal property which, even

though it is consumed, is not incorporated into the completed **Work** (consumable supplies) and tangible personal property that the **Contractor** is required to remove from the **Site** during or upon completion of the **Work**. The **Contractor** and its **Subcontractors** and **Materialmen** shall be responsible for and pay any and all applicable taxes, including sales and compensating use taxes, on such leased tools, machinery, equipment or other property and upon all such consumable supplies and tangible personal property that the **Contractor** is required to remove from the **Site** during or upon completion of the **Work**.

- 62.2 The **Contractor** agrees to sell and the **City** agrees to purchase all tangible personal property, other than consumable supplies and other tangible personal property that the **Contractor** is required to remove from the **Site** during or upon completion of the **Work**, that is required, necessary or proper for or incidental to the construction of the **Project** covered by this **Contract**. The sum paid under this **Contract** for such tangible personal property shall be in full payment and consideration for the sale of such tangible personal property.
 - 62.2.1 The **Contractor** agrees to construct the **Project** and to perform all **Work**, labor and services rendered, necessary, proper or incidental thereto for the sum shown in the bid for the performance of such **Work**, labor, and services, and the sum so paid pursuant to this **Contract** for such **Work**, labor, and services, shall be in full consideration for the performance by the **Contractor** of all its duties and obligations under this **Contract** in connection with said **Work**, labor, and services.
- 62.3 20 NYCRR Section 541.3(d) provides that a **Contractor**'s purchases of tangible personal property that is either incorporated into real property owned by a governmental entity or purchased for and sold to a governmental entity are exempt from sales and use tax. The **City** shall not pay sales tax for any such tangible personal property that it purchases from the **Contractor** pursuant to the **Contract.** With respect to such tangible personal property, the **Contractor**, at the request of the **City**, shall furnish to the **City** such bills of sale and other instruments as may be required by the **City**, properly executed, acknowledged and delivered assuring to the **City** title to such tangible personal property, free of liens and/or encumbrances, and the **Contractor** shall mark or otherwise identify all such tangible personal property as the property of the **City**.
- 62.4 Title to all tangible personal property to be sold by the **Contractor** to the **City** pursuant to the provisions of the **Contract** shall immediately vest in and become the sole property of the **City** upon delivery of such tangible personal property to the **Site**. Notwithstanding such transfer of title, the **Contractor** shall have the full and continuing responsibility to install such tangible personal property in accordance with the provisions of this **Contract**, protect it, maintain it in a proper condition and forthwith repair, replace and make good any damage thereto, theft or disappearance thereof, and furnish additional tangible personal property in place of any that may be lost, stolen or rendered unusable, without cost to the **City**, until such time as the **Work** covered by the **Contract** is fully accepted by the **City**. Such transfer of title shall in no way affect any of the **Contractor's** obligations hereunder. In the event that, after title has passed to the **City**, any of the tangible personal property is rejected as being defective or otherwise unsatisfactory, title to all such tangible personal property shall be deemed to have been transferred back to the **Contractor**.
- 62.5 The purchase by **Subcontractors** or **Materialmen** of tangible personal property to be sold hereunder shall be a purchase or procurement for resale to the **Contractor** (either directly or through other **Subcontractors**) and therefore not subject to the aforesaid sales and compensating use taxes, provided that the subcontracts and purchase agreements provide for the resale of such tangible personal property and that such subcontracts and purchase agreements are in a form similar to this **Contract** with respect to the separation of the sale of consumable supplies and tangible personal property that the

Contractor is required to remove from the **Site** during or upon completion of the **Work** from the **Work** and labor, services, and any other matters to be provided, and provided further that the subcontracts and purchase agreements provide separate prices for tangible personal property and all other services and matters. Such separation shall actually be followed in practice, including the separation of payments for tangible personal property from the payments for other **Work** and labor and other things to be provided.

- 62.6 The **Contractor** and its **Subcontractors** and **Materialmen** shall furnish a **Contractor** Exempt Purchase Certificate to all persons, firms or corporations from which they purchase tangible personal property for the performance of the **Work** covered by this **Contract**.
- 62.7 In the event any of the provisions of this Article 62 shall be deemed to be in conflict with any other provisions of this **Contract** or create any ambiguity, then the provisions of this Article 62 shall control.

ARTICLE 63. INVESTIGATION(S) CLAUSE

- 63.1 The parties to this **Contract** agree to cooperate fully and faithfully with any investigation, audit or inquiry conducted by a United States, a State of New York (State) or a **City** governmental agency or authority that is empowered directly or by designation to compel the attendance of witnesses and to examine witnesses under oath, or conducted by the Inspector General of a governmental agency that is a party in interest to the transaction, submitted bid, submitted proposal, contract, lease, permit or license that is the subject of the investigation, audit or inquiry.
- 63.2 If any person who has been advised that his/her statement, and any information from such statement, will not be used against him/her in any subsequent criminal proceeding refuses to testify before a grand jury or other governmental agency or authority empowered directly or by designation to compel the attendance of witnesses and to examine witnesses under oath concerning the award of or performance under any transaction, agreement, lease, permit, contract, or license entered into with the **City**, the State, or any political subdivision or public authority thereof, or the Port Authority of New York and New Jersey, or any local development corporation within the **City**, or any public benefit corporation organized under the **Laws** of the State of New York, or;
- 63.3 If any person refuses to testify for a reason other than the assertion of his/her privilege against self incrimination in an investigation, audit or inquiry conducted by a **City** or State governmental agency or authority empowered directly or by designation to compel the attendance of witnesses and to take testimony under oath, or by the Inspector General of the governmental agency that is a party in interest in, and is seeking testimony concerning the award of, or performance under any transaction, agreement, lease, permit, contract, or license entered into with the **City**, the State, or any political subdivision thereof or any local development corporation within the **City**, then;
- 63.4 The **Commissioner** whose **Agency** is a party in interest to the transaction, submitted bid, submitted proposal, contract, lease, permit, or license shall convene a hearing, upon not less than five (5) **Days**' written notice to the parties involved to determine if any penalties should attach for the failure of a person to testify.
- 63.5 If any non-governmental party to the hearing requests an adjournment, the **Commissioner** who convened the hearing may, upon granting the adjournment, suspend any contract, lease, permit, or license, pending the final determination pursuant to Article 63.7 without the **City** incurring any penalty or damages for delay or otherwise.

- 63.6 The penalties which may attach after a final determination by the **Commissioner** may include but shall not exceed:
 - 63.6.1 The disqualification for a period not to exceed five (5) years from the date of an adverse determination for any person, or any entity of which such person was a member at the time the testimony was sought, from submitting bids for, or transacting business with, or entering into or obtaining any contract, lease, permit or license with or from the **City**; and/or
 - 63.6.2 The cancellation or termination of any and all such existing **City** contracts, leases, permits or licenses that the refusal to testify concerns and that have not been assigned as permitted under this **Contract**, nor the proceeds of which pledged, to an unaffiliated and unrelated institutional lender for fair value prior to the issuance of the notice scheduling the hearing, without the **City** incurring any penalty or damages on account of such cancellation or termination; monies lawfully due for goods delivered, work done, rentals, or fees accrued prior to the cancellation or termination shall be paid by the **City**.
- 63.7 The **Commissioner** shall consider and address in reaching his/her determination and in assessing an appropriate penalty the factors in Articles 63.7.1 and 63.7.2. The **Commissioner** may also consider, if relevant and appropriate, the criteria established in Articles 63.7.3 and 63.7.4, in addition to any other information which may be relevant and appropriate:
 - 63.7.1 The party's good faith endeavors or lack thereof to cooperate fully and faithfully with any governmental investigation or audit, including but not limited to the discipline, discharge, or disassociation of any person failing to testify, the production of accurate and complete books and records, and the forthcoming testimony of all other members, agents, assignees or fiduciaries whose testimony is sought.
 - 63.7.2 The relationship of the person who refused to testify to any entity that is a party to the hearing, including but not limited to, whether the person whose testimony is sought has an ownership interest in the entity and/or the degree of authority and responsibility the person has within the entity.
 - 63.7.3 The nexus of the testimony sought to the subject entity and its contracts, leases, permits or licenses with the **City**.
 - 63.7.4 The effect a penalty may have on an unaffiliated and unrelated party or entity that has a significant interest in an entity subject to penalties under Article 63.6, provided that the party or entity has given actual notice to the **Commissioner** upon the acquisition of the interest, or at the hearing called for in Article 63.4, gives notice and proves that such interest was previously acquired. Under either circumstance the party or entity shall present evidence at the hearing demonstrating the potential adverse impact a penalty will have on such person or entity.

63.8 Definitions:

- 63.8.1 The term "license" or "permit" as used in this Article 63 shall be defined as a license, permit, franchise or concession not granted as a matter of right.
- 63.8.2 The term "person" as used in this Article 63 shall be defined as any natural person doing business alone or associated with another person or entity as a partner, director, officer, principal or employee.

- 63.8.3 The term "entity" as used in this Article 63 shall be defined as any firm, partnership, corporation, association, joint venture, or person that receives monies, benefits, licenses, leases, or permits from or through the **City** or otherwise transacts business with the **City**.
- 63.8.4 The term "member" as used in this Article 63 shall be defined as any person associated with another person or entity as a partner, director, officer, principal or employee.
- 63.9 In addition to and notwithstanding any other provision of this **Contract**, the **Commissioner** may in his/her sole discretion terminate this **Contract** upon not less than three (3) **Days'** written notice in the event the **Contractor** fails to promptly report in writing to the **Commissioner** of the Department of Investigations ("DOI") of the **City** any solicitation of money, goods, requests for future employment or other benefit or thing of value, by or on behalf of any employee of the **City** or other person, firm, corporation or entity for any purpose which may be related to the procurement or obtaining of this **Contract** by the **Contractor**, or affecting the performance of this **Contract**.

ARTICLE 64. TERMINATION BY THE CITY

- 64.1 In addition to termination pursuant to any other article of this **Contract**, the **Commissioner** may, at any time, terminate this **Contract** by written notice to the **Contractor**. In the event of termination, the **Contractor** shall, upon receipt of such notice, unless otherwise directed by the **Commissioner**:
 - 64.1.1 Stop **Work** on the date specified in the notice;
 - 64.1.2 Take such action as may be necessary for the protection and preservation of the **City's** materials and property;
 - 64.1.3 Cancel all cancelable orders for material and equipment;
 - 64.1.4 Assign to the **City** and deliver to the **Site** or another location designated by the **Commissioner**, any non-cancelable orders for material and equipment that is not capable of use except in the performance of this **Contract** and has been specifically fabricated for the sole purpose of this **Contract** and not incorporated in the **Work**;
 - 64.1.5 Take no action which will increase the amounts payable by the **City** under this **Contract**.
- 64.2 In the event of termination by the **City** pursuant to this Article 64, payment to the **Contractor** shall be in accordance with Articles 64.2.1, 64.2.2 or 64.2.3, to the extent that each respective article applies.
 - 64.2.1 Lump Sum Contracts or Items: On all lump sum **Contracts**, or on lump sum items in a **Contract**, the **City** will pay the **Contractor** the sum of the amounts described in Articles 64.2.1(a) and 64.2.1(b), less all payments previously made pursuant to this **Contract**. On lump sum **Contracts** only, the **City** will also pay the **Contractor** an additional sum as provided in Article 64.2.1(c).
 - 64.2.1(a) For **Work** completed prior to the notice of termination, the **Contractor** shall be paid a pro rata portion of the lump sum bid amount, plus approved change orders, based upon the percent completion of the **Work**, as determined by the

Commissioner. For the purpose of determining the pro rata portion of the lump sum bid amount to which the **Contractor** is entitled, the bid breakdown submitted in accordance with Article 41 shall be considered, but shall not be dispositive. The **Commissioner's** determination hereunder shall be final, binding, and conclusive.

64.2.1(b) For non-cancelable material and equipment that is not capable of use except in the performance of this **Contract** and has been specifically fabricated for the sole purpose of this **Contract**, but not yet incorporated in the **Work**, the **Contractor** shall be paid the lesser of the following, less salvage value:

64.2.1(b)(i) The Direct Cost, as defined in Article 64.2.4; or

64.2.1(b)(ii) The fair and reasonable value, if less than Direct Cost, of such material and equipment, plus necessary and reasonable delivery costs.

64.2.1(b)(iii) In addition, the **Contractor** shall be paid five (5%) percent of the amount described in Article 64.2.1(b)(i) or Article 64.2.1(b)(ii), whichever applies.

64.2.1(c) Except as otherwise provided in Article 64.2.1(d), on all lump sum **Contracts**, the **Contractor** shall be paid the percentage indicated below applied to the difference between the total lump sum bid amount and the total of all payments made prior to the notice of termination plus all payments allowed pursuant to Articles 64.2.1(a) and 64.2.1(b):

64.2.1(c)(i) Five (5%) percent of the first five million (\$5,000,000) dollars; and

64.2.1(c)(ii) Three (3%) percent of any amount between five million (\$5,000,000) dollars and fifteen million (\$15,000,000) dollars; plus

64.2.1(c)(iii) One (1%) percent of any amount over fifteen million (\$15,000,000) dollars.

64.2.1(d) In the event the **City** terminates a lump sum **Contract** pursuant to this Article 64 within ninety (90) **Days** after registration of the **Contract** with the **Comptroller**, the **Contractor** shall be paid one (1%) percent of the difference between the lump sum bid amount and the total of all payments made pursuant to this Article 64.2.

64.2.2 Unit Price Contracts or Items: On all unit price **Contracts**, or on unit price items in a **Contract**, the **City** will pay the **Contractor** the sum of the amounts described in Articles 64.2.2(a) and 64.2.2(b), less all payments previously made pursuant to this **Contract**:

64.2.2(a) For all completed units, the unit price stated in the **Contract**, and

64.2.2(b) For units that have been ordered but are only partially completed, the **Contractor** will be paid:

64.2.2(b)(i) A pro rata portion of the unit price stated in the **Contract** based upon the percent completion of the unit and

79

- 64.2.2(b)(ii) For non-cancelable material and equipment, payment will be made pursuant to Article 64.2.1(b).
- 64.2.3 Time and Materials Contracts or Items Based on Time and Material Records: On all **Contracts** or items in a **Contract** where payment for the **Work** is based on time and material records, the **Contractor** shall be paid in accordance with Article 26, less all payments previously made pursuant to this **Contract**.
- 64.2.4 Direct Costs: Direct Costs as used in this Article 64.2 shall mean:
 - 64.2.4(a) The actual purchase price of material and equipment, plus necessary and reasonable delivery costs,
 - 64.2.4(b) The actual cost of labor involved in construction and installation at the **Site**, and
 - 64.2.4(c) The actual cost of necessary bonds and insurance purchased pursuant to requirements of this **Contract** less any amounts that have been or should be refunded by the **Contractor's** sureties or insurance carriers.
 - 64.2.4(d) Direct Costs shall not include overhead.
- 64.3 In no event shall any payments under this Article 64 exceed the **Contract** price for such items.
- 64.4 All payments pursuant to Article 64 shall be in the nature of liquidated damages and shall be accepted by the **Contractor** in full satisfaction of all claims against the **City**.
- 64.5 The **City** may deduct or set off against any sums due and payable pursuant to this Article 64, any deductions authorized by this **Contract** or by **Law** (including but not limited to liquidated damages) and any claims it may have against the **Contractor**. The **City's** exercise of the right to terminate the **Contract** pursuant to this Article 64 shall not impair or otherwise effect the **City's** right to assert any claims it may have against the **Contractor** in a plenary action.
- 64.6 Where the **Work** covered by the **Contract** has been substantially completed, as determined in writing by the **Commissioner**, termination of the **Work** shall be handled as an omission of **Work** pursuant to Articles 29 and 33, in which case a change order will be issued to reflect an appropriate reduction in the **Contract** sum, or if the amount is determined after final payment, such amount shall be paid by the **Contractor**.

ARTICLE 65. CHOICE OF LAW, CONSENT TO JURISDICTION AND VENUE

- 65.1 This **Contract** shall be deemed to be executed in the **City** regardless of the domicile of the **Contractor**, and shall be governed by and construed in accordance with the **Laws** of the State of New York and the **Laws** of the United States, where applicable.
- 65.2 The parties agree that any and all claims asserted against the **City** arising under this **Contract** or related thereto shall be heard and determined in the courts of the State of New York ("New York State Courts") located in the **City** and County of New York. To effect this **Contract** and intent, the **Contractor** agrees:

- 65.2.1 If the **City** initiates any action against the **Contractor** in Federal court or in a New York State Court, service of process may be made on the **Contractor** either in person, wherever such **Contractor** may be found, or by registered mail addressed to the **Contractor** at its address as set forth in this **Contract**, or to such other address as the **Contractor** may provide to the **City** in writing; and
- 65.2.2 With respect to any action between the **City** and the **Contractor** in a New York State Court, the **Contractor** hereby expressly waives and relinquishes any rights it might otherwise have:
 - 65.2.2(a) To move to dismiss on grounds of forum non conveniens;
 - 65.2.2(b) To remove to Federal Court; and
 - 65.2.2(c) To move for a change of venue to a New York State Court outside New York County.
- 65.2.3 With respect to any action brought by the **City** against the **Contractor** in a Federal Court located in the **City**, the **Contractor** expressly waives and relinquishes any right it might otherwise have to move to transfer the action to a Federal Court outside the **City**.
- 65.2.4 If the **Contractor** commences any action against the **City** in a court located other than in the **City** and County of New York, upon request of the **City**, the **Contractor** shall either consent to a transfer of the action to a New York State Court of competent jurisdiction located in the **City** and County of New York or, if the Court where the action is initially brought will not or cannot transfer the action, the **Contractor** shall consent to dismiss such action without prejudice and may thereafter reinstate the action in a New York State Court of competent jurisdiction in New York County.
- 65.3 If any provision(s) of this Article 65 is held unenforceable for any reason, each and all other provision(s) shall nevertheless remain in full force and effect.

ARTICLE 66. PARTICIPATION IN AN INTERNATIONAL BOYCOTT

- 66.1 The **Contractor** agrees that neither the **Contractor** nor any substantially owned affiliated company is participating or shall participate in an international boycott in violation of the provisions of the Federal Export Administration Act of 1979, as amended, or the regulations of the United States Department of Commerce (Commerce Department) promulgated thereunder.
- 66.2 Upon the final determination by the Commerce Department or any other agency of the United States as to, or conviction of the **Contractor** or a substantially-owned affiliated company thereof for participation in an international boycott in violation of the provisions of the Export Administration Act of 1979, as amended, or the regulations promulgated thereunder, the **Comptroller** may, at his/her option, render forfeit and void this **Contract**.
- 66.3 The **Contractor** shall comply in all respects, with the provisions of Section 6-114 of the Administrative Code and the rules and regulations issued by the **Comptroller** thereunder.

ARTICLE 67. LOCALLY BASED ENTERPRISE PROGRAM

- 67.1 This **Contract** is subject to the requirements of Section 6-108.1 of the Administrative Code and regulations promulgated thereunder. No construction contract shall be awarded unless and until these requirements have been complied with in their entirety; however, compliance with this Article 67 is not required if the Agency sets Subcontractor Participation Goals for Minority- and Women-Owned Business Enterprises (M/WBEs).
- 67.2 Unless specifically waived by the **Commissioner** with the approval of the Division of Economic and Financial Opportunity of the **City** Department of Business Services, if any portion of the **Contract** is subcontracted, not less than ten (10%) percent of the total dollar amount of the **Contract** shall be awarded to locally based enterprises (LBEs); except that where less than ten (10%) percent of the total dollar amount of the **Contract** is subcontracted, such lesser percentage shall be so awarded.
 - 67.3 The **Contractor** shall not require performance and payment bonds from LBE **Subcontractors**.
- 67.4 If the **Contractor** has indicated prior to award that no **Work** will be subcontracted, no **Work** shall be subcontracted without the prior approval of the **Commissioner**, which shall be granted only if the **Contractor** makes a good faith effort beginning at least six (6) weeks before the **Work** is to be performed to obtain LBE **Subcontractors** to perform the **Work**.
- 67.5 If the **Contractor** has not identified sufficient LBE **Subcontractors** prior to award, it shall sign a letter of compliance stating that it complies with Section 6-108.1 of the Administrative Code, recognizes that achieving the LBE requirement is a condition of its **Contract**, and shall submit documentation demonstrating its good faith efforts to obtain LBEs. After award, the **Contractor** shall begin to solicit LBE's to perform subcontracted **Work** at least six (6) weeks before the date such **Work** is to be performed and shall demonstrate that a good faith effort has been made to obtain LBEs on each subcontract until it meets the required percentage.
- 67.6 Failure of the **Contractor** to comply with the requirements of Section 6-108.1 of the Administrative Code and the regulations promulgated thereunder shall constitute a material breach of this **Contract**. Remedy for such breach may include the imposition of any or all of the following sanctions:
 - 67.6.1 Reducing the **Contractor's** compensation by an amount equal to the dollar value of the percentage of the LBE subcontracting requirement not complied with;
 - 67.6.2 Declaring the **Contractor** in default;
 - 67.6.3 If the **Contractor** is an LBE, de-certifying and declaring the **Contractor** ineligible to participate in the LBE program for a period of up to three (3) years.

ARTICLE 68. ANTITRUST

68.1 The **Contractor** hereby assigns, sells, and transfers to the **City** all right, title, and interest in and to any claims and causes of action arising under the antitrust **Laws** of New York State or of the United States relating to the particular goods or services purchased or procured by the **City** under this **Contract**.

ARTICLE 69. MacBRIDE PRINCIPLES PROVISIONS

- 69.1 Notice To All Prospective **Contractors**:
 - 69.1.1 Local Law No. 34 of 1991 became effective on September 10, 1991 and added Section 6-115.1 of the Administrative Code. The local **Law** provides for certain restrictions on **City Contracts** to express the opposition of the people of the **City** to employment discrimination practices in Northern Ireland to promote freedom of work-place opportunity.
 - 69.1.2 Pursuant to Section 6-115.1, prospective **Contractors** for **Contracts** to provide goods or services involving an expenditure of an amount greater than ten thousand (\$10,000.) dollars, or for construction involving an amount greater than fifteen thousand (\$15,000.) dollars, are asked to sign a rider in which they covenant and represent, as a material condition of their **Contract**, that any business operations in Northern Ireland conducted by the **Contractor** and any individual or legal entity in which the **Contractor** holds a ten (10%) percent or greater ownership interest in the **Contractor** will be conducted in accordance with the MacBride Principles of nondiscrimination in employment.
 - 69.1.3 Prospective **Contractors** are not required to agree to these conditions. However, in the case of **Contracts** let by competitive sealed bidding, whenever the lowest responsible bidder has not agreed to stipulate to the conditions set forth in this notice and another bidder who has agreed to stipulate to such conditions has submitted a bid within five (5%) percent of the lowest responsible bid for a **Contract** to supply goods, services or contraction of comparable quality, the **Agency** shall refer such bids to the Mayor, the Speaker or other officials, as appropriate, who may determine, in accordance with applicable **Law**, that it is in the best interest of the **City** that the **Contract** be awarded to other than the lowest responsible pursuant to Section 313(b)(2) of the **City** Charter.
 - 69.1.4 In the case of **Contracts** let by other than competitive sealed bidding, if a prospective **Contractor** does not agree to these conditions, no **Agency**, elected official or the **City** Council shall award the **Contract** to that bidder unless the **Agency** seeking to use the goods, services or construction certifies in writing that the **Contract** is necessary for the **Agency** to perform its functions and there is no other responsible **Contractor** who will supply goods, services or construction of comparable quality at a comparable price.
- 69.2 In accordance with Section 6-115.1 of the Administrative Code, the **Contractor** stipulates that such **Contractor** and any individual or legal entity in which the **Contractor** holds a ten (10%) percent or greater ownership interest in the **Contractor** either:
 - 69.2.1 Have no business operations in Northern Ireland, or
 - 69.2.2 Shall take lawful steps in good faith to conduct any business operations they have in Northern Ireland in accordance with the MacBride Principles, and shall permit independent monitoring of their compliance with such principles.
 - 69.3 For purposes of this Article, the following terms shall have the following meanings:
 - 69.3.1 "MacBride Principles" shall mean those principles relating to nondiscrimination in employment and freedom of work-place opportunity which require employers doing business in Northern Ireland to:

- 69.3.1(a) increase the representation of individuals from under-represented religious groups in the workforce, including managerial, supervisory, administrative, clerical and technical jobs;
- 69.3.1(b) take steps to promote adequate security for the protection of employees from under-represented religious groups both at the work-place and while traveling to and from **Work**;
- 69.3.1(c) ban provocative religious or political emblems from the workplace;
- 69.3.1(d) publicly advertise all job openings and make special recruitment efforts to attract applicants from under-represented religious groups;
- 69.3.1(e) establish layoff, recall, and termination procedures which do not in practice favor a particular religious group;
- 69.3.1(f) abolish all job reservations, apprenticeship restrictions and different employment criteria which discriminate on the basis of religion;
- 69.3.1(g) develop training programs that will prepare substantial numbers of current employees from under-represented religious groups for skilled jobs, including the expansion of existing programs and the creation of new programs to train, upgrade, and improve the skills of workers from under-represented religious groups;
- 69.3.1(h) establish procedures to asses, identify, and actively recruit employees from under-represented religious groups with potential for further advancement; and
- 69.3.1(i) appoint a senior management staff member to oversee affirmative action efforts and develop a timetable to ensure their full implementation.
- 69.4 The Contractor agrees that the covenants and representations in Article 69.2 are material conditions to this Contract. In the event the Agency receives information that the Contractor who made the stipulation required by this Article 69 is in violation thereof, the Agency shall review such information and give the Contractor an opportunity to respond. If the Agency finds that a violation has occurred, the Agency shall have the right to declare the Contractor in default in default and/or terminate this Contract for cause and procure supplies, services or Work from another source in the manner the Agency deems proper. In the event of such termination, the Contractor shall pay to the Agency, or the **Agency** in its sole discretion may withhold from any amounts otherwise payable to the **Contractor**, the difference between the Contract price for the uncompleted portion of this Contract and the cost to the **Agency** of completing performance of this **Contract** either itself or by engaging another **Contractor** or Contractors. In the case of a requirement Contract, the Contractor shall be liable for such difference in price for the entire amount of supplies required by the Agency for the uncompleted term of Contractor's Contract. In the case of a construction Contract, the Agency shall also have the right to hold the **Contractor** in partial or total default in accordance with the default provisions of this **Contract**, and/or may seek debarment or suspension of the Contractor. The rights and remedies of the Agency hereunder shall be in addition to, and not in lieu of, any rights and remedies the Agency has pursuant to this **Contract** or by operation of **Law**.

ARTICLE 70. ELECTRONIC FILING/NYC DEVELOPMENT HUB

70.1 The **Contractor** shall electronically file all alteration type-2 and alteration type-3 applications via the New York City Development Hub Web site, except applications for the following types of minor alterations: enlargements, curb cuts, legalizations, fire alarms, builders pavement plans, and jobs filed on Landmark Preservation Commission calendared properties. All such filings must be professionally certified. Information about electronic filing via the New York City Development Hub is available on the **City** Department of Buildings Web site at www.nyc.gov/buildings.

ARTICLE 71. PROHIBITION OF TROPICAL HARDWOODS

71.1 Tropical hardwoods, as defined in Section 165 of the New York State Finance Law (Finance Law), shall not be utilized in the performance of this **Contract** except as expressly permitted by Section 165 of the Finance Law.

ARTICLE 72. CONFLICTS OF INTEREST

72.1 Section 2604 of the **City** Charter and other related provisions of the **City** Charter, the Administrative Code, and the Penal Law are applicable under the terms of this **Contract** in relation to conflicts of interest and shall be extended to **Subcontractors** authorized to perform **Work**, labor and services pursuant to this **Contract** and further, it shall be the duty and responsibility of the **Contractor** to so inform its respective **Subcontractors**. Notice is hereby given that, under certain circumstances, penalties may be invoked against the donor as well as the recipient of any form of valuable gift.

ARTICLE 73. MERGER CLAUSE

73.1 The written **Contract** herein, contains all the terms and conditions agreed upon by the parties hereto, and no other agreement, oral or otherwise, regarding the subject matter of this **Contract** shall be deemed to exist or to bind any of the parties hereto, or to vary any of the terms contained herein.

ARTICLE 74. STATEMENT OF WORK

74.1 The **Contractor** shall furnish all labor and materials and perform all **Work** in strict accordance with the **Specifications** and **Addenda** thereto, numbered as shown in Schedule A.

ARTICLE 75. COMPENSATION TO BE PAID TO CONTRACTOR

75.1 The **City** will pay and the **Contractor** will accept in full consideration for the performance of the **Contract**, subject to additions and deductions as provided herein, the total sum shown in Schedule A, this said sum being the amount at which the **Contract** was awarded to the **Contractor** at a public letting thereof, based upon the **Contractor's** bid for the **Contract**.

ARTICLE 76. ELECTRONIC FUNDS TRANSFER

76.1 In accordance with Section 6-107.1 of the Administrative Code, the **Contractor** agrees to accept payments under this **Contract** from the **City** by electronic funds transfer (EFT). An EFT is any

transfer of funds, other than a transaction originated by check, draft or similar paper instrument, which is initiated through an electronic terminal, telephonic instrument or computer or magnetic tape so as to order, instruct or authorize a financial institution to debit or credit an account. Prior to the first payment made under this **Contract**, the **Contractor** shall designate one financial institution or other authorized payment agent and shall complete the attached "EFT Vendor Payment Enrollment Form" in order to provide the Commissioner of the **City** Department of Finance with information necessary for the **Contractor** to receive electronic funds transfer payments through a designated financial institution or authorized payment agent. The crediting of the amount of a payment to the appropriate account on the books of a financial institution or other authorized payment agent designated by the **Contractor** shall constitute full satisfaction by the **City** for the amount of the payment under this **Contract**. The account information supplied by the **Contractor** to facilitate the electronic funds transfer shall remain confidential to the fullest extent provided by **Law**.

76.2 The **Commissioner** may waive the application of the requirements of this Article 76 to payments on contracts entered into pursuant to Section 315 of the **City** Charter. In addition, the Commissioner of the Department of Finance and the Comptroller may jointly issue standards pursuant to which the **Agency** may waive the requirements of this Article 76 for payments in the following circumstances: (i) for individuals or classes of individuals for whom compliance imposes a hardship; (ii) for classifications or types of checks; or (iii) in other circumstances as may be necessary in the interest of the **City**.

ARTICLE 77. RECORDS RETENTION

77.1 The **Contractor** agrees to retain all books, records, and other documents relevant to this **Contract** for six years after the final payment or termination of this **Contract**, whichever is later. **City**, state, and federal auditors and any other persons duly authorized by the **City** shall have full access to and the right to examine any such books, records, and other documents during the retention period.

ARTICLE 78. EXAMINATION AND VIEWING OF SITE, CONSIDERATION OF OTHER SOURCES OF INFORMATION AND CHANGED SITE CONDITIONS

78.1 Pre-Bidding (Investigation) Viewing of Site – Bidders must carefully view and examine the **Site** of the proposed **Work**, as well as its adjacent area, and seek other usual sources of information, for they will be conclusively presumed to have full knowledge of any and all conditions and hazards on, about or above the **Site** relating to or affecting in any way the performance of the **Work** to be done under the **Contract** that were or should have been known by a reasonably prudent bidder. To arrange a date for visiting the **Site**, bidders are to contact the **Agency** contact person specified in the bid documents.

78.2 Should the **Contractor** encounter during the progress of the Work site conditions or environmental hazards at the **Site** materially differing from any shown on the **Contract Drawings** or indicated in the **Specifications** or such conditions or environmental hazards as could not reasonably have been anticipated by the **Contractor**, which conditions or hazards will materially affect the cost of the **Work** to be done under the **Contract**, the attention of the **Commissioner** must be called immediately to such conditions or hazards before they are disturbed. The **Commissioner** shall thereupon promptly investigate the conditions or hazards. If the **Commissioner** finds that they do so materially differ, and that they could not have been reasonably anticipated by the **Contractor**, the **Contract** may be modified with the **Commissioner**'s written approval.

PART E: GENERAL CONDITIONS

Schedule "A" (Bonding and Insurance Requirements, etc.)

Performance Bond Form, if applicable

Payment Bond Form, if applicable

SCHEDULE A

GENERAL CONDITIONS TO CONSTRUCTION CONTRACT (INCLUDING GENERAL CONDITIONS RELATING TO ARTICLE 22 -- INSURANCE)

PART I. REQUIRED INFORMATION

INFORMATION FOR BIDDERS BID BOND	
The Contractor shall obtain a bid bond in the amount indicated to the right.	5%
INFORMATION FOR BIDDERS PERFORMANCE AND PAYMENT BONDS The Contractor shall obtain performance and payment bonds in the amount indicated to the right.	100%
CONTRACT ARTICLE 14. DATE FOR SUBSTANTIAL COMPLETION	365 consecutive calendar days
The Contractor shall substantially complete the Work in the number of calendar days indicated to the right.	
CONTRACT ARTICLE 15. LIQUIDATED DAMAGES	Value of Specific Work Order
If the Contractor fails to substantially complete the Work within the time fixed for substantial completion plus authorized time extensions or if the Contractor , in the sole determination of the Commissioner , has abandoned the Work , the Contractor shall pay to the City the amount indicated to the right based on the value of Specific Work Order.	\$250.00/PER DAY
CONTRACT ARTICLE 17. SUB-CONTRACTOR	Not to exceed 49% of the Contract price
The Contractor shall not make subcontracts totaling an amount more than the percentage of the total Contract price indicated to the right.	
CONTRACT ARTICLE 21. RETAINAGE	1% of the value of the Work

The Commissioner shall deduct and retain until the	
substantial completion of the Work the percent	
value of the Work indicated to the right.	
CONTRACT ARTICLE 22.	
(Per Directions Below)	
CONTRACT ARTICLE 24.	1% of Contract price
<u>DEPOSIT GUARANTEE</u>	170 of Contract price
As security for the faithful performance of its	
obligations, the Contractor, upon filing its	
requisition for payment on Substantial	
Completion, shall deposit with the Commissioner	
a sum equal to the percentage of the Contract price	
indicated to the right.	
CONTRACT ARTICLE 24.	
PERIOD OF GUARANTEE	
The Contractor shall guarantee its work, free of	
defects in materials, installation and operation	
(excluding routine maintenance) for a period of two	
(2) years after completion of the work. During this	
period the Contractor shall replace any such	
defective materials promptly and free of charge to	
the Department.	
the Department.	
CONTRACT ARTICLE 74.	I di Di ilia di Di
STATEMENT OF WORK	Insert the Required Information Below.
The Contractor shall furnish all labor and materials and	
perform all Work in strict accordance with the	
Contract Drawings, Specifications, and all Addenda	
thereto, numbered as shown in the column to the right.	
CONTRACT ARTICLE 75.	
COMPENSATION TO BE PAID TO CONTRACTOR	Amount for which the Contract was
Z Z Z Z Z Z Z Z Z Z Z Z Z Z Z Z Z Z Z	awarded:
	awaraca.

The **City** shall pay and the **Contractor** shall accept in full consideration for the performance of the **Contract**, subject to additions and deductions as provided herein, the total sum **shown in the column to the right**, this said sum being the amount at which the **Contract** was awarded to the **Contractor** at a public letting thereof, based upon the **Contractor's** bid for the **Contract**.

\$ N/A

[Agency: If the Bid Price, or any portion thereof, is based on unit prices, insert the words "Not to Exceed" before the amount.]

PART II. TYPES OF INSURANCE, MINIMUM LIMITS AND SPECIAL CONDITIONS

<u>Note</u>: All certificate(s) of insurance submitted pursuant to Contract Article 22.3.3 must be accompanied by a Certification by Broker consistent with Part III below and include the following information:

- For each insurance policy, the name and NAIC number of issuing company, number of policy, and effective dates;
- Policy limits consistent with the requirements listed below;
- Additional insureds or loss payees consistent with the requirements listed below; and
- The number assigned to the Contract by the City (in the "Description of Operations" field).

Insurance indicated by a blackened box (\blacksquare) or by X in a \square to left will be required under this contract

		T
Types of Insurance		Minimum Limits and Special
(per Article 22 in its entirety, including listed paragraph)		Conditions
Commercial Constal Lightlity	Art. 22.1.1	The minimum limits shall be
■ Commercial General Liability	AII. 22.1.1	\$2,000,000.00 per occurrence and
		\$4,000,000.00 per project aggregate
		applicable to this Contract unless the
		Work requires a permit from the
		Department of Buildings and greater
		limits of Commercial General
		Liability Insurance are required
		pursuant to 1 RCNY section 101-08.
		Additional Insureds:
		1. City of New York, including its
		officials and employees, with
		coverage at least as broad as ISO
		Forms CG 20 10 and CG 20 37, and
		2. All person(s) or organization(s), if
		any, that Article 22.1.1(b) of the
		Contract requires to be named as
		Additional Insured(s), with coverage
		at least as broad as ISO Form CG 20
		26. The Additional Insured
		endorsement shall either specify the
		entity's name, if known, or the
		entity's title (e.g., Project Manager).
		(1.8.)
		3. [Agency: If appropriate, insert

		names of other entities to be covered as Additional Insureds.]
 ■ Workers' Compensation ■ Disability Benefits Insurance ■ Employers' Liability □ Jones Act □ U.S. Longshoremen's and Harbo Compensation Act 	Art. 22.1.2 Art. 22.1.2 Art. 22.1.3 r Workers Art. 22.1.3	Workers' Compensation, Employers' Liability, and Disability Benefits Insurance: Statutory per New York State law without regard to jurisdiction. Note: The following forms are acceptable: (1) New York State Workers' Compensation Board Form No. C-105.2, (2) State Insurance Fund Form No. U-26.3, (3) New York State Workers' Compensation Board Form No. DB-120.1 and (3) Request for WC/DB Exemption Form No. CE-200. The City will not accept an ACORD form as proof of Workers' Compensation or Disability Insurance. Jones Act and U.S. Longshoremen's and Harbor Workers' Compensation Act: Statutory per U.S. law.
□ Builders Risk	Art. 22.1.4	Contractor the Named Insured; the City both an Additional Insured and one of the loss payees as its interests may appear. If the Work does not involve construction of a new building or gut renovation work, the Contractor may provide an installation floater in lieu of Builders Risk insurance. Note: Builders Risk Insurance may terminate upon Substantial Completion of the Work in its entirety.

■ Commercial Auto Liability	Art. 22.1.5	\$1,000,000.00 per accident combined single limit
		If vehicles are used for transporting hazardous materials, the Contractor shall provide pollution liability broadened coverage for covered vehicles (endorsement CA 99 48) as well as proof of MCS 90

☐ Contractors Pollution Liability	Art. 22.1.6	\$N/A per occurrence
		\$N/A aggregate
		Additional Insureds: 1. City of New York, including its officials and employees, and
		2.
		3.
☐ Marine Protection and Indemnity	Art. 22.1.7(a)	\$ N/A per occurrence
		\$ N/A aggregate
		Additional Insureds: 1. City of New York, including its officials and employees, and 2.
		3.

☐ Hull and Machinery Insurance	Art. 22.1.7(b)	\$ N/A per occurrence
		\$ N/A aggregate
		Additional Insureds: 1. City of New York, including its officials and employees, and 2.
		3.
☐ Marine Pollution Liability	Art. 22.1.7(c)	\$ N/A each occurrence
		Additional Insureds: 1. City of New York, including its officials and employees, and 2.
		3.

[OTHER]	Art. 22.1.8	[If other type(s) of insurance need to be required under the Contract, the Contracting Agency should (a) check the box and fill in the type of insurance in left-hand column, and (b) in this right-hand column, specify appropriate limit(s) and appropriate Named Insured and Additional Insured(s). Note that if Railroad Protective Liability Insurance is required, the appropriate Named Insured is the owner of the railroad and there are no additional insureds.]
[OTHER]	Art. 22.1.8	[See directly above.]

SCHEDULE A

CERTIFICATES OF INSURANCE

Instructions to New York City Agencies, Departments, and Offices

All certificates of insurance (except certificates of insurance solely evidencing Workers' Compensation Insurance, Employer's Liability Insurance, and/or Disability Benefits Insurance) must be accompanied by one of the following:

(1) the Certification by Insurance Broker or Agent on the following page setting forth the required information and signatures;

-- OR --

(2) copies of all policies as certified by an authorized representative of the issuing insurance carrier that are referenced in such certificate of insurance. If any policy is not available at the time of submission, certified binders may be submitted until such time as the policy is available, at which time a certified copy of the policy shall be submitted.

SCHEDULE A

CITY OF NEW YORK CERTIFICATION BY INSURANCE BROKER OR AGENT

The undersigned insurance broker or agent represents to the City of New York that the attached Certificate of Insurance is accurate in all material respects.

	[Name of broker or agent (typewritten)]			
	[Address of broker or agent (typewritten)]			
	[Email address of broker or agent (typewritten)]			
	[Phone number/Fax number of broker or agent (typewritten)]			
	[Signature of authorized official, broker, or agent]			
	[Name and title of authorized official, broker, or agent (typewritten)]			
State of County of)			
County of)			
Sworn to before me this	day of 20			
NOTARY PU	BLIC FOR THE STATE OF			

SCHEDULE A (GENERAL CONDITIONS TO CONSTRUCTION CONTRACT)

PART IV. ADDRESS OF COMMISSIONER

Wherever reference is made in Article 7 or Article 22 to documents to be sent to the	
Commissioner (e.g., notices, filings, or submissions), such documents shall be sent to the address set	
forth below or, in the absence of such address, to the Commissioner's address as provided elsewhere	in
this Contract.	
[Note to Contracting Agency: Fill in Risk Manager, ACCO or other person responsible for insurance]	

PAYMENT BOND FORM

WE	
	hereinafter
referred to as the "Principal," and	
	_
hereinafter referred to as the "Surety" (Sureties) are held and firmly bound to NEW YORK, hereinafter referred to as the "City" or to its successors and assig sum of	
(\$) Dollars, lawful money of the United States	of America for
the payment of which said sum of money well and truly to be made, we, and ourselves, our heirs, executors, administrators, successors and assigns, jointly	ŕ
firmly by these presents.	
WHEREAS, the Principal is about to enter, or has entered, into a contract in City for	writing with the
	a copy
of which Contract is annexed to and hereby made a part of this Bond as though he full;	erein set forth in
NOW, THEREFORE , the conditions of this obligation are such that if the its representatives or assigns and other Subcontractors to whom work under sublet and his or their successors and assigns shall promptly pay or cause to be	this Contract is

a) Wages and compensation for labor performed and services rendered by all persons engaged in the prosecution of the work under said Contract, and any amendment or extension thereof or addition thereto, whether such persons be agents, servants or employees of the Principal or of any such Subcontractor, including all persons so engaged who perform the work of laborers or mechanics

claims for:

at or in the vicinity of the site of the Project regardless of any contractual relationship between the Principal or such Subcontractors, or his or their successors or assigns, on the one hand and such laborers or mechanics on the other, but not including office employees not regularly stationed at the site of the Project; and/or

Materials and supplies (where incorporated in the permanent structure or not), as well as fuels, oils, implements or machinery furnished, used or consumed by said Principal or any Subcontractor at or in the vicinity of the site of the Project in the prosecution of the work under said Contract and any amendment or extension thereof or addition thereto; then this obligation shall be void; otherwise to remain in full force and effect and the Surety shall fulfill its obligations under this Payment Bond.

This bond is subject to the following additional conditions, limitations and agreements:

- a) The Principal and Surety (Sureties) agree that this bond shall be for the benefit of any materialman or laborer having a just claim, as well as the City itself.
- All persons who have performed labor, rendered services or furnished materials and supplies, as aforesaid, shall have a direct right of action against the Principal and its or their successors and assigns, and the Surety (Sureties) herein, or against either or both or any of them and their successors and assigns. Such persons may sue in their own name, and may prosecute the suit to judgment and execution without the necessity of joining with any other person as party plaintiff.
- c) The Principal and Surety (Sureties) agree that neither of them will hold the City liable for any judgment for costs or otherwise, obtained by either or both of them against a laborer or materialman in a suit brought by either a laborer or materialman under this bond for moneys allegedly due for performing work or furnishing material.
- d) The Surety (Sureties) or its successors and assigns shall not be liable for any compensation recoverable by an employee or laborer under the Workers' Compensation Law.

e) In no event shall the Surety (Sureties), or its successors or assigns, be liable for a greater sum than the penalty of this bond or be subject to any suit, action or proceeding hereon that is instituted by any person, firm, or corporation hereunder later than two (2) years after the complete performance of said Contract and final settlement thereof.

The Principal, for himself and his successors and assigns, and the Surety (Sureties), for itself and its successors and assigns, do hereby expressly waive any objection that might be interposed as to the right of the City to require a bond containing the foregoing provisions, and they do hereby further expressly waive any defense which they or either of them might interpose to an action brought hereon by any person, firm, or corporation, including Subcontractors, materialmen and third persons, for work, labor, services, supplies or material performed, rendered, or furnished as aforesaid upon the ground that there is no law authorizing the City to require the foregoing provisions to be placed in this Payment Bond.

And the Surety (Sureties) for values received, for itself and its successors and assigns hereby stipulate(s) and agree(s) that the obligation of said Surety (Sureties), and its bonds shall be in no way impaired or affected by any extension of time, modification, omission, addition, or change in or of the said Contract or the work to be performed thereunder, or by any payment thereunder before the time required therein, or by any waiver of any provisions thereof, or by any assignment, subletting or other transfer thereof or of any part thereof, or of any work to be performed, or any moneys due or to become due thereunder; and said Surety (Sureties) does hereby waive notice of any and all of such extensions, modifications, omissions, additions, changes, payments, waivers, assignments, subcontracts and transfers, and hereby expressly stipulates and agrees that any and all things done and omitted to be done by and in relation to assignees, subcontractors, and other transferees shall have the same effect as to said Surety (Sureties) as though done or omitted to be done by or in relation to said Principal.

IN WITNESS V	WHEREOF, the Princ	cipal an	d the Surety (Sureties) have hereunto set their
hands and seals ar	nd such of them as are	corpora	ations have caused their corporate seals to be
hereto affixed and	d these presents to be	signed	by their proper officers this day of
	_, 20 .		
			(LS)
			Principal (ES)
(Seal)		By:	
		J	
			Surety
			Surcey
(C1)		D	
(Seal)		By:	
			<u> </u>
			Surety
(Seal)		By:	<u></u>
			Surety
			v
(Seal)		By:	
(Scar)		Dy.	

PERFORMANCE BOND

That we,
hereinafter referred to as the "Principal," and,
hereinafter referred to as the "Surety" ("Sureties") are held and firmly bound to THE CITY OF NEW YORK, hereinafter referred to as the "City" or to its successors and assigns in the penal sum of
(\$) Dollars, lawful money of the United States for the payment of which said sum of money well and truly to be made, we, and each of us, bind ourselves, our heirs, executors, administrators, successors and assigns, jointly and severally, firmly by these presents.
WHEREAS, The Principal is about to enter, or has entered, into a Contract in writing with the City for

a copy of which Contract is annexed to and hereby made a part of this bond as though herein set forth in full;

NOW, THEREFORE, the conditions of this obligation are such that if the Principal, his or its representatives or assigns, shall well and faithfully perform the said Contract and all modifications, amendments, additions and alterations thereto that may hereafter be made, according to its terms and its true intent and meaning, including repair and or replacement of defective work

and guarantees of maintenance for the periods stated in the Contract, and shall fully indemnify and save harmless the City from all cost and damage which it may suffer by reason of the Principal's default of the Contract, and shall fully reimburse and repay the City for all outlay and expense which the City may incur in making good any such default and shall protect the said City of New York against, and pay any and all amounts, damages, cost and judgments which may or shall be recovered against said City or its officers or agents or which the said City of New York may be called upon to pay any person or corporation by reason of any damages arising or growing out of the Principal's default of the Contract, then this obligation shall be null and void, otherwise to remain in full force and effect.

The Surety (Sureties), for value received, hereby stipulates and agrees, upon written notice from the City that the City has determined that the Principal is in default of the Contract, to (1) pay the City the cost to complete the contract as determined by the City in excess of the balance of the Contract held by the City, plus any damages or costs to which the City is entitled, up to the full amount of the above penal sum, (2) fully perform and complete the Work to be performed under the Contract, pursuant to the terms, conditions, and covenants thereof, or (3) tender a completion Contractor that is acceptable to the City. The Surety (Sureties) further agrees, at its option, either to notify the City that it elects to pay the city the cost of completion plus any applicable damages and costs under option (1) above, or to commence and diligently perform the Work specified in the Contract, including physical site work, within twenty-five (25) business days after written notice thereof from the City and, if the Surety elects to fully perform and complete the Work, then to complete all Work within the time set forth in the Contract or such other time as agreed to between the City and Surety in accordance with the Contract. If the Surety elects to tender payment pursuant to (1) above, then the Surety shall tender such amount within fifteen (15) business days notification from the City of the cost of completion. The Surety and the City reserve all rights and defenses each may have against the other; provided, however, that the Surety expressly agrees that its reservation of rights shall not provide a basis for non-performance of its obligation to pay the City the cost of completion, to commence and complete all Work as provided herein, or to tender a completion contractor.

The Surety (Sureties), for value received, for itself and its successors and assigns, hereby stipulates and agrees that the obligation of said Surety (Sureties) and its bond shall be in no way impaired or affected by any extension of time, modification, omission, addition, or change in or to the said Contract or the Work to be performed thereunder, or by any payment thereunder before the time required therein, or by any waiver of any provisions thereof, or any moneys due or to become due thereunder; and said Surety (Sureties) does hereby waive notice of any and all of such extensions, modifications, omissions, additions, changes, payments, and waivers, and hereby expressly stipulates and agrees that any and all things done and omitted to be done by and in relation to subcontractors shall have the same effect as to said Surety (Sureties) as though done or omitted to be done by or in relation to said Principal. Notwithstanding the above, if the City makes payments to the Principal before the time required by the contract that in the aggregate exceed \$100,000 or 10% of the Contract price, whichever is less, and that have not become earned prior to the Principal being found to be in default, then all payments made to the Principal before the time required by the Contract shall be added to the remaining contract value available to be paid for the completion of

the Contract as if such sums had not been paid to the Principal, but shall not provide a basis for non-performance of its obligation to pay the City the cost of completion, to commence and to complete all Work as provided herein, or to tender a completion contractor

IN WITNESS WHEREOF, The Principal and the Surety (Sureties) have hereunto set their hands and seals, and such of them as are corporations have caused their corporate seals to be hereunto affixed and these presents to be signed by their proper officers, this

	day of	20
(Seal)		(L.S.) Principal
		<u>.</u>
	By	<u>.</u>
	Ву	<u>.</u>
	Ву	<u>.</u>
	By	<u>.</u>
	By	

Bond Premium Rate	<u> </u>
Bond Premium Cost	<u>.</u>

If the Contractor (Principal) is a partnership, the bond should be signed by each of the individuals who are partners.

If the Contractor (Principal) is a corporation, the bond should be signed in its correct corporate name by a duly authorized officer, agent, or attorney-in-fact.

There should be executed an appropriate number of counterparts of the bond corresponding to the number of counterparts of the Contract.

ACKNOWLEDGMENT OF PRINCIPAL IF A CORPORATION

State of	C	County of	SS:
On this	day of	20	before me personally
came	,		
to me known, w	ho, being by me duly swo	orn did depose and say that h	e/she resides
at			
		; that he/she irporation described in and wh	s the
	ofthe cor	rporation described in and wh	nich executed the foregoing
	_		y order of the directors of said
corporation as th	ne duly authorized and bir	nding act thereof.	
N. 4 D.11	C CD 1	-	
Notary Public of	Commissioner of Deeds	5.	
,	CKNOWI FOCMENT	Γ OF PRINCIPAL IF A PA	DTNEDCHID
<u> </u>	ICKNOW LEDGIVIEN	OF I KINCHAL IF A LA	KINEKSIIII
State of	C	County of	ss:
On this	day of	20	before me personally
came	1 1 1 1 1 1	orn did depose and say that h	/ 1 : 1
		orn did depose and say that h	e/she resides
at		41 41 /1 :	
		that ne/sne i	sship existing under the laws of and which executed the
the State of		, a ilmited/general partners	snip existing under the laws of
forescine instru	, l	the partnership described in a	and which executed the
		ned his/her name to the foreg	oing instrument as the duty
authorized and b	pinding act of said partner	rsnip.	
Notary Public or	Commissioner of Deeds	-	
1 TOTAL Y I HOLLE OF	Commissioner of Decus	.	

ACKNOWLEDGMENT OF PRINCIPAL IF AN INDIVIDUAL

Affix Acknowledgments and justification of Sureties

State of	te ofCounty of		SS:
On this	day of	20	before me personally
came			
to me known, w	ho, being by me duly swor	n did depose and say that	he/she resides
at			
		, and that 1	he/she is the individual whose
	bed to the within instrume said individual executed the	_	me that by his/her signature on
Notary Public or	Commissioner of Deeds.		

PART F: ATTACHMENTS

Attachment A	Participation By Minority-Owned And Women-Owned Business Enterprises
	In City Procurement
	 Notice to Prospective Contractors
	Schedule B
Attachment B	Construction Employment Report
Attachment C	Sub-contracting Compliance Notice
Attachment D	Undue Familiarity and Prevention of Sexual Abuse of Inmates by Staff
	And Other Inmates
Attachment E	Security Clearance Request and Authorization Form
Attachment F	Security Requirements for All Work Performed on Riker's Island
Attachment G	Prevailing Wage Schedule
Attachment H	Notice to Bidders: Apprenticeship Agreement
Attachment H	Notice to Bidders: Apprenticeship Agreement

ATTACHMENT A

PARTICIPATION BY MINORITY-OWNED AND WOMEN-OWNED BUSINESS ENTERPRISES IN CITY PROCUREMENT

NOTICE TO ALL PROSPECTIVE CONTRACTORS

PARTICIPATION BY MINORITY-OWNED AND WOMEN-OWNED BUSINESS ENTERPRISES IN CITY PROCUREMENT

ARTICLE I. M/WBE PROGRAM

Local Law No. 129 of 2005 added and Local Law 1 of 2013 amended Section 6-129 of the Administrative Code of the City of New York (hereinafter "Section 6-129"). Section 6-129 establishes the program for participation in City procurement ("M/WBE Program") by minority-owned business enterprises ("MBEs") and women-owned business enterprises ("WBEs"), certified in accordance with Section 1304 of the New York City Charter. As stated in Section 6-129, the intent of the program is to address the impact of discrimination on the City's procurement process, and to promote the public interest in avoiding fraud and favoritism in the procurement process, increasing competition for City business, and lowering contract costs. The contract provisions contained herein are pursuant to Section 6-129, and the rules of the Department of Small Business Services ("DSBS") promulgated thereunder.

If this Contract is subject to the M/WBE Program established by Section 6-129, the specific requirements of MBE and/or WBE participation for this Contract are set forth in Schedule B of the Contract (entitled the "M/WBE Utilization Plan"), and are detailed below.

The Contractor must comply with all applicable MBE and WBE requirements for this Contract.

All provisions of Section 6-129 are hereby incorporated in the Contract by reference and all terms used herein that are not defined herein shall have the meanings given such terms in Section 6-129.

Article I, Part A, below, sets forth provisions related to the participation goals for construction, standard and professional services contracts.

Article I, Part B, below, sets forth miscellaneous provisions related to the M/WBE Program.

PART A

<u>PARTICIPATION GOALS FOR CONSTRUCTION, STANDARD</u> AND PROFESSIONAL SERVICES CONTRACTS OR TASK ORDERS

1. The MBE and/or WBE Participation Goals established for this Contract or Task Orders issued pursuant to this Contract, ("Participation Goals"), as applicable, are set forth on Schedule B, Part I to this Contract (see Page 1, line 1 Total Participation Goals) or will be set forth on Schedule B, Part I to Task Orders issued pursuant to this Contract, as applicable.

The **Participation Goals** represent a percentage of the total dollar value of the Contract or Task Order, as applicable, that may be achieved by awarding subcontracts to firms certified with New York City Department of Small Business Services as MBEs and/or WBEs, and/or by crediting the participation of prime contractors and/or qualified joint ventures as provided in Section 3 below, unless the goals have been waived or modified by Agency in accordance with Section 6-129 and Part A, Sections 10 and 11 below, respectively.

2. If **Participation Goals** have been established for this Contract or Task Orders issued pursuant to this Contract, Contractor agrees or shall agree as a material term of the Contract that Contractor shall be subject to the

Participation Goals, unless the goals are waived or modified by Agency in accordance with Section 6-129 and Part A, Sections 10 and 11 below, respectively.

3. If **Participation Goals** have been established for this Contract or Task Order issued pursuant to this Contract, a Contractor that is an MBE and/or WBE shall be permitted to count its own participation toward fulfillment of the relevant **Participation Goal**, provided that in accordance with Section 6-129 the value of Contractor's participation shall be determined by subtracting from the total value of the Contract or Task Order, as applicable, any amounts that the Contractor pays to direct subcontractors (as defined in Section 6-129(c)(13)), and provided further that a Contractor that is certified as both an MBE and a WBE may count its own participation either toward the goal for MBEs or the goal for WBEs, but not both.

A Contractor that is a qualified joint venture (as defined in Section 6-129(c)(30)) shall be permitted to count a percentage of its own participation toward fulfillment of the relevant **Participation Goal**. In accordance with Section 6-129, the value of Contractor's participation shall be determined by subtracting from the total value of the Contract or Task Order, as applicable, any amounts that Contractor pays to direct subcontractors, and then multiplying the remainder by the percentage to be applied to total profit to determine the amount to which an MBE or WBE is entitled pursuant to the joint venture agreement, provided that where a participant in a joint venture is certified as both an MBE and a WBE, such amount shall be counted either toward the goal for MBEs or the goal for WBEs, but not both.

- 4. A. If **Participation Goals** have been established for this Contract, a prospective contractor shall be required to submit with its bid or proposal, as applicable, a completed Schedule B, M/WBE Utilization Plan, Part II (see Pages 2-4) indicating: (a) whether the contractor is an MBE or WBE, or qualified joint venture; (b) the percentage of work it intends to award to direct subcontractors; and (c) in cases where the contractor intends to award direct subcontracts, a description of the type and dollar value of work designated for participation by MBEs and/or WBEs, and the time frames in which such work is scheduled to begin and end. In the event that this M/WBE Utilization Plan indicates that the bidder or proposer, as applicable, does not intend to meet the **Participation Goals**, the bid or proposal, as applicable, shall be deemed non-responsive, unless Agency has granted the bidder or proposer, as applicable, a preaward waiver of the **Participation Goals** in accordance with Section 6-129 and Part A, Section 10 below.
- B. (i) If this Contract is for a master services agreement or other requirements type contract that will result in the issuance of Task Orders that will be individually registered ("Master Services Agreement") and is subject to M/WBE **Participation Goals**, a prospective contractor shall be required to submit with its bid or proposal, as applicable, a completed Schedule B, M/WBE Participation Requirements for Master Services Agreements That Will Require Individually Registered Task Orders, Part II (page 2) indicating the prospective contractor's certification and required affirmations to make all reasonable good faith efforts to meet participation goals established on each individual Task Order issued pursuant to this Contract, or if a partial waiver is obtained or such goals are modified by the Agency, to meet the modified **Participation Goals** by soliciting and obtaining the participation of certified MBE and/or WBE firms. In the event that the Schedule B indicates that the bidder or proposer, as applicable, does not intend to meet the **Participation Goals** that may be established on Task Orders issued pursuant to this Contract, the bid or proposal, as applicable, shall be deemed non-responsive.
- (ii) **Participation Goals** on a Master Services Agreement will be established for individual Task Orders issued after the Master Services Agreement is awarded. If **Participation Goals** have been established on a Task Order, a contractor shall be required to submit a Schedule B M/WBE Utilization Plan For Independently Registered Task Orders That Are Issued Pursuant to Master Services Agreements, Part II (see Pages 2-4) indicating: (a) whether the contractor is an MBE or WBE, or qualified joint venture; (b) the percentage of work it intends to award to direct subcontractors; and (c) in cases where the contractor intends to award direct subcontracts, a description of the type and dollar value of work designated for participation by MBEs and/or WBEs, and the time frames in which such work is scheduled to begin and end. The contractor must engage in good faith efforts to meet the **Participation Goals** as

established for the Task Order unless Agency has granted the contractor a pre-award waiver of the **Participation Goals** in accordance with Section 6-129 and Part A, Section 10 below.

- C. The bidder/proposer must complete the schedule B included herein (Schedule B, Part II). A schedule B submitted by the bidder/proposer which does not include the vendor certification and required affirmations (see Section V of Part II) will be deemed to be non-responsive, unless a full waiver of the Participation Goals is granted (Schedule B, Part III). In the event that the City determines that the bidder/proposer has submitted a Schedule B where the vendor certification and required Affirmations are completed but other aspects of the schedule B are not complete, or contain a copy or computation error that is at odds with the vendor certification and affirmations, the bidder/proposer will be notified by the agency and will be given four (4) calendar days from receipt of notification to cure the specified deficiencies and return a completed Schedule B to the agency. Failure to do so will result in a determination that the bid/proposal is non-responsive. Receipt of notification is defined as the date notice is e-mailed or faxed (if the bidder/proposer has provided an e-mail address or fax number), or no later than five (5) calendar days from the date of mailing or upon delivery, if delivered.
- Where an M/WBE Utilization Plan has been submitted, the Contractor shall, within 30 days of issuance by Agency of a notice to proceed, submit a list of proposed persons or entities to which it intends to award subcontracts within the subsequent 12 months. In the case of multi-year contracts, such list shall also be submitted every year thereafter. The Agency may also require the Contractor to report periodically about the contracts awarded by its direct subcontractors to indirect subcontractors (as defined in Section 6-129(c)(22)). PLEASE NOTE: If this Contract is a public works project subject to GML §101(5) (i.e., a contract valued at or below \$3M for projects in New York City) or if the Contract is subject to a project labor agreement in accordance with Labor Law \$222, and the bidder is required to identify at the time of bid submission its intended subcontractors for the Wicks trades (plumbing and gas fitting; steam heating, hot water heating, ventilating and air conditioning (HVAC); and electric wiring), the Contractor must identify all those to which it intends to award construction subcontracts for any portion of the Wicks trade work at the time of bid submission, regardless of what point in the life of the contract such subcontracts will occur. In identifying intended subcontractors in the bid submission, bidders may satisfy any Participation Goals established for this Contract by proposing one or more subcontractors that are MBEs and/or WBEs for any portion of the Wicks trade work. In the event that the Contractor's selection of a subcontractor is disapproved, the Contractor shall have a reasonable time to propose alternate subcontractors.
- 6. MBE and WBE firms must be certified by DSBS in order for the Contractor to credit such firms' participation toward the attainment of the **Participation Goals**. Such certification must occur prior to the firms' commencement of work. A list of MBE and WBE firms may be obtained from the DSBS website at www.nyc.gov/buycertified, by emailing DSBS at buyer@sbs.nyc.gov, by calling (212) 513-6356, or by visiting or writing DSBS at 110 William St., New York, New York, 10038, 7th floor. Eligible firms that have not yet been certified may contact DSBS in order to seek certification by visiting www.nyc.gov/getcertified, emailing MWBE@sbs.nyc.gov, or calling the DSBS certification helpline at (212) 513-6311. A firm that is certified as both an MBE and a WBE may be counted either toward the goal for MBEs or the goal for WBEs, but not both. No credit shall be given for participation by a graduate MBE or graduate WBE, as defined in Section 6-129(c)(20).
- 7. Where an **M/WBE** Utilization Plan has been submitted, the Contractor shall, with each voucher for payment, and/or periodically as Agency may require, submit statements, certified under penalty of perjury, which shall include, but not be limited to,: the total amount the Contractor paid to its direct subcontractors, and, where applicable pursuant to Section 6-129(j), the total amount direct subcontractors paid to indirect subcontractors; the names, addresses and contact numbers of each MBE or WBE hired as a subcontractor by the Contractor, and, where applicable, hired by any of the Contractor's direct subcontractors; and the dates and amounts paid to each MBE or WBE. The Contractor

shall also submit, along with its voucher for final payment: the total amount it paid to subcontractors, and, where applicable pursuant to Section 6-129(j), the total amount its direct subcontractors paid directly to their indirect subcontractors; and a final list, certified under penalty of perjury, which shall include the name, address and contact information of each subcontractor that is an MBE or WBE, the work performed by, and the dates and amounts paid to each.

- 8. If payments made to, or work performed by, MBEs or WBEs are less than the amount specified in the Contractor's **M/WBE** Utilization Plan, Agency shall take appropriate action, in accordance with Section 6-129 and Article II below, unless the Contractor has obtained a modification of its **M/WBE** Utilization Plan in accordance with Section 6-129 and Part A, Section 11 below.
- 9. Where an **M/WBE** Utilization Plan has been submitted, and the Contractor requests a change order the value of which exceeds the greater of 10 percent of the Contract or Task Order, as applicable, or \$500,000, Agency shall review the scope of work for the Contract or Task Order, as applicable, and the scale and types of work involved in the change order, and determine whether the **Participation Goals** should be modified.
- 10. Pre-award waiver of **the Participation Goals**. (a) A bidder or proposer, or contractor with respect to a Task Order, may seek a pre-award full or partial waiver of the Participation Goals in accordance with Section 6-129, which requests that Agency change one or more **Participation Goals** on the grounds that the **Participation Goals** are unreasonable in light of the availability of certified firms to perform the services required, or by demonstrating that it has legitimate business reasons for proposing a lower level of subcontracting in its M/WBE Utilization Plan.
- (b) To apply for a full or partial waiver of the **Participation Goals**, a bidder, proposer, or contractor, as applicable, must complete Part III (Page 5) of Schedule B and submit such request no later than seven (7) calendar days prior to the date and time the bids, proposals, or Task Orders are due, in writing to the Agency by email at ______ or via facsimile at () ______ . Bidders, proposers, or contractors, as applicable, who have submitted requests will receive an Agency response by no later than two (2) calendar days prior to the due date for bids, proposals, or Task Orders; provided, however, that if that date would fall on a weekend or holiday, an Agency response will be provided by close-of-business on the business day before such weekend or holiday date.
- (c) If the Agency determines that the **Participation Goals** are unreasonable in light of the availability of certified firms to perform the services required, it shall revise the solicitation and extend the deadline for bids and proposals, or revise the Task Order, as applicable.
- (d) Agency may grant a full or partial waiver of the **Participation Goals** to a bidder, proposer or contractor, as applicable, who demonstrates—before submission of the bid, proposal or Task Order, as applicable—that it has legitimate business reasons for proposing the level of subcontracting in its **M/WBE** Utilization Plan. In making its determination, Agency shall consider factors that shall include, but not be limited to, whether the bidder, proposer or contractor, as applicable, has the capacity and the bona fide intention to perform the Contract without any subcontracting, or to perform the Contract without awarding the amount of subcontracts represented by the **Participation Goals**. In making such determination, Agency may consider whether the **M/WBE** Utilization Plan is consistent with past subcontracting practices of the bidder, proposer or contractor, as applicable, has made efforts to form a joint venture with a certified firm, and whether the bidder, proposer, or contractor, as applicable, has made good faith efforts to identify other portions of the Contract that it intends to subcontract.
- 11. Modification of M/WBE Utilization Plan. (a) A Contractor may request a modification of its M/WBE Utilization Plan after award of this Contract. PLEASE NOTE: If this Contract is a public works project subject to GML §101(5) (i.e., a contract valued at or below \$3M for projects in New York City) or if the Contract is

subject to a project labor agreement in accordance with Labor Law §222, and the bidder is required to identify at the time of bid submission its intended subcontractors for the Wicks trades (plumbing and gas fitting; steam heating, hot water heating, ventilating and air conditioning (HVAC); and electric wiring), the Contractor may request a Modification of its M/WBE Utilization Plan as part of its bid submission. The Agency may grant a request for Modification of a Contractor's M/WBE Utilization Plan if it determines that the Contractor has established, with appropriate documentary and other evidence, that it made reasonable, good faith efforts to meet the Participation Goals. In making such determination, Agency shall consider evidence of the following efforts, as applicable, along with any other relevant factors:

- (i) The Contractor advertised opportunities to participate in the Contract, where appropriate, in general circulation media, trade and professional association publications and small business media, and publications of minority and women's business organizations;
- (ii) The Contractor provided notice of specific opportunities to participate in the Contract, in a timely manner, to minority and women's business organizations;
- (iii) The Contractor sent written notices, by certified mail or facsimile, in a timely manner, to advise MBEs or WBEs that their interest in the Contract was solicited:
- (iv) The Contractor made efforts to identify portions of the work that could be substituted for portions originally designated for participation by MBEs and/or WBEs in the **M/WBE** Utilization Plan, and for which the Contractor claims an inability to retain MBEs or WBEs;
- (v) The Contractor held meetings with MBEs and/or WBEs prior to the date their bids or proposals were due, for the purpose of explaining in detail the scope and requirements of the work for which their bids or proposals were solicited;
- (vi) The Contractor made efforts to negotiate with MBEs and/or WBEs as relevant to perform specific subcontracts, or act as suppliers or service providers;
- (vii) Timely written requests for assistance made by the Contractor to Agency's M/WBE liaison officer and to DSBS;
- (viii) Description of how recommendations made by DSBS and Agency were acted upon and an explanation of why action upon such recommendations did not lead to the desired level of participation of MBEs and/or WBEs.

Agency's M/WBE officer shall provide written notice to the Contractor of the determination.

- (b) The Agency may modify the **Participation Goals** when the scope of the work has been changed by the Agency in a manner that affects the scale and types of work that the Contractor indicated in its **M/WBE Utilization Plan** would be awarded to subcontractors.
- 12. If this Contract is for an indefinite quantity of construction, standard or professional services or is a requirements type contract and the Contractor has submitted an **M/WBE** Utilization Plan and has committed to subcontract work to MBEs and/or WBEs in order to meet the **Participation Goals**, the Contractor will not be deemed in violation of the M/WBE Program requirements for this Contract with regard to any work which was intended to be subcontracted to an MBE and/or WBE to the extent that the Agency has determined that such work is not needed.
- 13. If **Participation Goals** have been established for this Contract or a Task Order issued pursuant to this Contract, at least once annually during the term of the Contract or Task Order, as applicable, Agency shall review the

Contractor's progress toward attainment of its **M/WBE** Utilization Plan, including but not limited to, by reviewing the percentage of work the Contractor has actually awarded to MBE and/or WBE subcontractors and the payments the Contractor made to such subcontractors.

14. If **Participation Goals** have been established for this Contract or a Task Order issued pursuant to this Contract, Agency shall evaluate and assess the Contractor's performance in meeting those goals, and such evaluation and assessment shall become part of the Contractor's overall contract performance evaluation.

PART B

MISCELLANEOUS

- 1. The Contractor shall take notice that, if this solicitation requires the establishment of a **M/WBE** Utilization Plan, the resulting contract may be audited by DSBS to determine compliance with Section 6-129. See §6-129(e)(10). Furthermore, such resulting contract may also be examined by the City's Comptroller to assess compliance with the **M/WBE** Utilization Plan.
- 2. Pursuant to DSBS rules, construction contracts that include a requirement for a **M/WBE** Utilization Plan shall not be subject to the law governing Locally Based Enterprises set forth in Section 6-108.1 of the Administrative Code of the City of New York.
- 3. DSBS is available to assist contractors and potential contractors in determining the availability of MBEs and/or WBEs to participate as subcontractors, and in identifying opportunities that are appropriate for participation by MBEs and/or WBEs in contracts.
- 4. Prospective contractors are encouraged to enter into qualified joint venture agreements with MBEs and/or WBEs as defined by Section 6-129(c)(30).
- 5. By submitting a bid or proposal the Contractor hereby acknowledges its understanding of the M/WBE Program requirements set forth herein and the pertinent provisions of Section 6-129, and any rules promulgated thereunder, and if awarded this Contract, the Contractor hereby agrees to comply with the M/WBE Program requirements of this Contract and pertinent provisions of Section 6-129, and any rules promulgated thereunder, all of which shall be deemed to be material terms of this Contract. The Contractor hereby agrees to make all reasonable, good faith efforts to solicit and obtain the participation of MBEs and/or WBEs to meet the required **Participation Goals**.

ARTICLE II. ENFORCEMENT

- 1. If Agency determines that a bidder or proposer, as applicable, has, in relation to this procurement, violated Section 6-129 or the DSBS rules promulgated pursuant to Section 6-129, Agency may disqualify such bidder or proposer, as applicable, from competing for this Contract and the Agency may revoke such bidder's or proposer's prequalification status, if applicable.
- 2. Whenever Agency believes that the Contractor or a subcontractor is not in compliance with Section 6-129 or the DSBS rules promulgated pursuant to Section 6-129, or any provision of this Contract that implements Section 6-129, including, but not limited to any **M/WBE** Utilization Plan, Agency shall send a written notice to the Contractor describing the alleged noncompliance and offering the Contractor an opportunity to be heard. Agency shall then conduct an investigation to determine whether such Contractor or subcontractor is in compliance.

- 3. In the event that the Contractor has been found to have violated Section 6-129, the DSBS rules promulgated pursuant to Section 6-129, or any provision of this Contract that implements Section 6-129, including, but not limited to, any **M/WBE** Utilization Plan, Agency may determine that one of the following actions should be taken:
 - (a) entering into an agreement with the Contractor allowing the Contractor to cure the violation;
 - (b) revoking the Contractor's pre-qualification to bid or make proposals for future contracts;
 - (c) making a finding that the Contractor is in default of the Contract;
 - (d) terminating the Contract;
 - (e) declaring the Contractor to be in breach of Contract;
 - (f) withholding payment or reimbursement;
 - (g) determining not to renew the Contract;
 - (h) assessing actual and consequential damages;
 - (i) assessing liquidated damages or reducing fees, provided that liquidated damages may be based on amounts representing costs of delays in carrying out the purposes of the M/WBE Program, or in meeting the purposes of the Contract, the costs of meeting utilization goals through additional procurements, the administrative costs of investigation and enforcement, or other factors set forth in the Contract;
 - (j) exercising rights under the Contract to procure goods, services or construction from another contractor and charge the cost of such contract to the Contractor that has been found to be in noncompliance; or
 - (k) taking any other appropriate remedy.
- 4. If an M/WBE Utilization Plan has been submitted, and pursuant to this Article II, Section 3, the Contractor has been found to have failed to fulfill its Participation Goals contained in its M/WBE Utilization Plan or the Participation Goals as modified by Agency pursuant to Article I, Part A, Section 11, Agency may assess liquidated damages in the amount of ten percent (10%) of the difference between the dollar amount of work required to be awarded to MBE and/or WBE firms to meet the Participation Goals and the dollar amount the Contractor actually awarded and paid, and/or credited, to MBE and/or WBE firms. In view of the difficulty of accurately ascertaining the loss which the City will suffer by reason of Contractor's failure to meet the Participation Goals, the foregoing amount is hereby fixed and agreed as the liquidated damages that the City will suffer by reason of such failure, and not as a penalty. Agency may deduct and retain out of any monies which may become due under this Contract the amount of any such liquidated damages; and in case the amount which may become due under this Contract shall be less than the amount of liquidated damages suffered by the City, the Contractor shall be liable to pay the difference.
- 5. Whenever Agency has reason to believe that an MBE and/or WBE is not qualified for certification, or is participating in a contract in a manner that does not serve a commercially useful function (as defined in Section 6-129(c)(8)), or has violated any provision of Section 6-129, Agency shall notify the Commissioner of DSBS who shall determine whether the certification of such business enterprise should be revoked.
- 6. Statements made in any instrument submitted to Agency pursuant to Section 6-129 shall be submitted under penalty of perjury and any false or misleading statement or omission shall be grounds for the application of any

applicable criminal and/or civil penalties for perjury. The making of a false or fraudulent statement by an MBE and/or WBE in any instrument submitted pursuant to Section 6-129 shall, in addition, be grounds for revocation of its certification.

7. The Contractor's record in implementing its **M/WBE** Utilization Plan shall be a factor in the evaluation of its performance. Whenever Agency determines that a Contractor's compliance with an **M/WBE** Utilization Plan has been unsatisfactory, Agency shall, after consultation with the City Chief Procurement Officer, file an advice of caution form for inclusion in VENDEX as caution data.

· · · · · ·		
ax ID #:	APT E-PIN #:	- N7218RNNNG
$a \wedge i \cup \pi$.	$\triangle I I \square I \square $	0121000003



SCHEDULE B - M/WBE Utilization Plan Part I: M/WBE Participation Goals

Part I to be completed by contracting agency

Contract Overview							
APT E- Pin # Project Title/	07218B0009		_ FMS Pr	oject ID#:			
Agency PIN # Bid/Proposal	072201821CPD						
Response Date	2017-11-13						
Contracting Agency	DOC						
Agency Address	75-20 Astoria Blvd., Ste 160	City	East Elmhu	ırst Stat	e NY	Zip Code	11370
, igonoj , iaanooo		_	Laot Liiiii			p	11010
Contact Person	Phillip Emmanuel Intatano 718-546-0692		Title Email	Contract Ma phillip.intata		2)/0 (20)/	
Telephone #	710-040-0092		EIIIaII	priiiip.iritatai	10@000.1	iyc.gov	
Project Description	(attach additional pages if necessary)						
It is the objective of the Department of Correction, Division of Capital Policy and Development, to secure qualified Mechanical Contractors to provide construction for the Installation of Chiller Water Riser at Vernon C. Bain Center (VCBC) located at 1 Halleck Street, Bronx, NY 10474							

<u>M/WBE Participation Goals for Services</u>

<u>Enter the percentage amount for each group or for an unspecified goal. Please note that there are no goals for Asian Americans in Professional Services.</u>

Prime Contract Industry: Construction

Unspecified 20% or 0 Black American 0% Hispanic American 0% Asian American 0% Women 0% Total Participation Goals 20%	Group	Percentage
Black American 0% Hispanic American 0% Asian American 0% Women 0%	<u>Unspecified</u>	20%
Hispanic American 0% Asian American 0% Women 0%	or	
Asian American 0% Women 0%	Black American	0%
Women 0%	Hispanic American	0%
	Asian American	0%
Total Participation Goals 20%	Women	0%
	Total Participation Goals	20%

Tax ID #:	APT E-PIN #:	07218B0009

SCHEDULE B - Part II: M/WBE Participation Plan

Part II to be completed by the bidder/proposer.

Please note: For Non-M/WBE Prime Contractors who will NOT subcontract any services and will self-perform the entire contract, you must obtain a FULL waiver by completing the Waiver Application on pages 5 and 6 and timely submitting it to the contracting agency pursuant to the Notice to Prospective Contractors. Once a FULL WAIVER is granted, it must be included with your bid or proposal and you do not have to complete or submit this form with your bid or proposal.

Section I: Prime Contractor Contact Inform	nation				
Tax ID #			FMS Vendor ID #		
Business Name			Contact Person _		
Address					
Telephone #	Email _				
Section II: M/WBE Utilization Goal Calcula	tion: Check the appli	cab	le box and complete sub	section.	
PRIME CONTRACTOR ADOPTIN			<u> </u>		 }
	Total Bid/Proposal		Agency Total		
☐ For Prime Contractors (including Qualified Joint Ventures and M/WBE	Value .		Participation Goals (Line 1, Page 1)		Calculated M/WBE Participation Amount
firms) adopting Agency M/WBE Participation Goals.					
Calculate the total dollar value of your total bid that you agree will be awarded to M/WBE subcontractors for services and/or credited to an M/WBE prime contractor or Qualified Joint Venture.					
Please review the Notice to Prospective Contractors for more information on how to obtain credit for M/WBE participation.	\$	x		=	\$ Line 2
PRIME CONTRACTOR OBTAINS M/WBE PARTICIPATION GOALS		ΙV		DOPTIN	G MODIFIED
☐ For Prime Contractors (including Qualified Joint Ventures and M/WBE	Total Bid/Proposal Value		Adjusted Participation Goal (From Partial Waiver)		Calculated M/WBE Participation Amount
firms) adopting Modified M/WBE Participation Goals.					
Calculate the total dollar value of your total bid that you agree will be awarded to M/WBE subcontractors for services and/or credited to an M/WBE prime contractor or Qualified Joint Venture.					
Please review the Notice to Prospective Contractors for more information on how to obtain credit for M/WBE participation.	\$	x		=	\$ Line 3

Tax ID #:	APT E-PIN #: 07218B0009
Notice to Prospective Contract	Plan: How Proposer/Bidder Will Fulfill M/WBE Participation Goals. Please review the tors for more information on how to obtain credit for M/WBE participation. Check or Bidder will fulfill the M/WBE Participation Goals:
the value of which is at least the to non-M/WBE firms will not be contractor: MBE WBE As a Qualified Joint Venture value of any work subcontracted The value of any work subcontracted Goals.	ctor that will self-perform and/or subcontract to other M/WBE firms a portion of the contract amount located on Lines 2 or 3 above, as applicable. The value of any work subcontracted redited towards fulfillment of M/WBE Participation Goals. Please check all that apply to with an M/WBE partner, in which the value of the M/WBE partner's participation and/or the to other M/WBE firms is at least the amount located on Lines 2 or 3 above, as applicable. cted to non M/WBE firms will not be credited towards fulfillment of M/WBE Participation tractor that will enter into subcontracts with M/WBE firms the value of which is at least the above, as applicable.
Section IV: General Contract Info	ormation
_	ge of the total contract dollar value that you expect to award in subcontracts for services,
✓ Scopes of Subcontract Work	Enter brief description of the type(s) and dollar value of subcontracts for all/any services you plan on subcontracting if awarded this contract. For each item, indicate whether the work is designated for participation by MBEs and/or WBEs and the time frame in which such work is scheduled to begin and end. Use additional sheets if necessary. 1

Tax ID #:	APT E-PIN #:07218B0009
Section V: Vendor Certification and Required Affirmations	
I hereby:	
1) acknowledge my understanding of the M/WBE participation requirement provisions of Section 6-129 of the Administrative Code of the City of New promulgated thereunder;	
2) affirm that the information supplied in support of this M/WBE Utilizatio 3) agree, if awarded this Contract, to comply with the M/WBE participation pertinent provisions of Section 6-129, and the rules promulgated thereur material terms of this Contract;	on requirements of this Contract, the
4) agree and affirm that it is a material term of this Contract that the Venthe M/WBE Participation Goals to certified MBEs and/or WBEs, unless a modified by the Agency; and	
5) agree and affirm, if awarded this Contract, to make all reasonable, go Participation Goals, or If a partial waiver is obtained or such goals are modified Participation Goals by soliciting and obtaining the participation	nodified by the Agency, to meet the

Tax ID #:	APT E-PIN #:	07218B0009

SCHEDULE B - PART III - REQUEST FOR WAIVER OF M/WBE PARTICIPATION REQUIREMENT

Tax ID #	FMS Vendor	ID#
Business Name		
Contact Name	Telephone #	Email
_	•	Response Due Date
	_ ·	·
APT E-PIN # (for this	procurement): 07218B0009	Contracting Agency: DOC
M/WBE Participa	tion Goals as described in bid/solicitation documents	
20	0% —— Agency M/WBE Participation Goal	
Proposed M/WBE Pa	rticipation Goal as anticipated by vendor seeking waive	er
•	% of the total contract value anticipated <u>in good faith</u>	
	services and/or credited to an M/WBE Prime Contr	actor or Qualified Joint Venture.
Basis for Waiver R	equest: Check appropriate box & explain in detail below	w (attach additional pages if needed)
e vendor will self- Vendor has othe	od faith intention to do so on this contract. (Attach perform and subcontract to other vendors or consu r legitimate business reasons for proposing the M/\	ıltants.)
e vendor will self- Vendor has othe eparate cover. References st 3 most recent con	perform and subcontract to other vendors or consu	lltants.) WBE Participation Goal above. Explain u
ne vendor will self- Vendor has othe eparate cover. References ist 3 most recent con	perform and subcontract to other vendors or consumal legitimate business reasons for proposing the M/N performed for NYC agencies (if any). Include info	lltants.) WBE Participation Goal above. Explain u
ne vendor will self- Vendor has othe eparate cover. References ist 3 most recent con erformance of such o	perform and subcontract to other vendors or consumar legitimate business reasons for proposing the M/N per legitimate business reasons r	Iltants.) NBE Participation Goal above. Explain un rmation for each subcontract awarded in
he vendor will self- Vendor has othe eparate cover. References ist 3 most recent conterformance of such of	perform and subcontract to other vendors or consult legitimate business reasons for proposing the M/N intracts performed for NYC agencies (if any). Include information and more pages if necessary. AGENCY Total Amount	Iltants.) NBE Participation Goal above. Explain un rmation for each subcontract awarded in
Ne vendor will self- Vendor has othe eparate cover. References ist 3 most recent con erformance of such of CONTRACT NO. Total Contract Amount Item of Work	perform and subcontract to other vendors or consult religitimate business reasons for proposing the M/N particles of tracts performed for NYC agencies (if any). Include information contracts. Add more pages if necessary. AGENCY Total Amount Subcontracted Item of Work	NBE Participation Goal above. Explain un rmation for each subcontract awarded in DATE COMPLETED Item of Work
Ne vendor will self- Vendor has other eparate cover. References set 3 most recent conterformance of such of the contract of the contract of the content of the contract of th	perform and subcontract to other vendors or consult religitimate business reasons for proposing the M/N entracts performed for NYC agencies (if any). Include information and the secontracts. Add more pages if necessary. AGENCY Total Amount Subcontracted	NBE Participation Goal above. Explain un rmation for each subcontract awarded in DATE COMPLETED
Ne vendor will self- Vendor has other eparate cover. References set 3 most recent conterformance of such of the contract of the contract of the content of the contract of th	perform and subcontract to other vendors or consult religitimate business reasons for proposing the M/N particles of the second	NBE Participation Goal above. Explain un rmation for each subcontract awarded in DATE COMPLETED Item of Work Subcontracted and
Ne vendor will self- Vendor has other eparate cover. References ist 3 most recent conterformance of such of the contract of t	perform and subcontract to other vendors or consult religitimate business reasons for proposing the M/N particles of the second	NBE Participation Goal above. Explain un rmation for each subcontract awarded in DATE COMPLETED Item of Work Subcontracted and
References ist 3 most recent conerformance of such a CONTRACT NO. Total Contract Amount Item of Work Subcontracted and Value of subcontract	perform and subcontract to other vendors or consult religitimate business reasons for proposing the M/N particles performed for NYC agencies (if any). Include information contracts. Add more pages if necessary. AGENCY Total Amount Subcontracted \$ Item of Work Subcontracted and Value of subcontract	NBE Participation Goal above. Explain un rmation for each subcontract awarded in DATE COMPLETED Item of Work Subcontracted and Value of subcontract
References ist 3 most recent conerformance of such of CONTRACT NO. Total Contract Amount Item of Work Subcontracted and Value of subcontract CONTRACT NO. Total Contract Amount Item of Work Subcontracted and Value of subcontract CONTRACT NO. Total Contract Amount	perform and subcontract to other vendors or consult religitimate business reasons for proposing the M/N particles and tracts performed for NYC agencies (if any). Include information contracts. Add more pages if necessary. AGENCY Total Amount Subcontracted and Value of subcontract AGENCY Total Amount Subcontracted \$ AGENCY Total Amount Subcontracted \$	NBE Participation Goal above. Explain un rmation for each subcontract awarded in DATE COMPLETED Item of Work Subcontracted and Value of subcontract DATE COMPLETED
References ist 3 most recent conerformance of such of CONTRACT NO. Total Contract Amount Item of Work Subcontracted and Value of subcontract CONTRACT NO. Total Contract Amount Item of Work Subcontract Value of Subcontract Item of Work Item of Work	perform and subcontract to other vendors or consult religitimate business reasons for proposing the M/N particles and tracts performed for NYC agencies (if any). Include information and tracts. Add more pages if necessary. AGENCY Total Amount Subcontracted and Value of subcontract AGENCY Total Amount Subcontracted \$ Item of Work Subcontracted \$ Item of Work	Iltants.) WBE Participation Goal above. Explain un rmation for each subcontract awarded in DATE COMPLETED Item of Work Subcontracted and Value of subcontract DATE COMPLETED Item of Work
References ist 3 most recent conterformance of such of the contract Amount Item of Work Subcontracted and Value of subcontract CONTRACT NO. Total Contract Amount Item of Work Subcontracted and Value of subcontract Amount Item of Work Subcontracted and Item of Work Subcontracted and	perform and subcontract to other vendors or consult religitimate business reasons for proposing the M/N particles and tracts performed for NYC agencies (if any). Include information contracts. Add more pages if necessary. AGENCY Total Amount Subcontracted and Value of subcontract AGENCY Total Amount Subcontracted \$ AGENCY Total Amount Subcontracted \$	NBE Participation Goal above. Explain un rmation for each subcontract awarded in DATE COMPLETED Item of Work Subcontracted and Value of subcontract DATE COMPLETED
References ist 3 most recent conerformance of such of CONTRACT NO. Total Contract Amount Item of Work Subcontracted and Value of subcontract CONTRACT NO. Total Contract Amount Item of Work Subcontract Amount Item of Work Subcontract Amount Item of Work Subcontracted and	perform and subcontract to other vendors or consult religitimate business reasons for proposing the M/N particles and tracts performed for NYC agencies (if any). Include information and tracts. Add more pages if necessary. AGENCY Total Amount Subcontracted and Value of subcontract AGENCY Total Amount Subcontracted \$ Item of Work Subcontracted \$ Item of Work Subcontracted \$ Item of Work Subcontracted and	Itants.) WBE Participation Goal above. Explain un rmation for each subcontract awarded in DATE COMPLETED Item of Work Subcontracted and Value of subcontract DATE COMPLETED Item of Work Subcontracted and Value of subcontract
References ist 3 most recent converformance of such of the contract Amount Item of Work Subcontracted and Value of subcontract CONTRACT NO. Total Contract Amount Item of Work Subcontracted and Value of subcontracted and Value of subcontract Letter of Work Item of Work Item of Work	perform and subcontract to other vendors or consult religitimate business reasons for proposing the M/N particles and tracts performed for NYC agencies (if any). Include information and tracts. Add more pages if necessary. AGENCY Total Amount Subcontracted and Value of subcontract AGENCY Total Amount Subcontracted \$ Item of Work Subcontracted \$ Item of Work Subcontracted \$ Item of Work Subcontracted and	Itants.) WBE Participation Goal above. Explain un rmation for each subcontract awarded in DATE COMPLETED Item of Work Subcontracted and Value of subcontract DATE COMPLETED Item of Work Subcontracted and Value of subcontract
References ist 3 most recent conterformance of such a CONTRACT NO. Total Contract Amount Item of Work Subcontracted and Value of subcontract Amount Item of Work Subcontract CONTRACT NO. Total Contract Amount Item of Work Subcontract Amount Item of Work Subcontract	perform and subcontract to other vendors or consult religitimate business reasons for proposing the M/N particles of the series	NBE Participation Goal above. Explain un mation for each subcontract awarded in DATE COMPLETED Item of Work Subcontracted and Value of subcontract DATE COMPLETED Item of Work Subcontracted and Value of subcontract
References ist 3 most recent conterformance of such of the contract Amount Item of Work Subcontracted and Value of subcontracted Amount Item of Work Subcontracted Amount Value of Subcontract	perform and subcontract to other vendors or consult religitimate business reasons for proposing the M/N performed for NYC agencies (if any). Include information contracts. Add more pages if necessary. AGENCY Total Amount Subcontracted Item of Work Subcontracted and Value of subcontracted AGENCY Total Amount Subcontracted AGENCY Item of Work Subcontracted and Value of subcontract AGENCY Total Amount Subcontracted and Value of subcontract AGENCY Total Amount Total Amount	NBE Participation Goal above. Explain un mation for each subcontract awarded in DATE COMPLETED Item of Work Subcontracted and Value of subcontract DATE COMPLETED Item of Work Subcontracted and Value of subcontract
References ist 3 most recent conterformance of such of the contract Amount Item of Work Subcontracted and Value of subcontracted and Value of subcontract Item of Work Subcontracted and Value of Subcontracted an	perform and subcontract to other vendors or consult religitimate business reasons for proposing the M/N performed for NYC agencies (if any). Include information contracts. Add more pages if necessary. AGENCY Total Amount Subcontracted Item of Work Subcontracted and Value of subcontracted AGENCY Total Amount Subcontracted AGENCY Total Amount Subcontracted and Value of subcontract AGENCY AGENCY Total Amount Subcontracted and Value of subcontract AGENCY Total Amount Total Amount	NBE Participation Goal above. Explain un mation for each subcontract awarded in DATE COMPLETED Item of Work Subcontracted and Value of subcontract DATE COMPLETED Item of Work Subcontracted and Value of subcontract

Tax ID #:		APT E-PIN #: 07218B0009
List 3 most recent contracts perfo such contracts. Add more pages	ormed for other entities. Include informatio s if necessary.	n for each subcontract awarded in performance of
(Complete ONLY if vendor has perfo	ormed fewer than 3 New York City contracts.)	
TYPE OF Contract	AGENCY/ENTITY	DATE COMPLETED
Manager at agency/entity that hir	ed vendor (Name/Phone No./Email)	
Total Contract	Total Amount	
Amount \$	Subcontracted \$	
Type of Work Subcontracted		
TYPE OF Contract	AGENCY/ENTITY	DATE COMPLETED
Manager at agency/entity that hir	ed vendor (Name/Phone No./Email)	
Total Contract	Total Amount	
Amount \$	Subcontracted \$	
Item of Work	Item of Work	Item of Work
Subcontracted and Value of	Subcontracted and Value of	Subcontracted and Value of
subcontract	subcontract	subcontract
TYPE OF Contract	AGENCY/ENTITY	DATE COMPLETED
Manager at agency/entity that hir	red vendor (Name/Phone No./Email)	· · · · · · · · · · · · · · · · · · ·
Total Contract	Total Amount	
Amount \$	Subcontracted \$	
Item of Work Subcontracted	Item of Work Subcontracted	Item of Work Subcontracted and
and Value of	and Value of	Value of
subcontract	subcontract	subcontract
VENDOR CERTIFICATION: I had and that this request is made in		in support of this waiver request is true and correct
Signature:		Date:
Print Name:		Title:
01-1-1-1		
Shaded area below is for agency AGENCY CHIEF CONTRACTII		
Signature:	NG OFFICER AFFROVAL	Date:
CITY CHIEF PROCUREMENT		
Signature:		Date:
Waiver Determination		
Full Waiver Approved: Waiver Denied: Partial Waiver Approved: Revised Participation Goa		

APT E-PIN #: 07218B0009

ATTACHMENT B CONSTRUCTION EMPLOYMENT REPORT

The City of New York Department of Small Business Services
Division of Labor Services Contract Compliance Unit
110 William Street, New York, New York 10038

Phone: (212) 513 – 6323 Fax: (212) 618-8879

CONSTRUCTION EMPLOYMENT REPORT

GENERAL INFORMATION

1.	Your contractual relationship in this contract is:	Prime contractor S	ubcontractor		
1a.	Are M/WBE goals attached to this project? Yes	No			
2.	Please check one of the following if your firm would like information on how to certify with the City of New York as a:				
	Minority Owned Business EnterpriseWomen Owned Business EnterpriseDisadvantaged Business Enterprise	Locally Based Be Emerging Busine	-		
2a.	If you are certified as an MBE, WBE, LBE, EBE or certified with?				
3.	Please indicate if you would like assistance from SE contracting opportunities: Yes No	3S in identifying certified	M/WBEs for		
4.	Is this project subject to a project labor agreement?	Yes No			
5.	Are you a Union contractor? Yes No If yes, please list which local(s) you affiliated with				
6.	Are you a Veteran owned company? Yes No)			
PAR ⁻	T I: CONTRACTOR/SUBCONTRACTOR INFORMAT	ΓΙΟΝ			
7.					
	Employer Identification Number or Federal Tax I.D.		Email Address		
8.	Company Name				
9.					
	Company Address and Zip Code				
10.	Chief Operating Officer	Telephone Numl	oor		
4.4	Office Operating Officer	relephone Numi	Jei		
11.	Designated Equal Opportunity Compliance Officer (If same as Item #10, write "same")	Telephone Numl	oer		
12.					
	Name of Prime Contractor and Contact Person (If same as Item #8, write "same")				

13.	Number of employees in your company:	
14.	Contract information:	
	(a)	(b) Contract Amount
	(a) Contracting Agency (City Agency)	Contract Amount
	(c)	(d)
	(c) Procurement Identification Number (PIN)	(d)Contract Registration Number (CT#)
	(e)	(f)
	(e)Projected Commencement Date	(f)Projected Completion Date
	(g) Description and location of proposed contract:	
15.	Has your firm been reviewed by the Division of La and issued a Certificate of Approval? Yes No	
	If yes, attach a copy of certificate.	
16.	Has DLS within the past month reviewed an Empl and issued a Conditional Certificate of Approval?	
	If yes, attach a copy of certificate.	
WI	TE: DLS WILL NOT ISSUE A CONTINUED CERT TH THIS CONTRACT UNLESS THE REQUIRED ON NOITIONAL CERTIFICATES OF APPROVAL HAV	ORRECTIVE ACTIONS IN PRIOR
17.	Has an Employment Report already been submitted Employment Report) for which you have not yet reference. If yes,	
	Date submitted:	
	Agency to which submitted:	
	Name of Agency Person:	
	Contract No: Telephone:	
18.	Has your company in the past 36 months been au Labor, Office of Federal Contract Compliance Pro	
	If yes,	
Page 2		

	(a) Name and address of OFCCP office.				
		as a Certificate of Equal Employment Compliance issued within the past 36 months?			
	If	yes, attach a copy of such certificate.			
	(c) W	ere any corrective actions required or agreed to? Yes No			
	If	yes, attach a copy of such requirements or agreements.			
	(d) W	ere any deficiencies found? Yes No			
	lf	yes, attach a copy of such findings.			
19.	is res	r company or its affiliates a member or members of an employers' trade association which ponsible for negotiating collective bargaining agreements (CBA) which affect construction tring? Yes No			
	If yes	, attach a list of such associations and all applicable CBA's.			
PART	II: DO	CUMENTS REQUIRED			
20.	broch	e following policies or practices, attach the relevant documents (e.g., printed booklets, ures, manuals, memoranda, etc.). If the policy(ies) are unwritten, attach a full explanation practices. See instructions.			
	(8	Health benefit coverage/description(s) for all management, nonunion and union employees (whether company or union administered)			
	(k	o) Disability, life, other insurance coverage/description			
	(0	c) Employee Policy/Handbook			
	(c	d) Personnel Policy/Manual			
	(e	e) Supervisor's Policy/Manual			
	(f	Pension plan or 401k coverage/description for all management, nonunion and union employees, whether company or union administered			
	(g	g) Collective bargaining agreement(s).			
	(h	n) Employment Application(s)			
	(i) Employee evaluation policy/form(s).			
	(j	Does your firm have medical and/or non-medical (i.e. education, military, personal, pregnancy, child care) leave policy?			

21.	To comply with the Immigration Reform and Control Act of 1986 when and of whom does your firm require the completion of an I-9 Form?				
	(a) Prior to job offer Yes No (b) After a conditional job offer Yes No (c) After a job offer Yes No (d) Within the first three days on the job Yes No (e) To some applicants Yes No (f) To all applicants Yes No (g) To some employees Yes No (h) To all employees Yes No				
22.	Explain where and how completed I-9 Forms, with their supportive documentation, are maintained and made accessible.				
23.	Does your firm or any of its collective bargaining agreements require job applicants to take a medical examination? Yes No If yes, is the medical examination given: (a) Prior to a job offer				
24.	Do you have a written equal employment opportunity (EEO) policy? Yes No				
	If yes, list the document(s) and page number(s) where these written policies are located.				
25.	Does the company have a current affirmative action plan(s) (AAP) Minorities and Women Individuals with handicaps Other. Please specify				
26.	Does your firm or collective bargaining agreement(s) have an internal grievance procedure with respect to EEO complaints? Yes No				
	If yes, please attach a copy of this policy.				
	If no, attach a report detailing your firm's unwritten procedure for handling EEO complaints.				

27.	Has any employee, within the past three years, filed a complaint pursuant to an internal grievance procedure or with any official of your firm with respect to equal employment opportunity? Yes No			
	If yes, attach an internal complaint log. See instructions.			
28.	Has your firm, within the past three years, been named as a defendant (or respondent) in any administrative or judicial action where the complainant (plaintiff) alleged violation of any anti-discrimination or affirmative action laws? Yes No			
	If yes, attach a log. See instructions.			
29.	Are there any jobs for which there are physical qualifications? Yes No			
	If yes, list the job(s), submit a job description and state the reason(s) for the qualification(s).			
30.	Are there any jobs for which there are age, race, color, national origin, sex, creed, disability, marital status, sexual orientation, or citizenship qualifications? Yes No			
	If yes, list the job(s), submit a job description and state the reason(s) for the qualification(s).			

SIGNATURE PAGE

I, (print name of authorized official signing) hereby certify that the information submitted herewith is true and complete to the best of my knowledge and belief and submitted with the understanding that compliance with New York City's equal employment requirements, as contained in Chapter 56 of the City Charter, Executive Order No. 50 (1980), as amended, and the implementing Rules and Regulations, is a contractual obligation. I also agree on behalf of the company to submit a certified copy of payroll records to the Division of Labor Services on a monthly basis.				
Contractor's Name				
Name of person who prepared this	Employment Report		Title	
Name of official authorized to sign of	on behalf of the contra	actor	Title	
Telephone Number				
Signature of authorized official			Date	
If contractors are found to be underutilizing minorities and females in any given trade based on Chapter 56 Section 3H, the Division of Labor Services reserves the right to request the contractor's workforce data and to implement an employment program.				
Contractors who fail to comply with the above mentioned requirements or are found to be in noncompliance may be subject to the withholding of final payment.				
Willful or fraudulent falsifications of any data or information submitted herewith may result in the termination of the contract between the City and the bidder or contractor and in disapproval of future contracts for a period of up to five years. Further, such falsification may result in civil and/and or criminal prosecution.				
To the extent permitted by law and Charter Chapter 56 of the City Char and Regulations, all information pro	rter and Executive Or	der No. 50 (1980) and the implementing Rules	
O	nly original signatur	es accepted.		
Sworn to before me this	day of	_ 20		
Notary Public	Authorized Signatu	re	Date	
Page 6				

FC	ORM A. CONTRACT BID	INFORMATION: USE OF SU	BCONTRACTORS/TRADES										
	1. Do you plan to subco	Do you plan to subcontractor work on this contract? Yes No											
	2. If yes, complete the c	chart below.											
		d subcontractors with a subcontract may be awarded an		00 must complete an Employn	nent Report for review and								
	SUBCONTRACTOR'S NAME*	OWNERSHIP (ENTER APPROPRIATE CODE LETTERS BELOW)	WORK TO BE PERFORMED BY SUBCONTRACTOR	TRADE PROJECTED FOR USE BY SUBCONTRACTOR	PROJECTED DOLLAR VALUE OF SUBCONTRACT								
	*If subcontractor is presen	itly unknown, please enter th	e trade (craft name).										

OWNERSHIP CODES

W: White

B: Black H: Hispanic A: Asian

N: Native American

F: Female

Page 8	
Revised 8/13	
FOR OFFICIAL USE ONLY:	File No

FORM B: PROJECTED WORKFORCE

TRADE CLASSIFICATION CODES

(J) Journeylevel Workers (H) Helper

(TOT) Total by Column

(A) Apprentice (TRN) Trainee

For each trade to be engaged by your company for this project, enter the projected workforce for Males and Females by trade classification on the charts below.

Trade:			ı	WALES			FEMALES					
Union Affiliation, if applicable	 e	(1) White Non Hisp.	(2) Black Non Hisp.	(3)	(4) Asian	(5) Native Amer.	1 1	(6) White Non Hisp.	(7) Black Non Hisp.	(8)	(9) Asian	(10) Native Amer.
Total (Col. #1-10):	 J						-					
Total Minority, Male & Fema (Col. #2,3,4,5,7,8,9, & 10):							-					
Total Female (Col. #6 – 10):	A TRN						-					
	тот											

What are the recruitment sources for you projected hires (i.e., unions, government employment office, job tap center, community outreach)?								

Page 9
Revised 8/13
FOR OFFICIAL USE ONLY: File No._____

FORM B: PROJECTED WORKFORCE

Trade:				ľ	MALES				FEMALES				
Union Affiliation, if applica	ble		(1) White Non Hisp.	(2) Black Non Hisp.	(3)	(4) Asian	(5) Native Amer.	1	(6) White Non Hisp.	(7) Black Non Hisp.	(8)	(9) Asian	(10) Native Amer.
Total (Col. #1-10):		J											
Total Minority, Male & Fen		Н											
(Col. #2,3,4,5,7,8,9, & 10)	:	Α											
Total Female (Col. #6 – 10):	TF	RN											
	TO	ТС											
				1			1			1	1	1	

What are the recruitment sources for you projected hires (i.e., unions, government employment office, job tap center, community outreach)?									

FORM C: CURRENT WORKFORCE

TRADE CLASSIFICATION CODES

(J) Journeylevel Workers (H) Helper

(TOT) Total by Column

(A) Apprentice (TRN) Trainee

For each trade currently engaged by your company for all work performed in New York City, enter the current workforce for Males and Females by trade classification on the charts below.

Trade:			ı	MALES					FE	MALES		
Union Affiliation, if applicable		(1) White Non Hisp.	(2) Black Non Hisp.	(3)	(4) Asian	(5) Native Amer.	1 г	(6) White Non Hisp.	(7) Black Non Hisp.	(8)	(9) Asian	(10) Native Amer.
Total (Col. #1-10):	J											
Total Minority, Male & Female (Col. #2,3,4,5,7,8,9, & 10):	H											
	Α											
Total Female (Col. #6 – 10):	TRN											
	ТОТ											

What are the recruitment sources for you projected hires (i.e., unions, government employment office, job tap center, community outreach)?							

Page 11
Revised 8/13
FOR OFFICIAL USE ONLY: File No._____

FORM C: CURRENT WORKFORCE

Trade:			1	MALES					FE	MALES		
Union Affiliation, if applicable	_	(1) White Non Hisp.	(2) Black Non Hisp.	(3)	(4) Asian	(5) Native Amer.	٦	(6) White Non Hisp.	(7) Black Non Hisp.	(8)	(9) Asian	(10) Native Amer.
Total (Col. #1-10):	J											
Total Minority, Male & Female	H e											
(Col. #2,3,4,5,7,8,9, & 10):	Α											
Total Female (Col. #6 – 10):	TRN											
	ТОТ											
			1	•	•	1			1	1	1	

What are the recruitment sources for you projected hires (i.e., unions, government employment office, job tap center, community outreach)?							

ATTACHMENT C SUBCONTRACTING COMPLIANCE NOTICE

SUB-CONTRACTING COMPLIANCE NOTICE

Notice for Bidders:

As of March 2013 the City has implemented a new web based subcontractor reporting system through the City's Payee Information Portal (PIP), available at www.nyc.gov/pip. In order to use the new system, a PIP account will be required. Detailed instructions on creating a PIP account and using the new system are also available at that site. Additional assistance with PIP may be received by emailing the Financial Information Services Agency Help Desk at pip@fisa.nyc.gov.

In order to obtain subcontractor approval under Article 11 of Part D, section 3.02 of Appendix A or Article 17 of the Standard Construction Contract and PPB Rule §4-13, Contractor is required to list the subcontractor in the system. For each subcontractor listed, Contractor is required to provide the following information: maximum contract value, description of subcontractor work, start and end date of the subcontract and identification of the subcontractor's industry. Thereafter, Contractor will be required to report in the system the payments made to each subcontractor within 30 days of making the payment. If any of the required information changes throughout the term of the contract, Contractor will be required to revise the information in the system.

Failure of the Contractor to list a subcontractor and/or to report subcontractor payments in a timely fashion may result in the Agency declaring the Contractor in default of the Contract and will subject Contractor to liquidated damages in the amount of \$100 per day for each day that the Contractor fails to identify a subcontractor along with the required information about the subcontractor and/or fails to report payments to a subcontractor, beyond the time frames set forth herein or in the notice from the City. For construction contracts, the provisions of Article 15 of the Standard Construction Contract shall govern the issue of liquidated damages. Contractor hereby agrees to these provisions.

CITY OF NEW YORK SUBCONTRACTOR APPROVAL FORM

For subcontracts to be approved before contract registration Column on left indicates whom that section is to be completed by

_ <u></u>			PRIME CONTR			TION				
AGENCY	Agency: Unit/Div:									
AGI										
	Contract Descrip									
		PR	IME CONTRAC			CATION				
	Name:			EIN/SS	N:					
			SUBCONTRAC	TORIN	IFORM <i>A</i>	TION				
	Name:			PIP Ver	ndor #:					
Œ	*Phone:			*Fax:	_		· -			
TO	*Address:			*City:			*State/	Zip:		
AC	*EIN/SSN:			*E-Mail	•					
PRIME CONTACTOR	Subcontract Des	cription:						•		
\mathcal{Z}	Approx Subconti			Approx	Start Date	-/_/_	Approx	End Date/_/		
ME		s DSBS-certified	as: M/WBE EB	E 🗌 or L	BE (che	ck all that a	pply & no	ote status below)		
<u></u>	YES□		ication Pending					NO		
ė.	Prime Contract	or Certification:	hereby affirm that	the inforn	nation sup	plied is true	and cor	rect.		
	Signature					Title				
	Print Name					Date				
	Email					Phone				
			ACENCY DDE	LIBAINIA	DV DEV	/IE\A/				
		PLE/	AGENCY PRE ASE SEE PAGE				;			
AGENCY	Agency Prelimin	ary Review Compl	eted By:				Da	nte		
AGE	1. VENDEX		2. Employment			3. Refe	rences			
	4. PLA		5. Apprenticesh	ip 🗌		6. Licer	ises			
			PRIME CONTR	ACTOF	RESPO	DNSE				
PRIME CONTACTOR		poxes checked in to all relevant require						ne		

^{*}Not required if subcontractor is in PIP

CITY OF NEW YORK SUBCONTRACTOR APPROVAL FORM

For subcontracts to be approved after contract registration

Column on left indicates whom that section is to be completed by

	P	RIME CONTR	ACT INFORMATI	ON	
	Agency:		Unit/Div:		
	Contract ID:		Prime Vendor:		
	Prime Contract Description:		······································		
ζ	Subcontractor Name:				
Ž	Subcontract ID (from PIP):				
AGENCY	Agency Preliminary Review Comple	Date			
	1. VENDEX	2. Employment		3. References	
	4. PLA	5. Apprenticeshi	р	6. Licenses	
Œ	P	RIME CONTR	ACTOR RESPON	ISE	
PRIME CONTACTO	For each of the boxes checked in the Subcontractor of all relevant require				

CITY OF NEW YORK SUBCONTRACTOR APPROVAL FORM

Page 2

Prime Vendor Preliminary Review Follow-up Instructions

After completing the Preliminary Review, the agency will mark, on Page 1, the box for any item requiring follow-up and return the form the to the Prime Vendor. The Prime Vendor should follow the instructions below for each of the boxes checked in the Agency Preliminary Review on Page 1, and return the form to the agency with any required documentation.

1. VENDEX

If Box 1 (VENDEX) is checked, the agency has granted preliminary approval, and determined that the subcontractor is required to file VENDEX Questionnaires with the Mayor's Office of Contract Services. A VENDEX Vendor Questionnaire and Principal Questionnaire must be filed where the subcontract dollar amount is ≥ \$100,000 or where the aggregate business with the City is ≥ \$100,000 during the preceding twelve months. The VENDEX Questionnaires and Guide can be downloaded from http://www.nyc.gov/html/selltonyc/html/tocvendex.html.

2. Employment

If Box 2 (Employment) is checked, the subcontractor must complete a Division of Labor Services (DLS) Construction Employment Report. A subcontractor selected to perform work on a construction project funded or assisted by the City of New York must complete a DLS Construction Employment Report if the subcontract dollar amount > \$750,000.For construction projects funded in whole or in part by the federal government, a DLS Construction Employment Report must be completed if the proposed subcontract value > \$10,000.For non-construction goods/services subcontracts > \$100,000, employment reports are required for any subcontractor with > 50 employees, and a certificate is required for those with fewer employees.

3. References

If Box 3 (References) is checked, you as the prime contractor must provide references with respect to the subcontractor's ability to perform, consisting of a list of three completed comparable projects. References shall include a full description/location of each project, scope of work, value of project, and the names and phone numbers of owners, architect or engineer who supervised the work. Please attach your documentation to your response.

4. PLA

If Box 4 (PLA) is checked, you as the prime contractor must obtain signed Letter of Assent from the subcontractor which demonstrates that the subcontractor agrees to the terms of the PLA. Please attach the subcontractor's signed Letter of Assent to your response.

5. Apprenticeship

If Box 5 (Apprenticeship) is checked, you as the prime contractor must provide the agency with proof that the subcontractor maintains an apprenticeship agreement appropriate for the scope of work to be performed, that the apprenticeship agreement has been registered with and approved by the New York State Commission of Labor, and that the program has three years of current, successful experience in providing career opportunities.

6. Licenses

If Box 6 (Licenses) is checked, you as the prime contractor must document that the subcontractor has all required licenses. Please attach your documentation to your response.

ATTACHMENT D

UNDUE FAMILIARITY AND PREVENTION OF SEXUAL ABUSE OF INMATES BY STAFF AND OTHER INMATES



NEW YORK CITY DEPARTMENT OF CORRECTION

Cynthia Brann, Acting Commissioner

Ava B. Rice, Assistant Commissioner Contracts and Procurement Agency Chief Contracting Officer

Bulova Corporate Center 75-20 Astoria Boulevard, Suite 160 East Elmhurst, NY 11370 Office: 718 546-0690

Fax: 718 278-6205

Dated
RE: "Undue Familiarity and Prevention of Sexual Abuse of Inmates by Staff and Other Inmates", Memorandum number 01/08, effective 2/07/08.
Dear Vendor:
All current Department of Correction contractors are required to acknowledge receipt and full compliance of the Agency's current "Undue Familiarity and Prevention of Sexual Abuse of Inmates by Staff and Other Inmates," which is attached to this memorandum. You have ten (10) days from the date of receipt of this letter to return the signed acknowledgement page in the enclosed self-address envelope. Failure to do so may cause the Agency to commence contract termination procedures.
Please contact me at 718-546-0690 if you have any questions. I may also be reached by email at doc.nyc.gov . In the interim, I thank you for your full cooperation and compliance.
Yours truly,
Ava B. Rice
I hereby acknowledge receipt of the "Undue Familiarity and Prevention of Sexual Abuse by Staff and other Inmates".
Vendor Name
Vendor Representative's Name (Print)
Vendor Representative's Signature
Date



THE CITY OF NEW YORK DEPARTMENT OF CORRECTION

MEMORANDUM



[] NEW]	X] REVISED	SUBJECT
EFFECTIVE DATE 02/07/08	NUMBER 01/08	PAGE 1 OF 3 PAGES	UNDUE FAMILIARITY AND PREVENTION OF SEXUAL ABUSE OF INMATES BY STAFF AND OTHER INMATES

TO

ALL STAFF

FROM

MARTIN F. HORN, COMMISSIONER

This message is addressed to all of you who work in our jails, whether you are an employee of the Department of Correction, an employee of another agency, a volunteer, contractor or vendor. Our collective mission is to keep our jails, the inmates, and staff, safe.

We take pride in providing a safe environment for all individuals who are committed to our custody. It is the professionalism of all of us that has established the Department as a leader in the field of corrections. We maintain high standards of behavior and demand the highest level of integrity.

- The way we behave around inmates is key to our success. We must perform our job with integrity. When boundaries are crossed, we become ineffective and the safety of each of us is threatened.
- Once you accept a gift or favor, introduce a single piece of contraband or single an inmate
 out for special treatment----with the first letter you carry in or out, the first cigarette you
 provide, the infraction you quash----the door is opened for the inmate to control you and
 influence your further actions.

And that becomes a serious threat to the safety of fellow staff and other inmates.

- 'Undue familiarity' is a direct violation of our Rules and Regulations. It is the Department's policy to seek termination of those who violate this rule. This behavior includes any social activity with an inmate that is not directly related to one's duties. Such behavior may involve, for example, the granting of a special favor or privilege, a phone call, accepting of a gift, bringing in contraband, a romantic relationship or at its worst, sexual conduct. Undue familiarity is not only a violation of our rules and regulations, but may also be a criminal offense.
- One of the worst offenses staff can commit is to engage in any sexual conduct with an inmate, or make sexual threats.



EFFECTIVE DATE 02/07/08

MEMORANDUM

01/08

NUMBER

SUBJECT

UNDUE FAMILIARITY AND PREVENTION OF SEXUAL ABUSE OF INMATES BY STAFF AND OTHER INMATES

PAGE 2 OF 3 PAGES



- The Department of Correction has zero tolerance for sexual abuse of inmates. No one is allowed to have sexual contact with any person who is incarcerated. Other inmates and employees are prohibited from asking, demanding, forcing, or participating in a sexual act with an inmate. This applies to EVERYONE including uniformed and civilian employees of the Department, as well as contractors, vendors, volunteers, and employees of other agencies who work in the jails.
- In addition to the Department policy, New York State Law clearly states that inmates are not able to give consent to sexual conduct with an employee. (Penal Law §130.05, subdivision 3). Individuals considered employees under this law include not only uniformed and civilian employees of the Department, but contractors, vendors, volunteers, employees of other agencies and all other persons who provide a direct service to inmates. In the same way that an underage minor can not consent to sex with an adult, so too an inmate can not consent to sex with employees. There is no such thing as consensual sex between employees and inmates. Any such sexual misconduct is a sex crime---whether it occurs inside a correctional facility, during transportation, or at any other time during an inmate's custody.
- The personal consequences for an employee who has any sexual contact with an inmate or sexually threatens an inmate are severe. Not only will that individual be terminated but they will also be arrested and criminally prosecuted. If convicted they face imprisonment and registration as a sex offender. The employee may also be required to pay monetary damages to the inmate out of his or her own pocket.
- This illegal behavior also poses a grave risk to all staff. The offending employee has totally compromised himself or herself, no different than if he or she were to smuggle weapons to an inmate.
- All allegations of sexual abuse and sexual threats will be investigated promptly and thoroughly.
- You all play a critical role in identifying and preventing a potential incident of sexual abuse, and responding if such an incident occurs.
- Equally important to us is the protection of inmates from sexual assaults by other inmates. The Department prohibits sexual acts between inmates, whether voluntary or coerced. Inmates who are observed engaging in a sexual act or soliciting a sexual act with another inmate must be ordered to cease their actions. Where the sex is voluntary, infractions will be processed for all the involved parties. Inmates who commit sexual abuse or assaults will be re-arrested and prosecuted to the full extent of the law. Employees who fail to stop such assaults as they are occurring and/or fail to report them are subject to disciplinary action, including termination. Inmates who are victims or in danger must be protected.



EFFECTIVE DATE 02/07/08

MEMORANDUM

NUMBER 01/08 SUBJECT

UNDUE FAMILIARITY AND PREVENTION OF SEXUAL ABUSE OF INMATES BY STAFF AND OTHER INMATES

PAGE 3 OF 3 PAGES



- Each of us is responsible for being alert to signs of potential situations in which sexual abuse might occur as well as signs of victimization. And all of us also have the duty to report any knowledge or information we may have about an employee who sexually abuses or engages in undue familiarity with an inmate. You may either contact the Department of Investigation confidentially (numbers are posted in the facilities) or, DOC employees may report to the Tour Commander. You must report, or you will face disciplinary action vourself. All allegations must be reported.
- Any employee who receives a report of inmate-on-inmate sexual abuse, must immediately notify their supervisor. An employee who intentionally fails to report such information will be subject to disciplinary charges.
- There is another role for staff to play in the prevention of sexual abuse of inmates, and that is to encourage inmates to report sexual abuse as well as any other concerns about their safety. If an inmate makes an allegation against staff or other inmates they will be offered immediate protection, medical examination and mental health services and counseling by our chaplains. And the complaint will be reported to the appropriate law enforcement officials and thoroughly investigated. We need your help in getting that message out to the inmates so that they will not be afraid to come forward if they are being victimized.

The Department is very proud of its work force and all of you who come to work day in and day out and perform your jobs professionally, with integrity. Our tradition of excellence requires that we all join together and do everything possible to make sure our zero tolerance policy is part of our culture and value system, because it is the right thing to do!

COMMISSIONER

Attachment:

Directive #5010, Preventing Inmate Sexual Abuse, dated 05/01/07 (as amended).

Supersedes:

Memorandum #02/07, UNDUE FAMILIARITY AND PREVENTION OF SEXUAL ABUSE OF INMATES BY STAFF AND OTHER INMATES, dated 05/01/07.

ATTACHMENT E SECURITY CLEARANCE REQUEST AND AUTHORIZATION FORM

The City of New York Department of Correction



Special Operations Division Rikers Island Security Unit

Form SOD/RISU2 | CLEARANCE REQUEST AND AUTHORIZATION FORM

Effective 3/16/98

SECTION #1 –									•		
Complete all of the required Notification of denials via fa								pproval.	The comn	and receiv	es
Wardens/Commanding Officers or Deputy Wardens shall initiate facility clearance red All other commands (bureaus, divisions or units) – Senior Staff Members or Command Officers or Executive Officers, only. It is the responsibility of each facility/command ensure that visitors are advised of the security/safety issues of the Riker's Is. Correction Complex (e.g speed limit, securing vehicles, display of ID/pass, unauthorized items)					Nehicle Access/Pass			on Rikers Is. Main Control Bldg.			Telephone # (718) 546-1578 (718) 546-1565 (718) 546-1539
SECTION #2 – Comman	d Requests / Escort Inforr	nation									
Date Requested:	Requested By (Print Last a	and First Name)	Rank	Title:	Shio	eld/ID#	Comn	ommand Telephone #:			
Uniform Escort Provided? ☐ Yes ☐ No	Escort Officer (Print Last	and First Name)	Rank		Shi	eld #:	Comn	nand:		ohone #:	
Command Authorization	Sr. Staff/Comm. Off./Dep.	Warden/Exec. Of	f.: Rank/	Title:	Shi	eld/ID #:	Comn	nand:	Telep	hone #:	
Approved Denied											
SECTION #3 – Clearan	as / Visit Information	COMPAN	V NA MI	r•							
					sitors' Fu	11			_		V Title
Date of Visit:	Visitors' Full Name	Ti	tle	* 1	Name			Ti	tle		i Title
	1.			6.							11.
Estimated Time of Arrival:	2.			7.							12.
	3.			8.							13.
Agency / DOC Affiliation	4.			9.							14.
Destinations (Check All Tha	5.			10.							15.
□ ARDC □ JATC □ AMKC □ NIC □ CIFM/HHP □ OBCC/CPSU □ GMDC □ RMSC/STEP □ GRVC □ WF/CDU	Assets Management/Environmental Health						Visitor Control Bldg				
Reason For Visit Cons	struction Delivery	Repair	Volunteer Worl	ζ	Typ	e of Access	s/Pass	Gate #1	Restricted	☐ Eas	t/West Parking Field
☐ Clerg	y Meeting	☐ Survey ☐	Other (Specify)			Gate #2 Restri	cted	Gate #1	Unrestricted	Oth	er (Specify)
SECTION #4 – Vehicle I	nformation										
☐ Chack Here if None	In the event the number of	of vehicles excee	ds four (4)	, attacl	additio	nal vehicle	e informe	ation on a	ı 600ar.		
Vehicle Year	Make Mod	lel Cole	or	License	Plate	State			Vehicle	е Туре	
#1							☐ Car	☐ Van	☐ Bus	☐ Truck	Other
#2							☐ Car	□ Van	☐ Bus	☐ Truck	Other
#3							☐ Car	□ van	☐ Bus	☐ Truck	Other
#4							☐ Car	□ van	☐ Bus	☐ Truck	☐ Other
SECTION #5 – FOR SOI	USE ONLY:										
Date Received:	Reviewed By (Clearance C	Officer)	Rank:	Sh	eld#:				SOD Ti	me Stam	n
/ /									202 11	e stamp	
Time Received:	Approved By (SOD/RISU	Supervisor)	Rank:	Sh	eld#:						
: hr.											
Final Determination	Type of Access/Pass:	☐ Gate #1 Restric	ted	D East	/West Doels:	ng Field					
☐ Approved ☐ Denied	Gate #2 Restricted	Gate #1 Restrict Gate #1Unrestr		East/West Parking Field Other (Specify)							
Remarks											

ATTACHMENT F

SECURITY REQUIREMENTS FOR ALL WORK PERFORMED ON RIKERS ISLAND



Date

NEW YORK CITY DEPARTMENT OF CORRECTION Cynthia Brann, Acting Commissioner

Ava B. Rice, Assistant Commissioner Contracts and Procurement Agency Chief Contracting Officer

75-20 Astoria Boulevard, Suite 160 East Elmhurst, NY 11370 Office: 718 546-0690

Fax: 718 278-6205

Dated RE: **Security Requirements** Dear Vendor: All current Department of Correction contractors are required to acknowledge receipt and full compliance of the Agency's current "Security Requirements", which is attached to this memorandum. You have ten (10) days from the date of receipt of this letter to return the signed acknowledgement page. Failure to do so may cause the Agency to commence contract termination procedures. Please contact Ava B. Rice at 718-546-0690 if you have any questions. I may also be reached by email at docacco@doc.nyc.gov. In the interim, I thank you for your full cooperation and compliance. Yours truly, an 3. Rece Ava B. Rice I hereby acknowledge receipt of the "Security Requirements". Vendor Name Vendor Representative's Name (Print) Vendor Representative's Signature

CONSTRUCTION CONTRACTS: SECURITY REQUIREMENTS FOR ALL WORK PERFORMED ON RIKERS ISLAND AND BOROUGH FACILITIES

All contractors and their employees including subcontractors must comply with all security and traffic regulations instituted by the Department of Correction.

For the purpose of these security requirements, subcontractors and their employees shall be considered employees of the contractor. Contractors are responsible for informing all subcontractors of these requirements. When the term contractor is used herein it shall mean contractor and subcontractor.

DOC may perform a background investigation on any employee of the Contractor who enters DOC premises. Contractor agrees to replace any employee deemed a security risk by DOC.

S1: IDENTIFICATION OF EMPLOYEES

- 1. All contractors and their employees who have authorized business at a DOC facility are required to report for identification and approval at established security control points. For employees working on Rikers Island, the security control point shall be the Construction Registration trailer, located in the parking field directly adjacent to the Queens side of the Rikers Island Bridge. At off island facilities the security control point shall be the facility's front entrance.
- 2. Each contractor shall furnish its employees with an identification (ID) card. The ID card shall be standard size (approximately 2 inches by 3 inches), laminated and furnished with either a clip or light chain so that it may be secured to the person wearing it. The ID cards shall be sequentially numbered and contain the following:
 - The company name;
 - A recognizable photo of the employee;
 - The employee's printed name and signature; and
 - Expiration date (to be provided by the Department's Construction Management Unit).
- 3. These ID cards are typically exchanged at a facility for an institutional pass when the employee enters the facility. ID cards/institutional passes must be prominently displayed and secured while the wearer is at a DOC facility. Additionally, identification must be produced upon demand of Department of Correction personnel assigned to various checkpoints, as well as security patrols.
 - 4. The contractor shall furnish the Department's Construction Management Unit (CMU) with a duplicate employee identification card for record keeping purposes.
- 5. The loss of any ID card or institutional pass must be reported immediately to the nearest officer on duty. The officer shall then promptly notify his/her supervisor who shall then take appropriate action.
 - 6. The contractor must notify the Construction Management Unit of the termination of any of its employees by close of business on the day of the termination.
- 7. Each contractor shall arrange clearances for all new employees through the Construction Management Unit.

8. Each contractor shall keep the Construction Management Unit informed at all times as to the employment status of its employees.

S2: DELIVERING MATERIAL AND EQUIPMENT TO JOB SITES

- 1. Contractors must obtain clearance from the Construction Management Unit for all deliveries of material and equipment to Department facilities. Upon receiving approval, the delivery shall be made directly to the loading platform of the facility involved. All employees reporting for business (non-delivery staff) shall arrive at the main entrance of the respective facility and abide by that facility's security procedures.
- 2.a. To avoid any potential traffic congestion, the Construction Management Unit must receive advance notice of all deliveries of material and heavy equipment to or from Rikers Island that require the use of wide load vehicles.
 - b. For vehicles delivering material and equipment to Rikers Island also refer to Section S3.
- 3. All vehicles and material contained therein are subject to random searches and inspections. Searches may involve the use of the Canine Unit.
- 4. In order to remove any materials or equipment from DOC property, Contractor's supervisors will sign their names on a form "Authorization to Take Materials Out of DOC Facilities"; to certify that the property being taken from the DOC facility is their property only, and not that of the City of New York, except in the event that removal of DOC property is specified by contract documents, which shall be reported to the Construction Management Unit. Such authorization must be received prior to the removal of any material from a Department facility. All materials to be removed are to be scheduled and verified by the Construction Management Unit.

S3: CONTRACTOR'S VEHICLES

- 1. Drivers of contractor vehicles intending to drive to Rikers Island are directed to report to the security control point (see S1.1) on the date and time of the scheduled delivery. The driver will be required to produce the following current and valid documents to the officer:
 - i. A drivers license;
 - ii. The vehicle's registration; and
 - iii. Vehicle Insurance Card.

Additionally, all occupants of the vehicle will be required to produce their employee ID cards and some form of government issued identification with photo (i.e., Driver's license) to the officer.

Upon producing the above noted documents to the officer's satisfaction, the officer will issue the driver a vehicle access pass and allow the driver and the occupants of the vehicle access to Rikers Island.

Note: Access to Rikers Island and/or any Department of Correction facility shall be limited to employees of the contractors (as described herein). Employees shall remain on Rikers Island and/or in the facility for only the time needed to carry out their business.

- 2. The vehicle access pass must be prominently displayed in the windshield inside the vehicle at all times.
- 3. Vehicles must be secured when not occupied. The vehicle must be turned off and the ignition key must be removed. Additionally, all windows must be closed and doors and trunks locked.
- 4. Vehicles are not permitted to be left at DOC facilities or on DOC Property at the conclusion of each workday.
- 5. Vehicle access passes and any issued DOC identification cards/tags must be turned in upon leaving Rikers Island.
- 6. All vehicles are subject to a search at any time while on Rikers Island or on the grounds of any DOC facility and also will be searched prior to departing Rikers Island and borough facilities. Searches will include a visual inspection of the vehicle's trunk, passenger and/or cargo compartment and the undercarriage. Additionally, all vehicle occupants will be required to produce their identification cards prior to departing Rikers Island or any DOC facility.

S4: TRAFFIC REGULATIONS

- 1. Drivers shall obey all posted traffic regulations and speed restrictions.
- 2. Passing vehicles on the Rikers Island Bridge is strictly prohibited.
- 3. Drivers and the occupants of their vehicles must produce their identification at all checkpoints.
- 4. Drivers must yield to all emergency vehicles.
- 5. The maximum weight limit on Rikers Island Bridge is 36 Tons.

S5: SECURITY PROCEDURES AND ISSUES

- 1. Contractors and their employees must remain within the physical limits of their work area. Contractors are forbidden to move into any other area on the Island unless permission is obtained by the Construction Management Unit. There is no walking permitted on Rikers Island outside of the respective work site or delivery destination.
- 2. Contractors, subcontractors, and their employees are forbidden to take or bring into a DOC facility, any articles for an inmate.
- 3. Contractors and their employees shall not contact, or communicate with or give anything to inmates.
- 4. Contractors and their employees shall not possess on their person any contraband as described in paragraph #9 of this section.

- 5. Contractors will not place or install any trailers, tool sheds, or security shanties on a job site without approval of the Construction Management Unit after requesting such permission.
- 6.a. Contractors are responsible for the control and security of all tools, supplies, materials, and equipment used by employees regardless of actual ownership of the items. Trailers, tool sheds, or security shanties that are approved by the Construction Management Unit must be kept secured and locked by the contractor. Tools not in use must be kept under lock and key. Tools used during working hours must be checked into the contractor's storage sheds at the end of working hours.
 - b. Each contractor shall be responsible for the:
 - i. Control of all tools used by their employees; and
 - ii. Prevention of theft of tools by inmates
 - c. Each contractor shall establish rules to insure such control.
- 7. The personal vehicles of the contractor's employees are not permitted on Rikers Island or at Borough facility loading docks. No personal vehicles will be permitted to enter a DOC facility (not even for the purpose of carrying tools and equipment).
- 8.a. Food or lunch packages of the contractor's employees are subject to inspection by Department of Correction custodial personnel.
 - b. No food services are available to contractor's employees at DOC facilities.
- 9.a. Arrest and prosecution will follow violations of Sections 205.00, 205.20 and 205.25 of the New York State Penal Law, which are summarized as follows:
 - **SECTION 205.00.3** Contraband means any article or thing which a person confined in a detention facility is prohibited from obtaining or possessing by statute, rule, regulation or order.
 - <u>SECTION 205.00.4</u> Dangerous contraband means contraband which is capable of such use as may endanger the safety or security of a detention facility or any person therein.
 - **SECTION 205.20** A person is guilty of promoting prison contraband in the second degree when:
 - 1. He knowingly and unlawfully introduces any contraband into a detention facility.

SECTION 205.25 A person is guilty of promoting prison contraband in the first degree when:

- 1. He knowingly and unlawfully introduces any dangerous contraband into a detention facility.
- b. Contraband is described as any article, the presence of which, within the prison may jeopardize safety, security and good order, or impair the moral and physical welfare of prisoners or employees, or which is prohibited by Rules and Regulations of any institution.

- c. Items that are considered contraband include but are not limited to: unauthorized clothing, unattended tools, loose or unattended vehicle keys, knives, and items to be considered as such, prescription and over the counter medicines, spices, alcoholic beverages, money in the possession of inmates, tobacco and tobacco related products (see Section S7), unauthorized written communications to and from inmates that were not processed through the institutional mail rooms, unauthorized packages and carrying cases, as well as unsafe conditions of articles which in the opinion of the Warden would affect the security of the institution.
- 10. The introduction of electronic/recording devices into any facility without the approval of the Construction Management Unit and the Commanding Officer of that facility is strictly prohibited. Electronic/recording devices are defined as any type of instrument, which is designed to transmit and/or receive telephonic, electronic, digital, cellular or radio communication as well as any type of instrument designed to have sound and/or image recording or capturing capabilities. Examples of electronic/recording devices include but are not limited to: cellular or digital phones, any type of pager, two-way radio, text messaging or modem devices, cameras (digital or film), video recorders and tape or digital recording devices.
- 11. Any violation of the polices and procedures described herein or of any law, Departmental rule and regulation or institutional policy or procedure may result in criminal prosecution (when applicable) and /or the violating individual being banned from future access to Rikers Island or any Departmental facility.

S6: CONDUCT OF CONTRACTORS AND THEIR EMPLOYEES

- 1. The New York City Department of Correction has a zero tolerance policy with regard to sexual abuse and sexual threats directed at inmates in its custody. **No one** is allowed to have sexual contact with any person who is incarcerated. Other inmates and staff are prohibited from asking, demanding, forcing or participating in a sexual act with an inmate. This applies to EVERYONE including contractors, vendors, volunteers and employees of other agencies who work in the jails.
- 2. Rikers Island and all Department of Correction facilities are secure facilities. Any person working within secure areas shall exercise extreme caution at all times. Each contractor and its employees must comply with the following security regulations of the Department of Correction:
 - a. Personal identification must be produced on demand by the Department of Correction personnel assigned to checkpoints and security patrols.
 - b. Employees must remain in the area of their work assignment.
 - c. Employees shall not bring any article, letters, notes or messages on the premises for the purpose of giving them to an inmate.
 - d. Employees shall not take any article, letters, notes or messages from an inmate to any other person including another inmate.
 - e. Employees shall not bring alcoholic beverages (beer, wine or liquor) on the premises at any time. Nor shall employees bring drugs or medicines except those required to stock the first aid cabinets in the contractor's field offices.
 - f. Contractors and their employees are prohibited from burning and/or dumping any refuse, debris or rubble on Department property.

g. When one person engages in conduct, which constitutes a criminal offense, another person is criminally liable for such conduct when, acting with the culpability required for the commission thereof, he or she solicits, requests, commands, importunes, or intentionally aids such person to engage in such conduct.

S7: SMOKING PROHIBITION

- 1. The Department of Correction maintains a smoke-free environment in accordance with Local Law 47 of 2002, the Smoke Free Air Act which prohibits smoking in public places and workplaces. The following restrictions and procedures apply to all contractors and their employees.
 - a. The use of tobacco related products within any Department facility, office, and vehicle is prohibited;
 - b. This prohibition applies to all persons, including staff, inmates, and visitors;
 - c. In addition to the smoking restrictions, contractors and their employees are prohibited from introducing any type of tobacco products and lighting agents into any department premises that houses or detains inmates, or utilize inmate work details, including the entire area of Rikers Island.
 - For the purpose of this document, tobacco products include but are not limited to cigarettes, cigars, pipes, loose tobacco and rolling paper. Lighting agents include cigarette lighters and matches.
 - Securing these items in Construction Management Unit-approved trailers, tool sheds and security shanties located outside the premises or contractor vehicles is permitted.
- 2. a. Inmates are prohibited from smoking and possessing any form of tobacco products including but not limited to cigarettes, lighting agents, cigars, pipes, loose tobacco and rolling paper.
 - b. Any contractor or employee providing an inmate tobacco related products shall be deemed as promoting prison contraband and shall be subject to arrest.

ATTACHMENT G PREVAILING WAGE SCHEDULE

LABOR LAW §220 PREVAILING WAGE SCHEDULE

Workers, Laborers and Mechanics employed on a public work project must receive not less than the prevailing rate of wage and benefits for the classification of work performed by each upon such public work. Pursuant to Labor Law §220 the Comptroller of the City of New York has promulgated this schedule solely for Workers, Laborers and Mechanics engaged by private contractors on New York City public work contracts.

This schedule is a compilation of separate determinations of the prevailing rate of wage and supplements made by the Comptroller for each trade classification listed herein pursuant to New York State Labor Law section 220 (5). The source of the wage and supplement rates, whether a collective bargaining agreement, survey data or other, is listed at the end of each classification.

Agency Chief Contracting Officers should contact the Bureau of Labor Law's Classification Unit with any questions concerning trade classifications, prevailing rates or prevailing practices with respect to procurement on New York City public works contracts. Contractors are advised to review the Comptroller's Prevailing Wage Schedule before bidding on public works contracts. Contractors with questions concerning trade classifications, prevailing rates or prevailing practices with respect to public works contracts in the procurement stage must contact the contracting agency responsible for the procurement.

Any error as to compensation under the prevailing wage law or other information as to trade classification, made by the contracting agency in the contract documents or in any other communication, will not preclude a finding against the contractor of prevailing wage violation.

Any questions concerning trade classifications, prevailing rates or prevailing practices on New York City public works contracts that have already been awarded may be directed to the Bureau of Labor Law's Classification Unit by calling (212) 669-4443. All callers must have the agency name and contract registration number available when calling with questions on public works contracts. Please direct all other compliance issues to: Bureau of Labor Law, Attn: Wasyl Kinach, P.E., Office of the Comptroller, 1 Centre Street, Room 651, New York, N.Y. 10007; Fax (212) 669-4002.

The appropriate schedule of prevailing wages and benefits must be posted at all public work sites pursuant to Labor Law §220 (3-a) (a).

This schedule is applicable to work performed during the effective period, unless otherwise noted. Changes to this schedule are published on our web site www.comptroller.nyc.gov. Contractors must pay the wages and supplements in effect when the worker, laborer, mechanic performs the work. Preliminary schedules for future one-year periods appear in the City Record on or about June 1 each succeeding year. Final schedules appear on or about July 1 in the City Record and on our web site www.comptroller.nyc.gov.

The Comptroller's Office has attempted to include all overtime, shift and night differential, Holiday, Saturday, Sunday or other premium time work. However, this schedule does not set forth every prevailing practice with respect to such rates with which employers must comply. All such practices are nevertheless part of the employer's prevailing wage obligation and contained in the collective bargaining agreements of the prevailing wage unions. These collective bargaining agreements are available for inspection by appointment. Requests for appointments may be made by calling (212) 669-4443, Monday through Friday between the hours of 9 a.m. and 5 p.m.

Prevailing rates and ratios for apprentices are attached to this schedule in the Appendix. Pursuant to Labor Law §220 (3-e), only apprentices who are individually registered in a bona fide program to which the employer contractor is a participant, registered with the New York State Department of Labor, may be employed on a public work project. Workers who are not journey persons or not registered apprentices pursuant to Labor Law §220 (3-e) may not be substituted for apprentices and must be paid as journey persons.

Public Work construction, reconstruction, demolition, excavation, rehabilitation, repair, renovation, alteration, or improvement contracts awarded pursuant to a Project Labor Agreement ("PLA") in accordance with Labor Law section 222 may have different labor standards for shift, premium and overtime work. Please refer to the PLA's pre-negotiated labor agreements for wage and benefit rates applicable to work performed outside of the regular workday. More information is available at the Mayor's Office of Contract Services (MOCS) web page at http://www.nyc.gov/html/mocs/html/vendors/pla.shtml.

All the provisions of Labor Law section 220 remain applicable to PLA work including, but not limited to, the enforcement of prevailing wage requirements by the Comptroller; however, we will enforce shift, premium, overtime and other non-standard rates as they appear in a project's pre-negotiated labor agreement.

In order to meet their obligation to provide prevailing supplemental benefits to each covered employee, employers must either:

- 1) Provide bona fide fringe benefits which cost the employer no less than the prevailing supplemental benefits rate; or
- 2) Supplement the employee's hourly wage by an amount no less than the prevailing supplemental benefits rate; or
- 3) Provide a combination of bona fide fringe benefits and wage supplements which cost the employer no less than the prevailing supplemental benefits rate in total.

Although prevailing wage laws do not require employers to provide bona fide fringe benefits (as opposed to wage supplements) to their employees, other laws may. For example, the Employee Retirement Income Security Act, 29 U.S.C. § 1001 et seq., the Patient Protection and Affordable Care Act, 42 U.S.C. § 18001 et seq., and the New York City Paid Sick Leave Law, N.Y.C. Admin. Code § 20-911 et seq., require certain employers to provide certain benefits to their employees. Labor agreements to which employers are a party may also require certain benefits. The Comptroller's Office does not enforce these laws or agreements.

Employers must provide prevailing supplemental benefits at the straight time rate for each hour worked unless otherwise noted in the classification.

Wasyl Kinach, P.E.
Director of Classifications
Bureau of Labor Law

TABLE OF CONTENTS

CLASSIFICATION	<u>PAGE</u>
ASBESTOS HANDLER	5
BLASTER	5
BOILERMAKER	7
BRICKLAYER	8
CARPENTER - BUILDING COMMERCIAL	9
CARPENTER - HEAVY CONSTRUCTION WORK	10
CARPENTER - HIGH RISE CONCRETE FORMS	11
CARPENTER - SIDEWALK SHED, SCAFFOLD AND HOIST	12
CEMENT & CONCRETE WORKER	13
CEMENT MASON	14
CORE DRILLER	15
DERRICKPERSON AND RIGGER	16
DIVER	17
DOCKBUILDER - PILE DRIVER	18
DRIVER: TRUCK (TEAMSTER)	19
ELECTRICIAN	
ELECTRICIAN - ALARM TECHNICIAN	
ELECTRICIAN-STREET LIGHTING WORKER	
ELEVATOR CONSTRUCTOR	
ELEVATOR REPAIR & MAINTENANCE	
ENGINEER	
ENGINEER - CITY SURVEYOR AND CONSULTANT	
ENGINEER - FIELD (BUILDING CONSTRUCTION)	
ENGINEER - FIELD (HEAVY CONSTRUCTION)	
ENGINEER - FIELD (STEEL ERECTION)	
ENGINEER - OPERATING	
FLOOR COVERER	
GLAZIER	
GLAZIER - REPAIR & MAINTENANCE	
HEAT AND FROST INSULATOR	
HOUSE WRECKER	
IRON WORKER - ORNAMENTAL	_
IRON WORKER - STRUCTURAL	
LABORER	
LANDSCAPING	52

MARBLE MECHANIC	54
MASON TENDER	55
MASON TENDER (INTERIOR DEMOLITION WORKER)	56
METALLIC LATHER	56
MILLWRIGHT	57
MOSAIC MECHANIC	58
PAINTER	59
PAINTER - METAL POLISHER	60
PAINTER - STRIPER	61
PAINTER - STRUCTURAL STEEL	62
PAPERHANGER	63
PAVER AND ROADBUILDER	64
PLASTERER	66
PLASTERER - TENDER	67
PLUMBER	
PLUMBER (MECHNICAL EQUIPMENT AND SERVICE)	68
PLUMBER (RESIDENTIAL RATES FOR 1, 2 AND 3 FAMILY HOME CONSTRUCTION)	69
PLUMBER: PUMP & TANK	70
POINTER, WATERPROOFER, CAULKER, SANDBLASTER, STEAMBLASTER	71
ROOFER	72
SHEET METAL WORKER	
SHEET METAL WORKER - SPECIALTY	73
SHIPYARD WORKER	74
SIGN ERECTOR	76
STEAMFITTER	76
STEAMFITTER - REFRIGERATION AND AIR CONDITIONER	78
STONE MASON - SETTER	80
TAPER	
TELECOMMUNICATION WORKER	82
TILE FINISHER	83
TILE LAYER - SETTER	84
TIMBERPERSON	84
TUNNEL WORKER	85
WELDED	97

ASBESTOS HANDLER

(Hazardous Material; Disturbs, removes, encapsulates, repairs, or encloses friable asbestos material)

Asbestos Handler

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$36.00

Supplemental Benefit Rate per Hour: \$16.45

Overtime

Time and one half the regular rate after an 8 hour day.

Time and one half the regular rate for Sunday.

Time and one half the regular hourly rate after 40 hours in any work week.

Overtime Holidays

Time and one half the regular rate for work on the following holiday(s).

New Year's Day Good Friday Memorial Day

Independence Day

Labor Day

Thanksgiving Day

Christmas Day

Easter

Paid Holidays

None

(Local #78 and Local #12A)

BLASTER

Blaster

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$46.27

Supplemental Benefit Rate per Hour: \$47.99

Blaster (Hydraulic)

Effective Period: 7/1/2017 - 6/30/2018

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 5 of 87

Wage Rate per Hour: \$47.15

Supplemental Benefit Rate per Hour: \$47.99

<u> Blaster - Trac Drill Hydraulic</u>

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$41.29

Supplemental Benefit Rate per Hour: \$47.99

Blaster - Wagon: Air Trac: Quarry Bar: Drillrunners

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$40.46

Supplemental Benefit Rate per Hour: \$47.99

Blaster - Operators of Jack Hammers

Chippers: Spaders: Concrete Breakers: and all other pneumatic tools of like usage: Walk Behind Self Propelled

Hydraulic Asphalt and Concrete Breakers: Hydro (Water) Demolition

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$39.34

Supplemental Benefit Rate per Hour: \$47.99

Blaster - Powder Carriers

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$35.17

Supplemental Benefit Rate per Hour: \$47.99

Blaster - Hydraulic Trac Drill Chuck Tender

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$33.81

Supplemental Benefit Rate per Hour: \$47.99

Blaster - Chuck Tender & Nipper

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$33.00

Supplemental Benefit Rate per Hour: \$47.99

Blaster - Magazine Keepers: (Watch Person)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$18.22

Supplemental Benefit Rate per Hour: \$47.99

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 6 of 87

Overtime Description

Magazine Keepers:

Time and one half for work performed in excess of forty (40) hours per week and for work performed on Saturdays, Sundays and Holidays.

All Other Employees:

Time and one-half for the first two hours of overtime Monday through Friday, the first ten hours, the first ten hours of work on Saturday and for Make-up Time. Double time for all hours over ten Monday through Saturday (except make-up hours) and for all hours worked on Sunday and Holidays.

Overtime Holidays

Double time the regular rate for work on the following holiday(s).
New Year's Day
Memorial Day
Independence Day
Labor Day
Columbus Day
Thanksgiving Day
Christmas Day

Paid Holidays

None

Shift Rates

A single shift shall be 8 hours plus an unpaid lunch, starting at 8:00 A.M (or between 6:00 A.M. and 10:00 A.M. on weekdays). When two (2) shifts are employed, each shift shall be 8 hours plus $\frac{1}{2}$ hour unpaid lunch. When three (3) shifts are employed, each shift will work seven and one-half (7 $\frac{1}{2}$) hours, but will be paid for eight (8) hours, since only one-half ($\frac{1}{2}$) hour is allowed for mealtime. When two (2) or more shifts are employed, single time will be paid for each shift. The first 8 hours of any and all work performed Monday through Friday inclusive of any off-shift shall be at the single time rate.

(Local #29)

BOILERMAKER

Boilermaker

Effective Period: 7/1/2017 - 12/31/2017

Wage Rate per Hour: \$55.23

Supplemental Benefit Rate per Hour: \$42.96

Supplemental Note: For time and one half overtime - \$63.82 For double overtime - \$84.68

Effective Period: 1/1/2018 - 6/30/2018

Wage Rate per Hour: \$57.17

Supplemental Benefit Rate per Hour: \$43.62

Supplemental Note: For time and one half overtime - \$64.81 For double overtime - \$86.00

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 7 of 87

Overtime Description

For Repair and Maintenance work:

Time and one half the regular rate after an 8 hour day.

Time and one half the regular rate for Saturday.

Double time the regular rate for Sunday.

For New Construction work:

Double time the regular rate after an 8 hour day.

Double time the regular time rate for Saturday.

Double time the regular rate for Sunday.

Overtime Holidays

Double time the regular rate for work on the following holiday(s).

New Year's Day

President's Day

Memorial Day

Independence Day

Columbus Day

Election Day

Veteran's Day

Thanksgiving Day

Christmas Day

Quadruple time the regular rate for work on the following holiday(s). Labor Day

Paid Holidays

Good Friday
Day after Thanksgiving
Day before Christmas
Day before New Year's Day

Shift Rates

When shifts are required, the first shift shall work eight (8) hours at the regular straight-time hourly rate. The second shift shall work seven and one-half (7 $\frac{1}{2}$) hours and receive eight hours at the regular straight time hourly rate plus twenty-five cents (\$0.25) per hour. The third shift shall work seven (7) hours and receive eight hours at the regular straight time hourly rate plus fifty cents (\$0.50) per hour. A thirty (30) minute lunch period shall not be considered as time worked. Work in excess of the above shall be paid overtime at the appropriate new construction work or repair work overtime wage and supplemental benefit hourly rate.

(Local #5)

BRICKLAYER

<u>Bricklayer</u>

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$55.10

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 8 of 87

Supplemental Benefit Rate per Hour: \$31.20

Overtime

Time and one half the regular rate after a 7 hour day.

Time and one half the regular rate for Saturday.

Double time the regular rate for Sunday.

Saturday may be used as a make-up day at straight time when a day is lost during that week to inclement

weather.

Overtime Holidays

Double time the regular rate for work on the following holiday(s).

New Year's Day President's Day Memorial Day

Independence Day

Labor Day

Thanksgiving Day Christmas Day

Paid Holidays

None

Shift Rates

Overtime rates to be paid outside the regular scheduled work day.

(Bricklayer District Council)

CARPENTER - BUILDING COMMERCIAL

Building Commercial

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$52.50

Supplemental Benefit Rate per Hour: \$46.28

Overtime

Time and one half the regular rate after an 8 hour day.

Time and one half the regular rate for Saturday.

Double time the regular rate for Sunday.

Saturday may be used as a make-up day at straight time when a day is lost during that week to inclement weather.

Overtime Holidays

Double time the regular rate for work on the following holiday(s).

New Year's Day

Washington's Birthday

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 9 of 87

Memorial Day
Independence Day
Labor Day
Columbus Day
Presidential Election Day
Thanksgiving Day
Day after Thanksgiving
Christmas Day

Paid Holidays

None

Shift Rates

The second shift will receive one hour at the double time rate of pay for the last hour of the shift; eight hours pay for seven hours of work, nine hours pay for eight hours of work. There must be a first shift in order to work a second shift.

(Carpenters District Council)

CARPENTER - HEAVY CONSTRUCTION WORK

(Construction of Engineering Structures and Building Foundations)

Heavy Construction Work

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$52.63

Supplemental Benefit Rate per Hour: \$49.66

Overtime

Time and one half the regular rate after an 8 hour day.

Time and one half the regular rate for Saturday.

Double time the regular rate for Sunday.

Saturday may be used as a make-up day at straight time when a day is lost during that week to inclement weather.

Overtime Holidays

Double time the regular rate for work on the following holiday(s).

New Year's Day

President's Day

Memorial Day

Independence Day

Labor Day

Columbus Day

Presidential Election Day

Thanksgiving Day

Christmas Day

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 10 of 87

Paid Holidays

None

Shift Rates

Off shift work commencing between 5:00 P.M. and 11:00 P.M. shall work eight and one half hours allowing for one half hour for lunch. The wage rate shall be 113% of the straight time hourly wage rate.

(Carpenters District Council)

CARPENTER - HIGH RISE CONCRETE FORMS

(Excludes Engineering Structures and Building Foundations)

Carpenter High Rise A

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$50.78

Supplemental Benefit Rate per Hour: \$41.49

Carpenter High Rise B

Carpenter High Rise B worker is excluded from high risk operations such as erection decking, perimeter debris netting, leading edge work, self-climbing form systems, and the installation of cocoon systems unless directly supervised by a Carpenter High Rise A worker.

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$39.07

Supplemental Benefit Rate per Hour: \$16.65

Overtime

Time and one half the regular rate after an 8 hour day.

Time and one half the regular rate for Saturday.

Double time the regular rate for Sunday.

Saturday may be used as a make-up day at straight time when a day is lost during that week to inclement weather.

Overtime Holidays

Time and one half the regular rate for work on the following holiday(s).

New Year's Day

President's Day

Good Friday

Memorial Day

Independence Day

Labor Day

Columbus Day

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 11 of 87

Presidential Election Day Thanksgiving Day Christmas Day

Paid Holidays

None

Shift Rates

The second shift wage rate shall be 113% of the straight time hourly wage rate. There must be a first shift in order to work a second shift.

(Carpenters District Council)

CARPENTER - SIDEWALK SHED, SCAFFOLD AND HOIST

Carpenter - Hod Hoist

(Assisted by Mason Tender)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$50.50

Supplemental Benefit Rate per Hour: \$39.46

Overtime

Time and one half the regular rate after an 8 hour day.

Time and one half the regular rate for Saturday.

Double time the regular rate for Sunday.

Saturday may be used as a make-up day at straight time when a day is lost during that week to inclement weather.

Overtime Holidays

Double time the regular rate for work on the following holiday(s).

New Year's Day

President's Day

Memorial Day

Independence Day

Labor Day

Columbus Day

Presidential Election Day

Thanksgiving Day

Day after Thanksgiving

Christmas Day

Paid Holidays

None

Shift Rates

The second shift will receive one hour at the double time rate of pay for the last hour of the shift; eight hours pay for seven hours of work, nine hours pay for eight hours of work. There must be a first shift in order to work a second shift.

(Carpenters District Council)

CEMENT & CONCRETE WORKER

Cement & Concrete Worker

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$42.48

Supplemental Benefit Rate per Hour: \$26.00

Supplemental Note: \$29.50 on Saturdays; \$33.00 on Sundays & Holidays

Cement & Concrete Worker - (Hired after 2/6/2016)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$32.00

Supplemental Benefit Rate per Hour: \$18.00

Supplemental Note: \$19.50 on Saturdays; \$21.00 on Sundays & Holidays

Overtime Description

Time and one half the regular rate after 7 hour day (time and one half the regular rate after an 8 hour day when working with Dockbuilders on pile cap forms and for work below street level to the top of the foundation wall, not to exceed 2 feet or 3 feet above the sidewalk-brick shelf, when working on the foundation and structure.)

Overtime

Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

Overtime Holidays

Double time the regular rate for work on the following holiday(s).

New Year's Day
President's Day
Good Friday
Memorial Day
Independence Day
Labor Day
Columbus Day

Presidential Election Day

Thanksgiving Day Christmas Day

Paid Holidays

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 13 of 87

1/2 day before Christmas Day 1/2 day before New Year's Day

Shift Rates

On shift work extending over a twenty-four hour period, all shifts are paid at straight time.

(Cement Concrete Workers District Council)

CEMENT MASON

Cement Mason

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$42.62

Supplemental Benefit Rate per Hour: \$38.96

Supplemental Note: For time and one half overtime - \$48.21; For double overtime - \$57.46

Overtime Description

Time and one-half the regular rate after an 8 hour day, double time the regular rate after 10 hours. Time and one-half the regular rate on Saturday, double time the regular rate after 10 hours. Double time the regular rate on Sunday.

Overtime Holidays

Double time the regular rate for work on the following holiday(s).

New Year's Day President's Day

Good Friday

Memorial Day

Independence Day

Labor Day

Columbus Day

Presidential Election Day

Thanksgiving Day

Christmas Day

Paid Holidays

Any worker who reports to work on Christmas Eve or New Year's Eve pursuant to his employer's instruction shall be entitled to three (3) hours afternoon pay without working.

Shift Rates

For an off shift day, (work at times other than the regular 7:00 A.M. to 3:30 P.M. work day) a cement mason shall be paid at the regular hourly rate plus a 25% per hour differential. Four Days a week at Ten (10)hour day.

(Local #780) (BCA)

CORE DRILLER

Core Driller

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$38.82

Supplemental Benefit Rate per Hour: \$24.66

Core Driller Helper

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$30.96

Supplemental Benefit Rate per Hour: \$24.66

Core Driller Helper(Third year in the industry)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$27.86

Supplemental Benefit Rate per Hour: \$24.66

Core Driller Helper (Second year in the industry)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$24.77

Supplemental Benefit Rate per Hour: \$24.66

Core Driller Helper (First year in the industry)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$21.67

Supplemental Benefit Rate per Hour: \$24.66

Overtime Description

Time and one half the regular rate for work on a holiday plus Holiday pay when worked.

Overtime

Time and one half the regular rate after an 8 hour day.

Time and one half the regular rate for Saturday.

Double time the regular rate for Sunday.

Time and one half the regular rate for work on the following holiday(s).

Paid Holidays

New Year's Day Memorial Day Independence Day

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 15 of 87

Labor Day Thanksgiving Day Christmas Day

Shift Rates

The shift day shall be the continuous eight and one-half (8½) hours from 6:00 A.M. to 2:30 P.M. and from 2:30 P.M. to 11:00 P.M., including one-half (½) hour of employees regular rate of pay for lunch. When two (2) or more shifts are employed, single time shall be paid for each shift, but those employees employed on a shift other than from 8:00 A.M. to 5:00 P.M. shall, in addition, receive seventy-five cents (\$0.75) per hour differential for each hour worked. When three (3) shifts are needed, each shift shall work seven and one-half ($7 \frac{1}{2}$) hours paid for eight (8) hours of labor and be permitted one-half ($\frac{1}{2}$) hour for mealtime.

(Carpenters District Council)

DERRICKPERSON AND RIGGER

Derrick Person & Rigger

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$46.86

Supplemental Benefit Rate per Hour: \$51.40

Supplemental Note: The above supplemental rate applies for work performed in Manhattan, Bronx, Brooklyn and

Queens. \$52.82 - For work performed in Staten Island.

Derrick Person & Rigger - Site Work

Assists the Stone Mason-Setter in the setting of stone

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$40.29

Supplemental Benefit Rate per Hour: \$39.23

Overtime Description

The first two hours of overtime on weekdays and the first seven hours of work on Saturdays are paid at time and one half for wages and supplemental benefits. All additional overtimes is paid at double time for wages and supplemental benefits. Deduct \$1.42 from the Staten Island hourly benefits rate before computing overtime.

Overtime

Double time the regular rate for Sunday.

Overtime Holidays

Double time the regular rate for work on the following holiday(s). New Year's Day Washington's Birthday Good Friday Memorial Day

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 16 of 87

Independence Day Labor Day Thanksgiving Day Christmas Day

Paid Holidays

1/2 day on Christmas Eve if work is performed in the A.M.

(Local #197)

DIVER

Diver (Marine)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$66.66

Supplemental Benefit Rate per Hour: \$49.66

Diver Tender (Marine)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$47.34

Supplemental Benefit Rate per Hour: \$49.66

Overtime

Time and one half the regular rate after an 8 hour day.

Time and one half the regular rate for Saturday.

Double time the regular rate for Sunday.

Saturday may be used as a make-up day at straight time when a day is lost during that week to inclement weather.

Overtime Holidays

Double time the regular rate for work on the following holiday(s).

New Year's Day

President's Day

Memorial Day

Independence Day

Labor Day

Columbus Day

Presidential Election Day

Thanksgiving Day

Christmas Day

Paid Holidays

None

Shift Rates

When three shifts are utilized each shift shall work seven and one half-hours (7 1/2 hours) and paid for 8 hours, allowing for one half hour for lunch.

(Carpenters District Council)

DOCKBUILDER - PILE DRIVER

Dockbuilder - Pile Driver

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$52.63

Supplemental Benefit Rate per Hour: \$49.66

Overtime

Time and one half the regular rate after an 8 hour day.

Time and one half the regular rate for Saturday.

Double time the regular rate for Sunday.

Saturday may be used as a make-up day at straight time when a day is lost during that week to inclement weather.

Overtime Holidays

Double time the regular rate for work on the following holiday(s).

New Year's Day

President's Day

Memorial Day

Independence Day

Labor Day

Columbus Day

Presidential Election Day

Thanksgiving Day

Christmas Day

Paid Holidays

None

Shift Rates

Off shift work commencing between 5:00 P.M. and 11:00 P.M. shall work eight and one half hours allowing for one half hour for lunch. The wage rate shall be 113% of the straight time hourly wage rate.

(Carpenters District Council)

DRIVER: TRUCK (TEAMSTER)

Driver - Dump Truck

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$41.18

Supplemental Benefit Rate per Hour: \$44.79

Supplemental Note: Over 40 hours worked: at time and one half rate - \$19.94; at double time rate - \$26.58

Driver - Tractor Trailer

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$42.22

Supplemental Benefit Rate per Hour: \$45.40

Supplemental Note: Over 40 hours worked: at time and one half rate - \$17.55; at double time rate - \$23.40

Driver - Euclid & Turnapull Operator

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$42.78

Supplemental Benefit Rate per Hour: \$45.40

Supplemental Note: Over 40 hours worked: at time and one half rate - \$17.55 at double time rate - \$23.40

Overtime Description

For Paid Holidays: Holiday pay for all holidays shall be prorated based two hours per day for each day worked in the holiday week, not to exceed 8 hours of holiday pay. For Thanksgiving week, the prorated share shall be 5 1/3 hours of holiday pay for each day worked in Thanksgiving week.

Overtime

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday.

Double time the regular rate for Sunday.

Overtime Holidays

Double time the regular rate for work on the following holiday(s).

New Year's Day

President's Day

Memorial Day

Independence Day

Labor Day

Columbus Day

Veteran's Day

Thanksgiving Day

Day after Thanksgiving

Christmas Day

Paid Holidays

New Year's Day President's Day Memorial Day

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 19 of 87

Independence Day Labor Day Columbus Day Veteran's Day Thanksgiving Day Day after Thanksgiving Christmas Day

Shift Rates

Off single shift work commencing between 6:00 P.M. and 5:00 A.M. shall work eight and one half hours allowing for one half hour for lunch and receive 9 hours pay for 8 hours of work.

Driver Redi-Mix (Sand & Gravel)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$38.40

Supplemental Benefit Rate per Hour: \$42.12

Supplemental Note: Over 40 hours worked: time and one half rate \$15.99, double time rate \$21.33

Overtime Description

For Paid Holidays: Employees working two (2) days in the calendar week in which the holiday falls are to paid for these holidays, provided they shape each remaining workday during that calendar week.

Overtime

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

Overtime Holidays

Double time the regular rate for work on the following holiday(s). President's Day Columbus Day Veteran's Day

Triple time the regular rate for work on the following holiday(s).
New Year's Day
Memorial Day
Independence Day
Labor Day
Thanksgiving Day
Christmas Day

Paid Holidays

New Year's Day President's Day Memorial Day Independence Day Labor Day Columbus Day

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 20 of 87

Election Day Thanksgiving Day Christmas Day

(Local #282)

ELECTRICIAN

(Including all low voltage cabling carrying data; video; and voice in combination with data and or video.)

Electrician "A" (Regular Day / Day Shift)

Effective Period: 7/1/2017 - 5/9/2018 Wage Rate per Hour: \$56.00

Supplemental Benefit Rate per Hour: \$54.35

Effective Period: 5/10/2018 - 6/30/2018

Wage Rate per Hour: \$56.00

Supplemental Benefit Rate per Hour: \$55.72

Electrician "A" (Regular Day Overtime after 7 hrs / Day Shift Overtime after 8 hrs)

Effective Period: 7/1/2017 - 5/9/2018 Wage Rate per Hour: \$84.00

Supplemental Benefit Rate per Hour: \$57.86

Effective Period: 5/10/2018 - 6/30/2018

Wage Rate per Hour: \$84.00

Supplemental Benefit Rate per Hour: \$59.23

Electrician "A" (Swing Shift)

Effective Period: 7/1/2017 - 5/9/2018

Wage Rate per Hour: \$65.71

Supplemental Benefit Rate per Hour: \$61.94

Effective Period: 5/10/2018 - 6/30/2018

Wage Rate per Hour: \$65.71

Supplemental Benefit Rate per Hour: \$63.52

Electrician "A" (Swing Shift Overtime After 7.5 hours)

Effective Period: 7/1/2017 - 5/9/2018

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 21 of 87

Wage Rate per Hour: \$98.57

Supplemental Benefit Rate per Hour: \$66.05

Effective Period: 5/10/2018 - 6/30/2018

Wage Rate per Hour: \$98.57

Supplemental Benefit Rate per Hour: \$67.64

Electrician "A" (Graveyard Shift)

Effective Period: 7/1/2017 - 5/9/2018 Wage Rate per Hour: \$73.60

Supplemental Benefit Rate per Hour: \$68.33

Effective Period: 5/10/2018 - 6/30/2018

Wage Rate per Hour: \$73.60

Supplemental Benefit Rate per Hour: \$70.09

Electrician "A" (Graveyard Shift Overtime After 7 hours)

Effective Period: 7/1/2017 - 5/9/2018 Wage Rate per Hour: \$110.40

Supplemental Benefit Rate per Hour: \$72.95

Effective Period: 5/10/2018 - 6/30/2018

Wage Rate per Hour: \$110.40

Supplemental Benefit Rate per Hour: \$74.70

Overtime

Time and one half the regular rate after a 7 hour day. Time and one half the regular rate for Saturday. Time and one half the regular rate for Sunday.

Overtime Holidays

New Year's Day
Martin Luther King Jr. Day
President's Day
Memorial Day
Independence Day
Labor Day

Time and one half the regular rate for work on a holiday.

Columbus Day
Veteran's Day
Thanksgiving Day
Day after Thanksgiving

Christmas Day

Paid Holidays

None

Shift Rates

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 22 of 87

When so elected by the Employer, one or more shifts of at least five days duration may be scheduled as follows: Day Shift: 8:00 am to 4:30 pm, Swing Shift 4:30 pm to 12:30 am, Graveyard Shift: 12:30 am to 8:00 am.

For multiple shifts of temporary light and/or power, the temporary light and/or power employee shall be paid for 8 hours at the straight time rate. For three or less workers performing 8 hours temporary light and/or power the supplemental benefit rate is \$25.67 and effective 5/10/18 \$25.92.

Electrician "M" (First 8 hours)

"M" rated work shall be defined as jobbing: electrical work of limited duration and scope, also consisting of repairs and/or replacement of electrical and tele-data equipment. Includes all work necessary to retrofit, service, maintain and repair all kinds of lighting fixtures and local lighting controls and washing and cleaning of foregoing fixtures.

Effective Period: 7/1/2017 - 5/9/2018 Wage Rate per Hour: **\$28.50**

Supplemental Benefit Rate per Hour: \$22.10

First and Second Year "M" Wage Rate Per Hour: \$24.00 First and Second Year "M" Supplemental Rate: \$19.80

Effective Period: 5/10/2018 - 6/30/2018

Wage Rate per Hour: \$29.00

Supplemental Benefit Rate per Hour: \$22.65

First and Second Year "M" Wage Rate Per Hour: \$24.50 First and Second Year "M" Supplemental Rate: \$20.30

Electrician "M" (Overtime After First 8 hours)

"M" rated work shall be defined as jobbing: electrical work of limited duration and scope, also consisting of repairs and/or replacement of electrical and tele-data equipment. Includes all work necessary to retrofit, service, maintain and repair all kinds of lighting fixtures and local lighting controls and washing and cleaning of foregoing fixtures.

Effective Period: 7/1/2017 - 5/9/2018 Wage Rate per Hour: \$42.75

Supplemental Benefit Rate per Hour: \$23.89

First and Second Year "M" Wage Rate Per Hour: \$36.00 First and Second Year "M" Supplemental Rate: \$21.30

Effective Period: 5/10/2018 - 6/30/2018

Wage Rate per Hour: \$43.50

Supplemental Benefit Rate per Hour: \$24.47

First and Second Year "M" Wage Rate Per Hour: \$36.75 First and Second Year "M" Supplemental Rate: \$21.84

Overtime

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Time and one half the regular rate for Sunday.

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 23 of 87

Overtime Holidays

Time and one half the regular rate for work on the following holiday(s).

New Year's Day

Martin Luther King Jr. Day

President's Day

Memorial Day

Independence Day

Labor Day

Columbus Day

Veteran's Day

Thanksgiving Day

Day after Thanksgiving

Christmas Day

Paid Holidays

None

(Local #3)

ELECTRICIAN - ALARM TECHNICIAN

(Scope of Work - Inspect, test, repair, and replace defective, malfunctioning, or broken devices, components and controls of Fire, Burglar and Security Systems)

Alarm Technician

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$32.40

Supplemental Benefit Rate per Hour: \$16.10

Supplemental Note: \$14.60 only after 8 hours worked in a day

Overtime Description

Time and one half the regular rate for work on the following holidays: Columbus Day, Veterans Day, Day after Thanksgiving.

Double time the regular rate for work on the following holidays: New Year's day, Martin Luther King Jr. Day, President's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, Christmas Day.

Overtime

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

Paid Holidays

New Year's Day

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 24 of 87

Martin Luther King Jr. Day President's Day Memorial Day Independence Day Labor Day Columbus Day Veteran's Day Thanksgiving Day Day after Thanksgiving Christmas Day

Shift Rates

Night Differential is based upon a ten percent (10%) differential between the hours of 4:00 P.M. and 12:30 A.M. and a fifteen percent (15%) differential for the hours 12:00 A.M. to 8:00 A.M.

Vacation

At least 1 year of employment......ten (10) days 5 years or more of employment......fifteen (15) days 10 years of employment......twenty (20) days Plus one Personal Day per year

Sick Days:

One day per Year. Up to 4 vacation days may be used as sick days.

(Local #3)

ELECTRICIAN-STREET LIGHTING WORKER

Electrician - Electro Pole Electrician

Effective Period: 7/1/2017 - 5/15/2018

Wage Rate per Hour: \$56.00

Supplemental Benefit Rate per Hour: \$56.26

Effective Period: 5/16/2018 - 6/30/2018

Wage Rate per Hour: \$56.00

Supplemental Benefit Rate per Hour: \$57.63

Electrician - Electro Pole Foundation Installer

Effective Period: 7/1/2017 - 5/15/2018

Wage Rate per Hour: \$41.54

Supplemental Benefit Rate per Hour: \$41.02

Effective Period: 5/16/2018 - 6/30/2018

Wage Rate per Hour: \$42.16

Supplemental Benefit Rate per Hour: \$42.19

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 25 of 87

Electrician - Electro Pole Maintainer

Effective Period: 7/1/2017 - 5/16/2018

Wage Rate per Hour: \$35.58

Supplemental Benefit Rate per Hour: \$36.89

Effective Period: 5/17/2018 - 6/30/2018

Wage Rate per Hour: \$36.11

Supplemental Benefit Rate per Hour: \$37.93

Overtime Description

Electrician - Electro Pole Electrician: Time and one half the regular rate after a 7 hour day and after 5 consecutive days worked per week.

Electrician - Electro Pole Foundation Installer: Time and one half the regular rate after 8 hours within a 24 hour period and Saturday and Sunday.

Electrician - Electro Pole Maintainer: Time and one half the regular rate after a 7 hour day and after 5 consecutive days worked per week. Saturdays and Sundays may be used as a make-up day at straight time when a day is lost during the week to inclement weather.

Overtime Holidays

Time and one half the regular rate for work on the following holiday(s).

New Year's Day

Martin Luther King Jr. Day

President's Day

Memorial Day

Independence Day

Labor Day

Columbus Day

Veteran's Day

Thanksgiving Day

Paid Holidays

Christmas Day

Day after Thanksgiving

None

(Local #3)

ELEVATOR CONSTRUCTOR

Elevator Constructor

Effective Period: 7/1/2017 - 3/16/2018

Wage Rate per Hour: \$62.64

Supplemental Benefit Rate per Hour: \$34.25

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 26 of 87

Effective Period: 3/17/2018 - 6/30/2018

Wage Rate per Hour: \$64.48

Supplemental Benefit Rate per Hour: \$35.85

Overtime Description

For New Construction: work performed after 7 or 8 hour day, Saturday, Sunday or between 4:30pm and 7:00am shall be paid at double time rate.

Existing buildings: work performed after an 8 hour day, Saturday, Sunday or between 5:30pm and 7:00 am shall be paid time and one half.

Overtime

Double time the regular rate for work on the following holiday(s).

Paid Holidays

New Year's Day
President's Day
Good Friday
Memorial Day
Independence Day
Labor Day
Columbus Day
Veteran's Day
Thanksgiving Day
Day after Thanksgiving
Christmas Day

Vacation

Employer contributes 8% of regular basic hourly rate as vacation pay for employees with more than 15 years of service, and 6% for employees with 5 to 15 years of service, and 4% for employees with less than 5 years of service.

(Local #1)

ELEVATOR REPAIR & MAINTENANCE

Elevator Service/Modernization Mechanic

Effective Period: 7/1/2017 - 3/16/2018

Wage Rate per Hour: \$49.14

Supplemental Benefit Rate per Hour: \$34.11

Effective Period: 3/17/2018 - 6/30/2018

Wage Rate per Hour: \$50.49

Supplemental Benefit Rate per Hour: \$35.71

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 27 of 87

Overtime Description

For Scheduled Service Work: Double time - work scheduled in advance by two or more workers performed on Sundays, Holidays, and between midnight and 7:00am.

Overtime

Time and one half the regular rate after an 8 hour day.

Time and one half the regular rate for Saturday.

Time and one half the regular rate for Sunday.

Time and one half the regular rate for work on a holiday plus the day's pay.

Paid Holidays

New Year's Day
President's Day
Good Friday
Memorial Day
Independence Day
Labor Day
Columbus Day
Veteran's Day
Thanksgiving Day
Day after Thanksgiving
Christmas Day

Shift Rates

Afternoon shift - regularly hourly rate plus a (15%) fifteen percent differential. Graveyard shift - time and one half the regular rate.

Vacation

Employer contributes 8% of regular basic hourly rate as vacation pay for employees with more than 15 years of service, and 6% for employees with 5 to 15 years of service, and 4% for employees with less than 5 years of service.

(Local #1)

ENGINEER

Engineer - Heavy Construction Operating Engineer I

Cherrypickers 20 tons and over and Loaders (rubber tired and/or tractor type with a manufacturer's minimum rated capacity of six cubic yards and over).

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$67.32

Supplemental Benefit Rate per Hour: \$36.87 Supplemental Note: \$66.34 on overtime

Shift Wage Rate: \$107.71

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 28 of 87

Engineer - Heavy Construction Operating Engineer II

Backhoes, Basin Machines, Groover, Mechanical Sweepers, Bobcat, Boom Truck, Barrier Transport (Barrier Mover) & machines of similar nature. Operation of Churn Drills and machines of a similar nature, Stetco Silent Hoist and machines of similar nature, Vac-Alls, Meyers Machines, John Beam and machines of a similar nature, Ross Carriers and Travel Lifts and machines of a similar nature, Bulldozers, Scrapers and Turn-a-Pulls: Tugger Hoists (Used exclusively for handling excavated material); Tractors with attachments, Hyster and Roustabout Cranes, Cherrypickers. Austin Western, Grove and machines of a similar nature, Scoopmobiles, Monorails, Conveyors, Trenchers: Loaders-Rubber Tired and Tractor: Barber Greene and Eimco Loaders and Eimco Backhoes; Mighty Midget and similar breakers and Tampers, Curb and Gutter Pavers and Motor Patrol, Motor Graders and all machines of a similar nature. Locomotives 10 Tons or under. Mini-Max, Break-Tech and machines of a similar nature; Milling machines, robotic and demolition machines and machines of a similar nature, shot blaster, skid steer machines and machines of a similar nature including bobcat, pile rig rubber-tired excavator (37,000 lbs. and under), 2 man auger.

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$65.31

Supplemental Benefit Rate per Hour: \$36.87 Supplemental Note: \$66.34 on overtime

Shift Wage Rate: \$104.50

Engineer - Heavy Construction Operating Engineer III

Minor Equipment such as Tractors, Post Hole Diggers, Ditch Witch (Walk Behind), Road Finishing Machines, Rollers five tons and under, Tugger Hoists, Dual Purpose Trucks, Fork Lifts, and Dempsey Dumpers, Fireperson.

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$61.93

Supplemental Benefit Rate per Hour: \$36.87 Supplemental Note: \$66.34 on overtime

Shift Wage Rate: \$99.09

Engineer - Heavy Construction Maintenance Engineer I

Installing, Repairing, Maintaining, Dismantling and Manning of all equipment including Steel Cutting, Bending and Heat Sealing Machines, Mechanical Heaters, Grout Pumps, Bentonite Pumps & Plants, Screening Machines, Fusion Coupling Machines, Tunnel Boring Machines Moles and Machines of a similar nature, Power Packs, Mechanical Hydraulic Jacks; all drill rigs including but not limited to Churn, Rotary Caisson, Raised Bore & Drills of a similar nature; Personnel, Inspection & Safety Boats or any boats used to perform functions of same, Mine Hoists, Whirlies, all Climbing Cranes, all Tower Cranes, including but not limited to Truck Mounted and Crawler Type and machines of similar nature; Maintaining Hydraulic Drills and machines of a similar nature; Well Point System-Installation and dismantling; Burning, Welding, all Pumps regardless of size and/or motor power, except River Cofferdam Pumps and Wells Point Pumps; Motorized Buggies (three or more); equipment used in the cleaning and televising of sewers, but not limited to jet-rodder/vacuum truck, vacall/vactor, closed circuit television inspection equipment; high powered water pumps, jet pumps; screed machines and concrete finishing machines of a similar nature; vermeers.

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$65.00

Supplemental Benefit Rate per Hour: \$36.87 Supplemental Note: \$66.34 on overtime

Shift Wage Rate: \$104.00

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 29 of 87

Engineer - Heavy Construction Maintenance Engineer II

On Base Mounted Tower Cranes

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$85.53

Supplemental Benefit Rate per Hour: \$36.87 Supplemental Note: \$66.34 on overtime

Shift Wage Rate: \$136.85

Engineer - Heavy Construction Maintenance Engineer III

On Generators, Light Towers

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$42.73

Supplemental Benefit Rate per Hour: \$36.87 Supplemental Note: \$66.34 on overtime

Shift Wage Rate: \$68.37

Engineer - Heavy Construction Maintenance Engineer IV

On Pumps and Mixers including mud sucking

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$43.86

Supplemental Benefit Rate per Hour: \$36.87 Supplemental Note: \$66.34 on overtime

Shift Wage Rate: \$70.18

Engineer - Heavy Construction Oilers I

Gradalls, Cold Planer Grader, Concrete Pumps, Driving Truck Cranes, Driving and Operating Fuel and Grease Trucks.

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$58.57

Supplemental Benefit Rate per Hour: \$36.87 Supplemental Note: \$66.34 on overtime

Shift Wage Rate: \$93.71

Engineer - Heavy Construction Oilers II

All gasoline, electric, diesel or air operated Shovels, Draglines, Backhoes, Keystones, Pavers, Gunite Machines, Battery of Compressors, Crawler Cranes, two-person Trenching Machines.

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$40.36

Supplemental Benefit Rate per Hour: \$36.87

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 30 of 87

Supplemental Note: \$66.34 on overtime

Shift Wage Rate: \$64.58

Engineer - Steel Erection Maintenance Engineers

Derrick, Travelers, Tower, Crawler Tower and Climbing Cranes

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$61.13

Supplemental Benefit Rate per Hour: \$35.41 Supplemental Note: \$63.67 on overtime

Shift Wage Rate: \$97.81

<u> Engineer - Steel Erection Oiler I</u>

On a Truck Crane

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$57.21

Supplemental Benefit Rate per Hour: \$35.41 Supplemental Note: \$63.67 on overtime

Shift Wage Rate: \$91.54

Engineer - Steel Erection Oiler II

On a Crawler Crane

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$43.54

Supplemental Benefit Rate per Hour: \$35.41 Supplemental Note: \$63.67 on overtime

Shift Wage Rate: \$69.66

Overtime Description

On jobs of more than one shift, if the next shift employee fails to report for work through any cause over which the employer has no control, the employee on duty who works the next shift continues to work at the single time rate.

Overtime

Double time the regular rate after an 8 hour day.

Double time the regular time rate for Saturday.

Double time the regular rate for Sunday.

Double time the regular rate for work on the following holiday(s).

Paid Holidays

New Year's Day Lincoln's Birthday President's Day Memorial Day Independence Day

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 31 of 87

Labor Day
Columbus Day
Veteran's Day
Thanksgiving Day
Day after Thanksgiving
Christmas Day

Employees must work at least one day in the payroll week in which the holiday occurs to receive the paid holiday

Engineer - Building Work Maintenance Engineers I

Installing, repairing, maintaining, dismantling (of all equipment including: Steel Cutting and Bending Machines, Mechanical Heaters, Mine Hoists, Climbing Cranes, Tower Cranes, Linden Peine, Lorain, Liebherr, Mannes, or machines of a similar nature, Well Point Systems, Deep Well Pumps, Concrete Mixers with loading Device, Concrete Plants, Motor Generators when used for temporary power and lights), skid steer machines of a similar nature including bobcat.

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$58.30

Supplemental Benefit Rate per Hour: \$35.41 Supplemental Note: \$63.67 on overtime

Engineer - Building Work Maintenance Engineers II

On Pumps, Generators, Mixers and Heaters

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$45.28

Supplemental Benefit Rate per Hour: \$35.41 Supplemental Note: \$63.67 on overtime

Engineer - Building Work Oilers I

All gasoline, electric, diesel or air operated Gradealls: Concrete Pumps, Overhead Cranes in Power Houses: Their duties shall be to assist the Engineer in oiling, greasing and repairing of all machines; Driving Truck Cranes: Driving and Operating Fuel and Grease Trucks, Cherrypickers (hydraulic cranes) over 70,000 GVW, and machines of a similar nature.

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$55.42

Supplemental Benefit Rate per Hour: \$35.41 Supplemental Note: \$63.67 on overtime

Engineer - Building Work Oilers II

Oilers on Crawler Cranes, Backhoes, Trenching Machines, Gunite Machines, Compressors (three or more in Battery).

Effective Period: 7/1/2017 - 6/30/2018

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 32 of 87

Wage Rate per Hour: \$41.16

Supplemental Benefit Rate per Hour: \$35.41 Supplemental Note: \$63.67 on overtime

Overtime Description

On jobs of more than one shift, if an Employee fails to report for work through any cause over which the Employer has no control, the Employee on duty will continue to work at the rate of single time.

Overtime

Double time the regular rate after an 8 hour day.

Double time the regular time rate for Saturday.

Double time the regular rate for Sunday.

Double time the regular rate for work on the following holiday(s).

Paid Holidays

New Year's Day
Lincoln's Birthday
President's Day
Memorial Day
Independence Day
Labor Day
Columbus Day
Veteran's Day
Thanksgiving Day
Christmas Day

Employees must work at least one day in the payroll week in which the holiday occurs to receive the paid holiday

Shift Rates

Off Shift: double time the regular hourly rate.

(Local #15)

ENGINEER - CITY SURVEYOR AND CONSULTANT

Party Chief

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$38.18

Supplemental Benefit Rate per Hour: \$20.15

Supplemental Note: Overtime Benefit Rate - \$27.65 per hour (time & one half) \$35.15 per hour (double time).

Instrument Person

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$31.47

Supplemental Benefit Rate per Hour: \$20.15

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 33 of 87

Supplemental Note: Overtime Benefit Rate - \$27.65 per hour (time & one half) \$35.15 per hour (double time).

Rodperson

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$27.24

Supplemental Benefit Rate per Hour: \$20.15

Supplemental Note: Overtime Benefit Rate - \$27.65 per hour (time & one half) \$35.15 per hour (double time).

Overtime Description

Time and one half the regular rate after an 8 hour day, Time and one half the regular rate for Saturday for the first eight hours worked, Double time the regular time rate for Saturday for work performed in excess of eight hours, Double time the regular rate for Sunday and Double time the regular rate for work on a holiday.

Paid Holidays

New Year's Day
Lincoln's Birthday
President's Day
Memorial Day
Independence Day
Labor Day
Columbus Day
Veteran's Day
Thanksgiving Day
Day after Thanksgiving
Christmas Day

Employees must work at least one day in the payroll week in which the holiday occurs to receive the paid holiday

(Operating Engineer Local #15-D)

ENGINEER - FIELD (BUILDING CONSTRUCTION)

(Construction of Building Projects, Concrete Superstructures, etc.)

Field Engineer - BC Party Chief

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$60.10

Supplemental Benefit Rate per Hour: \$32.15

Supplemental Note: Overtime Benefit Rate - \$44.90 per hour (time & one half) \$57.65 per hour (double time).

Field Engineer - BC Instrument Person

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$46.69

Supplemental Benefit Rate per Hour: \$32.15

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 34 of 87

Supplemental Note: Overtime Benefit Rate - \$44.90 per hour (time & one half) \$57.65 per hour (double time).

Field Engineer - BC Rodperson

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$30.20

Supplemental Benefit Rate per Hour: \$32.15

Supplemental Note: Overtime Benefit Rate - \$44.90 per hour (time & one half) \$57.65 per hour (double time).

Overtime Description

Time and one half the regular rate after a 7 hour work and time and one half the regular rate for Saturday for the first seven hours worked, Double time the regular time rate for Saturday for work performed in excess of seven hours, Double time the regular rate for Sunday and Double time the regular rate for work on a holiday.

Paid Holidays

New Year's Day
President's Day
Good Friday
Memorial Day
Independence Day
Labor Day
Columbus Day
Veteran's Day
Thanksgiving Day

Christmas Dav

Employees must work at least one day in the payroll week in which the holiday occurs to receive the paid holiday

(Operating Engineer Local #15-D)

ENGINEER - FIELD (HEAVY CONSTRUCTION)

(Construction of Roads, Tunnels, Bridges, Sewers, Building Foundations, Engineering Structures etc.)

Field Engineer - HC Party Chief

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$70.25

Supplemental Benefit Rate per Hour: \$34.18

Supplemental Note: Overtime benefit rate - \$47.82 per hour (time & one half), \$61.46 per hour (double time).

<u>Field Engineer - HC Instrument Person</u>

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$51.64

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 35 of 87

Supplemental Benefit Rate per Hour: \$34.18

Supplemental Note: Overtime benefit rate - \$47.82 per hour (time & one half), \$61.46 per hour (double time).

<u>Field Engineer - HC Rodperson</u>

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$43.37

Supplemental Benefit Rate per Hour: \$34.18

Supplemental Note: Overtime benefit rate - \$47.82 per hour (time & one half), \$61.46 per hour (double time).

Overtime Description

Time and one half the regular rate after an 8 hour day, Time and one half the regular rate for Saturday for the first eight hours worked, Double time the regular time rate for Saturday for work performed in excess of eight hours, Double time the regular rate for Sunday and Double time the regular rate for work on a holiday.

Paid Holidays

New Year's Day
Lincoln's Birthday
President's Day
Memorial Day
Independence Day
Labor Day
Columbus Day
Veteran's Day
Thanksgiving Day
Christmas Day

Employees must work at least one day in the payroll week in which the holiday occurs to receive the paid holiday

(Operating Engineer Local #15-D)

ENGINEER - FIELD (STEEL ERECTION)

Field Engineer - Steel Erection Party Chief

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$63.64

Supplemental Benefit Rate per Hour: \$33.04

Supplemental Note: Overtime benefit rate - \$46.11 per hour (time & one half), \$59.18 per hour (double time).

<u>Field Engineer - Steel Erection Instrument Person</u>

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$49.59

Supplemental Benefit Rate per Hour: \$33.04

Supplemental Note: Overtime benefit rate - \$46.11 per hour (time & one half), \$59.18 per hour (double time).

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 36 of 87

Field Engineer - Steel Erection Rodperson

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$33.20

Supplemental Benefit Rate per Hour: \$33.04

Supplemental Note: Overtime benefit rate - \$46.11 per hour (time & one half), \$59.18 per hour (double time).

Overtime Description

Time and one half the regular rate for Saturday for the first eight hours worked.

Double time the regular rate for Saturday for work performed in excess of eight hours.

Overtime

Time and one half the regular rate after an 8 hour day.

Double time the regular rate for Sunday.

Double time the regular rate for work on the following holiday(s).

Paid Holidays

New Year's Day

Lincoln's Birthday

President's Day

Memorial Day

Independence Day

Labor Day

Columbus Day

Veteran's Day

Thanksgiving Day

Christmas Day

Employees must work at least one day in the payroll week in which the holiday occurs to receive the paid holiday

(Operating Engineer Local #15-D)

ENGINEER - OPERATING

Operating Engineer - Road & Heavy Construction I

Back Filling Machines, Cranes, Mucking Machines and Dual Drum Paver.

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$76.60

Supplemental Benefit Rate per Hour: \$31.10 Supplemental Note: \$56.50 overtime hours

Shift Wage Rate: \$122.56

Operating Engineer - Road & Heavy Construction II

Backhoes, Power Shovels, Hydraulic Clam Shells, Steel Erection, Moles and machines of a similar nature.

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 37 of 87

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$79.28

Supplemental Benefit Rate per Hour: \$31.10 Supplemental Note: \$56.50 overtime hours

Shift Wage Rate: \$126.85

Operating Engineer - Road & Heavy Construction III

Mine Hoists, Cranes, etc. (Used as Mine Hoists)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$81.80

Supplemental Benefit Rate per Hour: \$31.10 Supplemental Note: \$56.50 overtime hours

Shift Wage Rate: \$130.88

Operating Engineer - Road & Heavy Construction IV

Gradealls, Keystones, Cranes on land or water (with digging buckets), Bridge Cranes, Vermeer Cutter and machines of a similar nature, Trenching Machines.

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$79.85

Supplemental Benefit Rate per Hour: \$31.10 Supplemental Note: \$56.50 overtime hours

Shift Wage Rate: \$127.76

Operating Engineer - Road & Heavy Construction V

Pile Drivers & Rigs (employing Dock Builder foreperson): Derrick Boats, Tunnel Shovels.

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$78.29

Supplemental Benefit Rate per Hour: \$31.10 Supplemental Note: \$56.50 overtime hours

Shift Wage Rate: \$125.26

Operating Engineer - Road & Heavy Construction VI

Mixers (Concrete with loading attachment), Concrete Pavers, Cableways, Land Derricks, Power Houses (Low Air Pressure Units).

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$74.42

Supplemental Benefit Rate per Hour: \$31.10 Supplemental Note: \$56.50 overtime hours

Shift Wage Rate: \$119.07

Operating Engineer - Road & Heavy Construction VII

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 38 of 87

Barrier Movers, Barrier Transport and Machines of a Similar Nature.

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$60.22

Supplemental Benefit Rate per Hour: \$31.10 Supplemental Note: \$56.50 overtime hours

Shift Wage Rate: \$96.35

Operating Engineer - Road & Heavy Construction VIII

Utility Compressors

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$46.88

Supplemental Benefit Rate per Hour: \$31.10 Supplemental Note: \$56.50 overtime hours

Shift Wage Rate: \$58.92

<u>Operating Engineer - Road & Heavy Construction IX</u>

Horizontal Boring Rig

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$70.79

Supplemental Benefit Rate per Hour: \$31.10 Supplemental Note: \$56.50 overtime hours

Shift Wage Rate: \$113.26

Operating Engineer - Road & Heavy Construction X

Elevators (manually operated as personnel hoist).

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$65.12

Supplemental Benefit Rate per Hour: \$31.10 Supplemental Note: \$56.50 overtime hours

Shift Wage Rate: \$104.19

Operating Engineer - Road & Heavy Construction XI

Compressors (Portable 3 or more in battery), Driving of Truck Mounted Compressors, Well-point Pumps, Tugger Machines Well Point Pumps, Churn Drill.

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$50.73

Supplemental Benefit Rate per Hour: \$31.10 Supplemental Note: \$56.50 overtime hours

Shift Wage Rate: \$81.17

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 39 of 87

Operating Engineer - Road & Heavy Construction XII

All Drills and Machines of a similar nature.

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$75.19

Supplemental Benefit Rate per Hour: \$31.10 Supplemental Note: \$56.50 overtime hours

Shift Wage Rate: \$120.30

Operating Engineer - Road & Heavy Construction XIII

Concrete Pumps, Concrete Plant, Stone Crushers, Double Drum Hoist, Power Houses (other than above).

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$72.84

Supplemental Benefit Rate per Hour: \$31.10 Supplemental Note: \$56.50 overtime hours

Shift Wage Rate: \$116.54

Operating Engineer - Road & Heavy Construction XIV

Concrete Mixer

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$69.67

Supplemental Benefit Rate per Hour: \$31.10 Supplemental Note: \$56.50 overtime hours

Shift Wage Rate: \$111.47

Operating Engineer - Road & Heavy Construction XV

Compressors (Portable Single or two in Battery, not over 100 feet apart), Pumps (River Cofferdam) and Welding Machines, Push Button Machines, All Engines Irrespective of Power (Power-Pac) used to drive auxiliary equipment, Air, Hydraulic, etc.

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$47.18

Supplemental Benefit Rate per Hour: \$31.10 Supplemental Note: \$56.50 overtime hours

Shift Wage Rate: \$75.49

Operating Engineer - Road & Heavy Construction XVI

Concrete Breaking Machines, Hoists (Single Drum), Load Masters, Locomotives (over ten tons) and Dinkies over ten tons, Hydraulic Crane-Second Engineer.

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$66.56

Supplemental Benefit Rate per Hour: \$31.10

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 40 of 87

Supplemental Note: \$56.50 overtime hours

Shift Wage Rate: \$106.50

Operating Engineer - Road & Heavy Construction XVII

On-Site concrete plant engineer, On-site Asphalt Plant Engineer, and Vibratory console.

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$67.07

Supplemental Benefit Rate per Hour: \$31.10 Supplemental Note: \$56.50 overtime hours

Shift Wage Rate: \$107.31

Operating Engineer - Road & Heavy Construction XVIII

Tower Crane

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$95.98

Supplemental Benefit Rate per Hour: \$31.10 Supplemental Note: \$56.50 overtime hours

Shift Wage Rate: \$153.57

Operating Engineer - Paving I

Asphalt Spreaders, Autogrades (C.M.I.), Roto/Mil

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$74.42

Supplemental Benefit Rate per Hour: \$31.10 Supplemental Note: \$56.50 overtime hours

Shift Wage Rate: \$119.07

Operating Engineer - Paving II

Asphalt Roller

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$72.50

Supplemental Benefit Rate per Hour: \$31.10 Supplemental Note: \$56.50 overtime hours

Shift Wage Rate: \$116.00

<u> Operating Engineer - Paving III</u>

Asphalt Plants

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$61.43

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 41 of 87

Supplemental Benefit Rate per Hour: \$31.10 Supplemental Note: \$56.50 overtime hours

Shift Wage Rate: \$98.29

Operating Engineer - Concrete I

Cranes

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$79.50

Supplemental Benefit Rate per Hour: \$31.10 Supplemental Note: \$56.50 overtime hours

<u>Operating Engineer - Concrete II</u>

Compressors

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$47.54

Supplemental Benefit Rate per Hour: \$31.10 Supplemental Note: \$56.50 overtime hours

Operating Engineer - Concrete III

Micro-traps (Negative Air Machines), Vac-All Remediation System.

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$63.66

Supplemental Benefit Rate per Hour: \$31.10 Supplemental Note: \$56.50 overtime hours

Operating Engineer - Steel Erection I

Three Drum Derricks

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$82.23

Supplemental Benefit Rate per Hour: \$31.10 Supplemental Note: \$56.50 overtime hours

Shift Wage Rate: \$131.57

Operating Engineer - Steel Erection II

Cranes, 2 Drum Derricks, Hydraulic Cranes, Fork Lifts and Boom Trucks.

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$79.04

Supplemental Benefit Rate per Hour: \$31.10 Supplemental Note: \$56.50 overtime hours

Shift Wage Rate: \$126.46

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 42 of 87

Operating Engineer - Steel Erection III

Compressors, Welding Machines.

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$47.14

Supplemental Benefit Rate per Hour: \$31.10 Supplemental Note: \$56.50 overtime hours

Shift Wage Rate: \$75.42

Operating Engineer - Steel Erection IV

Compressors - Not Combined with Welding Machine.

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$44.91

Supplemental Benefit Rate per Hour: \$31.10 Supplemental Note: \$56.50 overtime hours

Shift Wage Rate: \$71.86

Operating Engineer - Building Work I

Forklifts, Plaster (Platform machine), Plaster Bucket, Concrete Pump and all other equipment used for hoisting material.

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$62.87

Supplemental Benefit Rate per Hour: \$31.10 Supplemental Note: \$56.50 overtime hours

<u> Operating Engineer - Building Work II</u>

Compressors, Welding Machines (Cutting Concrete-Tank Work), Paint Spraying, Sandblasting, Pumps (with the exclusion of Concrete Pumps), All Engines irrespective of Power (Power-Pac) used to drive Auxiliary Equipment, Air, Hydraulic, Jacking System, etc.

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$47.01

Supplemental Benefit Rate per Hour: \$31.10 Supplemental Note: \$56.50 overtime hours

Operating Engineer - Building Work III

Double Drum

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$71.60

Supplemental Benefit Rate per Hour: \$31.10 Supplemental Note: \$56.50 overtime hours

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 43 of 87

Operating Engineer - Building Work IV

Stone Derrick, Cranes, Hydraulic Cranes Boom Trucks.

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$75.87

Supplemental Benefit Rate per Hour: \$31.10 Supplemental Note: \$56.50 overtime hours

Operating Engineer - Building Work V

Dismantling and Erection of Cranes, Relief Engineer.

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$69.88

Supplemental Benefit Rate per Hour: \$31.10 Supplemental Note: \$56.50 overtime hours

Operating Engineer - Building Work VI

4 Pole Hoist, Single Drum Hoists.

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$69.14

Supplemental Benefit Rate per Hour: \$31.10 Supplemental Note: \$56.50 overtime hours

Operating Engineer - Building Work VII

Rack & Pinion and House Cars

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$54.92

Supplemental Benefit Rate per Hour: \$31.10 Supplemental Note: \$56.50 overtime hours

For New House Car projects Wage Rate per Hour \$43.77

Overtime Description

On jobs of more than one shift, if an Employee fails to report for work through any cause over which the Employer has no control, the Employee on duty will continue to work at the rate of single time.

For House Cars and Rack & Pinion only: Overtime paid at time and one-half for all hours in excess of eight hours in a day, Saturday, Sunday and Holidays worked.

Overtime

Double time the regular rate after an 8 hour day.

Double time the regular time rate for Saturday.

Double time the regular rate for Sunday.

Double time the regular rate for work on the following holiday(s).

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 44 of 87

Paid Holidays

New Year's Day
Lincoln's Birthday
President's Day
Memorial Day
Independence Day
Labor Day
Columbus Day
Veteran's Day
Thanksgiving Day
Day after Thanksgiving
Christmas Day

Employees must work at least one day in the payroll week in which the holiday occurs to receive the paid holiday

Shift Rates

For Steel Erection Only: Shifts may be worked at the single time rate at other than the regular working hours (8:00 A.M. to 4:30 P.M.) on the following work ONLY: Heavy construction jobs on work below the street level, over railroad tracks and on building jobs.

(Operating Engineer Local #14)

FLOOR COVERER

(Interior vinyl composition tile, sheath vinyl linoleum and wood parquet tile including site preparation and synthetic turf not including site preparation)

Floor Coverer

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$50.50

Supplemental Benefit Rate per Hour: \$45.88

Overtime

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

Overtime Holidays

Double time the regular rate for work on the following holiday(s).
New Year's Day
President's Day
Memorial Day
Independence Day
Labor Day
Columbus Day

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 45 of 87

Presidential Election Day Thanksgiving Day Day after Thanksgiving Christmas Day

Paid Holidays

1/2 day on Christmas Eve if work is performed in the A.M. 1/2 day on New Year's Eve if work is performed in the A.M.

Shift Rates

Two shifts may be utilized with the first shift working 8:00 A.M. to the end of the shift at the straight time of pay. The second shift will receive one hour at double time rate for the last hour of the shift. (eight for seven, nine for eight).

(Carpenters District Council)

GLAZIER

(New Construction, Remodeling, and Alteration)

Glazier

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$44.70

Supplemental Benefit Rate per Hour: \$40.99

Supplemental Note: Supplemental Benefit Overtime Rate: \$50.09

Overtime Description

An optional 8th hour can be worked at straight time rate. If 9th hour is worked, then both hours or more (8th & 9th or more) will be at the double time rate of pay.

Overtime

Double time the regular rate after a 7 hour day. Double time the regular time rate for Saturday. Double time the regular rate for Sunday.

Overtime Holidays

Double time the regular rate for work on the following holiday(s).
New Year's Day
President's Day
Memorial Day
Independence Day
Labor Day
Thanksgiving Day

Day after Thanksgiving

Christmas Day

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 46 of 87

Paid Holidays

None

Shift Rates

Shifts shall be any 7 hours beyond 4:00 P.M. for which the glazier shall receive 8 hours pay for 7 hours worked.

(Local #1281)

GLAZIER - REPAIR & MAINTENANCE

(For the Installation of Glass - All repair and maintenance work on a particular building, whenever performed, where the total cumulative contract value is under \$127,628. Except where enumerated (i.e. plate glass windows) does not apply to non-residential buildings.)

<u>Craft Jurisdiction for repair, maintenance and fabrication</u>

Plate glass replacement, Residential glass replacement, Residential mirrors and shower doors, Storm windows and storm doors, Residential replacement windows, Herculite door repairs, Door closer repairs, Retrofit apartment house (non commercial buildings), Glass tinting.

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$24.13

Supplemental Benefit Rate per Hour: \$21.12

Overtime

Time and one half the regular rate after an 8 hour day. Double time the regular rate for Sunday.

Time and one half the regular hourly rate after 40 hours in any work week.

Paid Holidays

New Year's Day
President's Day
Memorial Day
Independence Day
Labor Day
Thanksgiving Day
Day after Thanksgiving
Christmas Day

(Local #1281)

HEAT AND FROST INSULATOR

Heat & Frost Insulator

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$58.38

Supplemental Benefit Rate per Hour: \$39.46

Overtime Description

Double time shall be paid for supplemental benefits during overtime work. 8th hour paid at time and one half.

Overtime

Double time the regular rate after an 8 hour day. Double time the regular time rate for Saturday. Double time the regular rate for Sunday.

Overtime Holidays

Double time the regular rate for work on the following holiday(s).

New Year's Day

Martin Luther King Jr. Day

President's Day

Memorial Day

Independence Day

Columbus Day

Veteran's Day

Thanksgiving Day

Day after Thanksgiving

Christmas Day

Triple time the regular rate for work on the following holiday(s). Labor Day

Paid Holidays

None

Shift Rates

The first shift shall work seven hours at the regular straight time rate. The second and third shift shall work seven hours the regular straight time hourly rate plus a fourteen percent wage and benefit premium. Off hour work in occupied or retail buildings may be worked on weekdays with an increment of \$1.00 per hour and eight hours pay for seven (7) hours worked. Double time will apply for over seven (7) hours worked on weekdays, weekends or holidays.

(Local #12) (BCA)

HOUSE WRECKER (TOTAL DEMOLITION)

House Wrecker - Tier A

On all work sites the first, second, eleventh and every third House Wrecker thereafter will be Tier A House Wreckers (i.e. 1st, 2nd, 11th, 14th etc). Other House Wreckers may be Tier B House Wreckers.

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$36.33

Supplemental Benefit Rate per Hour: \$29.22

House Wrecker - Tier B

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$25.56

Supplemental Benefit Rate per Hour: \$21.63

Overtime

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

Overtime Holidays

Double time the regular rate for work on the following holiday(s).

New Year's Day President's Day Memorial Day Independence Day Labor Day

Thanksgiving Day Christmas Day

Paid Holidays

None

(Mason Tenders District Council)

IRON WORKER - ORNAMENTAL

Iron Worker - Ornamental

Effective Period: 7/1/2017 - 6/30/2018

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 49 of 87

Wage Rate per Hour: \$44.20

Supplemental Benefit Rate per Hour: \$51.57

Supplemental Note: Supplemental benefits are to be paid at the applicable overtime rate when overtime is in

effect.

Overtime Description

Time and one half the regular rate after a 7 hour day for a maximum of two hours on any regular work day (the 8th and 9th hour) and double time shall be paid for all work on a regular work day thereafter, time and one half the regular rate for Saturday for the first seven hours of work and double time shall be paid for all work on a Saturday thereafter.

Overtime

Double time the regular rate for Sunday.

Overtime Holidays

Double time the regular rate for work on the following holiday(s).

New Year's Day
President's Day
Memorial Day
Independence Day
Labor Day
Thanksgiving Day
Christmas Day

Paid Holidays

None

Shift Rates

For off shift work - 8 hours pay for 7 hours of work. When two or three shifts are employed on a job, Monday through Friday, the workday for each shift shall be seven hours and paid for ten and one-half hours at the single time rate. When two or three shifts are worked on Saturday, Sunday or holidays, each shift shall be seven hours and paid fifteen and three-quarters hours.

(Local #580)

IRON WORKER - STRUCTURAL

<u>Iron Worker - Structural</u>

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$50.05

Supplemental Benefit Rate per Hour: \$72.53

Supplemental Note: Supplemental benefits are to be paid at the applicable overtime rate when overtime is in

effect.

Overtime Description

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 50 of 87

Monday through Friday- the first eight hours are paid at straight time, the 9th and 10th hours are paid at time and one-half the regular rate, all additional weekday overtime is paid at double the regular rate. Saturdays- the first eight hours are paid at time and one-half the regular rate, double time thereafter. Sunday-all shifts are paid at double time.

Overtime

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

Overtime Holidays

Double time the regular rate for work on the following holiday(s).
New Year's Day
President's Day
Memorial Day
Independence Day
Labor Day
Thanksgiving Day
Christmas Day

Paid Holidays

1/2 day on Christmas Eve if work is performed in the A.M. 1/2 day on New Year's Eve if work is performed in the A.M.

Shift Rates

Monday through Friday - First Shift: First eight hours are paid at straight time, the 9th & 10th hours are paid at time and a half, double time paid thereafter. Second and third Shifts: First eight hours are paid at time and one-half, double time thereafter. Saturdays: All shifts, first eight hours paid at time and one-half, double time thereafter: Sunday all shifts are paid at double time.

(Local #40 & #361)

LABORER

(Foundation, Concrete, Excavating, Street Pipe Layer and Common)

<u>Laborer</u>

Excavation and foundation work for buildings, heavy construction, engineering work, and hazardous waste removal in connection with the above work. Landscaping tasks in connection with heavy construction work, engineering work and building projects. Projects include, but are not limited to pollution plants, sewers, parks, subways, bridges, highways, etc.

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$41.50

Supplemental Benefit Rate per Hour: \$40.63

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 51 of 87

Overtime

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

Overtime Holidays

Double time the regular rate for work on the following holiday(s).
New Year's Day
Memorial Day
Independence Day
Labor Day
Columbus Day
Thanksgiving Day
Christmas Day

Paid Holidays

Labor Day Thanksgiving Day

Shift Rates

When two shifts are employed, single time rate shall be paid for each shift. When three shifts are found necessary, each shift shall work seven and one half hours (7 $\frac{1}{2}$), but shall be paid for eight (8) hours of labor, and be permitted one half hour for lunch.

(Local #731)

LANDSCAPING

(Landscaping tasks, as well as tree pruning, tree removing, spraying and maintenance in connection with the planting of street trees and the planting of trees in city parks but not when such activities are performed as part of, or in connection with, other construction or reconstruction projects.)

Landscaper (Above 6 years experience)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$28.75

Supplemental Benefit Rate per Hour: \$15.55

<u>Landscaper (3 - 6 years experience)</u>

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$27.75

Supplemental Benefit Rate per Hour: \$15.55

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 52 of 87

Landscaper (up to 3 years experience)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$25.25

Supplemental Benefit Rate per Hour: \$15.55

Groundperson

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$25.25

Supplemental Benefit Rate per Hour: \$15.55

Tree Remover / Pruner

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$33.75

Supplemental Benefit Rate per Hour: \$15.55

Landscaper Sprayer (Pesticide Applicator)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$23.75

Supplemental Benefit Rate per Hour: \$15.55

Watering - Plant Maintainer

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$18.72

Supplemental Benefit Rate per Hour: \$15.55

Overtime Description

For all overtime work performed, supplemental benefits shall include an additional seventy-five (\$0.75) cents per hour.

Overtime

Time and one half the regular rate after an 8 hour day.

Time and one half the regular rate for Saturday.

Double time the regular rate for Sunday.

Time and one half the regular rate for work on a holiday plus the day's pay.

Paid Holidays

New Year's Day Memorial Day Independence Day Labor Day Thanksgiving Day Christmas Day

Shift Rates

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 53 of 87

Work performed on a 4pm to 12am shift has a 15% differential. Work performed on a 12am to 8am shift has a 20% differential.

(Local #175)

MARBLE MECHANIC

Marble Setter

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$52.74

Supplemental Benefit Rate per Hour: \$38.67

Marble Finisher

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$41.46

Supplemental Benefit Rate per Hour: \$36.64

Marble Polisher

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$37.93

Supplemental Benefit Rate per Hour: \$28.33

Overtime Description

Supplemental Benefit contributions are to be made at the applicable overtime rates. Time and one half the regular rate after a 7 hour day or time and one half the regular rate after an 8 hour day - chosen by Employer at the start of the project and then would last for the full duration of the project.

Overtime

Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

Overtime Holidays

Double time the regular rate for work on the following holiday(s).

New Year's Day

President's Day

Good Friday

Memorial Day

Independence Day

Lobor Dov

Labor Day

Columbus Day

Veteran's Day

Thanksgiving Day

Day after Thanksgiving

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 54 of 87

Christmas Day

Paid Holidays

None

(Local #7)

MASON TENDER

Mason Tender

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$37.90

Supplemental Benefit Rate per Hour: \$30.59

Overtime

Time and one half the regular rate after an 8 hour day.

Time and one half the regular rate for Saturday.

Double time the regular rate for Sunday.

Saturday may be used as a make-up day at straight time when a day is lost during that week to inclement weather.

Overtime Holidays

Double time the regular rate for work on the following holiday(s).

New Year's Day President's Day **Memorial Day** Independence Day **Labor Day** Thanksgiving Day

Christmas Day

Paid Holidays

None

Shift Rates

The Employer may work two (2) shifts with the first shift at the straight time wage rate and the second shift receiving eight (8) hours paid for seven (7) hours work at the straight time wage rate.

(Local #79)

MASON TENDER (INTERIOR DEMOLITION WORKER)

Mason Tender Tier A

Tier A Interior Demolition Worker performs all burning, chopping, and other technically skilled tasks related to interior demolition work.

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$36.19

Supplemental Benefit Rate per Hour: \$24.25

Mason Tender Tier B

Tier B Interior Demolition Worker performs manual work and work incidental to demolition work, such as loading and carting of debris from the work site to an area where it can be loaded in to bins/trucks for removal. Also performs clean-up of the site when demolition is completed.

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$25.38

Supplemental Benefit Rate per Hour: \$18.57

Overtime

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Sunday.

Overtime Holidays

Double time the regular rate for work on the following holiday(s).
New Year's Day
President's Day
Memorial Day
Independence Day
Labor Day
Thanksgiving Day
Christmas Day

Paid Holidays

None

(Local #79)

METALLIC LATHER

Metallic Lather

Effective Period: 7/1/2017 - 6/30/2018

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 56 of 87

Wage Rate per Hour: \$46.28

Supplemental Benefit Rate per Hour: \$42.92

Supplemental Note: Supplemental benefits for overtime are paid at the appropriate overtime rate.

Overtime Description

Overtime would be time and one half the regular rate after a seven (7) or eight (8) hours workday, which would be set at the start of the job.

Overtime

Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

Overtime Holidays

Double time the regular rate for work on the following holiday(s).
New Year's Day
Washington's Birthday
Memorial Day
Independence Day
Labor Day
Columbus Day
Thanksgiving Day
Christmas Day

Paid Holidays

1/2 day on Christmas Eve if work is performed in the A.M. 1/2 day on New Year's Eve if work is performed in the A.M.

Shift Rates

There will be no shift differential paid on the first shift if more than one shift is employed. The shift differential will remain \$12/hour on the second and third shift for the first eight (8) hours if worked. There will be no pyramiding on overtime worked on second and third shifts. The time and one half (1.5x) rate will be against the base wage rate, not the shift differential

(Local #46)

MILLWRIGHT

Millwright

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$51.50

Supplemental Benefit Rate per Hour: \$52.41

Overtime

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday.

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 57 of 87

Double time the regular rate for Sunday.

Saturday may be used as a make-up day at straight time when a day is lost during that week to inclement weather.

Overtime Holidays

Double time the regular rate for work on the following holiday(s).

New Year's Day
President's Day
Good Friday
Memorial Day
Independence Day
Labor Day
Columbus Day
Presidential Election Day
Thanksgiving Day
Christmas Day

Paid Holidays

1/2 day on Christmas Eve if work is performed in the A.M. 1/2 day on New Year's Eve if work is performed in the A.M.

Shift Rates

The first shift shall receive the straight time rate of pay. The second shift receives the straight time rate of pay plus fifteen (15%) per cent. Members of the second shift shall be allowed one half hour to eat, with this time being included in the hours of the workday established. There must be a first shift to work a second shift. All additional hours worked shall be paid at the time and one-half rate of pay plus fifteen (15%) per cent for weekday hours.

(Local #740)

MOSAIC MECHANIC

Mosaic Mechanic - Mosaic & Terrazzo Mechanic

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$46.86

Supplemental Benefit Rate per Hour: \$40.65

Supplemental Note: Supplemental benefits for overtime to be paid at the rate of \$51.67 per hour.

Mosaic Mechanic - Mosaic & Terrazzo Finisher

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$45.26

Supplemental Benefit Rate per Hour: \$40.63

Supplemental Note: Supplemental benefits for overtime to be paid at the rate of \$51.65

per hour.

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 58 of 87

Mosaic Mechanic - Machine Operator Grinder

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$45.26

Supplemental Benefit Rate per Hour: \$40.63

Supplemental Note: Supplemental benefits for overtime to be paid at the rate of \$51.65 per hour.

Overtime

Time and one half the regular rate after a 7 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

Overtime Holidays

Double time the regular rate for work on the following holiday(s).
New Year's Day
Washington's Birthday
Good Friday
Independence Day
Labor Day
Columbus Day
Veteran's Day
Thanksgiving Day

Christmas Day

Paid Holidays

Day after Thanksgiving

None

(Local #7)

PAINTER

Painter - Brush & Roller

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$42.50

Supplemental Benefit Rate per Hour: \$28.62 Supplemental Note: \$ 33.25 on overtime

Spray & Scaffold / Decorative / Sandblast

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$45.50

Supplemental Benefit Rate per Hour: \$28.62 Supplemental Note: \$ 33.25 on overtime

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 59 of 87

Overtime

Time and one half the regular rate after a 7 hour day. Time and one half the regular rate for Saturday. Time and one half the regular rate for Sunday.

Overtime Holidays

Time and one half the regular rate for work on the following holiday(s).

New Year's Day

President's Day

Memorial Day

Independence Day

Labor Day

Columbus Day

Thanksgiving Day

Christmas Day

Paid Holidays

None

(District Council of Painters #9)

PAINTER - METAL POLISHER

METAL POLISHER

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$29.73

Supplemental Benefit Rate per Hour: \$7.06

METAL POLISHER - NEW CONSTRUCTION

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$30.68

Supplemental Benefit Rate per Hour: \$7.06

METAL POLISHER - SCAFFOLD OVER 34 FEET

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$33.23

Supplemental Benefit Rate per Hour: \$7.06

Overtime Description

All work performed on Saturdays shall be paid at time-in-a half. The exception being; for suspended scaffold work and work deemed as a construction project; an eight (8) hour shift lost during the week due to

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 60 of 87

circumstances beyond the control of the employer, up to amaximumof eight (8) hours per week, may be worked on Saturday at the straight time rate.

Overtime

Time and one half the regular rate after an 8 hour day.

Time and one half the regular rate for Saturday.

Double time the regular rate for Sunday.

Saturday may be used as a make-up day at straight time when a day is lost during that week to inclement weather.

Triple time the regular rate for work on the following holiday(s).

Paid Holidays

New Year's Day
Martin Luther King Jr. Day
President's Day
Memorial Day
Independence Day
Labor Day
Columbus Day
Veteran's Day
Thanksgiving Day
Day after Thanksgiving
Christmas Day

Shift Rates

Four Days a week at Ten (10) hours straight a day.

Local 8A-28A

PAINTER - STRIPER

Striper (paint)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$35.00

Supplemental Benefit Rate per Hour: \$12.37

Supplemental Note: Overtime Supplemental Benefit rate - \$8.02; New Hire Rate (0-3 months) - \$0.00

Lineperson (thermoplastic)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$39.00

Supplemental Benefit Rate per Hour: \$12.37

Supplemental Note: Overtime Supplemental Benefit rate - \$8.02; New Hire Rate (0-3 months) - \$0.00

Overtime

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 61 of 87

Time and one half the regular rate after an 8 hour day.

Time and one half the regular rate for Saturday.

Double time the regular rate for Sunday.

Time and one half the regular rate for work on the following holiday(s).

Paid Holidays

New Year's Day
Good Friday
Memorial Day
Independence Day
Labor Day
Columbus Day
Presidential Election Day
Thanksgiving Day
Day after Thanksgiving
Christmas Day

Shift Rates

Employees hired before April 1, 2003: 15% night shift premium differential for work commenced at 9:00 PM or later.

Vacation

Employees with one to two years service shall accrue vacation based on hours worked: 250 hours worked - 1 day vacation; 500 hours worked - 2 days vacation; 750 hours worked - 3 days vacation; 900 hours worked - 4 days vacation; 1,000 hours worked - 5 days vacation. Employees with two to five years service receive two weeks vacation. Employees with five to twenty years service receive three weeks vacation. Employees with twenty to twenty-five years service receive four weeks vacation. Employees with 25 or more years service receive five weeks vacation. Vacation must be taken during winter months. 2 Personal Days except employees hired after 4/1/12 who do not have 2 years of service.

(Local #917)

PAINTER - STRUCTURAL STEEL

Painters on Structural Steel

Effective Period: 7/1/2017 - 9/30/2017 Wage Rate per Hour: \$49.50

Supplemental Benefit Rate per Hour: \$37.08

Effective Period: 10/1/2017 - 6/30/2018

Wage Rate per Hour: \$50.00

Supplemental Benefit Rate per Hour: \$38.33

Painter - Power Tool

Effective Period: 7/1/2017 - 9/30/2017

Wage Rate per Hour: \$55.50

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 62 of 87

Supplemental Benefit Rate per Hour: \$37.08

Overtime Wage Rate: \$6.00 above the "Painters on Structural Steel" overtime rate.

Effective Period: 10/1/2017 - 6/30/2018

Wage Rate per Hour: \$56.00

Supplemental Benefit Rate per Hour: \$38.33

Overtime Wage Rate: \$6.00 above the "Painters on Structural Steel" overtime rate.

Overtime Description

Supplemental Benefits shall be paid for each hour worked, up to forty (40) hours per week for the period of May 1st to November 15th or up to fifty (50) hours per week for the period of November 16th to April 30th.

Overtime

Time and one half the regular rate after a 7 hour day. Time and one half the regular rate for Saturday. Time and one half the regular rate for Sunday.

Overtime Holidays

Double time the regular rate for work on the following holiday(s).
New Year's Day
Memorial Day
Independence Day
Labor Day
Thanksgiving Day
Christmas Day

Paid Holidays

None

Shift Rates

Regular hourly rates plus a ten per cent (10%) differential

(Local #806)

PAPERHANGER

<u>Paperhanger</u>

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$44.89

Supplemental Benefit Rate per Hour: \$31.13

Supplemental Note: Supplemental benefits are to be paid at the appropriate straight time and overtime rate.

Overtime

Time and one half the regular rate after a 7 hour day. Time and one half the regular rate for Saturday.

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 63 of 87

Time and one half the regular rate for Sunday.

Overtime Holidays

Time and one half the regular rate for work on the following holiday(s).
New Year's Day
President's Day
Memorial Day
Independence Day
Labor Day
Thanksgiving Day
Day after Thanksgiving
Christmas Day

Paid Holidays

None

Shift Rates

Evening shift - 4:30 P.M. to 12:00 Midnight (regular rate of pay); any work performed before 7:00 A.M. shall be at time and one half the regular base rate of pay.

(District Council of Painters #9)

PAVER AND ROADBUILDER

Paver & Roadbuilder - Formsetter

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$45.85

Supplemental Benefit Rate per Hour: \$40.98

Paver & Roadbuilder - Laborer

Paving and road construction work, regardless of material used, including but not limited to preparation of job sites, removal of old surfaces, asphalt and/or concrete, by whatever method, including but not limited to milling; laying of concrete; laying of asphalt for temporary, patchwork, and utility paving (but not production paving); site preparation and incidental work before the installation of rubberized materials and similar surfaces; installation and repair of temporary construction fencing; slurry seal coating, maintenance of safety surfaces; play equipment installation, and other related work.

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$41.98

Supplemental Benefit Rate per Hour: \$40.98

Production Paver & Roadbuilder - Screed Person

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 64 of 87

(Production paving is asphalt paving when using a paving machine or on a project where a paving machine is traditionally used)

Adjustment of paving machinery on production paving jobs.

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$46.45

Supplemental Benefit Rate per Hour: \$40.98

Production Paver & Roadbuilder - Raker

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$45.85

Supplemental Benefit Rate per Hour: \$40.98

Production Paver & Roadbuilder - Shoveler

General laborer (except removal of surfaces - see Paver and Roadbuilder-Laborer) including but not limited to tamper, AC paint and liquid tar work.

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$42.37

Supplemental Benefit Rate per Hour: \$40.98

Overtime Description

If an employee works New Year's Day or Christmas Day, they receive the single time rate plus 25%.

Overtime

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

Overtime Holidays

Double time the regular rate for work on the following holiday(s).
Memorial Day
Independence Day
Labor Day
Columbus Day
Thanksgiving Day

Shift Rates

When two shifts are employed, the work period for each shift shall be a continuous eight (8) hours. When three shifts are employed, each shift will work seven and one half (7 $\frac{1}{2}$) hours but will be paid for eight (8) hours since only one half (1/2) hour is allowed for meal time.

When two or more shifts are employed, single time will be paid for each shift.

Night Work - On night work, the first eight (8) hours of work will be paid for at the single time rate, except that production paving work shall be paid at 10% over the single time rate for the screed person, rakers and shovelers directly involved only. This differential is to be paid when there is only one shift and the shift works at night. All other workers will be exempt. Hours worked over eight (8) hours during said shift shall be paid for at the time and one-half rate.

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 65 of 87

(Local #1010)

PLASTERER

Plasterer

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$44.93

Supplemental Benefit Rate per Hour: \$25.15

Overtime

Time and one half the regular rate after an 8 hour day.

Time and one half the regular rate for Saturday.

Double time the regular rate for Sunday.

Saturday may be used as a make-up day at straight time when a day is lost during that week to inclement weather.

Overtime Holidays

Double time the regular rate for work on the following holiday(s).

New Year's Day President's Day Memorial Day Independence Day Labor Day Thanksgiving Day

Paid Holidays

None

Shift Rates

Christmas Day

When it is not possible to conduct alteration work during regular work hours, in a building occupied by tenants, said work shall proceed on a shift basis: however work over seven (7) hours in any twenty four (24) hour period, the time after seven (7) hours shall be considered overtime.

The second shift shall start at a time between 3:30 p.m. and 7:00 p.m. and shall consist of seven (7) working hours and shall receive eight (8) hours of wages and benefits at the straight time rate. The workers on the second shift shall be allowed one-half ($\frac{1}{2}$) hour to eat with this time being included in the seven (7) hours of work.

(Local #262)

PLASTERER - TENDER

Plasterer - Tender

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$37.90

Supplemental Benefit Rate per Hour: \$30.59

Overtime

Time and one half the regular rate after an 8 hour day.

Time and one half the regular rate for Saturday.

Double time the regular rate for Sunday.

Saturday may be used as a make-up day at straight time when a day is lost during that week to inclement weather.

Overtime Holidays

Double time the regular rate for work on the following holiday(s).

New Year's Day

Washington's Birthday

Memorial Day

Independence Day

Labor Day

Presidential Election Day

Thanksgiving Day

Christmas Day

Paid Holidays

None

Shift Rates

When work commences outside regular work hours, workers receive an hour additional (differential) wage and supplement payment. Eight hours pay for seven hours work or nine hours pay for eight hours work.

(Mason Tenders District Council)

PLUMBER

<u>Plumber</u>

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$67.25

Supplemental Benefit Rate per Hour: \$31.80

Supplemental Note: Supplemental benefit contributions are to be made at the applicable overtime rates.

Plumber - Temporary Services

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 67 of 87

Temporary Services - When there are no Plumbers on the job site, there may be three shifts designed to cover the entire twenty-four hour period, including weekends if necessary, at the following rate straight time.

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$53.88

Supplemental Benefit Rate per Hour: \$25.36

Overtime Description

Double time the regular rate after a 7 hour day - unless for new construction site work where the plumbing contract price is \$1.5 million or less, the hours of labor can be 8 hours per day at the employers option. On Alteration jobs when other mechanical trades at the site are working an eighth hour at straight time, then the plumber shall also work an eighth hour at straight time.

Overtime

Double time the regular time rate for Saturday. Double time the regular rate for Sunday.

Overtime Holidays

Double time the regular rate for work on the following holiday(s).
New Year's Day
President's Day
Memorial Day
Independence Day
Labor Day
Columbus Day
Veteran's Day
Thanksgiving Day

Day after Thanksgiving Christmas Day

Shift Rates

Shift work, when directly specified in public agency or authority documents where plumbing contract is \$8 million or less, will be permitted. 30% shift premium shall be paid for wages and fringe benefits for 4:00 pm and midnight shifts Monday to Friday. 50% shift premium shall be paid for wages and fringe benefits for 4:00 pm and midnight shift work performed on weekends. For shift work on holidays, double time wages and fringe benefits shall be paid.

(Plumbers Local #1)

PLUMBER (MECHNICAL EQUIPMENT AND SERVICE)

(Mechanical Equipment and Service work shall include any repair and/or replacement of the present plumbing system.)

<u>Plumber</u>

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 68 of 87

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$41.20

Supplemental Benefit Rate per Hour: \$15.41

Overtime

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Time and one half the regular rate for Sunday.

Overtime Holidays

Time and one half the regular rate for work on the following holiday(s).

New Year's Day

President's Day

Memorial Day

Independence Day

Thanksgiving Day

Day after Thanksgiving

Christmas Day

Paid Holidays

None

(Plumbers Local # 1)

PLUMBER (RESIDENTIAL RATES FOR 1, 2 AND 3 FAMILY HOME CONSTRUCTION)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$46.66

Supplemental Benefit Rate per Hour: \$22.95

Overtime

Double time the regular rate after an 8 hour day. Double time the regular time rate for Saturday. Double time the regular rate for Sunday.

Overtime Holidays

Double time the regular rate for work on the following holiday(s).
New Year's Day
President's Day
Memorial Day
Independence Day
Labor Day
Columbus Day
Veteran's Day

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 69 of 87

Thanksgiving Day
Day after Thanksgiving
Christmas Day

Paid Holidays

None

Shift Rates

30% shift premium shall be paid for wages and fringe benefits for 4:00 pm and midnight shifts Monday to Friday. 50% shift premium shall be paid for wages and fringe benefits for 4:00 pm and midnight shift work performed on weekends. For shift work on holidays, double time wages and fringe benefits shall be paid.

(Plumbers Local #1)

PLUMBER: PUMP & TANK

Oil Trades (Installation and Maintenance)

Plumber - Pump & Tank

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$64.22

Supplemental Benefit Rate per Hour: \$23.21

Overtime

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Time and one half the regular rate for Sunday.

Overtime Holidays

Time and one half the regular rate for work on the following holiday(s).

New Year's Day

President's Day

Memorial Day

Independence Day

Labor Day

Columbus Day

Veteran's Day

Thanksgiving Day

Day after Thanksgiving

Christmas Day

Paid Holidays

None

Shift Rates

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 70 of 87

All work outside the regular workday (8:00 A.M. to 3:30 P.M.) is to be paid at time and one half the regular hourly rate

(Plumbers Local #1)

POINTER, WATERPROOFER, CAULKER, SANDBLASTER, STEAMBLASTER

(Exterior Building Renovation)

Journeyperson

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$52.57

Supplemental Benefit Rate per Hour: \$25.80

Overtime

Time and one half the regular rate after an 8 hour day.

Time and one half the regular rate for Saturday.

Time and one half the regular rate for Sunday.

Saturday may be used as a make-up day at straight time when a day is lost during that week to inclement weather.

Overtime Holidays

Time and one half the regular rate for work on the following holiday(s).

New Year's Day

Martin Luther King Jr. Day

President's Day

Memorial Day

Independence Day

Labor Day

Thanksgiving Day

Christmas Day

Paid Holidays

None

Shift Rates

All work outside the regular work day (an eight hour workday between the hours of 6:00 A.M. and 4:30 P.M.) is to be paid at time and one half the regular rate.

(Bricklayer District Council)

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 71 of 87

ROOFER

Roofer

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$41.50

Supplemental Benefit Rate per Hour: \$32.27

Overtime

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Time and one half the regular rate for Sunday.

Overtime Holidays

Time and one half the regular rate for work on the following holiday(s).

New Year's Day

Memorial Day
Independence Day
Labor Day
Thanksgiving Day
Christmas Day

Paid Holidays

None

Shift Rates

Second shift - Regular hourly rate plus a 10% differential. Third shift - Regular hourly rate plus a 15% differential.

(Local #8)

SHEET METAL WORKER

Sheet Metal Worker

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$48.90

Supplemental Benefit Rate per Hour: \$48.00

Supplemental Note: Supplemental benefit contributions are to be made at the applicable overtime rates.

<u> Sheet Metal Worker - Fan Maintenance</u>

(The temporary operation of fans or blowers in new or existing buildings for heating and/or ventilation, and/or air conditioning prior to the completion of the project.)

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 72 of 87

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$39.12

Supplemental Benefit Rate per Hour: \$48.00

Sheet Metal Worker - Duct Cleaner

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$12.90

Supplemental Benefit Rate per Hour: \$8.07

Overtime

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

Overtime Holidays

Double time the regular rate for work on the following holiday(s).

New Year's Day

Martin Luther King Jr. Day

President's Day

Memorial Day

Independence Day

Labor Day

Columbus Day

Veteran's Day

Thanksgiving Day

Day after Thanksgiving

Christmas Day

Paid Holidays

None

Shift Rates

Work that can only be performed outside regular working hours (eight hours of work between 7:30 A.M. and 3:30 P.M.) - First shift (work between 3:30 P.M. and 11:30 P.M.) - 10% differential above the established hourly rate. Second shift (work between 11:30 P.M. and 7:30 A.M.) - 15% differential above the established hourly rate.

For Fan Maintenance: On all full shifts of fan maintenance work the straight time hourly rate of pay will be paid for each shift, including nights, Saturdays, Sundays, and holidays.

(Local #28)

SHEET METAL WORKER - SPECIALTY (Decking & Siding)

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 73 of 87

Sheet Metal Specialty Worker

The first worker to perform this work must be paid at the rate of the Sheet Metal Worker. The second and third workers shall be paid the Specialty Worker Rate. The ratio of One Sheet Metal Worker, then Two Specialty Workers shall be utilized thereafter.

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$44.57

Supplemental Benefit Rate per Hour: \$25.02

Supplemental Note: Supplemental benefit contributions are to be made at the applicable overtime rates.

Overtime

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

Overtime Holidays

Double time the regular rate for work on the following holiday(s).

New Year's Day

Martin Luther King Jr. Day

President's Day

Memorial Day

Independence Day

Labor Day

Columbus Day

Veteran's Day

Thanksgiving Day

Christmas Day

Paid Holidays

None

(Local #28)

SHIPYARD WORKER

Shipyard Mechanic - First Class

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$28.12

Supplemental Benefit Rate per Hour: \$3.03

Shipyard Mechanic - Second Class

Effective Period: 7/1/2017 - 6/30/2018

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 74 of 87

Wage Rate per Hour: \$23.35

Supplemental Benefit Rate per Hour: \$2.85

Shipyard Laborer - First Class

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$20.96

Supplemental Benefit Rate per Hour: \$2.76

Shipyard Laborer - Second Class

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$15.24

Supplemental Benefit Rate per Hour: \$2.54

Shipyard Dockhand - First Class

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$22.89

Supplemental Benefit Rate per Hour: \$2.83

Shipyard Dockhand - Second Class

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$16.51

Supplemental Benefit Rate per Hour: \$2.58

Overtime Description

Work performed on holiday is paid double time the regular hourly wage rate plus holiday pay.

Overtime

Time and one half the regular rate after an 8 hour day.

Time and one half the regular rate for Saturday.

Double time the regular rate for Sunday.

Time and one half the regular hourly rate after 40 hours in any work week.

Paid Holidays

New Year's Day
Martin Luther King Jr. Day
President's Day
Good Friday
Memorial Day
Independence Day
Labor Day
Thanksgiving Day
Day after Thanksgiving
Christmas Day

Based on Survey Data

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 75 of 87

SIGN ERECTOR

(Sheet Metal, Plastic, Electric, and Neon)

Sign Erector

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$47.67

Supplemental Benefit Rate per Hour: \$50.67

Overtime

Time and one half the regular rate after a 7 hour day.
Time and one half the regular rate for Saturday.
Time and one half the regular rate for Sunday.

Time and one half the regular rate for work on the following holiday(s).

Paid Holidays

New Year's Day
Washington's Birthday
Memorial Day
Independence Day
Labor Day
Columbus Day
Election Day
Thanksgiving Day
Day after Thanksgiving
Christmas Day

Shift Rates

Time and one half the regular hourly rate is to be paid for all hours worked outside the regular workday either (7:00 A.M. through 2:30 P.M.) or (8:00 A.M. through 3:30 P.M.)

(Local #137)

STEAMFITTER

Steamfitter I

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$55.50

Supplemental Benefit Rate per Hour: \$55.29

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 76 of 87

Supplemental Note: Overtime supplemental benefit rate: \$109.84

Steamfitter -Temporary Services

The steamfitters shall not do any other work and shall not be permitted to work more than one shift in a twentyfour hour day. When steamfitters are present during the regular working day, no temporary services steamfitter will be required

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$42.18

Supplemental Benefit Rate per Hour: \$44.84

Overtime

Double time the regular rate after a 7 hour day. Double time the regular time rate for Saturday. Double time the regular rate for Sunday.

Overtime Holidays

Double time the regular rate for work on the following holiday(s).
New Year's Day
President's Day
Memorial Day
Independence Day
Labor Day
Columbus Day
Veteran's Day
Thanksgiving Day
Day after Thanksgiving
Christmas Day

Paid Holidays

None

Shift Rates

Work performed between 3:30 P.M. and 7:00 A.M. and on Saturdays, Sundays and Holidays shall be at double time the regular hourly rate and paid at the overtime supplemental benefit rate above.

Steamfitter II

For heating, ventilation, air conditioning and mechanical public works contracts with a dollar value not to exceed \$15,000,000 and for fire protection/sprinkler public works contracts not to exceed \$1,500,000.

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$55.50

Supplemental Benefit Rate per Hour: \$55.29

Supplemental Note: Overtime supplemental benefit rate: \$109.84

Steamfitter -Temporary Services

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 77 of 87

The steamfitters shall not do any other work and shall not be permitted to work more than one shift in a twenty-four hour day. When steamfitters are present during the regular working day, no temporary services steamfitter will be required.

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$42.18

Supplemental Benefit Rate per Hour: \$44.84

Overtime

Double time the regular rate after an 8 hour day. Double time the regular time rate for Saturday. Double time the regular rate for Sunday.

Overtime Holidays

Double time the regular rate for work on the following holiday(s).

New Year's Day

President's Day

Memorial Day

Independence Day

Labor Day

Columbus Day

Veteran's Day

Thanksgiving Day

Day after Thanksgiving

Christmas Day

Paid Holidays

None

Shift Rates

May be performed outside of the regular workday except Saturday, Sunday and Holidays. A shift shall consist of eight working hours. All work performed in excess of eight hours shall be paid at double time. No shift shall commence after 7:00 P.M. on Friday or 7:00 P.M. the day before holidays. All work performed after 12:01 A.M. Saturday or 12:01 A.M. the day before a Holiday will be paid at double time. When shift work is performed the wage rate for regular time worked is a thirty percent premium together with fringe benefits.

On Transit Authority projects, where work is performed in the vicinity of tracks all shift work on weekends and holidays may be performed at the regular shift rates.

Local #638

STEAMFITTER - REFRIGERATION AND AIR CONDITIONER

(Maintenance and Installation Service Person)

Refrigeration and Air Conditioner Mechanic

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 78 of 87

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$39.50

Supplemental Benefit Rate per Hour: \$15.81

Refrigeration and Air Conditioner Service Person V

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$32.46

Supplemental Benefit Rate per Hour: \$14.16

Refrigeration and Air Conditioner Service Person IV

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$26.89

Supplemental Benefit Rate per Hour: \$12.80

Refrigeration and Air Conditioner Service Person III

Filter changing and maintenance thereof, oil and greasing, tower and coil cleaning, scraping and painting, general housekeeping, taking of water samples.

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$23.08

Supplemental Benefit Rate per Hour: \$11.79

Refrigeration and Air Conditioner Service Person II

Filter changing and maintenance thereof, oil and greasing, tower and coil cleaning, scraping and painting, general housekeeping, taking of water samples.

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$19.14

Supplemental Benefit Rate per Hour: \$10.85

Refrigeration and Air Conditioner Service Person I

Filter changing and maintenance thereof, oil and greasing, tower and coil cleaning, scraping and painting, general housekeeping, taking of water samples.

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$14.00

Supplemental Benefit Rate per Hour: \$9.76

Overtime

Time and one half the regular rate after an 8 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 79 of 87

Overtime Holidays

Double time the regular rate for work on the following holiday(s).

New Year's Day Independence Day Labor Day Veteran's Day Thanksgiving Day Christmas Day

Double time and one half the regular rate for work on the following holiday(s).

Martin Luther King Jr. Day

President's Day Memorial Day Columbus Day

Paid Holidays

New Year's Day
Martin Luther King Jr. Day
President's Day
Memorial Day
Independence Day
Labor Day
Columbus Day
Veteran's Day
Thanksgiving Day
Christmas Day

(Local #638B)

STONE MASON - SETTER

Stone Mason - Setter

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$53.62

Supplemental Benefit Rate per Hour: \$41.65

Overtime

Time and one half the regular rate after a 7 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

Overtime Holidays

Double time the regular rate for work on the following holiday(s). New Year's Day Washington's Birthday Good Friday

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 80 of 87

Memorial Day Independence Day Labor Day Thanksgiving Day Christmas Day

Paid Holidays

1/2 day on Christmas Eve if work is performed in the A.M.

Shift Rates

For all work outside the regular workday (8:00 A.M. to 3:30 P.M. Monday through Friday), the pay shall be straight time plus a ten percent (10%) differential.

(Bricklayers District Council)

TAPER

Drywall Taper

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$47.82

Supplemental Benefit Rate per Hour: \$22.68

Overtime

Time and one half the regular rate after a 7 hour day. Time and one half the regular rate for Saturday. Time and one half the regular rate for Sunday.

Overtime Holidays

Time and one half the regular rate for work on the following holiday(s).

New Year's Day
Martin Luther King Jr. Day
President's Day
Good Friday
Memorial Day
Independence Day
Labor Day
Columbus Day

Thanksgiving Day

Christmas Day

Paid Holidays

Any worker who reports to work on Christmas Eve or New Year's Eve pursuant to his employer's instruction shall be entitled to three (3) hours afternoon pay without working.

(Local #1974)

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 81 of 87

TELECOMMUNICATION WORKER

(Voice Installation Only)

Telecommunication Worker

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$40.35

Supplemental Benefit Rate per Hour: \$13.19

Supplemental Note: The above rate applies for Manhattan, Bronx, Brooklyn, Queens. \$12.64 for Staten Island

only.

Overtime

Time and one half the regular rate after a 7 hour day. Time and one half the regular rate for Saturday. Time and one half the regular rate for Sunday.

Overtime Holidays

Time and one half the regular rate for work on the following holiday(s).

New Year's Day
Lincoln's Birthday
Washington's Birthday
Memorial Day
Independence Day
Labor Day
Columbus Day

Election Day

Veteran's Day

Thanksgiving Day

Christmas Day

Paid Holidays

New Year's Day

Lincoln's Birthday

Washington's Birthday

Memorial Day

Independence Day

Labor Day

Columbus Day

Election Day

Veteran's Day

Thanksgiving Day

Christmas Day

Employees have the option of observing either Martin Luther King's Birthday or the day after Thanksgiving instead of Lincoln's Birthday

Shift Rates

For any workday that starts before 8A.M. or ends after 6P.M. there is a 10% differential for the applicable worker's hourly rate.

Vacation

After 6 months......one week.

After 12 months but less than 7 years.....two weeks.

After 7 or more but less than 15 years.....three weeks.

After 15 years or more but less than 25 years.........four weeks.

(C.W.A.)

TILE FINISHER

Tile Finisher

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$41.13

Supplemental Benefit Rate per Hour: \$31.18

Overtime

Time and one half the regular rate after a 7 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

Overtime Holidays

Double time the regular rate for work on the following holiday(s).

New Year's Day President's Day Good Friday Memorial Day Independence Day Labor Day Columbus Day

Veteran's Day

Thanksgiving Day

Day after Thanksgiving

Christmas Day

Paid Holidays

None

Shift Rates

Off shift work day (work performed outside the regular 8:00 A.M. to 3:30 P.M. workday): shift differential of one and one quarter (1¹/₄) times the regular straight time rate of pay for the seven hours of actual off-shift work.

(Local #7)

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 83 of 87

TILE LAYER - SETTER

Tile Layer - Setter

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$53.19

Supplemental Benefit Rate per Hour: \$35.35

Overtime

Time and one half the regular rate after a 7 hour day. Time and one half the regular rate for Saturday. Double time the regular rate for Sunday.

Overtime Holidays

Double time the regular rate for work on the following holiday(s).

New Year's Day

President's Day

Good Friday

Memorial Day

Independence Day

Labor Day

Columbus Day

Veteran's Day

Thanksgiving Day

Shift Rates

Christmas Dav

Day after Thanksgiving

Off shift work day (work performed outside the regular 8:00 A.M. to 3:30 P.M. workday): shift differential of one and one quarter (1½) times the regular straight time rate of pay for the seven hours of actual off-shift work.

(Local #7)

TIMBERPERSON

Timberperson

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$48.00

Supplemental Benefit Rate per Hour: \$49.16

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 84 of 87

Overtime

Time and one half the regular rate after an 8 hour day.

Time and one half the regular rate for Saturday.

Double time the regular rate for Sunday.

Saturday may be used as a make-up day at straight time when a day is lost during that week to inclement weather.

Time and one half the regular hourly rate after 40 hours in any work week.

Overtime Holidays

Double time the regular rate for work on the following holiday(s).

New Year's Day

President's Day

Memorial Day

Independence Day

Labor Day

Columbus Day

Presidential Election Day

Thanksgiving Day

Paid Holidays

None

Shift Rates

Christmas Dav

Off shift work commencing between 5:00 P.M. and 11:00 P.M. shall work eight and one half hours allowing for one half hour for lunch. The wage rate shall be 113% of the straight time hourly wage rate.

(Local #1536)

TUNNEL WORKER

Blasters, Mucking Machine Operators (Compressed Air Rates)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$62.37

Supplemental Benefit Rate per Hour: \$52.39

Tunnel Workers (Compressed Air Rates)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$60.21

Supplemental Benefit Rate per Hour: \$50.65

Top Nipper (Compressed Air Rates)

Effective Period: 7/1/2017 - 6/30/2018

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 85 of 87

Wage Rate per Hour: \$59.11

Supplemental Benefit Rate per Hour: \$49.74

<u>Outside Lock Tender, Outside Gauge Tender, Muck Lock Tender (Compressed Air Rates)</u>

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$58.04

Supplemental Benefit Rate per Hour: \$48.81

Bottom Bell & Top Bell Signal Person: Shaft Person (Compressed Air Rates)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$58.04

Supplemental Benefit Rate per Hour: \$48.81

Changehouse Attendant: Powder Watchperson (Compressed Air Rates)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$50.87

Supplemental Benefit Rate per Hour: \$46.11

Blasters (Free Air Rates)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$59.52

Supplemental Benefit Rate per Hour: \$50.03

Tunnel Workers (Free Air Rates)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$56.97

Supplemental Benefit Rate per Hour: \$47.89

All Others (Free Air Rates)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$52.63

Supplemental Benefit Rate per Hour: \$44.29

Microtunneling (Free Air Rates)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$45.58

Supplemental Benefit Rate per Hour: \$38.31

Overtime Description

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 86 of 87

For Repair-Maintenance Work on Existing Equipment and Facilities - Time and one half the regular rate after a 7 hour day, or for Saturday, or for Sunday. Double time the regular rate for work on a holiday. For Small-Bore Micro Tunneling Machines - Time and one-half the regular rate shall be paid for all overtime.

Overtime

Double time the regular rate after an 8 hour day.

Double time the regular time rate for Saturday.

Double time the regular rate for Sunday.

Double time the regular rate for work on the following holiday(s).

Paid Holidays

New Year's Day
Lincoln's Birthday
President's Day
Memorial Day
Independence Day
Labor Day
Columbus Day
Election Day
Veteran's Day
Thanksgiving Day
Christmas Day

(Local #147)

WELDER

TO BE PAID AT THE RATE OF THE JOURNEYPERSON IN THE TRADE PERFORMING THE WORK.

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 87 of 87

OFFICE OF THE COMPTROLLER

CITY OF NEW YORK

220 APPRENTICESHIP PREVAILING WAGE SCHEDULE

APPENDIX

Pursuant to Labor Law §220 (3-e), only apprentices who are individually registered in a bona fide program to which the employer contractor is a participant and registered with the New York State Department of Labor, may be employed on a public work project.

Any employee listed on a payroll at an apprentice wage rate, who is not registered as above, shall be paid the journey person wage rate for the classification of work he actually performed.

Apprentice ratios are established to ensure the proper safety, training and supervision of apprentices. A ratio establishes the number of journey workers required for each apprentice in a program and on a job site. Ratios are interpreted as follows: in the case of a 1:1, 1:4 ratio, there must be one journey worker for the first apprentice, and four additional journey workers for each subsequent apprentice.

TABLE OF CONTENTS

CLASSIFICATION	<u>PAGE</u>
ASBESTOS HANDLER	3
BOILERMAKER	3
BRICKLAYER	4
CARPENTER	
CARPENTER - HIGH RISE CONCRETE FORMS	6
CEMENT MASON	
CEMENT AND CONCRETE WORKER	7
DERRICKPERSON & RIGGER (STONE)	8
DOCKBUILDER/PILE DRIVER	
ELECTRICIAN	
ELEVATOR CONSTRUCTOR	
ELEVATOR REPAIR & MAINTENANCE	_
ENGINEER	
ENGINEER - OPERATING	
FLOOR COVERER	
GLAZIER	
HEAT & FROST INSULATOR	
HOUSE WRECKER	
IRON WORKER - ORNAMENTAL	
IRON WORKER - STRUCTURAL	
LABORER (FOUNDATION, CONCRETE, EXCAVATING, STREET PIPE LAYER & COMMON)	
MARBLE MECHANICS	
MASON TENDER	
METALLIC LATHER	
MILLWRIGHT	
PAVER AND ROADBUILDER	
PAINTER	
PAINTER - METAL POLISHER	_
PAINTER - STRUCTURAL STEEL	_
PLASTERER	_
PLASTERER - TENDER	
PLUMBER	
POINTER, WATERPROOFER, CAULKER, SANDBLASTER, STEAMBLASTER	
ROOFER	
SHEET METAL WORKER	
SIGN ERECTORSTEAMFITTER	
STONE MASON - SETTER	
TAPER	
TILE LAYER - SETTER	
TILE LAYER - SETTER	35 26

ASBESTOS HANDLER

(Ratio of Apprentice Journeyperson: 1 to 1, 1 to 3)

Asbestos Handler (First 1000 Hours)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 78% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$14.25

Asbestos Handler (Second 1000 Hours)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 80% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$14.25

Asbestos Handler (Third 1000 Hours)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 83% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$14.25

Asbestos Handler (Fourth 1000 Hours)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 89% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$14.25

(Local #78)

BOILERMAKER

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

Boilermaker (First Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 65% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$30.84

Effective 1/1/2018 - Supplemental Benefit Rate Per Hour: \$31.26

Boilermaker (Second Year: 1st Six Months)

Effective Period: 7/1/2017 - 6/30/2018

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 3 of 36

Wage Rate Per Hour: 70% of Journeyperson's rate

Supplemental Benefit Rate Per Hour: \$32.57

Effective 1/1/2018 - Supplemental Benefit Rate Per Hour: \$33.02

Boilermaker (Second Year: 2nd Six Months)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 75% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$34.29

Effective 1/1/2018 - Supplemental Benefit Rate Per Hour: \$34.78

Boilermaker (Third Year: 1st Six Months)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 80% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$36.03

Effective 1/1/2018- Supplemental Benefit Rate Per Hour: \$36.56

Boilermaker (Third Year: 2nd Six Months)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 85% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$37.76

Effective 1/1/2018 - Supplemental Benefit Rate Per Hour: \$38.32

Boilermaker (Fourth Year: 1st Six Months)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 90% of Journeyperson's rate

Supplemental Benefit Rate Per Hour: \$39.51

Effective 1/1/2018 - Supplemental Benefit Rate Per Hour: \$40.09

Boilermaker (Fourth Year: 2nd Six Months)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 95% of Journeyperson's rate

Supplemental Benefit Rate Per Hour: \$41.22

Effective 1/1/2018- Supplemental Benefit Rate Per Hour: \$41.84

(Local #5)

BRICKLAYER

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 4)

Bricklayer (First 750 Hours)

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 4 of 36

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 50% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$18.80

Bricklayer (Second 750 Hours)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 60% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$18.80

Bricklayer (Third 750 Hours)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 70% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$18.80

Bricklayer (Fourth 750 Hours)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 80% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$18.80

Bricklayer (Fifth 750 Hours)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 90% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$18.80

Bricklayer (Sixth 750 Hours)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 95% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$18.80

(Bricklayer District Council)

CARPENTER

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 4)

Carpenter (First Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 40% of Journeyperson's rate

Supplemental Benefit Rate Per Hour For Building Apprentice: \$31.34

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 5 of 36

Supplemental Benefit Rate Per Hour For Heavy Apprentice: \$33.03

Carpenter (Second Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 50% of Journeyperson's rate

Supplemental Benefit Rate Per Hour For Building Apprentice: \$31.34 Supplemental Benefit Rate Per Hour For Heavy Apprentice: \$33.03

Carpenter (Third Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 65% of Journeyperson's rate

Supplemental Benefit Rate Per Hour For Building Apprentice: \$31.34 Supplemental Benefit Rate Per Hour For Heavy Apprentice: \$33.03

Carpenter (Fourth Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 80% of Journeyperson's rate

Supplemental Benefit Rate Per Hour For Building Apprentice: \$31.34 Supplemental Benefit Rate Per Hour For Heavy Apprentice: \$33.03

(Carpenters District Council)

CARPENTER - HIGH RISE CONCRETE FORMS

(Ratio of Apprentice to Journeyperson: 1 to 1, 2 to 5)

Carpenter - High Rise (First Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$16.86

Supplemental Benefit Rate per Hour: \$16.20

Carpenter - High Rise (Second Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$23.16

Supplemental Benefit Rate per Hour: \$16.33

Carpenter - High Rise (Third Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$29.61

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 6 of 36

Supplemental Benefit Rate per Hour: \$16.46

Carpenter - High Rise (Fourth Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$37.07

Supplemental Benefit Rate per Hour: \$16.61

(Carpenters District Council)

CEMENT MASON

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 4)

Cement Mason (First Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 50% of Journeyperson's Rate

Cement Mason (Second Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 60% of Journeyperson's Rate

<u> Cement Mason (Third Year)</u>

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 70% of Journeyperson's Rate

(Local #780)

CEMENT AND CONCRETE WORKER

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

Cement & Concrete Worker (First 1333 hours)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 50% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$17.75

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 7 of 36

Cement & Concrete Worker (Second 1333 hours)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 65% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$23.03

Cement & Concrete Worker (Last 1334 hours)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 80% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$24.30

Cement & Concrete Worker (Hired after 2/6/2016 - First 1334 hours)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: \$16.96

Supplemental Benefit Rate Per Hour: \$11.80

Cement & Concrete Worker (Hired after 2/6/2016 - Second 1334 hours)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: \$22.08

Supplemental Benefit Rate Per Hour: \$16.49

Cement & Concrete Worker (Hired after 2/6/2016 - Last 1334 hours)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: \$27.20

Supplemental Benefit Rate Per Hour: \$17.33

(Cement Concrete Workers District Council)

DERRICKPERSON & RIGGER (STONE)

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 4)

Derrickperson & Rigger (stone) - First Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 50% of Journeyperson's rate

Supplemental Benefit Rate Per Hour: 50% of Journeyperson's rate

<u>Derrickperson & Rigger (stone) - Second Year: 1st Six Months</u>

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 70% of Journeyperson's rate

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 8 of 36

Supplemental Benefit Rate Per Hour: 75% of Journeyperson's rate

Derrickperson & Rigger (stone) - Second Year: 2nd Six Months

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 80% of Journeyperson's rate

Supplemental Benefit Rate Per Hour: 75% of Journeyperson's rate

Derrickperson & Rigger (stone) - Third Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 90% of Journeyperson's rate

Supplemental Benefit Rate Per Hour: 75% of Journeyperson's rate

(Local #197)

DOCKBUILDER/PILE DRIVER

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 6)

Dockbuilder/Pile Driver (First Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 40% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$33.03

Dockbuilder/Pile Driver (Second Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 50% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$33.03

Dockbuilder/Pile Driver (Third Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 65% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$33.03

Dockbuilder/Pile Driver (Fourth Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 80% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$33.03

(Carpenters District Council)

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 9 of 36

ELECTRICIAN

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

Electrician (First Term: 0-6 Months)

Effective Period: 7/1/2017 - 5/9/2018 Wage Rate per Hour: \$14.00

Supplemental Benefit Rate per Hour: \$12.37
Overtime Supplemental Rate Per Hour: \$13.29

Effective Period: 5/10/2018 - 6/30/2018

Wage Rate per Hour: \$14.50

Supplemental Benefit Rate per Hour: \$12.63
Overtime Supplemental Rate Per Hour: \$13.58

Electrician (First Term: 7-12 Months)

Effective Period: 7/1/2017 - 5/9/2018 Wage Rate per Hour: \$15.00

Supplemental Benefit Rate per Hour: \$12.88
Overtime Supplemental Rate Per Hour: \$13.87

Effective Period: 5/10/2018 - 6/30/2018

Wage Rate per Hour: \$15.50

Supplemental Benefit Rate per Hour: \$13.14
Overtime Supplemental Rate Per Hour: \$14.16

Electrician (Second Term: 0-6 Months)

Effective Period: 7/1/2017 - 5/9/2018 Wage Rate per Hour: \$16.00

Supplemental Benefit Rate per Hour: \$13.39
Overtime Supplemental Rate Per Hour: \$14.44

Effective Period: 5/10/2018 - 6/30/2018

Wage Rate per Hour: \$16.50

Supplemental Benefit Rate per Hour: \$13.64
Overtime Supplemental Rate Per Hour: \$14.73

Electrician (Second Term: 7-12 Months)

Effective Period: 7/1/2017 - 5/9/2018 Wage Rate per Hour: \$17.00

Supplemental Benefit Rate per Hour: \$13.90

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 10 of 36

Overtime Supplemental Rate Per Hour: \$15.02

Effective Period: 5/10/2018 - 6/30/2018

Wage Rate per Hour: \$17.50

Supplemental Benefit Rate per Hour: \$14.15
Overtime Supplemental Rate Per Hour: \$15.31

Electrician (Third Term: 0-6 Months)

Effective Period: 7/1/2017 - 5/9/2018 Wage Rate per Hour: \$18.00

Supplemental Benefit Rate per Hour: \$14.41
Overtime Supplemental Rate Per Hour: \$15.59

Effective Period: 5/10/2018 - 6/30/2018

Wage Rate per Hour: \$18.50

Supplemental Benefit Rate per Hour: \$14.66
Overtime Supplemental Rate Per Hour: \$15.88

Electrician (Third Term: 7-12 Months)

Effective Period: 7/1/2017 - 5/9/2018 Wage Rate per Hour: **\$19.00**

Supplemental Benefit Rate per Hour: \$14.92
Overtime Supplemental Rate Per Hour: \$16.17

Effective Period: 5/10/2018 - 6/30/2018

Wage Rate per Hour: \$19.50

Supplemental Benefit Rate per Hour: \$15.17
Overtime Supplemental Rate Per Hour: \$16.45

Electrician (Fourth Term: 0-6 Months)

Effective Period: 7/1/2017 - 5/9/2018 Wage Rate per Hour: **\$20.00**

Supplemental Benefit Rate per Hour: \$15.43
Overtime Supplemental Rate Per Hour: \$16.74

Effective Period: 5/10/2018 - 6/30/2018

Wage Rate per Hour: \$20.50

Supplemental Benefit Rate per Hour: \$15.68
Overtime Supplemental Rate Per Hour: \$17.03

Electrician (Fourth Term: 7-12 Months)

Effective Period: 7/1/2017 - 5/9/2018

Wage Rate per Hour: \$22.00

Supplemental Benefit Rate per Hour: \$16.44 Overtime Supplemental Rate Per Hour: \$17.89

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 11 of 36

Effective Period: 5/10/2018 - 6/30/2018

Wage Rate per Hour: \$22.50

Supplemental Benefit Rate per Hour: \$16.70 Overtime Supplemental Rate Per Hour: \$18.18

Electrician (Fifth Term: 0-12 Months)

Effective Period: 7/1/2017 - 5/9/2018 Wage Rate per Hour: **\$24.00**

Supplemental Benefit Rate per Hour: \$19.80 Overtime Supplemental Rate Per Hour: \$21.30

Effective Period: 5/10/2018 - 6/30/2018

Wage Rate per Hour: \$24.50

Supplemental Benefit Rate per Hour: \$20.30 Overtime Supplemental Rate Per Hour: \$21.84

Electrician (Fifth Term: 13-18 Months)

Effective Period: 7/1/2017 - 5/9/2018 Wage Rate per Hour: **\$28.50**

Supplemental Benefit Rate per Hour: \$22.10 Overtime Supplemental Rate Per Hour: \$23.89

Effective Period: 5/10/2018 - 6/30/2018

Wage Rate per Hour: \$29.00

Supplemental Benefit Rate per Hour: \$22.65
Overtime Supplemental Rate Per Hour: \$24.47

Overtime Description

Overtime Wage paid at time and one half the regular rate

(Local #3)

ELEVATOR CONSTRUCTOR

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 2)

Elevator (Constructor) - First Year

Effective Period: 7/1/2017 - 3/16/2018

Wage Rate Per Hour: 50% of Journeyperson's rate

Supplemental Rate Per Hour: \$29.88

Effective Period: 3/17/2018 - 6/30/2018

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 12 of 36

Wage Rate Per Hour: 50% of Journeyperson's rate

Supplemental Rate Per Hour: \$31.35

Elevator (Constructor) - Second Year

Effective Period: 7/1/2017 - 3/16/2018

Wage Rate Per Hour: 55% of Journeyperson's rate

Supplemental Rate Per Hour: \$30.31

Effective Period: 3/17/2018 - 6/30/2018

Wage Rate Per Hour: 55% of Journeyperson's rate

Supplemental Rate Per Hour: \$31.80

Elevator (Constructor) - Third Year

Effective Period: 7/1/2017 - 3/16/2018

Wage Rate Per Hour: 65% of Journeyperson's rate

Supplemental Rate Per Hour: \$31.19

Effective Period: 3/17/2018 - 6/30/2018

Wage Rate Per Hour: 65% of Journeyperson's rate

Supplemental Rate Per Hour: \$32.70

Elevator (Constructor) - Fourth Year

Effective Period: 7/1/2017 - 3/16/2018

Wage Rate Per Hour: 75% of Journeyperson's rate

Supplemental Rate Per Hour: \$32.07

Effective Period: 3/17/2018 - 6/30/2018

Wage Rate Per Hour: 75% of Journeyperson's rate

Supplemental Rate Per Hour: \$33.60

(Local #1)

ELEVATOR REPAIR & MAINTENANCE

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 2)

Elevator Service/Modernization Mechanic (First Year)

Effective Period: 7/1/2017 - 3/16/2018

Wage Rate Per Hour: 50% of Journeyperson's rate

Supplemental Benefit Per Hour: \$29.80

Effective Period: 3/17/2018 - 6/30/2018

Wage Rate Per Hour: 50% of Journeyperson's rate

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 13 of 36

Supplemental Benefit Per Hour: \$31.28

Elevator Service/Modernization Mechanic (Second Year)

Effective Period: 7/1/2017 - 3/16/2018

Wage Rate Per Hour: 55% of Journeyperson's rate

Supplemental Benefit Per Hour: \$30.23

Effective Period: 3/17/2018 - 6/30/2018

Wage Rate Per Hour: 55% of Journeyperson's rate

Supplemental Benefit Per Hour: \$31.72

Elevator Service/Modernization Mechanic (Third Year)

Effective Period: 7/1/2017 - 3/16/2018

Wage Rate Per Hour: 65% of Journeyperson's rate

Supplemental Benefit Per Hour: \$31.09

Effective Period: 3/17/2018 - 6/30/2018

Wage Rate Per Hour: 65% of Journeyperson's rate

Supplemental Benefit Per Hour: \$32.60

Elevator Service/Modernization Mechanic (Fourth Year)

Effective Period: 7/1/2017 - 3/16/2018

Wage Rate Per Hour: 75% of Journeyperson's rate

Supplemental Benefit Per Hour: \$31.95

Effective Period: 3/17/2018 - 6/30/2018

Wage Rate Per Hour: 75% of Journeyperson's rate

Supplemental Benefit Per Hour: \$33.49

(Local #1)

ENGINEER

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 5)

<u> Engineer - First Year</u>

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$24.77

Supplemental Benefit Rate per Hour: \$24.62

Engineer - Second Year

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 14 of 36

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$30.97

Supplemental Benefit Rate per Hour: \$24.62

Engineer - Third Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$34.06

Supplemental Benefit Rate per Hour: \$24.62

Engineer - Fourth Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$37.16

Supplemental Benefit Rate per Hour: \$24.62

(Local #15)

ENGINEER - OPERATING

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 5)

Operating Engineer - First Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour 40% of Journeyperson's Rate

Supplemental Benefit Per Hour: \$20.85

Operating Engineer - Second Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 50% of Journeyperson's Rate

Supplemental Benefit Per Hour: \$20.85

Operating Engineer - Third Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 60% of Journeyperson's Rate

Supplemental Benefit Per Hour: \$20.85

(Local #14)

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 15 of 36

FLOOR COVERER

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 4)

Floor Coverer (First Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 40% of Journeyperson's rate

Supplemental Rate Per Hour: \$31.14

Floor Coverer (Second Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 50% of Journeyperson's rate

Supplemental Rate Per Hour: \$31.14

Floor Coverer (Third Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 65% of Journeyperson's rate

Supplemental Rate Per Hour: \$31.14

Floor Coverer (Fourth Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 80% of Journeyperson's rate

Supplemental Rate Per Hour: \$31.14

(Carpenters District Council)

GLAZIER

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

Glazier (First Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 40% of Journeyperson's rate

Supplemental Rate Per Hour: \$15.26

<u> Glazier (Second Year)</u>

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 50% of Journeyperson's rate

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 16 of 36

Supplemental Rate Per Hour: \$25.36

Glazier (Third Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 60% of Journeyperson's rate

Supplemental Rate Per Hour: \$28.62

Glazier (Fourth Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 80% of Journeyperson's rate

Supplemental Rate Per Hour: \$34.67

(Local #1281)

HEAT & FROST INSULATOR

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

Heat & Frost Insulator (First Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 40% of Journeyperson's rate

Heat & Frost Insulator (Second Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 60% of Journeyperson's rate

Heat & Frost Insulator (Third Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 70% of Journeyperson's rate

Heat & Frost Insulator (Fourth Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 80% of Journeyperson's rate

(Local #12)

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 17 of 36

HOUSE WRECKER (TOTAL DEMOLITION)

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

House Wrecker - First Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$21.17

Supplemental Benefit Rate per Hour: \$18.54

House Wrecker - Second Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$22.32

Supplemental Benefit Rate per Hour: \$18.54

House Wrecker - Third Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$23.97

Supplemental Benefit Rate per Hour: \$18.54

House Wrecker - Fourth Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$26.53

Supplemental Benefit Rate per Hour: \$18.54

(Mason Tenders District Council)

IRON WORKER - ORNAMENTAL

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 4)

Iron Worker (Ornamental) - 1st Ten Months

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 50% of Journeyperson's rate

Supplemental Rate Per Hour: \$39.40

Iron Worker (Ornamental) - 11 -16 Months

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 18 of 36

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 55% of Journeyperson's rate

Supplemental Rate Per Hour: \$40.62

Iron Worker (Ornamental) - 17 - 22 Months

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 60% of Journeyperson's rate

Supplemental Rate Per Hour: \$41.83

Iron Worker (Ornamental) - 23 - 28 Months

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 70% of Journeyperson's rate

Supplemental Rate Per Hour: \$44.27

Iron Worker (Ornamental) - 29 - 36 Months

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 80% of Journeyperson's rate

Supplemental Rate Per Hour: \$46.70

(Local #580)

IRON WORKER - STRUCTURAL

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 6)

Iron Worker (Structural) - 1st Six Months

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$26.12

Supplemental Benefit Rate per Hour: \$50.22

Iron Worker (Structural) - 7- 18 Months

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$26.72

Supplemental Benefit Rate per Hour: \$50.22

Iron Worker (Structural) - 19 - 36 months

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$27.32

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 19 of 36

Supplemental Benefit Rate per Hour: \$50.22

(Local #40 and #361)

LABORER (FOUNDATION, CONCRETE, EXCAVATING, STREET PIPE LAYER & COMMON)

(Ratio Apprentice to Journeyperson: 1 to 1, 1 to 3)

<u>Laborer (Foundation, Concrete, Excavating, Street Pipe Layer & Common) - First</u> 1000 hours

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 50% of Journeyperson's rate

Supplemental Rate Per Hour: \$40.63

<u>Laborer (Foundation, Concrete, Excavating, Street Pipe Layer & Common) - Second 1000 hours</u>

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 60% of Journeyperson's rate

Supplemental Rate Per Hour: \$40.63

<u>Laborer (Foundation, Concrete, Excavating, Street Pipe Layer & Common) -</u> Third 1000 hours

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 75% of Journeyperson's rate

Supplemental Rate Per Hour: \$40.63

<u>Laborer (Foundation, Concrete, Excavating, Street Pipe Layer & Common) -</u> Fourth 1000 hours

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 90% of Journeyperson's rate

Supplemental Rate Per Hour: \$40.63

(Local #731)

MARBLE MECHANICS

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 4)

Cutters & Setters - First 750 Hours

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 50% of Journeyperson's rate

NO BENEFITS PAID DURING THE FIRST TWO MONTHS (PROBATIONARY PERIOD)

Cutters & Setters - Second 750 Hours

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 55% of Journeyperson's rate

Cutters & Setters - Third 750 Hours

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 65% of Journeyperson's rate

Cutters & Setters - Fourth 750 Hours

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 75% of Journeyperson's rate

Cutters & Setters - Fifth 750 Hours

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 85% of Journeyperson's rate

Cutters & Setters - Sixth 750 Hours

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 95% of Journeyperson's rate

Polishers & Finishers - First 750 Hours

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 50% of Journeyperson's rate

NO BENEFITS PAID DURING THE FIRST TWO MONTHS (PROBATIONARY PERIOD)

Polishers & Finishers - Second 750 Hours

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 60% of Journeyperson's rate

Polishers & Finishers - Third 750 Hours

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 21 of 36

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 75% of Journeyperson's rate

Polishers & Finishers - Fourth 750 Hours

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 90% of Journeyperson's rate

(Local #7)

MASON TENDER

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

Mason Tender - First Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$21.39

Supplemental Benefit Rate per Hour: \$19.65

Mason Tender - Second Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$22.54

Supplemental Benefit Rate per Hour: \$19.65

Mason Tender - Third Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$24.29

Supplemental Benefit Rate per Hour: \$19.70

Mason Tender - Fourth Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$26.95

Supplemental Benefit Rate per Hour: \$19.70

(Local #79)

METALLIC LATHER

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

Metallic Lather (First Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$28.38

Supplemental Benefit Rate per Hour: \$10.96

Metallic Lather (Second Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$32.38

Supplemental Benefit Rate per Hour: \$12.96

Metallic Lather (Third Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$35.38

Supplemental Benefit Rate per Hour: \$17.12

Metallic Lather (Fourth Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$37.38

Supplemental Benefit Rate per Hour: \$17.92

(Local #46)

MILLWRIGHT

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 4)

Millwright (First Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$28.33

Supplemental Benefit Rate per Hour: \$34.28

Millwright (Second Year)

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 23 of 36

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$33.48

Supplemental Benefit Rate per Hour: \$37.88

Millwright (Third Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$38.63

Supplemental Benefit Rate per Hour: \$42.13

Millwright (Fourth Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$48.93

Supplemental Benefit Rate per Hour: \$48.69

(Local #740)

PAVER AND ROADBUILDER

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

Paver and Roadbuilder - First Year (Minimum 1000 hours)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$27.86

Supplemental Benefit Rate per Hour: \$19.25

Paver and Roadbuilder - Second Year (Minimum 1000 hours)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$29.50

Supplemental Benefit Rate per Hour: \$19.25

(Local #1010)

PAINTER

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 24 of 36

Painter - Brush & Roller - First Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$17.00

Supplemental Benefit Rate per Hour: \$13.42

Painter - Brush & Roller - Second Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$21.25

Supplemental Benefit Rate per Hour: \$17.43

Painter - Brush & Roller - Third Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$25.50

Supplemental Benefit Rate per Hour: \$20.50

Painter - Brush & Roller - Fourth Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$34.00

Supplemental Benefit Rate per Hour: \$26.20

(District Council of Painters)

PAINTER - METAL POLISHER

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

Metal Polisher (First Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$11.75

Supplemental Benefit Rate per Hour: \$5.13

Metal Polisher (Second Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$13.00

Supplemental Benefit Rate per Hour: \$5.13

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 25 of 36

Metal Polisher (Third Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$15.75

Supplemental Benefit Rate per Hour: \$5.13

(Local 8A-28)

PAINTER - STRUCTURAL STEEL

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

Painters - Structural Steel (First Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 40% of Journeyperson's rate

Painters - Structural Steel (Second Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 60% of Journeyperson's rate

Painters - Structural Steel (Third Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 80% of Journeyperson's rate

(Local #806)

PLASTERER

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

Plasterer - First Year: 1st Six Months

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 40% of Journeyperson's rate

Supplemental Rate Per Hour: \$13.59

Plasterer - First Year: 2nd Six Months

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 26 of 36

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 45% of Journeyperson's rate

Supplemental Rate Per Hour: \$14.07

Plasterer - Second Year: 1st Six Months

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 55% of Journeyperson's rate

Supplemental Rate Per Hour: \$16.04

Plasterer - Second Year: 2nd Six Months

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 60% of Journeyperson's rate

Supplemental Rate Per Hour: \$17.12

Plasterer - Third Year: 1st Six Months

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 70% of Journeyperson's rate

Supplemental Rate Per Hour: \$19.29

Plasterer - Third Year: 2nd Six Months

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 75% of Journeyperson's rate

Supplemental Rate Per Hour: \$20.37

(Local #530)

PLASTERER - TENDER

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

Plasterer Tender - First Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$21.39

Supplemental Benefit Rate per Hour: \$19.65

Plasterer Tender - Second Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$22.54

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 27 of 36

Supplemental Benefit Rate per Hour: \$19.65

Plasterer Tender - Third Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$24.29

Supplemental Benefit Rate per Hour: \$19.70

Plasterer Tender - Fourth Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$26.95

Supplemental Benefit Rate per Hour: \$19.70

(Local #79)

PLUMBER

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

Plumber - First Year: 1st Six Months

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$16.28

Supplemental Benefit Rate per Hour: \$5.43

Plumber - First Year: 2nd Six Months

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$19.28

Supplemental Benefit Rate per Hour: \$6.43

Plumber - Second Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$26.35

Supplemental Benefit Rate per Hour: \$17.10

Plumber - Third Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$28.45

Supplemental Benefit Rate per Hour: \$17.10

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 28 of 36

Plumber - Fourth Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$31.30

Supplemental Benefit Rate per Hour: \$17.10

Plumber - Fifth Year: 1st Six Months

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$32.70

Supplemental Benefit Rate per Hour: \$17.10

Plumber - Fifth Year: 2nd Six Months

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$44.77

Supplemental Benefit Rate per Hour: \$17.10

(Plumbers Local #1)

POINTER, WATERPROOFER, CAULKER, SANDBLASTER, STEAMBLASTER

(Exterior Building Renovation)

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 4)

Pointer, Waterproofer, Caulker, Sandblaster, Steamblaster - First Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$25.89

Supplemental Benefit Rate per Hour: \$13.64

Pointer, Waterproofer, Caulker, Sandblaster, Steamblaster - Second Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$28.97

Supplemental Benefit Rate per Hour: \$18.15

Pointer, Waterproofer, Caulker, Sandblaster, Steamblaster - Third Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$34.12

Supplemental Benefit Rate per Hour: \$20.90

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 29 of 36

Pointer, Waterproofer, Caulker, Sandblaster, Steamblaster - Fourth Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$41.33

Supplemental Benefit Rate per Hour: \$21.60

(Bricklayer District Council)

ROOFER

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 2)

Roofer - First Year

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 35% of Journeyperson's Rate

Roofer - Second Year

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 50% of Journeyperson's Rate

Roofer - Third Year

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 60% of Journeyperson's Rate

Roofer - Fourth Year

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 75% of Journeyperson's Rate

(Local #8)

SHEET METAL WORKER

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

Sheet Metal Worker (0-6 Months)

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 30 of 36

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 25% of Journeyperson's rate

Supplemental Rate Per Hour: \$6.35

Sheet Metal Worker (7-18 Months)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 35% of Journeyperson's rate

Supplemental Rate Per Hour: \$17.12

Sheet Metal Worker (19-30 Months)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 45% of Journeyperson's rate

Supplemental Rate Per Hour: \$23.54

Sheet Metal Worker (31-36 Months)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 55% of Journeyperson's rate

Supplemental Rate Per Hour: \$27.70

Sheet Metal Worker (37-42 Months)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 60% of Journeyperson's rate

Supplemental Rate Per Hour: \$29.11

Sheet Metal Worker (43-48 Months)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 70% of Journeyperson's rate

Supplemental Rate Per Hour: \$33.96

Sheet Metal Worker (49-54 Months)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 75% of Journeyperson's rate

Supplemental Rate Per Hour: \$36.07

Sheet Metal Worker (55-60 Months)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 80% of Journeyperson's rate

Supplemental Rate Per Hour: \$38.15

(Local #28)

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 31 of 36

SIGN ERECTOR

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 4)

Sign Erector - First Year: 1st Six Months

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 35% of Journeyperson's rate

Supplemental Rate Per Hour: \$14.72

Sign Erector - First Year: 2nd Six Months

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 40% of Journeyperson's rate

Supplemental Rate Per Hour: \$16.71

<u>Sign Erector - Second Year: 1st Six Months</u>

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 45% of Journeyperson's rate

Supplemental Rate Per Hour: \$18.68

<u> Sign Erector - Second Year: 2nd Six Months</u>

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 50% of Journeyperson's rate

Supplemental Rate Per Hour: \$20.68

Sign Erector - Third Year: 1st Six Months

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 55% of Journeyperson's rate

Supplemental Rate Per Hour: \$27.72

<u> Sign Erector - Third Year: 2nd Six Months</u>

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 60% of Journeyperson's rate

Supplemental Rate Per Hour: \$30.57

Sign Erector - Fourth Year: 1st Six Months

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 65% of Journeyperson's rate

Supplemental Rate Per Hour: \$33.31

Sign Erector - Fourth Year: 2nd Six Months

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 32 of 36

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 70% of Journeyperson's rate

Supplemental Rate Per Hour: \$35.83

Sign Erector - Fifth Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 75% of Journeyperson's rate

Supplemental Rate Per Hour: \$38.32

Sign Erector - Sixth Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 80% of Journeyperson's rate

Supplemental Rate Per Hour: \$40.81

(Local #137)

STEAMFITTER

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

Steamfitter - First Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate and Supplemental Per Hour: 40% of Journeyperson's rate

Steamfitter - Second Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate and Supplemental Rate Per Hour: 50% of Journeyperson's rate.

Steamfitter - Third Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate and Supplemental Rate per Hour: 65% of Journeyperson's rate.

Steamfitter - Fourth Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate and Supplemental Rate Per Hour: 80% of Journeyperson's rate.

Steamfitter - Fifth Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate and Supplemental Rate Per Hour: 85% of Journeyperson's rate.

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 33 of 36

(Local #638)

STONE MASON - SETTER

(Ratio Apprentice of Journeyperson: 1 to 1, 1 to 2)

Stone Mason - Setters - First 750 Hours

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 50% of Journeyperson's rate

Stone Mason - Setters - Second 750 Hours

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 60% of Journeyperson's rate

Supplemental Rate Per Hour: 50% of Journeyperson's rate

Stone Mason - Setters - Third 750 Hours

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 70% of Journeyperson's rate

Supplemental Rate Per Hour: 50% of Journeyperson's rate

Stone Mason - Setters - Fourth 750 Hours

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 80% of Journeyperson's rate

Supplemental Rate Per Hour: 50% of Journeyperson's rate

Stone Mason - Setters - Fifth 750 Hours

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 90% of Journeyperson's rate

Supplemental Rate Per Hour: 50% of Journeyperson's rate

Stone Mason - Setters - Sixth 750 Hours

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 100% of Journeyperson's rate Supplemental Rate Per Hour: 50% of Journeyperson's rate

(Bricklayers District Council)

TAPER

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 4)

Drywall Taper - First Year

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 40% of Journeyperson's rate

Drywall Taper - Second Year

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 60% of Journeyperson's rate

Drywall Taper - Third Year

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 80% of Journeyperson's rate

(Local #1974)

TILE LAYER - SETTER

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 4)

Tile Layer - Setter - First 750 Hours

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 50% of Journeyperson's rate

<u>Tile Layer - Setter - Second 750 Hours</u>

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 55% of Journeyperson's rate

<u>Tile Layer - Setter - Third 750 Hours</u>

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 65% of Journeyperson's rate

<u>Tile Layer - Setter - Fourth 750 Hours</u>

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 35 of 36

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 75% of Journeyperson's rate

Tile Layer - Setter - Fifth 750 Hours

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 85% of Journeyperson's rate

Tile Layer - Setter - Sixth 750 Hours

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 95% of Journeyperson's rate

(Local #7)

TIMBERPERSON

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 6)

Timberperson - First Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 40% of Journeyperson's rate

Supplemental Rate Per Hour: \$32.79

Timberperson - Second Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 50% of Journeyperson's rate

Supplemental Rate Per Hour: \$32.79

<u> Timberperson - Third Year</u>

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 65% of Journeyperson's rate

Supplemental Rate Per Hour: \$32.79

<u> Timberperson - Fourth Year</u>

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 80% of Journeyperson's rate

Supplemental Rate Per Hour: \$32.79

(Local #1536)

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 36 of 36

OFFICE OF THE COMPTROLLER

CITY OF NEW YORK

220 APPRENTICESHIP PREVAILING WAGE SCHEDULE

APPENDIX

Pursuant to Labor Law §220 (3-e), only apprentices who are individually registered in a bona fide program to which the employer contractor is a participant and registered with the New York State Department of Labor, may be employed on a public work project.

Any employee listed on a payroll at an apprentice wage rate, who is not registered as above, shall be paid the journey person wage rate for the classification of work he actually performed.

Apprentice ratios are established to ensure the proper safety, training and supervision of apprentices. A ratio establishes the number of journey workers required for each apprentice in a program and on a job site. Ratios are interpreted as follows: in the case of a 1:1, 1:4 ratio, there must be one journey worker for the first apprentice, and four additional journey workers for each subsequent apprentice.

TABLE OF CONTENTS

CLASSIFICATION	<u>PAGE</u>
ASBESTOS HANDLER	_
BOILERMAKER	
BRICKLAYER	4
CARPENTER	
CARPENTER - HIGH RISE CONCRETE FORMS	6
CEMENT MASON	
CEMENT AND CONCRETE WORKER	
DERRICKPERSON & RIGGER (STONE)	8
DOCKBUILDER/PILE DRIVER	9
ELECTRICIAN	
ELEVATOR CONSTRUCTOR	12
ELEVATOR REPAIR & MAINTENANCE	13
ENGINEER	
ENGINEER - OPERATING	15
FLOOR COVERER	16
GLAZIER	16
HEAT & FROST INSULATOR	17
HOUSE WRECKER	18
IRON WORKER - ORNAMENTAL	18
IRON WORKER - STRUCTURAL	
LABORER (FOUNDATION, CONCRETE, EXCAVATING, STREET PIPE LAYER & COMMON)	20
MARBLE MECHANICS	21
MASON TENDER	22
METALLIC LATHER	23
MILLWRIGHT	23
PAVER AND ROADBUILDER	24
PAINTER	24
PAINTER - METAL POLISHER	25
PAINTER - STRUCTURAL STEEL	26
PLASTERER	26
PLASTERER - TENDER	27
PLUMBER	28
POINTER, WATERPROOFER, CAULKER, SANDBLASTER, STEAMBLASTER	29
ROOFER	30
SHEET METAL WORKER	30
SIGN ERECTOR	
STEAMFITTER	
STONE MASON - SETTER	34
TAPER	_
TILE LAYER - SETTER	
TIMBEDDED SON	36

ASBESTOS HANDLER

(Ratio of Apprentice Journeyperson: 1 to 1, 1 to 3)

Asbestos Handler (First 1000 Hours)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 78% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$14.25

Asbestos Handler (Second 1000 Hours)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 80% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$14.25

Asbestos Handler (Third 1000 Hours)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 83% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$14.25

Asbestos Handler (Fourth 1000 Hours)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 89% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$14.25

(Local #78)

BOILERMAKER

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

Boilermaker (First Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 65% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$30.84

Effective 1/1/2018 - Supplemental Benefit Rate Per Hour: \$31.26

Boilermaker (Second Year: 1st Six Months)

Effective Period: 7/1/2017 - 6/30/2018

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 3 of 36

Wage Rate Per Hour: 70% of Journeyperson's rate

Supplemental Benefit Rate Per Hour: \$32.57

Effective 1/1/2018 - Supplemental Benefit Rate Per Hour: \$33.02

Boilermaker (Second Year: 2nd Six Months)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 75% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$34.29

Effective 1/1/2018 - Supplemental Benefit Rate Per Hour: \$34.78

Boilermaker (Third Year: 1st Six Months)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 80% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$36.03

Effective 1/1/2018- Supplemental Benefit Rate Per Hour: \$36.56

Boilermaker (Third Year: 2nd Six Months)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 85% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$37.76

Effective 1/1/2018 - Supplemental Benefit Rate Per Hour: \$38.32

Boilermaker (Fourth Year: 1st Six Months)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 90% of Journeyperson's rate

Supplemental Benefit Rate Per Hour: \$39.51

Effective 1/1/2018 - Supplemental Benefit Rate Per Hour: \$40.09

Boilermaker (Fourth Year: 2nd Six Months)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 95% of Journeyperson's rate

Supplemental Benefit Rate Per Hour: \$41.22

Effective 1/1/2018- Supplemental Benefit Rate Per Hour: \$41.84

(Local #5)

BRICKLAYER

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 4)

Bricklayer (First 750 Hours)

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 4 of 36

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 50% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$18.80

Bricklayer (Second 750 Hours)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 60% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$18.80

Bricklayer (Third 750 Hours)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 70% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$18.80

Bricklayer (Fourth 750 Hours)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 80% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$18.80

Bricklayer (Fifth 750 Hours)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 90% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$18.80

Bricklayer (Sixth 750 Hours)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 95% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$18.80

(Bricklayer District Council)

CARPENTER

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 4)

Carpenter (First Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 40% of Journeyperson's rate

Supplemental Benefit Rate Per Hour For Building Apprentice: \$31.34

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 5 of 36

Supplemental Benefit Rate Per Hour For Heavy Apprentice: \$33.03

Carpenter (Second Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 50% of Journeyperson's rate

Supplemental Benefit Rate Per Hour For Building Apprentice: \$31.34 Supplemental Benefit Rate Per Hour For Heavy Apprentice: \$33.03

Carpenter (Third Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 65% of Journeyperson's rate

Supplemental Benefit Rate Per Hour For Building Apprentice: \$31.34 Supplemental Benefit Rate Per Hour For Heavy Apprentice: \$33.03

Carpenter (Fourth Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 80% of Journeyperson's rate

Supplemental Benefit Rate Per Hour For Building Apprentice: \$31.34 Supplemental Benefit Rate Per Hour For Heavy Apprentice: \$33.03

(Carpenters District Council)

CARPENTER - HIGH RISE CONCRETE FORMS

(Ratio of Apprentice to Journeyperson: 1 to 1, 2 to 5)

Carpenter - High Rise (First Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$16.86

Supplemental Benefit Rate per Hour: \$16.20

Carpenter - High Rise (Second Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$23.16

Supplemental Benefit Rate per Hour: \$16.33

Carpenter - High Rise (Third Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$29.61

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 6 of 36

Supplemental Benefit Rate per Hour: \$16.46

Carpenter - High Rise (Fourth Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$37.07

Supplemental Benefit Rate per Hour: \$16.61

(Carpenters District Council)

CEMENT MASON

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 4)

Cement Mason (First Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 50% of Journeyperson's Rate

Cement Mason (Second Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 60% of Journeyperson's Rate

<u> Cement Mason (Third Year)</u>

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 70% of Journeyperson's Rate

(Local #780)

CEMENT AND CONCRETE WORKER

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

Cement & Concrete Worker (First 1333 hours)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 50% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$17.75

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 7 of 36

Cement & Concrete Worker (Second 1333 hours)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 65% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$23.03

Cement & Concrete Worker (Last 1334 hours)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 80% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$24.30

Cement & Concrete Worker (Hired after 2/6/2016 - First 1334 hours)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: \$16.96

Supplemental Benefit Rate Per Hour: \$11.80

Cement & Concrete Worker (Hired after 2/6/2016 - Second 1334 hours)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: \$22.08

Supplemental Benefit Rate Per Hour: \$16.49

Cement & Concrete Worker (Hired after 2/6/2016 - Last 1334 hours)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: \$27.20

Supplemental Benefit Rate Per Hour: \$17.33

(Cement Concrete Workers District Council)

DERRICKPERSON & RIGGER (STONE)

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 4)

Derrickperson & Rigger (stone) - First Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 50% of Journeyperson's rate

Supplemental Benefit Rate Per Hour: 50% of Journeyperson's rate

<u>Derrickperson & Rigger (stone) - Second Year: 1st Six Months</u>

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 70% of Journeyperson's rate

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 8 of 36

Supplemental Benefit Rate Per Hour: 75% of Journeyperson's rate

Derrickperson & Rigger (stone) - Second Year: 2nd Six Months

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 80% of Journeyperson's rate

Supplemental Benefit Rate Per Hour: 75% of Journeyperson's rate

Derrickperson & Rigger (stone) - Third Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 90% of Journeyperson's rate

Supplemental Benefit Rate Per Hour: 75% of Journeyperson's rate

(Local #197)

DOCKBUILDER/PILE DRIVER

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 6)

Dockbuilder/Pile Driver (First Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 40% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$33.03

Dockbuilder/Pile Driver (Second Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 50% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$33.03

Dockbuilder/Pile Driver (Third Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 65% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$33.03

Dockbuilder/Pile Driver (Fourth Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 80% of Journeyperson's rate Supplemental Benefit Rate Per Hour: \$33.03

(Carpenters District Council)

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 9 of 36

ELECTRICIAN

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

Electrician (First Term: 0-6 Months)

Effective Period: 7/1/2017 - 5/9/2018 Wage Rate per Hour: **\$14.00**

Supplemental Benefit Rate per Hour: \$12.37
Overtime Supplemental Rate Per Hour: \$13.29

Effective Period: 5/10/2018 - 6/30/2018

Wage Rate per Hour: \$14.50

Supplemental Benefit Rate per Hour: \$12.63
Overtime Supplemental Rate Per Hour: \$13.58

Electrician (First Term: 7-12 Months)

Effective Period: 7/1/2017 - 5/9/2018 Wage Rate per Hour: \$15.00

Supplemental Benefit Rate per Hour: \$12.88
Overtime Supplemental Rate Per Hour: \$13.87

Effective Period: 5/10/2018 - 6/30/2018

Wage Rate per Hour: \$15.50

Supplemental Benefit Rate per Hour: \$13.14
Overtime Supplemental Rate Per Hour: \$14.16

Electrician (Second Term: 0-6 Months)

Effective Period: 7/1/2017 - 5/9/2018 Wage Rate per Hour: \$16.00

Supplemental Benefit Rate per Hour: \$13.39
Overtime Supplemental Rate Per Hour: \$14.44

Effective Period: 5/10/2018 - 6/30/2018

Wage Rate per Hour: \$16.50

Supplemental Benefit Rate per Hour: \$13.64
Overtime Supplemental Rate Per Hour: \$14.73

Electrician (Second Term: 7-12 Months)

Effective Period: 7/1/2017 - 5/9/2018 Wage Rate per Hour: \$17.00

Supplemental Benefit Rate per Hour: \$13.90

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 10 of 36

Overtime Supplemental Rate Per Hour: \$15.02

Effective Period: 5/10/2018 - 6/30/2018

Wage Rate per Hour: \$17.50

Supplemental Benefit Rate per Hour: \$14.15
Overtime Supplemental Rate Per Hour: \$15.31

Electrician (Third Term: 0-6 Months)

Effective Period: 7/1/2017 - 5/9/2018 Wage Rate per Hour: \$18.00

Supplemental Benefit Rate per Hour: \$14.41 Overtime Supplemental Rate Per Hour: \$15.59

Effective Period: 5/10/2018 - 6/30/2018

Wage Rate per Hour: \$18.50

Supplemental Benefit Rate per Hour: \$14.66
Overtime Supplemental Rate Per Hour: \$15.88

Electrician (Third Term: 7-12 Months)

Effective Period: 7/1/2017 - 5/9/2018 Wage Rate per Hour: **\$19.00**

Supplemental Benefit Rate per Hour: \$14.92
Overtime Supplemental Rate Per Hour: \$16.17

Effective Period: 5/10/2018 - 6/30/2018

Wage Rate per Hour: \$19.50

Supplemental Benefit Rate per Hour: \$15.17
Overtime Supplemental Rate Per Hour: \$16.45

Electrician (Fourth Term: 0-6 Months)

Effective Period: 7/1/2017 - 5/9/2018 Wage Rate per Hour: **\$20.00**

Supplemental Benefit Rate per Hour: \$15.43
Overtime Supplemental Rate Per Hour: \$16.74

Effective Period: 5/10/2018 - 6/30/2018

Wage Rate per Hour: \$20.50

Supplemental Benefit Rate per Hour: \$15.68
Overtime Supplemental Rate Per Hour: \$17.03

Electrician (Fourth Term: 7-12 Months)

Effective Period: 7/1/2017 - 5/9/2018

Wage Rate per Hour: \$22.00

Supplemental Benefit Rate per Hour: \$16.44 Overtime Supplemental Rate Per Hour: \$17.89

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 11 of 36

Effective Period: 5/10/2018 - 6/30/2018

Wage Rate per Hour: \$22.50

Supplemental Benefit Rate per Hour: \$16.70 Overtime Supplemental Rate Per Hour: \$18.18

Electrician (Fifth Term: 0-12 Months)

Effective Period: 7/1/2017 - 5/9/2018 Wage Rate per Hour: **\$24.00**

Supplemental Benefit Rate per Hour: \$19.80 Overtime Supplemental Rate Per Hour: \$21.30

Effective Period: 5/10/2018 - 6/30/2018

Wage Rate per Hour: \$24.50

Supplemental Benefit Rate per Hour: \$20.30 Overtime Supplemental Rate Per Hour: \$21.84

Electrician (Fifth Term: 13-18 Months)

Effective Period: 7/1/2017 - 5/9/2018 Wage Rate per Hour: **\$28.50**

Supplemental Benefit Rate per Hour: \$22.10 Overtime Supplemental Rate Per Hour: \$23.89

Effective Period: 5/10/2018 - 6/30/2018

Wage Rate per Hour: \$29.00

Supplemental Benefit Rate per Hour: \$22.65
Overtime Supplemental Rate Per Hour: \$24.47

Overtime Description

Overtime Wage paid at time and one half the regular rate

(Local #3)

ELEVATOR CONSTRUCTOR

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 2)

Elevator (Constructor) - First Year

Effective Period: 7/1/2017 - 3/16/2018

Wage Rate Per Hour: 50% of Journeyperson's rate

Supplemental Rate Per Hour: \$29.88

Effective Period: 3/17/2018 - 6/30/2018

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 12 of 36

Wage Rate Per Hour: 50% of Journeyperson's rate

Supplemental Rate Per Hour: \$31.35

Elevator (Constructor) - Second Year

Effective Period: 7/1/2017 - 3/16/2018

Wage Rate Per Hour: 55% of Journeyperson's rate

Supplemental Rate Per Hour: \$30.31

Effective Period: 3/17/2018 - 6/30/2018

Wage Rate Per Hour: 55% of Journeyperson's rate

Supplemental Rate Per Hour: \$31.80

Elevator (Constructor) - Third Year

Effective Period: 7/1/2017 - 3/16/2018

Wage Rate Per Hour: 65% of Journeyperson's rate

Supplemental Rate Per Hour: \$31.19

Effective Period: 3/17/2018 - 6/30/2018

Wage Rate Per Hour: 65% of Journeyperson's rate

Supplemental Rate Per Hour: \$32.70

Elevator (Constructor) - Fourth Year

Effective Period: 7/1/2017 - 3/16/2018

Wage Rate Per Hour: 75% of Journeyperson's rate

Supplemental Rate Per Hour: \$32.07

Effective Period: 3/17/2018 - 6/30/2018

Wage Rate Per Hour: 75% of Journeyperson's rate

Supplemental Rate Per Hour: \$33.60

(Local #1)

ELEVATOR REPAIR & MAINTENANCE

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 2)

Elevator Service/Modernization Mechanic (First Year)

Effective Period: 7/1/2017 - 3/16/2018

Wage Rate Per Hour: 50% of Journeyperson's rate

Supplemental Benefit Per Hour: \$29.80

Effective Period: 3/17/2018 - 6/30/2018

Wage Rate Per Hour: 50% of Journeyperson's rate

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 13 of 36

Supplemental Benefit Per Hour: \$31.28

Elevator Service/Modernization Mechanic (Second Year)

Effective Period: 7/1/2017 - 3/16/2018

Wage Rate Per Hour: 55% of Journeyperson's rate

Supplemental Benefit Per Hour: \$30.23

Effective Period: 3/17/2018 - 6/30/2018

Wage Rate Per Hour: 55% of Journeyperson's rate

Supplemental Benefit Per Hour: \$31.72

Elevator Service/Modernization Mechanic (Third Year)

Effective Period: 7/1/2017 - 3/16/2018

Wage Rate Per Hour: 65% of Journeyperson's rate

Supplemental Benefit Per Hour: \$31.09

Effective Period: 3/17/2018 - 6/30/2018

Wage Rate Per Hour: 65% of Journeyperson's rate

Supplemental Benefit Per Hour: \$32.60

Elevator Service/Modernization Mechanic (Fourth Year)

Effective Period: 7/1/2017 - 3/16/2018

Wage Rate Per Hour: 75% of Journeyperson's rate

Supplemental Benefit Per Hour: \$31.95

Effective Period: 3/17/2018 - 6/30/2018

Wage Rate Per Hour: 75% of Journeyperson's rate

Supplemental Benefit Per Hour: \$33.49

(Local #1)

ENGINEER

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 5)

<u> Engineer - First Year</u>

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$24.77

Supplemental Benefit Rate per Hour: \$24.62

Engineer - Second Year

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 14 of 36

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$30.97

Supplemental Benefit Rate per Hour: \$24.62

Engineer - Third Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$34.06

Supplemental Benefit Rate per Hour: \$24.62

Engineer - Fourth Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$37.16

Supplemental Benefit Rate per Hour: \$24.62

(Local #15)

ENGINEER - OPERATING

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 5)

Operating Engineer - First Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour 40% of Journeyperson's Rate

Supplemental Benefit Per Hour: \$20.85

Operating Engineer - Second Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 50% of Journeyperson's Rate

Supplemental Benefit Per Hour: \$20.85

Operating Engineer - Third Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 60% of Journeyperson's Rate

Supplemental Benefit Per Hour: \$20.85

(Local #14)

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 15 of 36

FLOOR COVERER

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 4)

Floor Coverer (First Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 40% of Journeyperson's rate

Supplemental Rate Per Hour: \$31.14

Floor Coverer (Second Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 50% of Journeyperson's rate

Supplemental Rate Per Hour: \$31.14

Floor Coverer (Third Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 65% of Journeyperson's rate

Supplemental Rate Per Hour: \$31.14

Floor Coverer (Fourth Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 80% of Journeyperson's rate

Supplemental Rate Per Hour: \$31.14

(Carpenters District Council)

GLAZIER

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

Glazier (First Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 40% of Journeyperson's rate

Supplemental Rate Per Hour: \$15.26

Glazier (Second Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 50% of Journeyperson's rate

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 16 of 36

Supplemental Rate Per Hour: \$25.36

Glazier (Third Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 60% of Journeyperson's rate

Supplemental Rate Per Hour: \$28.62

Glazier (Fourth Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 80% of Journeyperson's rate

Supplemental Rate Per Hour: \$34.67

(Local #1281)

HEAT & FROST INSULATOR

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

Heat & Frost Insulator (First Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 40% of Journeyperson's rate

Heat & Frost Insulator (Second Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 60% of Journeyperson's rate

Heat & Frost Insulator (Third Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 70% of Journeyperson's rate

Heat & Frost Insulator (Fourth Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 80% of Journeyperson's rate

(Local #12)

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 17 of 36

HOUSE WRECKER (TOTAL DEMOLITION)

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

House Wrecker - First Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$21.17

Supplemental Benefit Rate per Hour: \$18.54

House Wrecker - Second Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$22.32

Supplemental Benefit Rate per Hour: \$18.54

House Wrecker - Third Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$23.97

Supplemental Benefit Rate per Hour: \$18.54

House Wrecker - Fourth Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$26.53

Supplemental Benefit Rate per Hour: \$18.54

(Mason Tenders District Council)

IRON WORKER - ORNAMENTAL

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 4)

Iron Worker (Ornamental) - 1st Ten Months

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 50% of Journeyperson's rate

Supplemental Rate Per Hour: \$39.40

Iron Worker (Ornamental) - 11 -16 Months

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 18 of 36

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 55% of Journeyperson's rate

Supplemental Rate Per Hour: \$40.62

Iron Worker (Ornamental) - 17 - 22 Months

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 60% of Journeyperson's rate

Supplemental Rate Per Hour: \$41.83

Iron Worker (Ornamental) - 23 - 28 Months

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 70% of Journeyperson's rate

Supplemental Rate Per Hour: \$44.27

Iron Worker (Ornamental) - 29 - 36 Months

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 80% of Journeyperson's rate

Supplemental Rate Per Hour: \$46.70

(Local #580)

IRON WORKER - STRUCTURAL

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 6)

Iron Worker (Structural) - 1st Six Months

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$26.12

Supplemental Benefit Rate per Hour: \$50.22

Iron Worker (Structural) - 7- 18 Months

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$26.72

Supplemental Benefit Rate per Hour: \$50.22

Iron Worker (Structural) - 19 - 36 months

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$27.32

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 19 of 36

Supplemental Benefit Rate per Hour: \$50.22

(Local #40 and #361)

LABORER (FOUNDATION, CONCRETE, EXCAVATING, STREET PIPE LAYER & COMMON)

(Ratio Apprentice to Journeyperson: 1 to 1, 1 to 3)

<u>Laborer (Foundation, Concrete, Excavating, Street Pipe Layer & Common) - First</u> 1000 hours

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 50% of Journeyperson's rate

Supplemental Rate Per Hour: \$40.63

<u>Laborer (Foundation, Concrete, Excavating, Street Pipe Layer & Common) - Second 1000 hours</u>

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 60% of Journeyperson's rate

Supplemental Rate Per Hour: \$40.63

<u>Laborer (Foundation, Concrete, Excavating, Street Pipe Layer & Common) -</u> Third 1000 hours

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 75% of Journeyperson's rate

Supplemental Rate Per Hour: \$40.63

<u>Laborer (Foundation, Concrete, Excavating, Street Pipe Layer & Common) - Fourth 1000 hours</u>

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 90% of Journeyperson's rate

Supplemental Rate Per Hour: \$40.63

(Local #731)

MARBLE MECHANICS

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 4)

Cutters & Setters - First 750 Hours

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 50% of Journeyperson's rate

NO BENEFITS PAID DURING THE FIRST TWO MONTHS (PROBATIONARY PERIOD)

Cutters & Setters - Second 750 Hours

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 55% of Journeyperson's rate

Cutters & Setters - Third 750 Hours

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 65% of Journeyperson's rate

Cutters & Setters - Fourth 750 Hours

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 75% of Journeyperson's rate

Cutters & Setters - Fifth 750 Hours

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 85% of Journeyperson's rate

Cutters & Setters - Sixth 750 Hours

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 95% of Journeyperson's rate

Polishers & Finishers - First 750 Hours

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 50% of Journeyperson's rate

NO BENEFITS PAID DURING THE FIRST TWO MONTHS (PROBATIONARY PERIOD)

Polishers & Finishers - Second 750 Hours

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 60% of Journeyperson's rate

Polishers & Finishers - Third 750 Hours

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 21 of 36

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 75% of Journeyperson's rate

Polishers & Finishers - Fourth 750 Hours

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 90% of Journeyperson's rate

(Local #7)

MASON TENDER

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

Mason Tender - First Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$21.39

Supplemental Benefit Rate per Hour: \$19.65

Mason Tender - Second Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$22.54

Supplemental Benefit Rate per Hour: \$19.65

Mason Tender - Third Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$24.29

Supplemental Benefit Rate per Hour: \$19.70

Mason Tender - Fourth Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$26.95

Supplemental Benefit Rate per Hour: \$19.70

(Local #79)

METALLIC LATHER

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

Metallic Lather (First Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$28.38

Supplemental Benefit Rate per Hour: \$10.96

Metallic Lather (Second Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$32.38

Supplemental Benefit Rate per Hour: \$12.96

Metallic Lather (Third Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$35.38

Supplemental Benefit Rate per Hour: \$17.12

Metallic Lather (Fourth Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$37.38

Supplemental Benefit Rate per Hour: \$17.92

(Local #46)

MILLWRIGHT

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 4)

Millwright (First Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$28.33

Supplemental Benefit Rate per Hour: \$34.28

Millwright (Second Year)

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 23 of 36

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$33.48

Supplemental Benefit Rate per Hour: \$37.88

Millwright (Third Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$38.63

Supplemental Benefit Rate per Hour: \$42.13

Millwright (Fourth Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$48.93

Supplemental Benefit Rate per Hour: \$48.69

(Local #740)

PAVER AND ROADBUILDER

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

Paver and Roadbuilder - First Year (Minimum 1000 hours)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$27.86

Supplemental Benefit Rate per Hour: \$19.25

Paver and Roadbuilder - Second Year (Minimum 1000 hours)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$29.50

Supplemental Benefit Rate per Hour: \$19.25

(Local #1010)

PAINTER

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 24 of 36

Painter - Brush & Roller - First Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$17.00

Supplemental Benefit Rate per Hour: \$13.42

Painter - Brush & Roller - Second Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$21.25

Supplemental Benefit Rate per Hour: \$17.43

Painter - Brush & Roller - Third Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$25.50

Supplemental Benefit Rate per Hour: \$20.50

Painter - Brush & Roller - Fourth Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$34.00

Supplemental Benefit Rate per Hour: \$26.20

(District Council of Painters)

PAINTER - METAL POLISHER

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

Metal Polisher (First Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$11.75

Supplemental Benefit Rate per Hour: \$5.13

Metal Polisher (Second Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$13.00

Supplemental Benefit Rate per Hour: \$5.13

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 25 of 36

Metal Polisher (Third Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$15.75

Supplemental Benefit Rate per Hour: \$5.13

(Local 8A-28)

PAINTER - STRUCTURAL STEEL

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

Painters - Structural Steel (First Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 40% of Journeyperson's rate

Painters - Structural Steel (Second Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 60% of Journeyperson's rate

Painters - Structural Steel (Third Year)

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 80% of Journeyperson's rate

(Local #806)

PLASTERER

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

Plasterer - First Year: 1st Six Months

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 40% of Journeyperson's rate

Supplemental Rate Per Hour: \$13.59

Plasterer - First Year: 2nd Six Months

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 26 of 36

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 45% of Journeyperson's rate

Supplemental Rate Per Hour: \$14.07

Plasterer - Second Year: 1st Six Months

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 55% of Journeyperson's rate

Supplemental Rate Per Hour: \$16.04

Plasterer - Second Year: 2nd Six Months

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 60% of Journeyperson's rate

Supplemental Rate Per Hour: \$17.12

Plasterer - Third Year: 1st Six Months

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 70% of Journeyperson's rate

Supplemental Rate Per Hour: \$19.29

Plasterer - Third Year: 2nd Six Months

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 75% of Journeyperson's rate

Supplemental Rate Per Hour: \$20.37

(Local #530)

PLASTERER - TENDER

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

Plasterer Tender - First Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$21.39

Supplemental Benefit Rate per Hour: \$19.65

Plasterer Tender - Second Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$22.54

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 27 of 36

Supplemental Benefit Rate per Hour: \$19.65

Plasterer Tender - Third Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$24.29

Supplemental Benefit Rate per Hour: \$19.70

Plasterer Tender - Fourth Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$26.95

Supplemental Benefit Rate per Hour: \$19.70

(Local #79)

PLUMBER

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

Plumber - First Year: 1st Six Months

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$16.28

Supplemental Benefit Rate per Hour: \$5.43

Plumber - First Year: 2nd Six Months

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$19.28

Supplemental Benefit Rate per Hour: \$6.43

Plumber - Second Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$26.35

Supplemental Benefit Rate per Hour: \$17.10

Plumber - Third Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$28.45

Supplemental Benefit Rate per Hour: \$17.10

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 28 of 36

Plumber - Fourth Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$31.30

Supplemental Benefit Rate per Hour: \$17.10

Plumber - Fifth Year: 1st Six Months

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$32.70

Supplemental Benefit Rate per Hour: \$17.10

Plumber - Fifth Year: 2nd Six Months

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$44.77

Supplemental Benefit Rate per Hour: \$17.10

(Plumbers Local #1)

POINTER, WATERPROOFER, CAULKER, SANDBLASTER, STEAMBLASTER

(Exterior Building Renovation)

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 4)

Pointer, Waterproofer, Caulker, Sandblaster, Steamblaster - First Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$25.89

Supplemental Benefit Rate per Hour: \$13.64

Pointer, Waterproofer, Caulker, Sandblaster, Steamblaster - Second Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$28.97

Supplemental Benefit Rate per Hour: \$18.15

Pointer, Waterproofer, Caulker, Sandblaster, Steamblaster - Third Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$34.12

Supplemental Benefit Rate per Hour: \$20.90

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 29 of 36

Pointer, Waterproofer, Caulker, Sandblaster, Steamblaster - Fourth Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate per Hour: \$41.33

Supplemental Benefit Rate per Hour: \$21.60

(Bricklayer District Council)

ROOFER

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 2)

Roofer - First Year

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 35% of Journeyperson's Rate

Roofer - Second Year

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 50% of Journeyperson's Rate

Roofer - Third Year

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 60% of Journeyperson's Rate

Roofer - Fourth Year

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 75% of Journeyperson's Rate

(Local #8)

SHEET METAL WORKER

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

Sheet Metal Worker (0-6 Months)

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 30 of 36

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 25% of Journeyperson's rate

Supplemental Rate Per Hour: \$6.35

Sheet Metal Worker (7-18 Months)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 35% of Journeyperson's rate

Supplemental Rate Per Hour: \$17.12

Sheet Metal Worker (19-30 Months)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 45% of Journeyperson's rate

Supplemental Rate Per Hour: \$23.54

Sheet Metal Worker (31-36 Months)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 55% of Journeyperson's rate

Supplemental Rate Per Hour: \$27.70

Sheet Metal Worker (37-42 Months)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 60% of Journeyperson's rate

Supplemental Rate Per Hour: \$29.11

Sheet Metal Worker (43-48 Months)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 70% of Journeyperson's rate

Supplemental Rate Per Hour: \$33.96

Sheet Metal Worker (49-54 Months)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 75% of Journeyperson's rate

Supplemental Rate Per Hour: \$36.07

Sheet Metal Worker (55-60 Months)

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 80% of Journeyperson's rate

Supplemental Rate Per Hour: \$38.15

(Local #28)

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 31 of 36

SIGN ERECTOR

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 4)

Sign Erector - First Year: 1st Six Months

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 35% of Journeyperson's rate

Supplemental Rate Per Hour: \$14.72

Sign Erector - First Year: 2nd Six Months

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 40% of Journeyperson's rate

Supplemental Rate Per Hour: \$16.71

<u>Sign Erector - Second Year: 1st Six Months</u>

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 45% of Journeyperson's rate

Supplemental Rate Per Hour: \$18.68

<u> Sign Erector - Second Year: 2nd Six Months</u>

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 50% of Journeyperson's rate

Supplemental Rate Per Hour: \$20.68

Sign Erector - Third Year: 1st Six Months

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 55% of Journeyperson's rate

Supplemental Rate Per Hour: \$27.72

Sign Erector - Third Year: 2nd Six Months

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 60% of Journeyperson's rate

Supplemental Rate Per Hour: \$30.57

Sign Erector - Fourth Year: 1st Six Months

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 65% of Journeyperson's rate

Supplemental Rate Per Hour: \$33.31

Sign Erector - Fourth Year: 2nd Six Months

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 32 of 36

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 70% of Journeyperson's rate

Supplemental Rate Per Hour: \$35.83

Sign Erector - Fifth Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 75% of Journeyperson's rate

Supplemental Rate Per Hour: \$38.32

Sign Erector - Sixth Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 80% of Journeyperson's rate

Supplemental Rate Per Hour: \$40.81

(Local #137)

STEAMFITTER

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 3)

Steamfitter - First Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate and Supplemental Per Hour: 40% of Journeyperson's rate

Steamfitter - Second Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate and Supplemental Rate Per Hour: 50% of Journeyperson's rate.

Steamfitter - Third Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate and Supplemental Rate per Hour: 65% of Journeyperson's rate.

Steamfitter - Fourth Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate and Supplemental Rate Per Hour: 80% of Journeyperson's rate.

Steamfitter - Fifth Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate and Supplemental Rate Per Hour: 85% of Journeyperson's rate.

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 33 of 36

(Local #638)

STONE MASON - SETTER

(Ratio Apprentice of Journeyperson: 1 to 1, 1 to 2)

Stone Mason - Setters - First 750 Hours

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 50% of Journeyperson's rate

Stone Mason - Setters - Second 750 Hours

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 60% of Journeyperson's rate

Supplemental Rate Per Hour: 50% of Journeyperson's rate

Stone Mason - Setters - Third 750 Hours

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 70% of Journeyperson's rate

Supplemental Rate Per Hour: 50% of Journeyperson's rate

Stone Mason - Setters - Fourth 750 Hours

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 80% of Journeyperson's rate

Supplemental Rate Per Hour: 50% of Journeyperson's rate

Stone Mason - Setters - Fifth 750 Hours

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 90% of Journeyperson's rate

Supplemental Rate Per Hour: 50% of Journeyperson's rate

Stone Mason - Setters - Sixth 750 Hours

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 100% of Journeyperson's rate Supplemental Rate Per Hour: 50% of Journeyperson's rate

(Bricklayers District Council)

TAPER

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 4)

Drywall Taper - First Year

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 40% of Journeyperson's rate

Drywall Taper - Second Year

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 60% of Journeyperson's rate

Drywall Taper - Third Year

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 80% of Journeyperson's rate

(Local #1974)

TILE LAYER - SETTER

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 4)

Tile Layer - Setter - First 750 Hours

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 50% of Journeyperson's rate

<u>Tile Layer - Setter - Second 750 Hours</u>

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 55% of Journeyperson's rate

<u>Tile Layer - Setter - Third 750 Hours</u>

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 65% of Journeyperson's rate

<u>Tile Layer - Setter - Fourth 750 Hours</u>

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 35 of 36

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 75% of Journeyperson's rate

Tile Layer - Setter - Fifth 750 Hours

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 85% of Journeyperson's rate

Tile Layer - Setter - Sixth 750 Hours

Effective Period: 7/1/2017 - 6/30/2018

Wage and Supplemental Rate Per Hour: 95% of Journeyperson's rate

(Local #7)

TIMBERPERSON

(Ratio of Apprentice to Journeyperson: 1 to 1, 1 to 6)

Timberperson - First Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 40% of Journeyperson's rate

Supplemental Rate Per Hour: \$32.79

Timberperson - Second Year

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 50% of Journeyperson's rate

Supplemental Rate Per Hour: \$32.79

<u> Timberperson - Third Year</u>

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 65% of Journeyperson's rate

Supplemental Rate Per Hour: \$32.79

<u> Timberperson - Fourth Year</u>

Effective Period: 7/1/2017 - 6/30/2018

Wage Rate Per Hour: 80% of Journeyperson's rate

Supplemental Rate Per Hour: \$32.79

(Local #1536)

PUBLISH DATE: 7/1/2017 EFFECTIVE PERIOD: JULY 1, 2017 THROUGH JUNE 30, 2018 Page 36 of 36

ATTACHMENT H

Notice to Bidders: Apprenticeship Agreement

NOTICE TO BIDDERS - APPRENTICESHIP AGREEMENTS

Please be advised that, pursuant to the authority granted to the City under Labor Law §816-b, the Department of Correction hereby requires that the contractor awarded a contract as a result of this solicitation, and any of its subcontractors with subcontracts worth two million dollars or over, have, prior to entering into such contract or subcontract, apprenticeship agreements appropriate for the type and scope of work to be performed that have been registered with, and approved by, the New York State Commissioner of Labor. In addition, the contractor and its subcontractors will be required to show that such apprenticeship programs have successfully passed the two year Probation period following the initial registration date of such programs with the New York State Department of Labor.

The failure to prove, upon request, that these requirements have been met shall result in the contract not being awarded to the contractor or the subcontractor not being approved.

Please be further advised that, pursuant to Labor Law §220, the allowable ratio of apprentices to journeypersons in any craft classification shall not be greater than the ratio permitted to the contractor as to its workforce on any job under the registered apprenticeship program.

CONTR		NIO
CONIN	\mathbf{AUI}	NU.

CITY OF NEW YORK DEPARTMENT OF CORRECTION



FOR FURNISHING ALL LABOR AND MATERIAL NECESSARY AND REQUIRED FOR:

Vernon C. Bain Center (VCBC) Chilled Water Risers and Pumps Replacement

PROCUREMENT IDENTIFICATION NUMBER

PIN 072201821CPD

EPIN 07218B0009
