


APPENDIX E
TRAFFIC AND TRANSIT



Legend

- M66 Route
- M72 Route
- M31 Route
- ⊕ Assumed Future Bus Stop

Future Bus Route Modifications as Analyzed

Appendix E
Pedestrian Mitigation Measures

Intersection	Crosswalk	Impacted Period	No Build Signal Timing	Proposed Mitigation Plan	
				Build Signal Timing	Proposed Mitigation Measures
West 60th Street and Amsterdam Ave.	North	AM/PM	36/37/36/36	37/37/40/38	Transfer 1s from NS to EW during the weekday AM period. Transfer 4s from NS to EW during the weekday PM period. Transfer 2s from NS to EW during the Sat MD period. Widen south crosswalk from 12 ft to 15.3 ft. Widen north crosswalk from 12.8 ft to 16.9 ft.
	West		54/53/54/54	53/53/50/53	
	South	AM/PM/Sat MD	36/37/36/36	37/37/40/38	
	East		54/53/54/54	53/53/50/53	
West 60th Street and Columbus Ave.	North	AM/PM/Sat MD	40/40/40/40	44/43/44/43	Transfer 4s from NS to EW during the weekday AM and PM periods. Transfer 3s from NS to EW during the weekday midday and Sat MD periods. Widen south crosswalk from 12 ft to 15.8 ft. Widen north crosswalk from 15 ft to 17.6 ft. Widen west crosswalk from 13 ft to 14 ft.
	West		51/51/51/51	47/48/47/48	
	South	AM/MD/PM/Sat MD	40/40/40/40	44/43/44/43	
	East		51/51/51/51	47/48/47/48	
West 59th Street and West End Avenue	North	AM/PM/Sat MD	30/30/30/30	33/30/30/30	Transfer 3s from NS to EW during the weekday AM period. Widen north crosswalk from 10.8 ft to 12.5 ft.
	West		60/60/60/60	57/60/60/60	

Notes:

(1) Signal timings shown indicate Walk plus Flashing Don't Walk for each crosswalk and as AM/MD/PM/Sat MD.

This table has been added to the FSEIS.