

Installation of Elevators at 46th St.-Bliss St. Station Queens November-December 2024



Construction Bulletin

The MTA has initiated the construction of two new street-to-platform elevators, two new street-to-platform stairs, and four mezzanine-to-platform stair replacements. These upgrades provide full ADA accessibility and improve customer experience in the transit system.

ACTIVITY & CLOSURES	SCHEDULE & EQUIPMENT	NIGHT WORK
MPT (Maintenance and Protection of Traffic) mobilization for watermain relocation and main phase of work. Closure of 1 lane on each EB and WB Queens Blvd & closure of parking lot between 45 th & 46 th Street as well as adjacent to pedestrian plaza between 46 th & 47 th Street.	Mobilization for MPT to occur Late October – Early November. Watermain work to occur in Mid November – Early December Main Phase work to occur from end of water main work until end of project. <u>Equipment:</u> Drills, water jet truck, attenuator truck, and excavator.	Yes, potentially to have striping setup on roadway overnight, but closure of lanes 24/7.
Watermain removal on EB Queens Blvd. Excavator to be used. Jackhammers, drills & saws to be used	Mid November – Early December <u>Equipment:</u> Excavator, jackhammers, drills, and saws.	No. Work hours 7AM – 4PM
Micropile installation.	Mid November-Late December <u>Equipment:</u> Micropile rig, excavator, and jackhammers.	No. Work hours 7AM – 4PM