


Greening Our Future



A proposal and funding request to Community Board #3
Environment Committee /Con Ed Sub-Committee

From: The Lower Eastside Girls Club

Contact: Lyn Pentecost, Ph.D.

212-982-1633 X 104

gogirl@girlsclub.org

www.girlsclub.org

THE LOWER EASTSIDE GIRLS CLUB

56 East 1st Street
New York, N.Y. 10003
Phone: (212) 982-1633

www.girlsclub.org



The Lower Eastside Girls Club is dedicated to providing a place where girls ages 8 to 18 can grow, learn, have fun, and develop confidence in themselves and their ability to make a difference in the world. By delivering strong and innovative arts, athletic, cultural, life-skills and career-oriented programming, we provide our girls with the vision to plan -- and the tools to build -- their future.

June 8, 2011

To: Members of the Community Board #3 Con Ed Settlement Fund Committee

From: Lyn Pentecost, Executive Director, The Lower Eastside Girls Club

Re: Request for Settlement Funds to install planted roofs and a green wall system in the new Lower Eastside Girls Club currently under construction on Avenue D between 7th and 8th Street.

Based on feedback from the committee on May 1, 2011, The Girls Club is resubmitting our proposal in modified form, requesting support for the piece of the proposal that will be ready for installation in Spring 2012.

Attached to this request are fully approved architectural plans and analysis including:

- Overall Building Vision and floor plan descriptions
- Architects Work Plan
- 1st Third and 4th floor plans
- Roof Details
- Budgets for Installation and Maintenance
- Installation timeline
- Site Utility Plan and Roof Drainage Details
- Vine wall Blocking Details
- Roofing and Waterproofing Products to be used.

Basic Infrastructure. Architectural design and building/roof construction costs are covered by our capital project funds. The actual 'green' components, which we are requesting funds for, are an add-on to our basic budget.

The cost of installation: labor and materials is: \$213,000

Planted Green Wall: \$42,000

Three year Annual Maintenance is estimated at: \$28,555

Environmental Educator/ Green Organizer for 3 years is estimated at: \$180,000

Ancillary Care/Health Study to be produced by Ryan Nena Health Center: \$30,000

Total Green Roof and support activities: \$493,555

Request to CB#3 Con Ed Committee is: \$255,000

Lyn Pentecost, Ph.D.
Executive Director,
The Lower Eastside Girls Club
www.girlsclub.org



CUTRIGORSE TOOMAN & ALLEN ARCHITECTS, P.C.
 100 West 27th Street
 20th Floor
 New York, NY 10019
 Phone: 212.243.7454 Fax: 212.243.7480 info@ctaarchitects.com

OWNER:
 Lower Eastside Girls Club
 The Housing Company
 200 West 27th Street
 New York, NY 10019

MEP:
 Mechanical Engineers
 505 8th Avenue
 20th Floor
 New York, NY 10018


STRUCTURAL:
 Lower Eastside Girls Club
 The Housing Company
 200 West 27th Street
 New York, NY 10019

CONTRACTORS:
 CCM Construction LLC
 50 West 23rd Street
 New York, NY 10011

NO.	DATE	REVISION
A	12/15/08	BID SET
B	02/23/09	DOB OBJECTIONS RESPONSE
C	03/09/09	95% / BID SET
D	10/30/09	100% / BID SET
E	04/21/10	DOB SUBMISSION
F	05/17/10	CONSULTATION COORDINATION
G	08/15/10	100% CONSTRUCTION SET

- 03/08/11 BULLETIN #4
- 02/08/11 RF #97
- 07/23/10 BULLETIN #3
- 07/23/10 RF #41
- 07/06/10 BULLETIN #1
- 06/03/10 REVISED HOUSE TRAP
- 05/20/09 RF #22
- 05/19/09 RF #6

KEY PLAN




PROJECT:
LOWER EASTSIDE GIRLS CLUB
101 AVENUE D
NEW YORK, NY 10009

DRAWING TITLE:
FIRST FLOOR PLAN

SCALE & SIGNATURE:

DATE: 11 FEBRUARY 2008
 PROJECT NO: 9700521
 DRAWING BY: JH
 CHECKED BY: JH
 DATE: 11 FEBRUARY 2008

A-101.00
 348187



SCALE: 1/8" = 1'-0"

1 1ST FLOOR PLAN

OUTSBOREL TOOHAN & ALLAN ARCHITECTS, P.C.
 151 West 20th Street, 8th Floor, New York, New York, 10011-0810
 Tel: 212.754.7474 Fax: 212.754.7474
 www.outsorel.com

OWNER:
 THE EASTSIDE GIRLS CLUB
 101 Avenue D
 New York, NY 10009

MEP:
 The Eastside Girls Club
 101 Avenue D
 New York, NY 10009

STRUCTURAL:
 The Eastside Girls Club
 101 Avenue D
 New York, NY 10009

EXPERIOR:
 The Eastside Girls Club
 101 Avenue D
 New York, NY 10009

DATE: 12/15/08
 REVISION: 02/23/09
 NO. A

12/15/08 BID SET
 02/23/09 DOB OBJECTIONS RESPONSE
 03/09/09 95% ADO FOR CONSTRUCTION
 04/21/10 DOB SUBMISSION
 05/10/10 CONSTRUCTION SET COORDINATION
 06/15/10 100% CONSTRUCTION SET

NO. B
 NO. C
 NO. D
 NO. E
 NO. F
 NO. G

03/08/11 BULLETIN #4
 12/20/10 REV. WALL SECTION
 07/06/10 BULLETIN #1
 07/06/10 REF #47
 05/19/09 REF #6
 05/20/09 REF #22



KEY PLAN



PROJECT:
LOWER EASTSIDE GIRLS CLUB
 101 AVENUE D
 NEW YORK, NY 10009

DRAWING TITLE:
THIRD FLOOR PLAN

DATE: 11 FEBRUARY 2010
 PROJECT NO: 09006.01
 DRAWING BY: JH
 CHECKED BY: CT
 DWG NO: A-103.00
 SCALE: 1/8" = 1'-0"




SCALE: 1/8" = 1'-0"

1 THIRD FLOOR PLAN

NO.	DATE	REVISION
A	12/15/08	BID SET
B	02/23/09	DOB OBJECTIONS RESPONSE
C	03/09/09	95% / BID SET
D	10/30/09	100% ISSUE FOR CONSTRUCTION
E	04/21/10	DOB SUBMISSION
F	05/10/10	CONSTRUCTION SET COORDINATION
G	06/15/10	100% CONSTRUCTION SET

NO.	DATE	REVISION
1	03/08/11	BULLETIN # 4
2	09/21/10	BULLETIN # 3
3	08/17/10	BULLETIN # 2
4	07/20/10	BULLETIN # 1
5	12/08/09	HPD SUBMISSION
6	05/20/09	RFI # 22
7	05/19/09	RFI # 6




PROJECT:
LOWER EASTSIDE GIRLS CLUB
101 AVENUE D
NEW YORK, NY 10009

DRAWING TITLE:
FOURTH FLOOR PLAN

SEAL & SIGNATURE: [Signature Box]


DATE: 11 FEBRUARY 2009
PROJECT NO.: 97006.01
DRAWING BY: JM
CHECKED BY: CT
DWG NO.: A-104.00

CADD FILE NO.: 97006.01-A-104.00
37 811 R2



1 TYPICAL APARTMENT LAYOUTS - 4TH FLOOR


SCALE: 1/8" = 1'-0"



OUTCOURAGE TOOMAN & ALLEN ARCHITECTS, P.C.
 151 West 28th Street - 8th Floor New York, New York, 10001-6810
 Phone: 212-243-7491 Fax: 212-243-7495 info@outcourage.com
 OWNER: Friends of the Park, Inc. 320 West 57th Street New York, NY 10019
 OWNER/DEVELOPER: Friends of the Park, Inc. 320 West 57th Street New York, NY 10019
 MEP: Strategic Engineering Associates
 Structural: Dimension Engineering
 10th Floor 240 West 57th Street New York, NY 10019
 10th Floor 240 West 57th Street New York, NY 10019
 EXPEDITOR: Dimension Engineering
 40 North Street New York, NY 10011

DATE	REVISION	NO.
12/15/08	BID SET	A
02/23/09	DOB OBJECTIONS RESPONSE	B
03/09/09	95% / BID SET	C
10/20/09	100% ISSUE FOR CONSTRUCTION	D
04/21/10	DOB SUBMISSION	E
05/10/10	CONSTRUCTION SET COORDINATION	F
06/15/10	100% CONSTRUCTION SET	G


KEY PLAN




PROJECT:
LOWER EASTSIDE GIRLS CLUB
101 AVENUE D
NEW YORK, NY 10009

DRAWING TITLE:
ROOF
DETAILS

DATE: 11 FEBRUARY 2008
 PROJECT No: 07006-01
 DRAWING BY: SN
 CHECKED BY: CT
 DWG No: A-700.00
 CAD FILE No: 07006-01-A700.00
 104 of 141



1 SECTION DETAIL AT FENCE AT GREEN ROOF
 Scale: 1/8" = 1'-0" Actual Size



2 SECTION AT ROOF DRAIN
 Scale: 1/8" = 1'-0" Actual Size

DATE	REVISION	NO.
12/15/08	BID SET	A
02/23/09	DOB OBJECTIONS RESPONSE	B
03/09/09	95% / BID SET	C
10/30/09	100% ISSUE FOR CONSTRUCTION	D
04/21/10	DOB SUBMISSION	E
05/10/10	CONSTRUCTION SET COORDINATION	F
06/15/10	100% CONSTRUCTION SET	G

03/08/11 BULLETIN #4
 07/20/10 BULLETIN #1
 06/25/10 REF #46 RESPONSE


KEY PLAN

PROJECT: LOWER EASTSIDE GIRLS CLUB
 101 AVENUE D
 NEW YORK, NY 10009


DRAWING TITLE: GREEN ROOF DETAILS

DATE: 11 FEBRUARY 2009
 PROJECT NO: 97096.01
 DRAWING BY: SBI
 CHECKED BY: SBI
 DWG NO: CT


SCALE: 1/8" = 1'-0"
 A-703.00
 107 # 141




1 SECTION @PAVER TO GREEN ROOF TRANSITION
 Scale: Half Actual Size




2 SECTION @ VENT PENETRATION AT GREEN ROOF
 Scale: Half Actual Size



3 SECTION @ DRAIN AT GREEN ROOF
 Scale: Half Actual Size



4 SECTION @ DOOR SILL @ TOWER BULKHEAD
 Scale: Half Actual Size



HYDRAULIC CALCULATIONS (AVENUE "D")

- SITE INFORMATION:**

TOTAL AREA OF SITE: 15,152 SQ.FT./43,560 = 0.348 ACRES
 TRIBUTARY AREA: 100' OF SITE FROM AVENUE "D"
 A(TR) = 10,511 SQ.FT = 0.241 ACRES
 MAIN ROOFED AREA: 5,763 SQ.FT./43,560 = 0.1323 ACRES
 4TH FLOOR ROOFED AREA: 3,074 SQ.FT./43,560 = 0.0706 ACRES
 AUX. AREA: 985 SQ.FT./43,560 = 0.0226 ACRES
- SANITARY DRAINAGE:**

TOTAL AREA OF SITE: 15,152 SQ.FT. = 0.348 ACRES
 TRIBUTARY AREA OF SITE: 10,745 SQ.FT = 0.247 ACRES
 ZONING : R-7
 POPULATION DENSITY = 230 PEOPLE PER ACRE
 SANITARY FLOW FROM SITE:

$$Q = \frac{\text{POPULATION DENSITY} \times A(\text{TR}) \times 150 \times 4}{7.48 \times 86,400}$$

$$Q = \frac{230 \times 0.247 \times 150 \times 4}{646,272}$$

$$Q = 0.0527 \text{ CFS PEAK SANITARY FLOW}$$

INFILTRATION = 0.002421 x 0.247 = 0.0006 CFS

TOTAL SANITARY FLOOR:
 Q(MAX.SAN.) = 0.0527 + 0.0006 = 0.0533 CFS
- ALLOWABLE STORM FLOW INTO COMBINED SEWER UNDER AVENUE "D":**
 (-30.0 FEET FROM AVENUE "D" 42"x28" COMBINED SEWER TO PROPERTY LINE)
 Q(ALL) = C x I x A(TR)
 WHERE:
 C = 0.6
 I = 5.95 INCHES PER HOUR
 A(TR) = TRIBUTARY AREA IN ACRES
 Q(ALL) = 0.6 x 5.95 x 0.241 = 0.88 CFS
- DEVELOPED STORM FLOW GENERATED FROM SITE:**

$$Q(\text{DEV}) = Q(\text{MAIN RF}) + Q(\text{4TH FL. RF}) + Q(\text{AUX. AREA})$$

$$Q(\text{MAIN RF}) = 1 \times 5.95 \times 0.1323 = 0.7872 \text{ CFS (DETAINED BY CONTROLLED FLOW DEVICES)}$$

$$Q(\text{4TH FL RF}) = 1 \times 5.95 \times 0.0706 = 0.4201 \text{ CFS (DETAINED BY CONTROLLED FLOW DEVICES)}$$

$$Q(\text{AUX.}) = 1 \times 5.95 \times 0.0226 = 0.1345 \text{ CFS (DISCHARGED TO SEWER)}$$

$$Q(\text{DEV}) = 0.7872 + 0.4201 + 0.1345 = 1.3418 \text{ CFS}$$
- RETENTION SYSTEM CALCULATIONS (CONTROLLED FLOW ROOF DRAINS)**

(MAIN ROOF SYSTEM)
 TOTAL ROOFED AREA: MAIN ROOF = 5,763 SQ.FT.; LOWER ROOF = 3,074 SQ.FT.
 WITH (4) ROOF DRAINS FOR MAIN ROOF = 5,763/4 = 1,441 SQ.FT. PER DRAIN
 WITH (2) ROOF DRAINS FOR LOWER ROOF = 3,074/2 = 1,537 SQ.FT. PER DRAIN
 10 YEARS STORM AND 24 HOURS MAXIMUM RETENTION ALLOWED
 (1) "JOSAM" (SERIES 28600 - AE) WITH THREADED ADJUSTABLE EXTENSION TO BE UTILIZED AND ALLOW 30 GPM FOR 1,441 & 1,537 SQ.FT FOR MAIN AND LOWER ROOF IN LESS THAN 24 HOURS. (10) DRAINS TO BE UTILIZED AT MAIN ROOF STORM FLOW FOR TOTAL OF 180 GPM.
 TOTAL STORM FLOW TO BE UTILIZED AT ROOFED AREA - 180 GPM.

TOTAL CALCULATED RESTRICTED FLOW:
 Q(RES) = 180 GPM x 1/60(MIN./HR) x 1/7.48(CU.FT./GALLON)
 Q(RES) = 180/(60 x 7.48) = 180/448.8 = 0.401 CFS

CONCLUSION:
 DEVELOPED STORM FLOW FROM SOUTH TRIBUTARY AREA (TO AVENUE "D" SEWER) OF 1.3418 CFS WILL BE RESTRICTED TO THE ALLOWABLE STORM FLOW FROM THE SITE OF 0.88 CFS OR LESS BY MEAN OF ROOF DETENTION AND CONTROLLED FLOW DEVICES. PROVIDE (6) DRAINS FACTORY SET TO 30 GPM EACH MODEL "FLO-SET" (SERIES 28600-AE) BY JOSAM.
- PROPOSED STORM FLOW TO SEWER:**

$$Q(\text{PROP. STORM TO SEWER}) = Q(\text{RES}) + Q(\text{AUX.})$$

$$Q(\text{PROP. STORM TO SEWER}) = 0.401 + 0.1345 = 0.5355 \text{ CFS}$$

$$Q(\text{STORM})(0.5355) < Q(\text{ALL})(0.88) \text{ THEREFORE IS OK}$$
- TOTAL COMBINED FLOW :**

$$Q(\text{COMB.}) = Q(\text{STORM}) + Q(\text{MAX. SAN.}) = 0.5355 + 0.0533 = 0.5888 \text{ CFS}$$

HYDRAULIC CALCULATIONS (EAST 7TH STREET)

- SITE INFORMATION:**

TOTAL AREA OF SITE: 15,152 SQ.FT./43,560 = 0.348 ACRES
 TRIBUTARY AREA: 100' OF SITE FROM EAST 7TH STREET
 A(TR) = 4,650 SQ. FT./43,560 = 0.1067 ACRES
 3RD FLOOR ROOFED AREA: 3,809 SQ.FT./43,560 = 0.0874 ACRES
 PAVED AREA = 1,521 SQ.FT./43,560 = 0.0349 ACRES
- SANITARY DRAINAGE:**

TOTAL AREA OF SITE: 15,152 SQ.FT. = 0.348 ACRES
 TRIBUTARY AREA OF SITE: 4,650 SQ. FT. = 0.1067 ACRES
 ZONING : R-7
 POPULATION DENSITY = 230 PEOPLE PER ACRE
 SANITARY FLOW FROM SITE:

$$Q = \frac{\text{POPULATION DENSITY} \times A(\text{TR}) \times 150 \times 4}{7.48 \times 86,400}$$

$$Q = \frac{230 \times 0.1067 \times 150 \times 4}{646,272}$$

$$Q = 0.0228 \text{ CFS PEAK SANITARY FLOW}$$

INFILTRATION = 0.00242 x 0.1067 = 0.0002 CFS

TOTAL SANITARY FLOOR:
 Q(MAX.SAN.) = 0.0228 + 0.0002 = 0.023 CFS
- ALLOWABLE STORM FLOW INTO COMBINED SEWER UNDER W 127th STREET:**
 (-23.0 FEET FROM EAST 7TH STREET 36"x24" COMBINED SEWER TO PROPERTY LINE)
 Q(ALL) = C x I x A(TR)
 WHERE:
 C = 0.6
 I = 5.95 INCHES PER HOUR
 A(TR) = TRIBUTARY AREA IN ACRES
 Q(ALL) = 0.6 x 5.95 x 0.1067 = 0.381 CFS
- DEVELOPED STORM FLOW GENERATED FROM SITE:**

$$Q(\text{DEV}) = Q(\text{3RD FL RF}) + Q(\text{PAVED})$$

$$Q(\text{3RD FL RF}) = 1 \times 5.95 \times 0.0874 = 0.5176 \text{ CFS (DETAINED BY CONTROLLED FLOW DEVICES)}$$

$$Q(\text{PAVED}) = 0.85 \times 5.95 \times 0.0349 = 0.1765 \text{ CFS (DISCHARGED TO SEWER)}$$

$$Q(\text{DEV}) = 0.5176 + 0.1765 = 0.6941 \text{ CFS}$$
- RETENTION SYSTEM CALCULATIONS (CONTROLLED FLOW ROOF DRAINS)**

(MAIN ROOF SYSTEM)
 TOTAL ROOFED AREA: 3RD FLOOR ROOF = 3,809 SQ.FT.
 WITH (3) ROOF DRAINS FOR MAIN ROOF = 3,809/3 = 1,270 SQ.FT. PER DRAIN
 10 YEARS STORM AND 24 HOURS MAXIMUM RETENTION ALLOWED
 (1) "JOSAM" (SERIES 28600 - AE) WITH THREADED ADJUSTABLE EXTENSION TO BE UTILIZED AND ALLOW 24 GPM FOR 1,270 SQ.FT. FOR MAIN ROOF IN LESS THAN 24 HOURS.
 (3) DRAINS TO BE UTILIZED AT MAIN ROOF STORM FLOW FOR TOTAL OF 72 GPM;
 TOTAL STORM FLOW TO BE UTILIZED AT ROOFED AREA - 72 GPM.

TOTAL CALCULATED RESTRICTED FLOW:
 Q(RES) = 72 GPM x 1/60(MIN./HR) x 1/7.48(CU.FT./GALLON)
 Q(RES) = 72/(60 x 7.48) = 72/448.8 = 0.167 CFS

CONCLUSION:
 DEVELOPED STORM FLOW FROM SOUTH TRIBUTARY AREA (7TH STREET SEWER) OF 0.6941 CFS WILL BE RESTRICTED TO THE ALLOWABLE STORM FLOW FROM THE SITE OF 0.381 CFS OR LESS BY MEAN OF ROOF DETENTION AND CONTROLLED FLOW DEVICES. PROVIDE (3) DRAINS FACTORY SET TO 24 GPM EACH MODEL "FLO-SET" (SERIES 28600-AE) BY JOSAM.
- PROPOSED STORM FLOW TO SEWER:**

$$Q(\text{PROP. STORM TO SEWER}) = Q(\text{RES}) + Q(\text{PAVED})$$


$$Q(\text{PROP. STORM TO SEWER}) = 0.167 + 0.1765 = 0.3435 \text{ CFS}$$

$$Q(\text{STORM})(0.3435) < Q(\text{ALL})(0.381) \text{ THEREFORE IS OK}$$
- TOTAL COMBINED FLOW :**

$$Q(\text{COMB.}) = Q(\text{STORM}) + Q(\text{MAX. SAN.}) = 0.3435 + 0.023 = 0.3665 \text{ CFS}$$



06/03/10 - RE-ISSUED TO DEP FOR APPROVAL
 04/23/10 - RE-ISSUED TO DEP FOR APPROVAL
 01/22/09 - RE-ISSUED TO DEP FOR APPROVAL




SITE UTILITY PLAN
SCALE: 1" = 30'-0"



LOCATION:
101 AVENUE "D",
NEW YORK, NY 10009
BLOCK: 377
LOT: 42
ZONE: R7-2
MAP: 12C
BUILDING DEP. #: 120026426

OWNER:
MS. KRISTIN NEIL, REP. OF THE DERMOT
COMPANY, INC.
320 WEST 57TH STREET, 5TH FLOOR
NEW YORK, NY 10019
TEL: (212) 262-1220



-10 EXTENSION 4" STD.
● CONFORMS WITH ASTM-C564.
▲ WITH CLAMP RING 2-1/4" MIN., 4-1/4" MAX.

ROOF DRAIN WITH THREADED
ADJUSTABLE EXTENTION
MODEL "FLO-SET"
(series 28600-AE) BY JOSAM.
CONTROLLED ROOF DRAIN DETAIL

06/03/10 - RE-ISSUED TO DEP FOR APPROVAL
04/23/10 - RE-ISSUED TO DEP FOR APPROVAL
01/22/09 - RE-ISSUED TO DEP FOR APPROVAL

ETTINGER ENGINEERING ASSOCIATES
605 EIGHTH AVENUE, NEW YORK, NY 10018
PH. (212) 244-2410 FAX (212) 643-1606
email: eea@ettingerengineering.com
www.ettingerengineering.com

SITE UTILITY PLAN
CONTROLLED ROOF DRAIN DETAIL
101 AVENUE "D"
NEW YORK, NY 10009

JOB NO: 1017
DATE: 12/18/08
SCALE: 1"=30'-0"
SU-101.1

BLOCK: 377, LOT: 42



LOWER EASTSIDE GIRLS CLUB





Starting with an empty lot
on Avenue D, we will build...



DERMOT

LOWER EASTSIDE GIRLS CLUB



DERMOT

LOWER EASTSIDE GIRLS CLUB



What's in the building?

- 30,000 sq ft community center
- 60,000 sq ft residential tower
- Mixed income housing - 50% market rate, 50% middle and low income






Facing the housing projects
and East River Park

The Lower Eastside Girls Club of New York Center for Community




Fourth Floor
Green Roof

Third Floor
Environmental Center
Green Roof
Amphitheater
Book Arts
Digital Archive



Art Studio
Construction Shop
Building Mechanical
Dome Access

Second Floor
Girls Club Offices
Leadership Center
Radio Lab
Photo/Video Center




Planetarium and Lobby
Dome Production Center
IT Center
Server Room
Incubator Offices

First Floor
Cafe, Kitchen
Courtyard



Girls Club Entrance
Gallery
Snack Bar
Multipurpose Room

F. LOCATION PLAN: (Attachment "F")



06/02/10 - RE-ISSUED TO DEP FOR APPROVAL
 04/23/10 - RE-ISSUED TO DEP FOR APPROVAL
 01/22/09 - RE-ISSUED TO DEP FOR APPROVAL



ETTINGER ENGINEERING ASSOCIATES

505 EIGHTH AVENUE, NEW YORK, NY 10018
 PH: (212) 244-2410 FAX (212) 643-1406

Drawing Title:

SITE UTILITY PLAN

Project:

**101 AVENUE "D"
 NEW YORK, NY 10009**

BLOCK: 377, LOT: 42

Job No.: 1017


Date: 12/18/08

Scale: 1"=30'-0"

Dwg. No.:


SU-102

OPTION A (PLAN)




NOTE: MAXIMUM WALL HEIGHT IS 15'-0".

OPTION B



PLAN



ELEVATION

NOTE: MAXIMUM WALL HEIGHT IS 15'-0".

DESIMONE
 18 WEST 18TH STREET, 10TH FLOOR
 NEW YORK, NEW YORK 10011
 T. 212.532.2211 F. 212.481.6108

TITLE: COURTYARD VINEWALL OPTIONS					
PROJECT: LOWER EASTSIDE GIRLS CLUB					
JOB #:	5036	SCALE:	1"=1'-0"	DATE:	04/11/2011
CHECKED:	JJ	DRAWN:	SHC	DWG. NO.	

SK-017

Town & Gardens Ltd.

328 East 25th Street (Grnd Fl)
New York, NY 10010

Analysis

April 23, 2011

Proposal # 00007869

Submitted To: Dave Pentecost

Project: Lower East Side Girls Club
101 Ave D
New York, NY 10009

Scope

We propose to furnish the following scope of work to complete the above mentioned project:

Design Development

May through August 2011

Description

Design, layout and material reviews

Budgeting, samples, site reviews

Coordination, project management, meetings, LEEDS support

Estimated budget: \$5,800.00

EFVM Testing

EFVM Testing, Waterproof leak detection testing system to be installed at roof perimeter to detect any breaches in roof membrane on both levels.

November 2011

Description

EFVM Testing budget

Estimated budget: \$7,500.00

4" Extensive Built System 4th floor

February through April 2012

Description

Greenroof-Root Barrier 1 sf
Drain Away DA 50 Roll 208 sf
Truck and parking
Install root barrier, drainage and edging
Install soils
Debris and carting
Freight - extensive mixes
GeoEdge 3.5" x 4.5" Mill Finish
Greenroof-Growth Medium 1 cy bulk bags
Freight - pavers partial
Greenroof-Sedum Plugs
Plant sedum and perennial plugs and water in
Crane, set up and permits
Cleanup and apply tackifier
Freight plants
Freight root barrier
Freight drainage
Greenroof-Tackifier 1 sf
Hanover Paver, Custom Matrix 23.5" x 23.5" x 2"
Hanover Pedestal, 5/8" thick
Greenroof-Drain Inspection Boxes
Hanover Levelling Plates 1/16" & 1/8"
Greenroof-Perennial Plugs

Estimated budget: \$62,500.00

Environmental Center beds

Layout and construct garden beds

January-February 2012

Description

Synthetic lumber for planter walls and framing
Frame, level and construct beds
Deliver and layout materials
Truck and parking
Drain Away DA 50 Roll 208 sf ea
Greenroof-Root Barrier Rufco 2000B
Greenroof-Polymesh 1 sf
Filter fabric
Freight materials
Cleanup and remove debris
Miscellaneous Materials

Estimated budget: \$19,100.00

Environmental beds preparation

Prepare all beds with drainage and soils for plantings.

March 2012

Description

Plant Tone 40lb bag
Lime, pulverized by the 50 lb bag
Equipment
Move and install soils
Soil Bulk 1 cy yds
Crane, set up and permits, partial
Freight soils
Cleanup and wash down terrace

Estimated budget: \$7,300.00

Environmental beds plantings

April 2012

Description

(1) Betula nigra 'Heritage' 15 Gal
(20) Azaleas, Evergreen 5 Gal
(12) Spiraea Ogon 3 Gal
(24) Sedum spectabile 'Autumn Joy' 1 Gal
(24) Hosta - 1 Gal
(8) Hydrangea macrophylla 'Endless Summer' - 3 Gal
(2) Juniperus - torulosa 3-4'
(24) Fern (generic) 1 Gal
(18) Euonymus Fortunei 'Emerald Gaiety' 3 Gal
(18) Hakonechloa Macra 1 Gal
(18) Heuchera micrantha 'Plum Pudding' 1 Gal
Freight plants
Deliver and layout plantings
Install all plantings, mulch and water in
Hamptons Estate Mulch 2cf bag
Cleanup and wash down pavers
Truck and parking

Estimated budget: \$12,150.00

7th Street beds

Layout and construct garden beds.

January -February 2012

Description

Synthetic lumber for planter walls and framing
Frame, level and construct beds
Deliver and layout materials
Truck and parking
Drain Away DA 50 Roll 208 sf ea
Greenroof-Root Barrier Rufco 2000B
Greenroof-Polymesh 1 sf
Filter fabric
Freight materials
Cleanup and remove debris
Miscellaneous Materials

Estimated budget: \$21,900.00

7th Street beds preparation

Prepare all beds with drainage and soils for plantings.

March 2012

Description

Plant Tone 40lb bags
Lime, pulverized by the 50 lb bag
Equipment
Move and install soils
Soil Bulk 1 cy yds
Crane, set up and permits, partial .25
Freight soils
Cleanup and remove debris

Estimated budget: \$8,450.00

7th Street plantings

April 2012

Description

(18) Azaleas, Evergreen 5 Gal
(12) Spiraea Ogon 3 Gal
(18) Sedum spectabile 'Autumn Joy' 1 Gal
(24) Hosta (generic) - 1 Gal
(8) Hydrangea macrophylla 'Endless Summer' - 3 Gal
(18) Hakonechloa Macra 1 Gal
(18) Heuchera micrantha 'Plum Pudding' 1 Gal
Freight plants
Deliver and layout plantings
Install all plantings, mulch and water in
Hamptons Estate Mulch 2cf bag
Cleanup and wash down pavers
Truck and parking
(3) Buddleia davidii 5 Gal
(3) Buddleia "Lochinch" 3 Gal.
(3) Caryopteris Clan. 'Dark Knight' 3 Gal
(3) Caryopteris Clan. 'Sunshine Blue' 3 Gal
(6) Potentilla 2 gal
(8) Salvia nemerosa 'Blue Hill' 1 Gal
(12) Nepeta faassenii 'Blue Wonder' 1 Gal
(3) Potentilla 2 gal
(1) Prunus cerasifera (Purple Plum) 3 Gal
(1) Prunus serr. Kwanzan 1 1/2 --2 "
(1) Acer palmatum 'Bloodgood' 5-6'
(3) Rosa 'The Fairy' 2 Gal
(3) Santolina Rosmarinifolia 1 Gal
(12) Thyme - English 4.5"
(36) Herbs - Assorted

Estimated budget: \$14,500.00

Irrigation System

Install a fully automated drip irrigation system with master valve assembly, controller and backflow prevention device. Irrigation system to supply and feed all plantings and zone for green roof plantings beds. Irrigation lines to run along terrace perimeter and under pavers where appropriate.

April 2012

Description

Poly Pipe 1/2
Outlet Cover
Netafim drip line
Netafim bed basics Assemblies
Van & Parking
Rosin Paper Roll
Irrigation 1st Zone assembly W/Master Valve
Irrigation Additional Zones
Irrigation Assitant
Irrigation/Lighting Tech
Clock-Toro 4 station electronic w/ battery back up
Manifold #1Assembly

Estimated budget: \$11,000.00

Lighting

Lighting Allowance for LED low voltage lighting of exterior terrace spaces.
May 2012

Description

Lighting Allowance

Estimated budget: \$6,000.00

Benches

Supply and deliver and install Teak furniture. Benches include (5) individual straight benches and (2) curved benches. (1) table and (4) chairs.

June 2012

Description

(7) Teak Benches (1) table and (4) chairs
Freight
Move through building, unpack and layout

Estimated budget: \$18,500.00

Railings on parapets

Raise parapet heights at locations with built up beds.

December 2011

Description

Install metal railings to extend parapets at beds

Estimated budget: \$19,200.00

Total recommended budget: \$213,900.00

Town & Gardens Ltd.

328 East 25th Street (Grnd Fl)
New York, NY 10010

Analysis

April 28, 2011

Proposal # 00007888

Submitted To: David Pentecost

Project: Lower Eastside Girls Club
101 Avenue D
New York, NY 10009

Scope

We propose to furnish the following scope of work to complete the above mentioned project:

First year maintenance

Description

Crew labor, weed, prune, train, deadhead , cleanup
Hamptons Estate Mulch 3 cf bag
Van and parking
PlantTone 50lb bags
10-6-4 Fertilizer w/Iron, 50 lb bag
Horticultural Oil container
Horticultural Soap container
Wilt Pruf 1 gal
Crew labor mulching, fertilize
Debris and carting
Site reviews
Irrigation turn on (included)
Irrigation seasonal adjustments, cleaning filters
Irrigation draining and winterize
Check and clean drains

Estimated budget: \$8,365.00

Second Year Maintenance

Description

Crew labor, weed, prune, train, deadhead , cleanup
Hamptons Estate Mulch 3 cf bag
Van and parking
PlantTone 50lb bags
10-6-4 Fertilizer w/Iron, 50 lb bag
Horticultural Oil container
Horticultural Soap container
Wilt Pruf 1 gal
Crew labor mulching, fertilize
Debris and carting
Site reviews
Irrigation turn on
Irrigation seasonal adjustments, cleaning filters
Irrigation draining and winterize
Check and clean drains

Estimated budget: \$8,990.00

Third Year Maintenance

Description

Crew labor, weed, prune, train, deadhead , cleanup
Hamptons Estate Mulch 3 cf bag
Van and parking
PlantTone 50lb bags
10-6-4 Fertilizer w/Iron, 50 lb bag
Horticultural Oil container
Horticultural Soap container
Wilt Pruf 1 gal
Crew labor mulching, fertilize
Debris and carting
Site reviews
Irrigation turn on
Irrigation seasonal adjustments, cleaning filters
Irrigation draining and winterize
Check and clean drains

Estimated budget: \$9,200.00

Total recommended budget: \$26,555.00

SECTION 02900 - PRE-CULTIVATED GREEN ROOF OVERBURDEN SYSTEM

PART 1 GENERAL

1.01 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.02 DESCRIPTION OF WORK

A. Work of this Section includes all labor, materials, equipment and services necessary to complete the green roof installation as specified herein.

1. Drainage Mat Application over Membrane System
2. Root Barrier Application
3. Water Retention Fleece Application
4. Pre-cultivated Vegetation Mat Application
5. Overburden Installation over Green Roof Membrane

1.03 RELATED SECTIONS

- A. Section 03300 - Concrete
- B. Section 07520 - Modified Bitumen Roofing
- C. Section 02780 - Concrete Pavers

1.04 REFERENCE STANDARDS

A. References in these specifications to standards, test methods and codes, are implied to mean the latest edition of each such standard adopted. The following is an abbreviated list of associations, institutions, and societies that may be used as references throughout these specifications.

1. ASTM American Society for Testing and Materials, Philadelphia, PA
2. OSHA Occupational Safety and Health Administration, Washington, DC
3. SMACNA Sheet Metal and Air Conditioning Contractors National Association, Chantilly, VA
4. UL Underwriters Laboratories, Northbrook, IL

1.05 SUBMITTALS

A. Cross section of the green roof system detailing the components comprising the proposed pre-cultivated green roof overburden system.

B. Letter from the proposed primary roofing/waterproofing manufacturer confirming that the bidder is an acceptable Contractor authorized to install the proposed system.

C. Letter from the primary roofing/waterproofing manufacturer stating that the proposed application will comply with the manufacturer's requirements in order to qualify the project for the specified guarantee.

D. Suppliers printed recommendations for proper maintenance of the specified pre-cultivated green roof system.

1.06 QUALITY ASSURANCE

A. Scope of Work: The work to be performed under this specification shall include, but is not limited to, the following: attend necessary job meetings and furnish competent and full time supervision, experienced mechanics, all materials, tools, and equipment necessary to complete, in an acceptable manner, the green roof overburden system in accordance with this specification. Comply with the latest written application instructions of the supplier of the green roof overburden system.

B. Acceptable Products: Primary green roof overburden products shall be supplied by a single supplier.

C. Acceptable Contractor: Contractor shall be trained by the supplier of the green roof overburden system.

D. Local Regulations: Conform to regulations of public agencies, including any specific requirements of the city and/or state of jurisdiction.

E. Manufacturer Requirements: The primary supplier of the green roof overburden system products shall provide trained company personnel to attend necessary job meetings, perform periodic inspections as necessary, and conduct a final inspection upon successful completion of the project.

1.07 PRODUCT DELIVERY STORAGE AND HANDLING

A. Pre-Cultivated Plants: Deliver pre-cultivated plant material in such a manner as to preserve the quality of the plants protecting the vegetation mats from high/low temperature or wind damage. For transport times less than one day, a closed or open trailer may be used for delivery from the cultivation site to job site. For longer duration transport times, vegetation mats must be delivered in a climate controlled trailer. Upon arrival, the mats must be immediately off-loaded, plastic wrap removed, and the mats installed within 12 hours. If timely installation is not achievable, a holding area shall be reserved to unroll and store the mats until transport of the mats to the roof-top for immediate installation.

B. Damaged Material: Any materials that are found to be damaged or stored in any manner other than stated above will be rejected, removed and replaced at the Contractor's expense.

1.08 PROJECT/SITE CONDITIONS

A. Requirements Prior to Job Start

1. Notification: Give a minimum of 5 days notice to the Owner and manufacturer prior to commencing any work and notify both parties on a daily basis of any change in work schedule.

2. Permits: Obtain all permits required by local agencies and pay all fees which may be required for the performance of the work.

3. Safety: Familiarize every member of the application crew with all fire and safety regulations recommended by OSHA, NRCA and other industry or local governmental groups.

B. Protection Requirements

1. General: Install green roof overburden components in such a manner as to not damage or disturb any previously installed waterproofing membrane or roofing waterproofing membrane accessory components.

2. Limited Access: Prevent access by the public to materials, tools and equipment during the course of the project.

3. Debris Removal: Remove all debris daily from the project site and take to a legal dumping area authorized to receive such materials.

1.09 GUARANTY

A. Vegetation Guarantee Addendum: A addendum to the guarantee specified in Specification Section **07520**- Modified Bitumen Green Roof offering two years of coverage. The guarantee shall include oversight, maintenance, supervision and supply of additional plant or substrate materials by the supplier of the green roof system to ensure that the green system achieves and sustains at least 90% vegetated coverage after the first full year.

1. Two-year Siplast/Xero Flor Joint Green Roof Guarantee Addendum

PART 2 - PRODUCTS

2.01 PRE-CULTIVATED GREEN ROOF SYSTEM ASSEMBLY/PRODUCTS

A. Root Barrier

1. A 20 mil low-density polyethylene sheet for use over the roof membrane and below the water retention fleece.

a. XF112 Root Barrier by Xero Flor, Durham, NC

B. Drainage Mat

1. A layer of flexible, non-woven, entangled polymeric filaments with a perforated, geotextile filter-fabric bonded to the top side.

a. XF108H Drainage Mat by Xero Flor, Durham, NC

C. Water Retention Fleece

1. A fabric produced from a blend of recycled, synthetic fibers with a saturated weight of not more than 1.5 lbs/ft² (7.4 kg/m²).

a. XF159 Water-Retention Fleece by Xero Flor, Durham, NC

D. Growing Medium

1. A propriety mixture of lightweight, mineral based materials, including porous stone or brick aggregate, washed sand, and organic matter derived from composted biosolids, leaf and lawn litter, and/or poultry manure compost.

a. Xero Terr Growing Medium by Xero Flor, Durham, NC

E. Pre-cultivated Vegetation Mat

1. A textile-based vegetation carrier of lightweight fleece sewn to PA/PP entanglements bonded to geotextile fabric, filled with a growing medium, and pre-cultivated with an even layer of low-profile, drought-tolerant vegetation.

a. XF301 Pre-cultivated Vegetation Mat by Xero Flor, Durham, NC

F. Paver System: Refer to Section 02780.

G. River-Rock Ballast: River washed rock used as ballast shall meet the ASTM D 448 #57 requirements. Diameter of the rock particles shall maintain a nominal 3/4 inch to a maximum 1-1/2 inch range.

PART 3 - EXECUTION

3.01 PREPARATION

A. Root Barrier: Loose-lay over the entire area and lap sides and ends a minimum of 10 inches" (25 cm). Stagger end laps a minimum of 36 inches.

B. Drainage Mat: Install the water retention fabric with the nylon entanglement facing down and geotextile fabric surface facing up. Overlap the 4 inch extension of geotextile material over the preceding, previously applied course of drainage mat. Stagger end laps a minimum of 36 inches.

C. Water-retention Fleece: Install the water retention fleece on top of the drainage layer. Tightly abut pieces of water retention fleece against previously applied courses. Do not overlap. Stagger end joints a minimum of 36 inches.

D. Xero Terr Growing Medium: Evenly distribute 1 inch of growing medium over the water retention fleece layer. Thoroughly wet the growing medium and underlying water-retention fleece.

E. Pre-cultivated Vegetation Mat

1. Immediately prior to installation of the vegetation mat layer, saturate the growing medium, underlying water-retention. Failure to saturate green roof system base layers will result in severe stress to the root system and harm to the mat vegetation.

2. Overlay the saturated growing medium with the pre-cultivated vegetation mats, exposing the 4 inch (10 cm) strip of exposed lightweight fleece affixed to the mat underside to be overlapped by the adjacent vegetation mat. Stagger each row of adjacent vegetation mats by half the length of an individual mat to avoid alignment of end seams across rows. Upon complete installation of the mats, redistribute and/or supplement the growing medium to ensure even coverage across the

carrier mat. In areas or along edges where growing medium was lost or damaged during transport and handling, add growing medium to support vegetative coverage.

3. After installation is complete, immediately and thoroughly water the assembled vegetation mat system to assist with settling of individual components and to support recovery and establishment of the system vegetation.

F. Ballast: Distribute the river-rock ballast evenly over the drainage mat at a minimum rate of 1000lb/sq.

G. Pavers: Install the pavers following the instructions and requirements of the paver manufacturer and as indicated on the perimeter details.

3.02 FIELD QUALITY CONTROL AND INSPECTIONS

A. Site Condition: Leave all areas around job site free of debris, equipment, and related items after completion of job.

B. Notification Of Completion: Notify the manufacturer by means of manufacturer's printed Notification of Completion form of job completion in order to schedule a final inspection date.

C. Final Inspection

1. Post-Installation Meeting: Hold a meeting at the completion of the project, attended by all parties that were present at the pre-job conference. A punch list of items required for completion shall be compiled by the Contractor and the manufacturer's representative. Complete, sign, and mail the punch list form to the manufacturer's headquarters.

D. Issuance Of The Guarantee: Complete all post installation procedures and meet the manufacturer's final endorsement for issuance of the specified guarantee.

END OF SECTION 02900

Green Roof Valuation: A Probabilistic Economic Analysis of Environmental Benefits

Corrie Clark, Peter Adriaens, F. Brian Talbot*

University of Michigan

adriaens@umich.edu

Green (vegetated) roofs have gained global acceptance as a technology that has the potential to help mitigate the multifaceted, complex environmental problems of urban centers. While policies that encourage green roofs exist at the local and regional level, installation costs remain at a premium and deter investment in this technology. The objective of this paper is to quantitatively integrate the range of stormwater, energy, and air pollution benefits of green roofs into an economic model that captures both the building-specific and city scale implementation. Currently, green roofs are mainly valued based on increasing the roof longevity and their ability to reduce stormwater runoff, with occasional consideration of reducing building energy consumption. Proper valuation of these benefits can reduce the present value of a green roof if investors look beyond the upfront capital costs. In this paper a net present value (NPV) analysis comparing a conventional roof system to a green roof system demonstrates that at the end of the

green roof's lifetime the NPV for the green roof is less than the NPV for the conventional roof. Increasing evidence suggests that green roofs may play a significant role in urban air quality improvement. For example, public health benefits per metric ton of NO_x reduction are estimated to range from \$1683 to \$6383. These benefits were included in this study, and results indicate that this translates to an annual benefit of \$895 to \$3392 for a 2,000 square meter vegetated roof. Improved air quality leads to a mean NPV for the green roof that is 25% to 29% less than the mean conventional roof NPV. This study also assessed large-scale roof greening within the Detroit and Chicago metropolitan areas. Greening ten percent of metropolitan roofs would result in 1.53E4 to 1.85E4 Mg of NO_x reduction (from direct and indirect uptake) reducing annual public health costs between \$25.8 million to \$97.7 million in Detroit and between \$31 million to \$118 million in Chicago. Through innovative policies, the inclusion of air pollution mitigation and the reduction of municipal stormwater infrastructure costs in economic valuation of environmental benefits of green roofs can reduce the cost gap that currently hinders US investment in green roof technology.

Introduction

Continual growth and horizontal expansion of cities and surrounding areas in the United States of America (USA) increase stress on private and public utilities. The annual rate of urbanization in the USA is expected to be 1.19 percent between 2000 and 2030 exceeding the global urbanization rate of 1.8 percent and annual population growth estimates of 1 percent (1). Growth creates a demand for energy, water and sewer services, and transportation. To meet the increased energy demand, more than 150 new coal-fired power plants are proposed in the USA alone (2). Converting green space into neighborhoods, shopping malls, and other developments increases

stress to storm sewer systems. For example, forty-two percent of projected sewer infrastructure costs between 2001 and 2030 in Southeast Michigan is attributable to new sewer construction (3). New road infrastructure leads to increased vehicle emissions, and along with parking lots and rooftops, roads contribute to elevated urban surface temperatures by reducing a city's albedo. Increased urban temperatures, in combination with emissions from the electric utility industry, impact local and regional air quality (4). As growth is inevitable, a multi-faceted and scalable solution is needed to temper the environmental impacts of growing cities. Increasingly, developers, architects, and city planners recognize that green (vegetated) roofs may be part of the solution. Composed of a drainage layer, a solid matrix "soil" layer, and vegetation (5), green roofs increase the insular capabilities of roofs and restore the water balance between evapotranspiration and runoff (6).

There are two main parameters that influence the solar radiation reaching the roof deck, leaf foliage and soil media. The more extensive the foliage development of a particular plant, the more the heat flux through the roof decreases (7, 8, 9) and the greater decrease in surface temperatures (10). Thick soil layers insulate during summer months while thin layers result in little cooling benefit (9). The observed reduction in heat flow tends to be greater in the summer months (70-90%) than in the winter (10-30%) (11). Secondary parameters include relative humidity and wind speed. A dry environment and to a lesser extent wind speed increase the rate of evapotranspiration aiding the absorbance of solar radiation by plants (8, 9).

Green roofs can reduce the demand on sewer systems by retaining as much as fifty to seventy percent of annual rainfall precipitation depending on regional climate (12, 13). Rainfall retention is also affected by slope and substrate depth: in general, the flatter the roof, the greater the

retention and peak flow reduction (13, 14). Effects due to substrate depth are less transparent. While increased thickness provides increased storage capacity, moisture is also retained for a longer period of time limiting the effectiveness of retention for subsequent storm events.

Stormwater modeling has shown the potential benefits for large-scale roof-greening projects. For Washington, DC, greening 2 million square meters of rooftops could store over 1.6 million cubic meters annually (1.7% of citywide runoff); the volume captured would reduce the total number of combined sewer overflows (CSOs) by fifteen percent (15).

Green roofs exhibit the capacity to reduce pollution in urban environments. As elevated temperatures increase the production of ground level ozone (16), the reduction of the heat island effect through large-scale greening of roofs may indirectly reduce ozone and smog generation (17). The cooling of urban areas further reduces vertical thermal air movements affecting the movement of particulate matter (18). It was estimated that greening six percent of Toronto would reduce the urban heat island effect by 1 to 2 degrees Celsius preventing 0.62 MT (Mega tons) of greenhouse gases indirectly from urban heat island reduction (19).

A few studies have modeled the removal of air pollutants by green roofs. For example, Peck (2003) estimated that current roof greening (covers over 6.5 million square meters) results in a 5-10% reduction in NO_x and SO_2 concentrations in the air, and 30 tons of particulate matter (19). The potential benefit of green roofs to remove NO_2 , SO_2 , CO, PM10, and ozone has been studied using the Urban Forest Effects (UFORE) computer model (15, 20). The model was developed to quantify the benefits provided by urban forests given local hourly pollution concentrations, meteorological data, and plant-specific air pollution removal rates. Assuming a 50:50 mix of

evergreen shrubs and grasses, the estimated annual removal of all pollutants by green roofs (per ha.) ranged from 71.95 kg (Toronto) to 83.27 kg (Washington, DC) (20, 15).

Although green roofs have been shown to mitigate stormwater runoff volume and to reduce the heating and cooling loads of buildings, the challenge facing widespread integration of green roofs include the premium cost over conventional roofs, and widely diverging municipal management practices for stormwater and air pollution control. For example, in the USA, the financial burden of managing stormwater is rarely applied to property owners according to area and intensity of impervious area. While some cities have succeeded in encouraging the technology through a command-and-control approach (e.g. Tokyo, Japan; Berlin, Germany), the internal rate of return on the investment (or investment recuperation timeframe) is highly dependent on local conditions (21). Reducing the uncertainty in the quantification of economic benefits of green roofs is a necessary first step to develop policies aimed at stimulating widespread acceptance of the technology in the United States.

The objective of this paper is to quantitatively integrate probabilistic ranges of stormwater, energy, and air pollution benefits in an economic model capturing both the building-specific and city-wide scale. A secondary goal is to assess the impact and opportunities of market-based air credit valuation as a policy tool for green roof diffusion.

Materials and Methods

To address the need for a cost-benefit analysis, a two-fold approach was developed. The first step describes a cost-benefit analysis that can be applied to a range of green roof projects through a probabilistic evaluation procedure. This analysis provides information relevant to building owners, developers, or designers regarding the costs and benefits of green roof technology.

Results were scaled using both environmental and health benefits for a city. This section summarizes the steps for the cost-benefit analysis at the building and city scale.

Building Scale Analysis

The environmental benefits (stormwater reduction, energy savings, and air quality) of roof greening were quantified to assess environmental impact at the building scale, targeting mixed-use office buildings. Several parameters were evaluated: conventional and green roof installation costs, stormwater fees and fee reductions for green roofs, energy costs due to the heat flux through a roof and the potential savings by installing a green roof, and the additional economic valuation of the public health benefits due to air pollution mitigation.

Installation Costs for Conventional and Green Roofs To determine how the environmental benefits reduce the installation cost gap between green and conventional roofs, the magnitude of the gap was first determined. Cost and size data were obtained for seventy-five campus roofs from the University of Michigan in Ann Arbor, Michigan. From the sample, the mean cost of a conventional flat roof was determined to be \$167 per m² (standard deviation: \$28 per m²). The mean campus roof is 1870 m² and the mean building floor area is 9730 m².

The distribution of green roof installation costs was determined from available green roof case data (22, 23). As the price of green roofs can vary according to design and function (e.g. intensive green roof can serve as a garden), the cases used in the data analysis were limited to extensive roofs with a depth between 5 and 15 centimeters. The collected data represented the additional cost of the green roof components. The distributions of the conventional roof and green roof were summed to obtain the total cost of installation for a new green roof with a new

conventional roof. The mean difference between the cost of the green roof and the conventional roof is defined as the cost gap. The internal rate of return was then determined for each environmental benefit.

Stormwater Fees and Reductions Stormwater volume reduction by green roofs benefit municipalities; however, not all local water authorities pass the economic savings on to the owner of the green roof. Traditionally, the budget for stormwater management is provided through property taxes or potable water use fees. In recent years, municipalities have been moving toward stormwater fees based upon total impervious surface on a property, creating an opportunity to “credit” green roofs for stormwater reduction. For this study, data were collected from eleven municipalities with established stormwater management fees (Table 1, SI). It was assumed that the reduction in stormwater fees due to a green roof is normally-distributed at fifty percent of the stormwater fee for the building footprint. Impacts to stormwater infrastructure are only assessed at scale.

Energy Savings Determination and Valuation This study focuses on energy savings to mixed-use administrative/laboratory buildings at the University of Michigan campus in Ann Arbor, Michigan. Total expenditures for energy (natural gas and electricity) consumption (mean \$225,000), total energy consumption (mean 4050 MWh), and energy consumption by fuel source (mean 2370 MWh from electricity and 1670 MWh from natural gas) were obtained for 130 university buildings for fiscal year 2003. National commercial building energy consumption

statistics provided additional data (e.g. average commercial conductance, system load factors) (24). To determine the roof's contribution to the HVAC energy requirement, the heat flux through the roof was determined according to the following 1-dimensional heat flux equation:

$$\dot{Q} = h \cdot A \cdot \Delta T \quad (\text{Equation 1})$$

where Q is the heat flux through the roof (W), A is the area of the roof (m^2), ΔT is the temperature difference between the building interior and the ambient temperatures (K), and h is the heat transfer coefficient ($W/m^2/K$).

$$h = \frac{k}{\Delta x} = \frac{1}{R} \quad (\text{Equation 2})$$

h is a function of the thermal conductivity of a material, k , and the material thickness, Δx . The inverse of h is the R-value, which represents a material's resistance to heat flow. The larger the R, the less heat flux Q . In the construction industry, R-value ($ft^2 \cdot ^\circ F \cdot h/Btu$) is commonly used to compare the effectiveness of insulation in building materials. An average R-value of 11.34 $ft^2 \cdot ^\circ F \cdot h/Btu$ (conductance of 0.50 $W/m^2/K$) was assumed for the conventional roof according to national commercial building data (24).

Energy costs due to the heat flux were determined assuming natural gas for heating and electricity for cooling. With available energy expenditures per university building, prices were assumed to be \$0.08/kWh for electricity and \$0.02/kWh of natural gas. Energy savings through the use of a green roof were based on an assumption of an R-value of 1.2 $ft^2 \cdot ^\circ F \cdot h/Btu$ (conductance of 4.7 $W/m^2/K$) per centimeter depth for a 10.2-cm soil media. The total combined R-value for a conventional roof with a green roof is 23.4 $ft^2 \cdot ^\circ F \cdot h/Btu$ (total conductance of 0.24 $W/m^2/K$).

The requisite energy consumption by the HVAC system to compensate for the loss through the roof was then determined. Annual totals for heat loss and cooling loss were multiplied by a system factor as suggested by Huang and Franconi (24).

Air Quality Improvement and Valuation Impact on air quality was limited to the mitigation of nitrogen oxide (NO_x). Nitrogen oxide emission allowances are currently traded in the US aiding the exploration of a market-based economic valuation. To quantify nitrogen oxide uptake by plants (per unit area), data from Morikawa, et al. (1998) were used (25). That study evaluated the NO_x uptake potential of 217 plant taxa under controlled conditions in a greenhouse environment. Although sedums, the traditional vegetated roof plants of choice, were not evaluated, the study included a member of the same family, *Crassulaceae*. Published results were in terms of mg N g⁻¹ dry weight per 8 hours of daylight exposure. The following assumptions were made to obtain the uptake capacity per unit area (kg_{NO2} m⁻² y⁻¹): (i) Ninety percent of plant mass is water; (ii) Leaf thickness is 2 mm; (iii) Leaf area index (LAI) is 5 (m² leaf area per m² surface area); (iv) Average hours of daylight per day (twelve). Calculations were performed to capture the potential impact of all 217-plant taxa on NO_x uptake. The distribution of uptake potentials (Figure 1, SI) is assumed to be lognormal with a mean of 0.27 ± 0.44 kg_{NO2} m⁻² y⁻¹. An implicit assumption was that the uptake capacity is constant on a year-to-year basis.

Once the annual uptake of NO_x was determined, the result was translated to health benefits in dollars per year. These calculations were based upon two estimation methods developed by the US Environmental Protection Agency (EPA) as part of a regulatory impact analysis of NO_x reductions in 1998 (26, 27). The conclusion of the analysis for the Eastern US,

was that fewer premature deaths and fewer cases of chronic bronchitis translated into an economic benefit between \$1680 and \$6380 per Mg adjusted to 2006 dollars (27). The two estimates were based upon the results of several atmospheric models that provided estimates for secondary ozone, nitrogen deposition, and particulate formation (27). The range of economic benefit accounts for uncertainty in atmospheric acid sulfate concentration, which affects ammonium nitrate particulate formation (27). For the purposes of this study, the estimates are referred to as the *low estimate* (\$1680 per Mg) and the *high estimate* (\$6380 per Mg).

Economic Analysis and Sensitivity Analysis Once the costs and benefits were determined on a per unit area basis, the results were integrated into an economic model to determine the length of time required for a return on investment in a 2,000 m² green roof using a net present value (NPV) analysis (Table 2, SI). An interest rate of six percent and inflation rate of three percent were used.

It was assumed that the conventional roof would be replaced after twenty years (28). Maintenance costs have not been included in this analysis. Until plants are established (1-3 years), maintenance costs may be greater for a green roof. After establishment, expenses should be equal to or less than a conventional roof (18). A sensitivity analysis evaluated model sensitivity to economic parameters, climate factors, and variability in air pollution uptake.

City Scale Analysis

To assess the scalability of benefits, a city-wide greening evaluation was conducted and applied to two US cities (Chicago, Illinois and Detroit, Michigan) As total roof area data are unavailable for most cities, values were estimated through the extrapolation of roof area

estimates for Sacramento, California. (29). In that study authors used high-resolution orthophotos to link roof area to land use zones (residential, commercial, industrial). For the purpose of this study, the percentage roof area per land use zone in Sacramento was extrapolated to the Chicago and Detroit metropolitan areas. Chicago metropolitan land use data were aggregated from data sets provided by the Northeastern Illinois Planning Commission (1995) (30). For the Detroit metropolitan area, the individual county datasets were merged prior to accessing land use data for the region (31). For this analysis, areas were ignored if they fell outside of residential, commercial, or industrial land use zones or were primarily composed of undeveloped or minimally developed land (Figures 2 and 3, SI). For the Detroit metropolitan area, of 886,000 ha, it was estimated that roofs cover 54,200 ha. In the Chicago metropolitan areas (948,000 ha), 65,400 ha are estimated to be roofs. Environmental benefits for the metropolitan areas were then evaluated according to the procedures previously discussed.

Results and Discussion

The following summarizes the NPV analysis. The implications of the benefits on city environmental policy are also discussed.

Stormwater Benefits

The mean stormwater fee was found to be \$0.17/m² (standard deviation: \$0.12/m²) (32-41). Potential fee reductions for green roofs resulted in a mean stormwater fee of \$0.08/m² (standard deviation: \$0.06/m²). For the 2,000 m² roof, conventional roof fees would be \$340 while the green roof scenario would have fees of \$160 per year.

A few municipalities offer fee reductions to green roof projects (assuming reduced impervious area and adequate storm capture) to pass the value of the public benefit of stormwater reduction

to the building owner (e.g. Minneapolis, Minnesota) (37). Additional benefits may be captured by evaluating retention at the city scale. Deutsch et al (2005) estimated that greening ten percent of green roof ready buildings in Washington, DC (approximately 70 ha) would reduce infrastructure costs to the city's long-term control plan (LTCP) (estimated capital cost of 1.9 billion dollars) by 10 million dollars assuming the roofs would retain 450,000 cubic meters of the 97 million cubic meters of stormwater that are managed annually (15). For the Detroit metropolitan area, assuming a retention rate of 65% of annual precipitation (0.84m for Detroit), greening ten percent of rooftops (5420 ha) would retain more than 29 million cubic meters of water (Table 3, SI). Considering that the estimated costs of the LTCP are \$3.5 billion (42), this translates to a reduction of \$ 114 million, suggesting substantial opportunity to invest in above-ground roof infrastructure.

Energy Assessment

The heat flux was based on a 2,000 m² roof located in Ann Arbor, Michigan. The annual energy consumption was 129 MWh for the conventional roof (116 MWh for heating and 13 MWh for cooling), and 62 MWh for the green roof (56 MWh for heating and 6 MWh for cooling). Uncertainty for this calculation is not included in the NPV analysis as the link between frequency of precipitation and green roof soil media conductance has not been investigated in the literature. Based on energy costs for 2003 and adjusted to 2006 dollars (2003 energy expenditure data was available from the university and energy prices for 2004 and 2005 were unusually high), this translates in \$3,240 and \$1,580 per year for the conventional and green roof, respectively.

To verify the appropriateness of the assumptions used in the analysis, calculated energy costs through the conventional roof were compared to actual expended total natural gas and electric energy costs for university buildings. Assuming that 35% of total building energy consumption is due to heating, ventilation, and air conditioning (HVAC) system use (43), 90% of all buildings (75 total) were within the expected costs attributed to HVAC use. The eight buildings with higher energy expenditures had roof area-to-floor-space ratios much greater than one (R/F area \gg 1). The ratio can be explained by the inclusion of roof areas outside the interior building floor area (e.g. exterior walkways, loading docks), including these areas in the heat flux calculations would overestimate contribution to the HVAC consumption.

Sensitivity analysis included geographical location of the building. Based on the assumptions for conventional and green roof conductance, the percent difference in heat flux between the conventional roof and the green roof remains constant. However, the geographic location of the roof does change the total energy loss through the roof. Similar sized theoretical roofs were evaluated for Atlanta, Georgia and Portland, Oregon (two cities pursuing green roofs). Although the total energy consumed in both of these cities was less than the total energy consumed in Ann Arbor, the total cost for energy loss through a roof in Atlanta was greater due to increased electricity consumption for cooling (total cooling energy was 34 MWh for the conventional roof and 16 MWh for the green roof) (44). For Portland, a more moderate climate resulted in less energy use for heating and cooling, yielding lower annual energy expenditures (44). From this evaluation, annual energy expenditures for a 2,000 m² conventional roof range from \$2,000 to \$4,000 while the expenditures for a green roof of the same size range from \$1,000 to \$2,000.

Air Pollution Mitigation

The benefit assessment included both direct and indirect methods of uptake. The uptake capacity per area for the 217 plant taxa evaluated by Morikawa et al. (1998) had a mean of 0.27 kg_{NO₂}/m²/y (variance: 0.17 kg²_{NO₂}/m⁴/y²)(25). For a building with a roof area of 2000 square meters, this results in an uptake of 530 Mg_{NO₂}/y (variance: 700 Mg²_{NO₂}/y²). The public health benefits for greening a 2000 m² roof were determined to be \$890 (variance: 2.0E6 \$²) for the low benefit estimate and \$3390 (variance: 2.8E7 \$²) for the high benefit estimate.

The potential health benefits at the city scale from uptake of NO_x were determined and translated into economic terms according to the two EPA estimates. Greening ten percent of Chicago roofs (6540 ha) would uptake 17,400 Mg_{NO₂}/y resulting in city-wide benefits of \$29.2 million to \$111 million annually. For Detroit, greening ten percent (5420 ha) would uptake 14,400 Mg_{NO₂}/y, resulting in benefits of \$24.2 million to \$91.9 million annually.

These values were compared to two previous studies that relied on the Urban Forest Effects Deposition (UFORE-D) Model to evaluate air pollution mitigation scenarios in Toronto, Ontario and Washington, DC (20, 15). For Toronto, uptake values were found to be 0.0015 kg NO₂/m²/y (20), with Washington, DC similar at 0.0011 kg NO₂/m²/y (15). Using the UFORE-D model, the uptake is two orders of magnitude smaller than the mean uptake value (0.27 kg_{NO₂}/m²/y) based on experimental plant studies (25). While the DC study did not include an economic analysis, the Toronto study translated the economic benefits of all pollutant reductions (model evaluated CO, O₃, SO₂, and PM₁₀ in addition to NO₂) for the City of Toronto to be \$1.97 million annually (\$0.04 per square meter). The UFORE-D model assigns an economic value for NO₂ mitigation of \$6752 per metric ton removed, based on median externality values for the US and is consistent with the estimated benefit provided by the EPA.

There are several factors that could explain the difference in plant uptake rates (green house vs. UFORE model). The UFORE-D model limited the uptake, which was determined from calculations of atmospheric pollutant flux, boundary resistance, and a hybrid of big-leaf and multilayer canopy model (45), to a mix of two types of plants. The minimum uptake rate for this study is the same order of magnitude (Figure 1, SI) as the value determined by the UFORE-D model ($0.002 \text{ kg}_{\text{NO}_2}/\text{m}^2/\text{y}$). The UFORE-D model is based upon hourly weather conditions and assumes that uptake occurs only via dry deposition of pollutants onto vegetation (45). While this assumption is valid when NO_2 is considered, fast reaction rates in the troposphere yield compounds that are more water soluble (e.g. HNO_3) (46). Periods of precipitation were assumed to result in no pollutant uptake; the reported values of NO_2 uptake using the UFORE-D model would be expected to be less than the values used in the current study.

Large-scale roof greening also indirectly benefits public health by reducing energy consumption. Green roofs can reduce peak energy demand resulting in fewer atmospheric emissions from power plants that run additional generators at peak times. Based upon emissions data for coal-fired utilities and natural gas combustion, estimates for avoided emissions for greening ten percent of Chicago are 2.21 million $\text{Mg}_{\text{NO}_2}/\text{y}$ and for Detroit are 1.83 million $\text{Mg}_{\text{NO}_2}/\text{y}$ (Table 4, SI) (47). Combining both direct (plant uptake) and indirect (fossil fuel reduction) methods of emission mitigation, greening ten percent of area roofs in Detroit would decrease public health costs by \$3.1 billion to \$11.8 billion per year, and in Chicago public health benefits would be \$3.8 billion to \$14.2 billion per year.

Net Present Value Analysis

The results were integrated into an economic model to determine the length of time required for a return on investment (ROI) in a green roof. Figure 1 shows the results of the analysis over the lifetime of the green roof system, and evaluates the green roof under a low air pollution benefit and a high air pollution benefit. The green roof is more expensive than the conventional roof at installation (\$464,000 versus \$335,000). Over the 40-year lifetime of the roof, the NPV of the green roof system is between 25% (low air pollution benefit estimate) and 29% (high air pollution benefit estimate) less than the NPV for a conventional system (\$602,000).

Under the low estimate for health benefit valuation, the greatest potential economic contribution is due to energy savings. Annual benefits for the green roof system in this scenario are \$2740 (2006\$) per year. Energy savings account for nearly \$1670 or 61% of the benefits. In this scenario, benefits due to mitigation of nitrogen oxides account for 33% of the annual benefits. Stormwater fee savings only account for 7% of the annual benefits.

When a high estimate for valuation of public health benefits is used, air pollution mitigation becomes the dominant benefit economically. With total annual benefits of \$5240, 65% of the benefits (\$3390) are attributable to air pollution mitigation. Energy savings remain the same but account for only 32% of the total annual benefit. The stormwater benefit is further reduced to only three percent of the total. While the monetary value of the health benefits is uncertain, in both the high and low estimates, public health benefits contribute significantly to the total annual benefit of green roofs.

While currently green roof adoption is driven by stormwater benefits and energy savings (48), benefits due to direct air pollution uptake and energy savings control the ROI. Additional savings due to reduced onsite stormwater infrastructure are not included at the building scale as

infrastructure savings at individual building sites could only be realized for new building construction or significant renovation projects. Similarly, while system loads to HVAC were taken into account to determine the total reduction in energy, infrastructure savings (from size reduction) were not included. This analysis focused on the opportunity for green roofs on existing buildings that could support an extensive vegetated roof with minimal impact on the building and roof. All other parameters remaining constant, varying degree days to evaluate other climate regions (the southeastern states or the western states) changed the total energy consumed resulting in the \$2000 range for both the conventional and the green roof.

For large-scale urban greening projects, it should be noted that not all of these roofs may be conducive to green roof implementation due to restrictive architectural features (e.g. roof slope, HVAC system placement, structural limitations of building). The analysis contained here limits roof greening to twenty percent of existing roofs, similar to the analysis for Washington, DC by Deutsch et al. (15). For scaled stormwater benefits, the economic savings are over the long-term after greening projects began most likely occurring during normal maintenance and replacement of existing stormwater infrastructure.

Policy Implications



The mean green roof cost is 25 to 29 percent less over 40 years, with the investment breaking even after twenty years. Incorporation of air pollution benefits the greatest potential social cost factor into the economic analysis. Further work is required to incorporate HVAC size reductions, stormwater infrastructure size reductions, and multiple air pollutant reductions. Results from this analysis revealed that the benefit of improved air quality should not be ignored by policymakers as proper valuation of the benefit can greatly influence the NPV.

Proper valuation of environmental benefits requires changes to current policies that affect green roofs. Currently, the analysis performed here incorporated mean stormwater fees at \$ 0.17 per m² of land, yet projected long-term control plans are at \$3.36 per m² of land. Inclusion of these costs will impact the benefit analysis. Policies that make stormwater infrastructure expenses more transparent to the citizenry through stormwater fees or a market-based tradable permit scheme for contribution to impaired local waterways are two strategies that have potential to rectify the price discrepancy. Translating the air pollution mitigation ability of green roofs into an economic benefit to the technology would further reduce the NPV by 9%. This could be achieved through direct incentives reducing the upfront cost of a green roof or through the incorporation of green roofs into existing regional air pollution emission allowance markets. Further research into these policy alternatives will aid the design and development of strategies to translate the societal environmental and health benefits of green roofs to the building owners that ultimately construct green roofs.

To quantify the benefit of reducing NO_x emissions for building owners, green roofs could be integrated into the existing air emission allowance markets. If green roofs are considered an abatement technology, then incorporating sinks into a cap-and-trade program could allow the pollution taken up by a green roof to be traded on the open emissions allowance market. Such a program does not currently exist, in part due to the constraints placed on the demonstrations that a new technology fits abatement criteria. On-going research through professional organizations such as Green Roofs for Healthy Cities have emphasized the need for quantitative measurements of the green roof benefits (stormwater, energy, air) as a priority for influencing regional and national policy in this realm.

ACKNOWLEDGMENT. The authors thank the Graham Environmental Sustainability Institute for support.

SUPPORTING INFORMATION. Technical attributes for economic analysis.



c)




Figure 1. Net present value (NPV) analysis of the conventional roof and the green roof under two public health valuation scenarios. Annual benefits for the green roof are broken into economic value realized from stormwater reduction, energy savings, and air pollution reduction under (a) the high valuation and (b) the low valuation of the contribution of NO₂ reduction to public health. The benefits are incorporated into over the 40-year lifetime of the roof (c). At the end of year 20, the conventional roof is replaced; at this point the mean NPV of the green roof is less than the mean NPV of the conventional roof.

References

- (1) United Nations. Department of Economic and Social Affairs. Population Division. 2004. *World Urbanization Prospects: The 2003 Revision*. New York: United Nations. <http://www.un.org/esa/population/publications/wup2003/WUP2003Report.pdf>. Accessed 23 June 2006.
- (2) US Department of Energy. National Energy Technology Laboratory. *Tracking New Coal-Fired Power Plants: Coal's Resurgence in Electric Power Generation*. June 21, 2006. <http://www.netl.doe.gov/coal/refshelf/ncp.pdf>. Accessed June 22, 2006.
- (3) Southeast Michigan Council of Governments (SEMCOG). 2001. Investing in Southeast Michigan's Quality of Life: Sewer Infrastructure Needs. <http://www.semco.org/products/pdfs/sewerneeds2.pdf>. Accessed 26 February 2006.
- (4) Rosenfeld, Arthur H; Akbari, Hashem; Bretz, Sarah; Fishman, Beth L; Kurn, Dan M; Sailor, David; Taha, Haider. 1995. "Mitigation of Urban Heat Islands: Materials, Utility Programs, Updates," *Energy and Buildings*, 22: 255-265.
- (5) Lazzarin, Renato M; Castellotti, Francesco; Busato, Filippo. 2005. "Experimental Measurements and Numerical Modelling of a Green Roof," *Energy and Buildings*, 37: 1260-1267.
- (6) Scholz-Barth, Katrin. January 2001. Green Roofs: "Stormwater Management From the Top Down," *Environmental Design & Construction*, 4 (1).

- (7) Del Barrio, Elena Palomo. 1998. "Analysis of the green roofs cooling potential in buildings," *Energy and Buildings*, 27:179-193.
- (8) Niachou, A; Papakonstantinou, K; Santamouris, M; Tsangrassoulis, A; Mihalakakou, G. 2001. "Analysis of the green roof thermal properties and investigation of its energy performance," *Energy and Buildings*, 33:719-729.
- (9) Theodosiou, Theodore G. 2003. "Summer period analysis of the performance of a planted roof as a passive cooling technique," *Energy and Buildings*, 35:909-917.
- (10) Wong, Nyuk Hien; Chen, Yu; Ong, Chui Leng; Sia, Angela. 2003. "Investigation of thermal benefits of rooftop garden in the tropical environment," *Building and Environment*, 38:261-270.
- (11) Liu, Karen; Minor, John D. "Performance Evaluation of an Extensive Green Roof," *Proceedings for 3rd Annual Greening Rooftops for Sustainable Communities*. Washington, DC.
- (12) Hutchinson, D., P. Abrams, R. Retzlaff, Liptan, T. 2003. "Stormwater Monitoring Two Ecoroofs in Portland, Oregon, USA," *Proceedings for Greening Rooftops for Sustainable Communities*. Chicago, Illinois.
- (13) VanWoert, Nicholas D; Rowe, Bradley; Andresen, Jeffrey A.; Rugh, Clayton L.; Fernandez, R. Thomas; and Lan Xiao. 2005. "Green Roof Stormwater Retention: Effects of Roof Surface, Slope, and Media Depth," *Journal of Environmental Quality*, 34(3): 1036-1044.

(14) Moran, Amy; Hunt, Bill; and Jonathan Smith. 2005. "Hydrologic and Water Quality Performance from Green Roofs in Goldsboro and Raleigh, North Carolina," *3rd Annual Greening Rooftops for Sustainable Communities*. Washington, DC.

(15) Deutsch, B; Whitlow, H; Sullivan, M; and A Savineau. 2005. *Re-Greening Washington, DC: A Green Roof Vision Based on Quantifying Storm Water and Air Quality Benefits*. <http://www.caseytrees.org/pdfs/Green%20Roof%20Vision%20for%20DC%20-%20Full%20Report%20082405.pdf?id=48903>. Accessed 10 April 2006.

(16) Dousset, B; and F Gourmelon. 2003. "Satellite multi-sensor data analysis of urban surface temperatures and landcover," *ISPRS Journal of Photogrammetry and Remote Sensing*. 58(1-2):43-54.

(17) Solecki, William D; Rosenzweig, Cynthia; Cox, Jennifer; Parshall, Lily; Rosenthal, Joyce; and Sara Hodges. 2006. "Potential Impact of Green Roofs on the Urban Heat Island Effect," *Green Roofs in New York Metropolitan Region*. Technical Report. http://ccsr.columbia.edu/cig/greenroofs/Green_Roof_UHI.pdf. Accessed 15 October 2006.

(18) Peck, Steven and Monica Kuhn. 1999. *Design Guidelines for Green Roofs*. Canada Mortgage and Housing Corporation. <http://www.cmhc-schl.gc.ca/en/inpr/bude/himu/coedar/loader.cfm?url=/commonspot/security/getfile.cfm&PageID=70146>. Accessed 11 June 2006.

(19) Peck, Steven. 2003. "Towards an Integrated Green Roof Infrastructure Evaluation for Toronto," *The Green Roof Infrastructure Monitor*, 5(1): 4-5. <http://www.greenroofs.org/pdf/GRIM-Spring2003.pdf>. Accessed 11 June 2006.

(20) Banting, D; Doshi, H; Li, J; Missios, P; Au, A; Currie, BA; and M. Verrati. 2005. *Report on the Environmental Benefits and Costs of Green Roof Technology for the City of Toronto*. <http://www.toronto.ca/greenroofs/pdf/fullreport103105.pdf>. Accessed 2 September 2006.

(21) Lawlor, Gail; Currie, Beth Anne; Doshi, Hitesh; and Ireen Wieditz. 2006. *Green Roofs: A Resource Manual for Municipal Policy Makers*. CD-ROM. Canada Mortgage and Housing Corporation.

(22) Earth Pledge. 2005. *Green Roofs: Ecological Design and Construction*. Schiffer Publishing, Ltd.: Atglen, Pennsylvania.

(23) GRHC. 2005. "Green Roof Awards of Excellence," *3rd Annual Greening Rooftops for Sustainable Communities*. Washington, DC.

(24) Huang, Joe and Ellen Franconi. 1999. *Commercial Heating and Cooling Loads Component Analysis*. LBL 37208. Lawrence Berkeley National Laboratory: Berkeley, California.

(25) Morikawa, H; Takahasi, M; and Y. Kawamura. 1998. "More than a 600-fold Variation in Nitrogen Dioxide Assimilation among 217 Plant Taxa," *Plant, Cell and Environment*, 21: 180-190.

(26) Swift, Byron and Jan Mazurek. 2001. *Getting More for Four: Principles for Comprehensive Emissions Trading*. Progressive Policy Institute. http://www.ndol.org/documents/clean_energy_part2.pdf. Accessed 20 November 2006.

(27) US EPA. Office of Air and Radiation. 1998. *Regulatory Impact Analysis for the NOx SIP Call, FIP, and Section 126 Petitions*. EPA-452/R-98-003A.

(28) Coates, David T. *Roofs and Roofing: Design and Specification Handbook*. Whittles Publishing, Caithness, UK. 1993.

(29) Akbari, Hashem; Rose, Shea; and Haider Taha. 2003b. "Analyzing the land cover of an urban environment using high-resolution orthophotos," *Landscape and Urban Planning*. 63:1-14.

(30) Northeastern Illinois Planning Commission. 1995. *Chicago Region Data and GIS Catalog*. <http://www.nipc.cog.il.us>.

(31) Southeast Michigan Council of Governments (SEMCOG). 1995. *Land Use Data*.

(32) City of Ann Arbor, Michigan. Water Treatment Services. 2006. *Water, Sewer, and Stormwater Rates*. <http://www.ci.ann-arbor.mi.us/PublicServices/Water/CS/WaterSewerStormRates.pdf>. Accessed 13 September 2006.

(33) County of Gwinnett, Georgia. 2005. *A Resolution of the Gwinnett County Board of Commissioners to Establish a Rate Structure for a Stormwater Utility*.

<http://www.co.gwinnett.ga.us/departments/publicutilities/pdf/Stormwater%20Utility%20Rate%20Structure%20Resolution.pdf>. Accessed 14 September 2006.

(34) City of Bellevue, Washington. 2006 *Utility Rates*.
<http://www.ci.bellevue.wa.us/page.asp?view=22319>. Accessed 14 September 2006.

(35) City of Boulder, Colorado. 2006 *Utility Rates*.
http://www.ci.boulder.co.us/index.php?option=com_content&task=view&id=4884&Itemid=2128. Accessed 15 September 2006.

(36) City of Gainesville, Florida. Public Works Stormwater Division. *Stormwater Management Utility*. <http://www.cityofgainesville.org/pubworks/stormwater/>. Accessed 14 September 2006.

(37) City of Minneapolis, Minnesota. *Stormwater Rate*.
<http://www.ci.minneapolis.mn.us/stormwater/what-we-do/StormwaterRate.asp#TopOfPage>. Accessed 14 September 2006.

(38) City of Portland, Oregon. *Fiscal Year 2006/2007 Sewer Rates*.
<http://www.portlandonline.com/bes/index.cfm?a=117495&c=31019>. Accessed 14 September 2006.

(39) City of Seattle, Washington. *Drainage Rates*.
http://www.seattle.gov/util/Services/Drainage_&_Sewer/Rates/DRAINAGER_200312020900545.asp. Accessed 2 March 2007.

(40) City of Tacoma, Washington. Public Utilities. 2006. *Rates*.
<http://www.ci.tacoma.wa.us/waterservices/>. Accessed 14 September 2006.

- (41) District of Columbia. Water and Sewer Authority. *Rates*.
<http://www.dcwasa.com/customercare/rates.cfm#currentrates>. Accessed 13 September 2006.
- (42) Camp, Dresser, & McKee (CDM). 2003. *Wastewater Master Plan*. Prepared for the Detroit Water Sewerage Department. <http://www.dwsd.org/about/wastewater.html>. Accessed 7 September 2006.
- (43) D&R International, Ltd. August 2005. *2005 Buildings Energy Data Book*. Prepared for the Office of Planning Budget Formulation and Analysis, Energy Efficiency and Renewable Energy, US Department of Energy. <http://buildingsdatabook.eren.doe.gov/docs/2005bedb-0805.pdf>. Accessed 12 December 2005.
- (44) US Department of Commerce. National Oceanic and Atmospheric Administration. National Climatic Data Center. *US Climate Normals*. http://cdo.ncdc.noaa.gov/cgi-bin/climatenormals/climatenormals.pl?directive=prod_select2&prodtype=CLIM81&subnum=. Accessed 24 February 2007.
- (45) Nowak, DJ et al. *UFORE Methods*. Last modified April 2006. <http://www.fs.fed.us/ne/syracuse/UFOREMethods.pdf>. Accessed 12 January 2007.
- (46) Jacob, Daniel J. 1999. *Introduction to Atmospheric Chemistry*. Princeton University Press.
- (47) Franklin & Associates, 1992. *Appendix A: Energy Requirements and Environmental Emissions for Fuel Consumption*. Franklin Associates, Prairie Village, KS.
- (48) Lawlor, G; Currie, BA; Doshi, H; Wieditz, I. 2006. *Green Roofs: A Resource Manual for Policy Makers*. Canadian Mortgage and Housing Corporation.