

## Report of Materials and Equipment Acceptance Division

NYC Department of Buildings 280 Broadway, New York, NY 10007 Patricia Lancaster, FAIA, Commissioner (212) 566-5000, TTY: (212) 566-4769

Pursuant to Administrative Code Section 27-131, the following equipment or material has been found acceptable for use subject to the terms and conditions contained herein.

## MEA 180-04-E

Manufacturer: Rheem Manufacturing Co., for RUUD, P.O. Box 17010, Fort

Smith, AR 72917-7010.

Trade Name(s): RUUD.

**Product:** Outdoor air cooled condensers and compressor units.

Pertinent Code Section(s): 27-770, 27-777.

Prescribed Test(s): RS 13-6 (ANSI B9.1), RS 13-11 (CSA C22.2No. 236; UL

1995).

**Laboratory:** Underwriters Laboratories, Inc.

**Test Report(s):** No. SA7930 dated January 30, 2004.

**Description** – Outdoor air cooled condensing and compressor unit used for refrigeration and air conditioning systems. This is a component comprising condenser coil, fan motor and appropriate controls. Units, with cooling capacities are listed below:

Model No.	Mfr.'s Specified Nominal Cooling Capacity Tons
UAMC018*	1.5
UAMC024*	2.0
UAMC030*	2.5
UAMC036*	3.0
UAMC042*	3.5
UAMC048*	4.0
UAMC060*	5.0

Note - \* Model designation may be suffixed.

Terms and Conditions: That the above outdoor air-cooled condensers be accepted, under the following conditions:

- 1. All equipment shall be furnished with a permanently affixed metal tag stating that if installed in New York City within 100 feet of any dwelling unit window, there shall be compliance with all provisions of Section 27-770, as to maximum sound levels permitted for exterior mechanical equipment.
- 2. All shipments and deliveries of such equipment shall be provided with a metal tag, suitably placed, certifying that the equipment shipped or delivered is equivalent to that tested and accepted for use, as provided for in Section 27-131 of the Building Code.
- Approval of electrical equipment, apparatus, materials and devices shall be 3. obtained from the Bureau of Electrical Control before installation.

Examined By Sugars.